


Public Works Construction Standards

North Central Texas

Fifth Edition
Amended August 2023

Standard Specifications
Standard Drawings




North Central Texas Council of Governments

PUBLIC WORKS CONSTRUCTION STANDARDS

North Central Texas

Fifth Edition

Amended August 2023



**North Central Texas
Council of Governments**

616 Six Flags Drive, Centerpoint Two, Arlington, Texas 76011
P. O. Box 5888
Arlington, Texas 76005-5888
(817) 640-3300

© 2023 North Central Texas Council of Governments

PUBLIC WORKS CONSTRUCTION STANDARDS

North Central Texas

Fifth Edition

Amended August 2023

Table of Contents

BACKGROUND

WHAT IS NCTCOG?

COPYRIGHT; USE AND MODIFICATION

FOREWORD

ACKNOWLEDGEMENTS

EXECUTIVE SUMMARY

SECTION I -- STANDARD SPECIFICATIONS - Fifth Edition (Published 2017)

DIVISION 100 GENERAL PROVISIONS

DIVISION 200 SITE PROTECTION AND PREPARATION

DIVISION 300 ROADWAY CONSTRUCTION

DIVISION 400 ROADWAY MAINTENANCE AND REHABILITATION

DIVISION 500 UNDERGROUND CONDUIT CONSTRUCTION AND APPURTENANCES

DIVISION 600 CONDUIT AND APPURTENANCE REHABILITATION

DIVISION 700 STRUCTURES

DIVISION 800 MISCELLANEOUS CONSTRUCTION AND MATERIALS

INDEX

APPENDIX A MODEL FORMS

SECTION II -- STANDARD DRAWINGS - Amended Fifth Edition (Published 2023)

DIVISION 1000 EROSION AND SEDIMENT CONTROL

DIVISION 2000 PAVEMENT SYSTEMS

DIVISION 3000 GENERAL UNDERGROUND CONDUIT

DIVISION 4000 WATER DISTRIBUTION

DIVISION 5000 WASTEWATER COLLECTION

DIVISION 6000 STORM WATER DRAINAGE

WHAT IS NCTCOG?

The North Central Texas Council of Governments (NCTCOG) is a voluntary association of, by and for local governments, and was established to assist local governments in planning for common needs, cooperating for mutual benefit, and coordinating for sound regional development. NCTCOG's purpose is to strengthen both the individual and collective power of local governments and to help them recognize regional opportunities, eliminate unnecessary duplication, and make joint decisions.

NCTCOG serves a 16-county region of North Central Texas, which is centered around the two urban centers of Dallas and Fort Worth. NCTCOG has 228 member governments including 16 counties, 169 cities, 19 school districts, and 24 special districts. The area of the region is approximately 12,800 square miles, which is larger than nine states, and the population of the region is approximately 7 million, which is larger than 38 states.

NCTCOG's General Assembly, which annually elects the Executive Board, is composed of one elected or appointed official from each governmental member of the Council whose annual dues are current. The Executive Board, composed of 17 locally elected officials, and one ex-officio non-voting member of the legislature, is the policy-making body for all activities undertaken by the Council of Governments, including program activities and decisions, regional plans, and fiscal and budgetary policies. The Board is supported by technical, study, and policy development committees and a professional staff headed by Mike Eastland, Executive Director.

NCTCOG's offices are located at 616 Six Flags Drive, Arlington, Texas.

NCTCOG EXECUTIVE BOARD 2023-2024

Bill Heidemann
President

Mayor
City of Corinth

Chris Hill
Vice-President

County Judge
Collin County

Victoria Johnson
Secretary-Treasurer

Councilmember
City of Burleson

Andrew Piel
Past President

Councilmember
City of Arlington

Clay Jenkins

County Judge
Dallas County

Tim O'Hare

County Judge
Tarrant County

Cara Mendelsohn

Councilmember
City of Dallas

Carlos Flores

Councilmember
City of Fort Worth

Bobbie Mitchell

Commissioner
Denton County

J.D. Clark

County Judge
Wise County

Todd Little

County Judge
Ellis County

Jorja Clemson

Deputy Mayor Pro Tem
City of Grand Prairie

Linda Martin

Mayor
City of Euless

Bowie Hogg

Councilmember
City of Arlington

Jennifer Justice

Councilmember
City of Richardson

Kameron Raburn, PE

Commissioner
City of Ennis

Nick Stanley

Mayor
City of Aledo

Victoria Neave Criado

State Representative
District 107
Ex Officio, Nonvoting Member

NORTH CENTRAL TEXAS COUNCIL OF GOVERNMENTS PUBLIC WORKS COUNCIL 2022 - 2023

Michael Owen, Chair

City Engineer
City of Fort Worth

Carrie Jones, Vice Chair

Assistant Director of Public Works
for Streets/Traffic/Drainage
City of Plano

Stephen Belknap

Assistant Director of Development
Services
Denton County

Keith Brooks

Director of Public Works &
Transportation
City of Arlington

Jody Byerly

Director of Public Works
City of Carrollton

Juan Cadena

Operations Officer
City of Fort Worth

Chris Cha

Principal
Pacheco Koch

David Chacon

Senior Civil Engineer
City of Frisco

Lyndon Cox

Senior Principal/Engineer
Terracon Consultants

Lisa Crossman

Project Engineer
City of Mesquite

Lyndon Cox

Senior Principal/Dallas Materials
Services Department Manager
Terracon Consultants

Sam Davis

Vice President/General Manager
TexasBit

Jim Dulac

Assistant Director of Engineering
City of Richardson

Andrew Figueroa

Director of Public Works
City of Celina

Christopher Funches

Project Engineer
City of Arlington

Kumar Gali

Assistant Director of Public
Works, Operations
City of Coppell

Ali Hatefi

Director of Public Works
City of Dallas

Mark Hines

Assistant Director of Public Works
Collin County

John Ho

Vice President
Huitt-Zollars

Larry Hoover

Director of Public Works
City of White Settlement

Jeremy Hutt

Director of Public Works
City of Cleburne

Pritam Deshmukh

Watershed Protection Manager
City of Denton

Joseph Jackson

County Engineer/Assistant
Director
Tarrant County

Matt Leppia

Operations Manager
City of Weatherford

Jim Lockart

Assistant Director of Public
Works/Engineering
City of Waxahachie

Dillon Luna

Management Analyst
Town of Northlake

Keith Marvin

Director of Public Services
City of Lewisville

Keith Miertschin

Assistant Director of Operations
City of Grapevine

Scott Monaghan

Director of Public Works
City of Fate

Ronnie O'Brien

Assistant Director of Public
Works
City of Rowlett

Michael Polocek

Director of Engineering
City of Garland

Clayton Riggs

Director of Public Works
Town of Flower Mound

Cecelia Rutherford

Assistant Director
Dallas County

Paul Sparkman

Assistant Director of Public
Works
City of McKinney

Walter Thomas

City Engineer
City of Irving

Douglas Taylor

Operations Manager
City of Grand Prairie

Bart VanAmburgh

Director of Public Works
City of Mansfield

Connor VanSteenberg

North Texas Area Manager
Associated General Contractors
of Texas

Caroline Waggoner

Director of Public Works
City of North Richland Hills

Derek White

Assistant City Engineer
City of Dallas

Brooks Williams

City Manager
City of Ferris

Robert Woodbury

City Engineer
City of Cedar Hill

COPYRIGHT

This copyrighted document, in whole or in part, may not be photocopied, printed or otherwise reproduced without the prior written approval of NCTCOG's Director of Environment & Development.

USE AND MODIFICATION

The *Public Works Construction Standards* are regional provisions recommended by the Public Works Council and endorsed by the NCTCOG Executive Board. The use of these Standards shall be under the supervision and seal of a professional engineer in the State of Texas. Any modification to these Standard Specifications and Standard Drawings shall be clearly noted on engineering plans and contract documents prepared under the supervision and seal of a registered professional engineer.

FOREWORD

The August 2023 *Public Works Construction Standards North Central Texas, Amended Fifth Edition* represents the culmination of an intensive comprehensive review and refinement process to update the 2004 Second Edition of the Standard Drawings for Public Works Construction.

The *Public Works Construction Standards* represents over 40 years of regional cooperation and coordination between local government and private industry public works professionals in the North Central Texas region. Produced through a public process, this document combines Standard Specifications and Standard Drawings in one volume through two Sections. The Standard Drawings, are a graphical companion to the widely used "Blue Book". The North Central Texas Council of Governments' (NCTCOG) Public Works Council (PWC), composed of public works directors, utilities directors, city/county engineers, engineering consultants, associations, and contractors, is charged with the oversight, management, and development of regional public works construction standards. Since 1977 they have endeavored to establish and promote basic standards for public works construction throughout this region that can be modified by local governments to suit their individual needs. Approved by the PWC in August 2023, this *Public Works Construction Standards North Central Texas, Amended Fifth Edition* publication is yet another step towards that goal. Prior to this program, each local government prepared and administered its own specifications for the installation of streets, storm drainage, water mains and other public works. This disparity in public works standards creates several challenges. Use of the standards as the basic uniform specifications and drawings for North Central Texas should accomplish the following improvements:

- allow common interpretation of provisions for all disciplines involved in public works construction;
- simplify the bidding process for both local governments and contractors;
- provide a continuing amendment process to meet the changing demands of new technology, new materials and improved methods;
- reduce local government expenditures associated with staff or consultant development of specifications, drawings, and training of construction inspectors; and
- result in decreased construction costs for public works projects.

The *Public Works Construction Standards* are intended to be dynamic in nature. They are meant to be continually updated, supplemented, and improved. NCTCOG will periodically conduct reviews and refinements of the Standards. NCTCOG encourages the users of this document to notify NCTCOG of needed modifications to these standards or if there are provisions that should be added. Requests, comments, or questions regarding the Standards can be emailed to eandd@nctcog.org. Comments can also be mailed to the Public Works Council, care of NCTCOG Department of Environment & Development, P.O. Box 5888, Arlington, Texas 76005-5888.

Additional copies of this document may be purchased over the counter at 616 Six Flags Drive, Arlington, Texas 76011 or by calling (817) 640-3300. Electronic, downloadable versions of this document are available for purchase at <http://store2.nctcog.org/> or from the NCTCOG Department of Environment & Development. This document is copyrighted.

ACKNOWLEDGMENTS

The PWC's Public Works Construction Standards Subcommittee devoted their time and efforts during committee meetings and countless hours of preparation and research to develop these updated standards over the past few years. The purpose of these meetings was to comprehensively review, revise and update the Second Edition Standard Drawings. The PWC approved the *Public Works Construction Standards North Central Texas, Amended Fifth Edition* on August 17, 2023.

NCTCOG is sincerely appreciative of all of the public works professionals who provided their invaluable time and expertise in the review and production of these specifications.

EXECUTIVE SUMMARY

Governments exist to protect the health, safety, and welfare of residents. Public works is the foundation of a local government's responsibilities, whether it be providing roads for safe and efficient mobility, utilities for clean drinking water and removal of waste, parks for recreation, or stormwater and watershed management for improved water quality and protection from flooding. Management of public works facilities is an important role of cities, counties, and special districts and support a high quality of life in North Central Texas. The quality of the region's infrastructure, including roads, water distribution, wastewater collection, and storm drainage systems has always been a high priority and a source of pride for the region's communities.

For over 40 years, the North Central Texas Council of Governments (NCTCOG) has supported its member local governments and the public works industry by providing a forum for communication and coordination on regional public works issues. NCTCOG's Public Works Council (PWC), initially established as the Standard Specifications Advisory Committee in 1977, provides expertise and support to the NCTCOG Executive Board and staff on a wide range of local public works topics. In this role, the PWC provides continuing advice regarding the *Public Works Construction Standards*, and areas such as managing right-of-way, comprehensive storm water management, and regional pavement design guidance.

The *Public Works Construction Standards North Central Texas, Amended Fifth Edition* represents the update to the Standard Drawings from the 2004 Second Edition of the Public Works Construction Standards. The update is the result of feedback from NCTCOG's local government members and the engineering, supplier, and construction industries that confirmed the wide use of the document in North Central Texas. Additionally, regional input indicated that an update to the Standard Drawings from the 2004 Second Edition was needed to address new technologies, materials, and methods now common in the industry and practice in North Central Texas.

The PWC assembled the Standard Drawings Subcommittee to facilitate the update to the Standard Drawings from the 2004 Second Edition. The subcommittee included representation from NCTCOG member agencies, engineering consultants, and contractors.

- Division 1000
- Division 2000
- Division 3000
- Division 4000
- Division 5000
- Division 6000

The approach to developing the updated Standards included the following major phases shown in Exhibit 1. The Amended Fifth Edition update was focused only on updating the Standard Drawings and not the Standard Specifications.




Exhibit 1: Fifth Edition Public Works Construction Standards Update Phases

The Public Works Council fully endorsed the *Public Works Construction Standards North Central Texas, Amended Fifth Edition* on August 17, 2023. The NCTCOG Executive Board subsequently endorsed the *Public Works Construction Standards North Central Texas, Fifth Edition* on November 16, 2023. NCTCOG will provide information and outreach to local governments and the region as a result of the release of the Amended Fifth Edition.

A chronological history of the adopted versions of the *Public Works Construction Standards* is below for reference.




Exhibit 2: History of the *Public Works Construction Standards North Central Texas*

For further information about the Public Works Council or the *Public Works Construction Standards*, visit www.nctcog.org/envir/constructionstandards.

Section I

Standard Specifications


Fifth Edition

Amended August 2023



Division 100

General Provisions



DIVISION 100 GENERAL PROVISIONS**TABLE OF CONTENTS**

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
101.	DEFINITIONS AND ABBREVIATIONS	101-1 to 101-6
101.1.	Definitions	
101.2.	Abbreviations and Acronyms	
102.	PROPOSAL PROCEDURES	102-1 to 102-3
102.1.	Proposal Form	
102.2.	Quantities in Proposal Form	
102.3.	Examination of Plans, Specifications and Site of the Work	
102.4.	Preparation of Proposal	
102.5.	Proposal Guaranty	
102.6.	Filing of Proposals	
102.7.	Withdrawing Proposals	
102.8.	Opening Proposals	
102.9.	Consideration of Proposal	
102.10.	Irregular Proposals	
102.11.	Rejection of Proposals	
102.12.	Disqualification of Bidders	
102.13.	Return of Proposal Guaranty	
103.	AWARD AND EXECUTION CONTRACT	103-1 to 103-5
103.1.	Contractor's Warranties and Understanding	
103.2.	Award of Contract	
103.3.	Surety Bonds	
103.4.	Insurance	
103.5.	Execution of Contract	
103.6.	Notice to Proceed and Commencement of Work	
103.7.	Delay of Contract	
103.8.	Order of Work to be Performed	
104.	SCOPE OF WORK	104-1 to 104-4
104.1.	Intent of Contract Documents	
104.2.	Change or Modification of Contract	
104.3.	Disputed Work and Claims for Additional Compensation	
104.4.	Performance of Extra or Disputed Work	
105.	CONTROL OF WORK	105-1 to 105-6
105.1.	Contract Documents	
105.2.	Workmanship, Warranties and Guarantees	
105.3.	Shop Drawings, Product Data and Samples	
105.4.	Construction Stakes	
105.5.	Means and Methods of Construction	
105.6.	Supervision by Contractor	
105.7.	Owner's Representatives	
105.8.	Service of Notices	
105.9.	Inspection	
105.10.	Acceptance	

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
106.	CONTROL OF MATERIAL	106-1 to 106-2
106.1.	<u>Substitution of Materials</u>	
106.2.	<u>Materials and Equipment</u>	
106.3.	<u>Salvageable Material</u>	
106.4.	<u>Off-Site Storage</u>	
106.5.	<u>Samples and Tests of Materials</u>	
106.6.	<u>Surplus Materials</u>	
107.	LEGAL RELATIONS AND CONTRACT RESPONSIBILITIES	107-1 to 107-14
107.1.	<u>Contractor Independence</u>	
107.2.	<u>No Third Party Contractual Rights</u>	
107.3.	<u>Indemnification</u>	
107.4.	<u>Owner's Officers, Employees or Agents</u>	
107.5.	<u>Venue and Governing Law</u>	
107.6.	<u>No Waiver of Legal Rights</u>	
107.7.	<u>Severability</u>	
107.8.	<u>Headings</u>	
107.9.	<u>Obligation to Perform Functions</u>	
107.10.	<u>Performance of the Work</u>	
107.11.	<u>Successors and Assigns</u>	
107.12.	<u>Supervision and Construction of Procedures</u>	
107.13.	<u>Labor and Materials</u>	
107.14.	<u>Equal Employment Opportunity</u>	
107.15.	<u>State and Local Sales and Use Taxes</u>	
107.16.	<u>Patents</u>	
107.17.	<u>Compliance with Laws</u>	
107.18.	<u>Sanitary Provisions</u>	
107.19.	<u>Public Convenience and Safety</u>	
107.20.	<u>Protection of Work and of Persons and Property</u>	
107.21.	<u>Project Signs</u>	
107.22.	<u>Working Area</u>	
107.23.	<u>Railway Crossings</u>	
107.24.	<u>Existing Structures, Facilities and Appurtenances</u>	
107.25.	<u>Project Clean-Up</u>	
107.26.	<u>Disposal of Materials</u>	
107.27.	<u>Restoration of Property</u>	
107.28.	<u>Environmental Compliance</u>	

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
108.	PROSECUTION AND PROGRESS	108-1 to 108-8
108.1.	<u>Progress Schedule</u>	
108.2.	<u>Prosecution of the Work</u>	
108.3.	<u>Other Contractors; Obligation to Cooperate</u>	
108.4.	<u>Employees</u>	
108.5.	<u>Subcontracts</u>	
108.6.	<u>Contractor Work by its Own Forces</u>	
108.7.	<u>Owner's Right to Temporarily Suspend Work</u>	
108.8.	<u>Delays; Extension of Time; Liquidated Damages</u>	
108.9.	<u>Contractor Default: Owner's Right to Suspend Work and Annul Contract</u>	
108.10.	<u>Suspension by Court Order Against the Owner</u>	
108.11.	<u>Termination for Convenience of the Owner</u>	
108.12.	<u>Claims Against Owner and Action Thereon</u>	
108.13.	<u>Use of Completed Portions of Work</u>	
109.	MEASUREMENT AND PAYMENT	109-1 to 109-5
109.1.	<u>Payment for Labor and Material; No Liens</u>	
109.2.	<u>Payment for Materials</u>	
109.3.	<u>Payment for Extra Work</u>	
109.4.	<u>Payment Withheld</u>	
109.5.	<u>Monthly Estimate, Partial Payments, Retainage, Final Inspection, Acceptance and Final Payment</u>	
109.6.	<u>Wire Transfers</u>	
110.	AIR QUALITY REQUIREMENT FOR EQUIPMENT	110-1 to 110-2
110.1.	<u>Equipment Requirements</u>	
110.2.	<u>Operational Requirements</u>	
110.3.	<u>Reporting to Owner</u>	
110.4.	<u>Enforcement</u>	

ITEM 101. DEFINITIONS AND ABBREVIATIONS

101.1. DEFINITIONS

The following words and expressions, or pronouns used in their place, shall wherever they appear in this Contract be construed as follows, unless a different meaning is clear from the context:

Addendum, Bulletin or Letter of Clarification: Any additional contract provisions, or change, revisions or clarification of the contract documents issued in writing by the OWNER, to prospective bidders prior to the receipt of bids.

Advertisement: All of the legal publications pertaining to the work contemplated or under contract.

Approved, Directed, Required, and Words of Like Import: Whenever they apply to the work or its performance, the words “directed,” “required,” “permitted,” “ordered,” “designated,” “established,” “prescribed” and words of like import used in the contract, specifications or upon the drawings shall imply the direction, requirement, permission, order, designation or prescription of the OWNER; and “approved,” “acceptable,” “satisfactory” and words of like import shall mean approved by, acceptable to or satisfactory to the OWNER.

Backfill: embedment and final backfill

Base: a layer of specified material of plan thickness placed immediately below the pavement course surfacing.

Bedding: material upon which a pipe rests.

Bid: The written statement or statements duly filed with the OWNER specified in the advertisement for bids of these specifications by the person, persona, partnership, company, firm, association, or corporation proposing to do the work contemplated, including the approved form on which the formal bids for the work are to be prepared.

Bidder: Any person, persons, partnership, company, firm, association, or corporation acting directly or through a duly authorized representative submitting a bid for the work contemplated.

Bulletin: see Addendum.

Calendar Days: Any successive days of the week or month, no days being excepted. It shall be taken to mean the same as a normal calendar day.

Change Order: A properly authorized written order to the CONTRACTOR, signed by the OWNER directing an addition, deletion or revision in the work within the general scope of the contract documents, or authorizing an adjustment in the contract price or the contract time.

Completion Time: The time set forth in the contract for the performance and completion of the work contracted for. The time may be expressed as calendar days, working days or a specific date.

Conflict of Interest: A conflict of interest is when any person employed by bidder or bidder's company has any known business relationships, other than previous contracts awarded through a competitive bidding process, or has an existing relationship with any employee of the OWNER.

Construction Equipment: All machinery of 25 horsepower or more which is powered by an internal combustion engine, but which is not used solely for competition or as a motor vehicle subject to the requirements of Texas Transportation Code 502.002. This includes, but is not limited to, excavators, graders, generators, and similar equipment.

Contract or Contract Documents: Contract documents are all of the written, printed, typed and drawn instruments that comprise and govern the performance of the contract as defined herein. The contract and contract documents include the advertisement, instructions to bidders, proposal, addendum, specifications, including the general, special and technical conditions, provisions, plans or working drawings — and any change orders, or supplemental agreements pertaining to the work or materials thereof; and bonds and any additional documents incorporated by reference in the above.

Contract Price: The total monies payable to the CONTRACTOR under the terms and conditions of the contract documents. When used in such context, it may also mean the unit price of an item of work under the contract terms.

Contract Time: See “Completion Time”

Contract Work: Everything expressly or impliedly required to be furnished and done by the CONTRACTOR by any one or more parts of the contract documents, except “extra work” as hereinafter defined; it being understood that, in case of any inconsistency between any part or parts of this Contract, the OWNER shall determine which shall prevail in accordance with [Item 105.1](#). Contract Documents hereof.

Consulting Engineer: The person, firm, or entity hired as an independent consultant by the OWNER to design the Project and represent the OWNER in the administration of the CONTRACT in whatever capacity the OWNER designates; the OWNER may, at its sole option, designate the Consulting Engineer to be the Engineer for

purposes of administration of the CONTRACT. The Consulting Engineer shall be understood to be the Consulting Engineer of the OWNER, and nothing contained in the CONTRACT Documents shall be construed to make the Consulting Engineer an employee of the OWNER, nor shall they be construed to create any contractual or agency relationship between the Consulting Engineer and the CONTRACTOR. The term includes the officers, employees, associates, agents, and subconsultants of Consulting Engineer, if any.

CONTRACTOR: The person, persons, partnership, firm, corporation, association or organization, or any combination thereof, as an independent CONTRACTOR entering into the contract for the execution of the work, acting directly or through a duly authorized representative.

Other CONTRACTORS: Any CONTRACTOR, other than the CONTRACTOR or its SUBCONTRACTORS, who has a direct contract with the OWNER for work on or adjacent to the site of the work.

Days: See "Completion Time"

Deleterious: Substances, elements, or components are those that are damaging, harmful, undesirable, or adulterating to the integrity or purity of the specified base material.

Drawings or Contract Drawings: Only those drawings specifically entitled as such and as specified in the contract, or in any bulletin, or any detailed drawing furnished by the OWNER, pertaining or supplemental thereto.

Embedment: bedding and initial backfill.

Engineer: The Engineer or its duly authorized representative means the Engineer of the OWNER.

Equal: Materials, articles or methods which are of equal or higher quality than those specified or shown on the drawings and as further defined in [Item 106.1](#), Substitution of Materials, as determined by the OWNER.

Extra Work: Work other than that which is expressly or impliedly required by the Contract documents at the time of the execution of the Contract.

Final backfill: material required to fill the trench from the top of the initial backfill to ground elevation or subgrade of a street.

Hazardous Substance:

- (1) any asbestos or any material which contains any hydrated mineral silicate, including chrysotile, amosite, crocidolite, tremolite, anthophyllite, or actinolite, whether friable or non-friable;
- (2) any polychlorinated biphenyls (PCBs), or PCB-containing materials, or fluids;
- (3) radon; any other hazardous, radioactive, toxic, or noxious substance, material, pollutant, or solid, liquid or gaseous waste;
- (4) any pollutant or contaminant (including but not limited to petroleum, petroleum hydrocarbons, petroleum products, crude oil or any fractions thereof, any oil or gas exploration or production waste, any natural gas, synthetic gas or any mixture thereof, lead, or other toxic metals) which in its condition, concentration or area of release could have a significant effect on human health, the environment, or natural resources;
- (5) any substance that, whether by its nature or its use, is subject to regulation or requires environmental investigation, monitoring, or remediation under any federal, state, or local environmental laws, rules, or regulations;
- (6) any underground storage tanks, as defined in 42 U.S.C. Section 6991(1)(A)(I) (including those defined by Section 9001(1) of the 1984 Hazardous and Solid Waste Amendments to the Resource Conservation and Recovery Act, 42 U.S.C. Section 6901 et seq.; the Texas Water Code Annotated Section 26.344; and Title 30 of the Texas Administrative Code Sections 334.3 and 334.4), whether empty, filled or partially filled with any substance;
- (7) and any other hazardous material, hazardous waste, hazardous substance, solid waste, and toxic substance as those or similar terms are defined under any federal, state, or local environmental laws, rules, or regulations.

Initial backfill: material that covers the wastewater collection system and water lines.

Inspector: Any representative of the OWNER designated to inspect the work.

Letter of Clarification: see Addendum.

Low-Use Equipment: Any piece of equipment which is used for less than ten hours per week on a single public works contract.

Maintenance Bond: A bond executed by a corporate surety in accordance with Section 3503.002, Vernon's Texas Insurance Code, in the amount of the contract guaranteeing the prompt, full and faithful performance of the general guaranty and warranty contained in the Contract Documents.

Major Item: A major item is any line item of the work to be performed which amounts to 5 percent or more of the total contract amount.

Material Man or Supplier: Any SUBCONTRACTOR contracting with the CONTRACTOR, or any of its SUBCONTRACTORS, to fabricate or deliver or who actually fabricates or delivers, materials, supplies or equipment to be consumed or incorporated into the work.

Notice: Written notice effective the date of the postmark thereon, or if hand delivered, effective the date of hand delivery, or if electronically delivered, effective as described in [Item 105.8](#), Service of Notices.

OWNER: The public governmental agency identified throughout the contract documents or the entity as specifically identified in the contract. The term OWNER means the OWNER or its authorized representative(s).

OWNER's Representative: The Engineer or other duly authorized assistant, agent, inspector or superintendent acting within the scope of the particular duties instructed to him or her by the OWNER.

Payment Bond: A bond executed by a corporate surety in accordance with Section 3503.002, Texas Insurance Code and Chapter 2253, Texas Government Code, in the amount of the contract, solely for the protection and use of payment bond beneficiaries who have a direct contractual relationship with the general CONTRACTOR or a SUBCONTRACTOR to supply public work labor or material.

Performance Bond: A bond executed by a corporate surety in accordance with Section 3503.002, Texas Insurance Code and Chapter 2253, Texas Government Code, in the amount of the contract, solely for the protection of the OWNER, conditioned on the faithful performance of the work in accordance with the plans, specifications, and contract documents.

Plan or Plans: The plans are the drawings or reproductions therefrom made by or approved by the OWNER showing in detail the location, dimension and position of the various elements of the project, including such profiles, typical cross-sections, layout diagrams, working drawings, preliminary drawings and such supplemental drawings as the OWNER may issue to clarify other drawings or for the purpose of showing changes in the work hereinafter authorized by the OWNER. The plans are usually bound separately from the other parts of the Contract Documents, but they are part of the Contract Documents just as though they were bound therein.

Proposal: The written and signed offer of the bidder, when submitted on approved proposal forms, to perform the contemplated work and furnish the necessary material and labor in accordance with the provisions of the plans and specifications, special and general provisions, and all contract documents.

Site: The area upon or in which the CONTRACTOR's operations are carried on, and such other areas adjacent thereto as may be designated as such by the OWNER.

Special Provisions or Conditions: The special clauses of the contract, setting forth conditions or requirements peculiar to the specific project involved, supplementing the standard or general specifications and taking precedence over any conditions or requirements of the standard or general specifications with which they are in conflict.

Specifications or Contract Specifications: All of the general, special and technical conditions or provisions, and all addendum or supplements thereto.

Subbase: a layer of specified material of plan thickness between a base and a subgrade.

SUBCONTRACTORS: Any persons, firm or corporation, other than employees of the CONTRACTOR, who or which contracts with the CONTRACTOR to furnish, or who actually furnishes, labor and/or materials and equipment at or about the site.

Subgrade: that portion of the roadbed upon which the subbase, base or the pavement is to be placed. It includes the OWNER'S required distance beyond the back of the curb for streets, which are to be paved with concrete.

Superintendent: A person who has permission to act as an agent of the CONTRACTOR and has authority to issue both verbal and written agreements.

Sureties: The corporate bodies which are bound by such bonds as are required with and for the CONTRACTOR. The sureties engaged to be responsible for the entire and satisfactory fulfillment of the Contract, and for any and all requirements as set out in the specifications, Contract or plans. In order for a surety to be acceptable, the surety shall conform to the requirements of Section 3503.002, Texas Insurance Code.

Texas Low Emission Diesel (TxLED): Diesel fuel which is compliant with the TxLED program requirements as set forth by the TCEQ.

Work: All work including the furnishing of all labor, materials, tools, equipment, required submittals and incidentals to be performed by the CONTRACTOR under the terms of the contract.

Working Time: See "Completion Time"

Working Day: A working day is defined as a calendar day not including Saturdays, Sundays or those legal holidays as specified in the list prepared by the OWNER for contract purposes, in which weather or other

conditions not under the control of the CONTRACTOR shall permit the performance of the principal units of work underway for a continuous period of not less than seven hours between 7:00 am and 6:00 pm. A principal unit of work shall be that unit which controls the completion time of the contract.

101.2. ABBREVIATIONS AND ACRONYMS

References to specifications, standards, and guidelines throughout this text shall refer to the most current adopted versions. Wherever the abbreviations defined herein occur on the plans, in the specifications, contract, bonds, advertisement, proposal, or in any other document or instrument herein contemplated or to which the specifications apply or may apply, the intent and meaning shall be as follows:

%	Percent
'	Foot or Feet
"	Inch or Inches
#	Pound or pounds, or number if it precedes a numeral
AASHTO	American Association of State Highway and Transportation Officials
ABA	American Bankers Association
ACI	American Concrete Institute
am, a.m.	Before noon
ADA	Americans with Disabilities Act
ANSI	American National Standards Institute
Asph.	Asphalt
Assn.	Association
ASME	American Society of Mechanical Engineers
ASTM	American Society for Testing and Materials
APWA	American Public Works Association
AWPA	American Wood-Preservers' Association
AWS	American Welding Society
AWWA	American Water Works Association
B _c	Outside diameter of Pipe
B _d	Trench width
BMP	Best Management Practice
C	Centigrade
cc	Cubic Centimeter
CFR	Code of Federal Regulations
cfs	Cubic feet per second
CI	Cast Iron
CL	Center Line
cm	Centimeter
CO	Cleanout
C.O.C.	Cleveland Open Cup
Conc.	Concrete
Cond.	Conduit
Corr.	Corrugated
cSt	Centistokes (Viscosity)
Cu.	Cubic
Culv.	Culvert
CY, C.Y.	Cubic Yard
D	Inside Diameter
DI	Ductile Iron
Dia.	Diameter
Dr.	Driveway
Elev.	Elevation
F	Fahrenheit

FM	Factory Mutual
fps	Feet per second
Ft.	Foot or Feet
Gal.	Gallon
g, gm	Gram
HDPE	High Density Polyethylene
HP	Horsepower
Hr.	Hour
ID	Inside Diameter
in.	Inch or Inches
ISSA	International Slurry Surfacing Association
iSWM	Integrated Stormwater Management
Kg or kg	Kilogram
kPa	Kilopascals
L	Liter
Lb.	Pound or Pounds
LDPE	Low Density Polyethylene
LF.	Linear foot or feet
Lin.	Linear
LL	Liquid Limit
LLDPE	Linear Low Density Polyethylene
LMDPE	Linear Medium Density Polyethylene
LOI	Loss on Ignition
M	Meter
Max.	Maximum
MH	Manhole
Min.	Minimum or Minute
M.J.	Mechanical Joint
mm	Millimeter
Mod.	Modified
Mono.	Monolithic
mph	Miles per hour
MSS	Manufacturers Standardization Society of the Valve and Fittings Industry
MS4	Municipal Separate Storm Sewer System
MPa	Megapascal
MUTCD	(Texas) Manual on Uniform Traffic Control Devices
NACE	National Association of Corrosion Engineers
Nat'l	National
NEMA	National Electrical Manufacturers Association
No.	Number
N.P.T.	National Pipe Thread
NRMCA	National Ready-mixed Concrete
NSF	National Sanitation Foundation
o.d., OD	Outside Diameter
OSHA	Occupational Safety and Health Administration
oz.	Ounce
Pa	Pascal
PI, P.I.	Plasticity Index
pm, p.m.	After noon
psi	Pounds per Square Inch
PVC	Polyvinyl Chloride
PVCO	Molecularly Oriented PVC

R	Radius
RAP	Recycled/Reclaimed Asphalt Pavement
RCP	Reinforced Concrete Pipe
RCRA	Resource Conservation and Recovery Act
Reinf.	Reinforced or reinforcing
Rem.	Remove
Rep.	Replace
R/W, ROW,	Right-of-Way
R of W	
Sani., San.	Sanitary
Sec.	Second
S.F.	Square Foot or Saybolt Furol (Viscosity)
Sq.	Square
SSPC	The Society for Protective Coatings [formerly Steel Structures Painting Council]
St.	Street or Storm
Std.	Standard
Str.	Strength
SWPPP	Storm Water Pollution Prevention Plan
SY	Square Yard
TAC	Texas Administrative Code
TAS	Texas Accessibility Standards
Tex-###-X	Refer to TxDOT <i>Manual of Testing Procedures</i>
TCEQ	Texas Commission on Environmental Quality [formerly Texas Natural Resource Conservation Commission (TNRCC)]
TDLR	Texas Department of Licensing and Regulations
TMUTCD	Texas Manual on Uniform Traffic Control Devices
TxDOT	Texas Department of Transportation
TxDOT Item #	Refer to TxDOT <i>Standard Specifications for Construction of Highways, Streets and Bridges</i>
UL	Underwriter's Laboratory
um, µm	Micrometers
US, U.S.	United States
U.S.C.	United States Code
USEPA	United States Environmental Protection Agency
Vert.	Vertical
Vol.	Volume
Wt.	Weight
Yd.	Yard

ITEM 102. PROPOSAL PROCEDURES

102.1. PROPOSAL FORM

The OWNER shall furnish bidders with proposal forms which shall state the general location and description of the contemplated work and which shall contain an itemized list of the items of work to be done or materials to be furnished, and upon which bid prices are asked. The proposal form shall specify the form and amount of the proposal guaranty.

102.2. QUANTITIES IN PROPOSAL FORM

The quantities of the work and materials set forth in the proposal form or on the plans approximately represent the work to be performed and materials to be furnished, and are for the purpose of comparing the bids on a uniform basis. Payment shall be made to the CONTRACTOR only for the actual quantities of work performed or materials furnished as measured in the field or otherwise determined by the OWNER in accordance with the Contract; and it is understood that the quantities may be increased or decreased as hereinafter provided, without in any way invalidating the bid prices.

102.3. EXAMINATION OF PLANS, SPECIFICATIONS AND SITE OF THE WORK

Bidders are advised that the plans, specifications and other documents on file as stated in the advertisement shall constitute all the information, which the OWNER shall furnish. Bidders are required, prior to submitting any proposal, to review the plans and read the specifications, proposal, Contract and bond forms carefully; to obtain and read the most current versions of all referenced State, Federal, and National standards; to visit the site of the work; to examine carefully local conditions; to inform themselves by their independent research, tests and investigations of the difficulties to be encountered and judge for themselves the accessibility of the work and all attending circumstances affecting the cost of doing the work or time required for its completion; and to obtain all information required to make a proposal.

No information given by the OWNER or any official thereof, other than that shown on the plans and contained in the specifications, proposals and other Contract documents, shall be binding upon the OWNER. Bidders shall rely exclusively upon their own estimates, investigations, tests and other data, which are necessary for full and complete information upon which the proposal may be based. Any bidder, by submitting a bid, represents and warrants: that it has prepared the bid in accordance with the specifications, with full knowledge and understanding of the terms and provisions thereof; that it has done any inspection or test it deems appropriate; that it has reviewed, studied and examined its bid prior to the signing and submission of same; and that it was cognizant of the terms of its proposal, verified its calculations and found them to be correct and agrees to be bound thereby.

102.4. PREPARATION OF PROPOSAL

The bidder shall submit its proposal on the forms furnished or approved by the OWNER. All blank spaces in the form shall be correctly filled in and the bidder shall state the prices, both in words and numerals, for which it proposes to do the work contemplated or furnish the material required. Such prices shall be written in ink distinctly and legibly or submitted electronically if allowed by OWNER. In cases of discrepancy, the OWNER shall select the one most favorable to the OWNER, provided that it does not create a material mistake in the bid or otherwise change the result of bidding. If an individual submits the proposal, that individual or duly authorized agent must sign the proposal. If an association or partnership submits the proposal, the name and address must be given and the proposal signed by a duly authorized member of the association or partnership. If a corporation submits the proposal, the corporate name and business address must be given and the proposal signed by a duly authorized corporate officer or agent. Powers of attorney authorizing agents to sign the proposal must be properly certified and must be in writing and submitted with the proposal. The proposal shall be executed in ink. When allowed by the bid documents, bids by internet, electronic mail or facsimile are acceptable as long as all legal and bid requirements are met. The CONTRACTOR accepts all risks associated with bidding in this manner. It is understood and agreed that the proposal may not be withdrawn once the bid-opening process has begun.

102.4.1. Safety Record. If the safety record is part of the bid requirements in accordance with Section 252.0435, Local Government Code, each CONTRACTOR bidding on projects must submit a notarized

affidavit with its bid attesting to its safety record. This information may be considered in determining the responsibility of the bidder for purposes of award.

102.5. PROPOSAL GUARANTY

No proposal shall be considered unless it is accompanied by a cashier's check on any state or national bank or acceptable bidder's surety bond, as specified in [Item 103](#). Award and Execution of Contract, payable unconditionally to the OWNER. The cashier's check or bidder's surety bond shall be in the amount of not less than five percent of the total amount of the bid. The proposal guaranty is required by the OWNER as evidence of good faith and as a guarantee that if awarded the Contract, the bidder shall execute the Contract and furnish the required bonds and evidence of insurance within 10 days after receipt of the awarded Contract or pay the damages as set forth below. The bidder's surety bond shall be conditioned that, if the proposal is withdrawn after the bids have been opened or the CONTRACTOR refuses to execute the Contract in accordance with its proposal and provide the required surety bonds, the CONTRACTOR and the surety shall become liable to the OWNER for the amount of the bidder's surety bond.

In the event a cashier's check is submitted along with the proposal of the bidder, and the CONTRACTOR does not execute the Contract and provide the required surety bonds and evidence of insurance within 10 days after receipt of the awarded Contract, or withdraws its bid after bids have been opened, the OWNER shall be entitled to the proceeds of such check.

102.6. FILING OF PROPOSALS

No proposal shall be considered unless it is filed at the place and within the time limit for receiving proposals as stated in the advertisement and/or Notice to Bidders or any addendum. Each proposal shall be in a sealed envelope, plainly marked with the word "Proposal" and the name or description of the project as designated in the advertisement.

102.7. WITHDRAWING PROPOSALS

Proposals filed with the OWNER can be withdrawn or modified and redeposited prior to the time set for opening proposals. Request for non-consideration of proposals must be made in writing addressed to the OWNER prior to the time set for opening proposals. After other proposals are opened and publicly read, the proposal for which non-consideration is properly requested will be returned unopened. The proposal may not be withdrawn after the bid opening has commenced. The bidder, in submitting the same, warrants and represents that its bid has been carefully reviewed and checked and that it is in all things true and accurate and free of mistakes and that such bid shall not and cannot be withdrawn after opening because of any mistake committed by the bidder; provided, however, that any bidder may withdraw its bid 90 days after the actual date of opening thereof, should no award have been made to such bidder.

102.8. OPENING PROPOSALS

The proposals filed with the OWNER shall be opened at the time stated in the advertisement and/or in the Notice to Bidders or any subsequently issued addendum, and publicly read aloud, and shall thereafter remain on file with the OWNER. No Contract shall be awarded based on such proposals until after at least two days have elapsed.

102.9. CONSIDERATION OF PROPOSAL

After proposals are opened, the proposals shall be tabulated for comparison on the basis of the bid prices and quantities shown in the proposal. Until final award of the Contract, the OWNER reserves the right to reject any or all proposals, to waive technicalities or irregularities at its option, to re-advertise for new proposals or proceed to do the work otherwise in the best interests of the OWNER. Each bidder shall be furnished a copy of the bid tabulation upon request.

102.10. IRREGULAR PROPOSALS

Proposals shall be considered irregular if they show any omissions, alterations of form, additions, unbalanced values or conditions not called for, unauthorized alternate bids or other irregularities of any kind. The OWNER may reject any proposal containing any such irregularity. The OWNER, however, reserves the right to waive any irregularities and to make the award in the best interest of the OWNER.

The BIDDER or CONTRACTOR shall not take advantage of any error in the bidding or contract documents. Anything mentioned in the specifications and not shown on the drawings, or shown on the drawings and not mentioned in the specifications, shall be of like effect as if shown in or mentioned in both. In the case of any apparent difference between the drawings and specifications, or any other apparent error which the BIDDER or the CONTRACTOR may discover, the BIDDER or CONTRACTOR shall refer the matter to the OWNER, to which the decision of the OWNER shall govern. The OWNER shall have the right to correct any error discovered.

102.11. REJECTION OF PROPOSALS

The OWNER reserves the right to reject any or all proposals; and all proposals submitted are subject to this reservation. Proposals may be rejected for any of the following reasons, but not necessarily limited thereto:

- (1) proposal received after the time limit for receiving proposals as stated in the advertisement or any subsequently issued addendum;
- (2) proposal unaccompanied by the required bid security;
- (3) proposal constituting a nonresponsive bid;
- (4) proposal containing unsolicited conditions or qualifications;
- (5) failure to use the OWNER'S form of bid bond in submitting proposal, if included in the bid documents; or
- (6) a proposal submitted with a bid bond issued by a surplus line company or by a surety not licensed to transact insurance business in the State of Texas.
- (7) In the judgment of the OWNER, the proposal is incomplete.
- (8) All rejections shall be final.
- (9) The OWNER has the right to reject any and all bids and to accept or reject any and all schedules.

102.12. DISQUALIFICATION OF BIDDERS

Bidders may be disqualified and their proposal not considered for any of the following reasons, but not necessarily limited thereto:

- (1) reasonable belief that collusion exists among the bidders;
- (2) reasonable belief that any bidder is interested in more than one proposal for the work contemplated;
- (3) the bidder having a history of filing frequent, excessive, meritless, or fraudulent claims against the OWNER, or against other CONTRACTORS on a project of the OWNER, or against other OWNERS or CONTRACTORS;
- (4) the bidder or its surety having defaulted on a previous contract, or the bidder performing poorly on a previous or current contract;
- (5) lack of competency, skill, judgment, financial capability, resources, integrity, reputation, reliability or responsibility to perform the work as revealed by the bid proposal, bid questionnaires, financial statement, performance history or other relevant information obtained by the OWNER.
- (6) uncompleted work which in the judgment of the OWNER shall prevent or hinder the prompt completion of additional work if awarded;
- (7) failure of bidder to use OWNER'S form of bid bond in submitting its bid, or submission of a cashier's check drawn on a state or national bank not located in the OWNER'S jurisdictional area;
- (8) unbalanced value of any bid items;
- (9) the bidder is currently a party to any litigation against the OWNER.
- (10) bidder's unexcused failure to properly and/or timely complete a project with the OWNER.
- (11) the OWNER'S decision that the bidder is disqualified shall be final.

102.13. RETURN OF PROPOSAL GUARANTY

Upon request, the OWNER shall return the proposal guaranties accompanying all proposals (except for the three apparent low proposals, or per policy of the OWNER. The three apparent low proposal guaranties shall be retained by the OWNER until the required Contract and surety bonds have been executed, after which they shall be returned.

ITEM 103. AWARD AND EXECUTION OF CONTRACT

103.1. CONTRACTOR'S WARRANTIES AND UNDERSTANDING

In consideration of, and to induce the award of this Contract to it, the CONTRACTOR represents and warrants:

- (1) that it is financially solvent, and sufficiently experienced and competent to perform the work;
- (2) that the facts stated in the proposal and the information given by it pursuant to the bidding documents are true and correct in all respects;
- (3) that it has read, understood and complied with all the requirements set forth in the bidding documents;
- (4) that it is familiar with and understands all laws and regulations applicable to the work; and
- (5) unless otherwise specifically provided for in the Contract documents, the CONTRACTOR shall do all the work and shall furnish all the tools, equipment, machinery, materials, supplies, labor and appliances, except as herein otherwise specified, necessary or proper for performing and completing the work required by this Contract, in the manner and within the time herein prescribed.

By executing the Contract, the CONTRACTOR represents that it has visited the site of work, has fully familiarized itself with the local and on-site conditions under which the work is to be performed and has correlated its observation with the requirements of the Contract documents. In addition, the CONTRACTOR represents that it has satisfied itself as to subsurface conditions at the site of the work. Information, data and representations contained in the Contract documents pertaining to the conditions at the site, including subsurface conditions, are for information only and are not warranted or represented in any manner to accurately show the conditions at the site of the work. The CONTRACTOR agrees that it shall make no claims for damages; additional compensation or extension of time against the OWNER because of encountering actual conditions in the course of the work, which vary or differ from conditions or information, contained in the Contract documents. Except as provided in [Item 107.24](#), Existing Structures, Facilities and Appurtenances, all risks of differing subsurface conditions shall be borne solely by the CONTRACTOR.

CONTRACTOR assumes all risks for differing site conditions, and all risks and costs.

Unless otherwise stated in the Contract, the CONTRACTOR agrees that all or a portion of the work required by this Contract is a governmental function of the OWNER.

103.2. AWARD OF CONTRACT

The OWNER will attempt to award the Contract within 90 days after the opening of proposals. The award, if made, shall be to the lowest responsible bidder; but in no case shall the award be made until after investigations are made as to the responsibility of the bidder to whom it is proposed to award the Contract. If awarded the Contract, the bidder shall execute the Contract and furnish the required bonds and evidence of insurance within 10 days after receipt of the awarded Contract.

103.3. SURETY BONDS

103.3.1. CONTRACTOR Surety Bonds. With the execution and delivery of the Contract, the CONTRACTOR shall furnish and file with the OWNER in the amounts herein required, the surety bonds specified hereunder. Without exception, the OWNER'S bond forms must be used, and exclusive venue for any lawsuit in connection with such bonds shall be specified as the county in which the OWNER'S principal office is located. Such surety bonds shall be in accordance with the provisions of Texas Government Code, Chapter 2253, as amended, and Section 3503.002 of the Insurance Code, as amended. These bonds shall automatically be increased by the amount of any change order or supplemental agreement which increases the Contract price with or without notice to the surety, but in no event shall a change which reduces the Contract amount reduce the penal amount of such bonds. If performance and payment bond forms are included in the bid documents, these forms shall be used with this Contract.

103.3.1.1. Performance Bond. A good and sufficient bond in an amount not less than 100-percent of the approximate total amount of the Contract, as evidenced by the proposal tabulation, or, conditioned on the faithful performance of the work in accordance with the plans, specifications and Contract documents, including performance of any guarantees or warranties required by OWNER, and including any extensions thereof, for the protection of the OWNER. This bond shall provide for the repair and/or replacement of all defects due to faulty materials and workmanship that appear within a period of one

year from the date of completion and acceptance of the improvement by the OWNER or such lesser or greater period as may be designated in the Contract documents.

103.3.1.2. Payment Bond. A good and sufficient bond in an amount not less than 100-percent of the approximate total amount of the Contract, as evidenced by the proposal tabulation, or otherwise solely for the protection and use of payment bond beneficiaries who have a direct contractual relationship with the prime CONTRACTOR or a SUBCONTRACTOR to supply public work labor or material.

103.3.1.3. Additional or Substitute Bonds. If at any time the OWNER is or becomes dissatisfied with any surety on a performance or payment bond, the CONTRACTOR shall, within five days after notice from the OWNER to do so, substitute an acceptable bond (or bonds), or provide an additional bond, in such form and sum and signed by such other surety or sureties as may be satisfactory to the OWNER. The premiums on such bonds shall be paid by the CONTRACTOR without recourse to the OWNER. No further payments under the Contract shall be deemed due or payable until the substitute or additional bonds have been furnished to and accepted by the OWNER.

103.3.1.4. Bond Amounts Based on Contract Amount. If the amount of the Contract, including OWNER -accepted alternates and allowances, if any, is greater than \$100,000, Performance and Payment Bonds in 100% of the Contract amount are mandatory and shall be provided by the bidder receiving the award. If the Contract amount is greater than \$50,000 but less than or equal to \$100,000, only a Payment Bond in 100% of the Contract amount is mandatory; provided, however, that the bidder receiving the award may elect to furnish a Performance Bond in the same amount if the bidder so chooses. If the Contract amount is less than or equal to \$50,000, the bidder receiving the award may elect not to provide Performance and Payment Bonds; provided that in such event, no money will be paid to the CONTRACTOR until final completion and acceptance of all work by OWNER. If the bidder receiving the award elects to provide Performance and Payment Bonds in 100% of the Contract amount, progress payments will be disbursed in accordance with the applicable Contract provisions.

103.3.2. Developer Surety Bonds. In order to insure that it might not incur liabilities, an OWNER may require, before it gives approval of the plans for development, that the OWNER of said development shall provide sufficient surety bond(s) to guarantee that claims against such development, in the event of default, shall be satisfied. Model Forms A.10, through A.13, for private development are in Appendix A. Claimants may also seek recovery by other means.

103.3.3. Sureties. No sureties shall be accepted by the OWNER who are now in default or delinquent on any bonds or who are interested in any litigation against the OWNER. All bonds shall meet the applicable requirements of Section 3503.002, Texas Insurance Code and Chapter 2253, Texas Government Code, shall be made on forms furnished by the OWNER, and shall be executed by not less than one corporate surety authorized to do business in the State of Texas and acceptable to the OWNER. The Texas Insurance Board can be contacted at 800-578-4677. Each bond shall be executed by the CONTRACTOR and surety. Each surety shall designate on the bond the name, address and phone number of a representative for the surety located in a county of the State of Texas acceptable to the OWNER to whom any requisite notices may be delivered and on whom service of process may be had in matters arising out of such suretyship. The OWNER reserves the right to reject any and all sureties.

103.4. INSURANCE

Any insurance policies required under this [Item 103.4](#). Insurance may be written in combination with any of the others, where legally permitted, but none of the specified limits may be lowered thereby.

103.4.1. CONTRACTOR'S Insurance. Without limiting any of the other obligations or liabilities of the CONTRACTOR, during the term of the Contract the CONTRACTOR and each SUBCONTRACTOR at its own expense shall purchase and maintain the herein stipulated minimum insurance with companies duly approved to do business in the State of Texas and satisfactory to the OWNER. In no case shall the insurance be less than that specified in the contract by the OWNER. Certificates of each policy and a copy of each policy shall be delivered to the OWNER before any work is started, along with a written statement from the issuing company stating that said policy shall not be canceled, renewed or materially changed without 30 days advance written notice being given to the OWNER, except when the policy is being canceled for nonpayment of

premium, in which case 10 days advance written notice is required. Prior to the effective date of cancellation, the CONTRACTOR must deliver to the OWNER a replacement certificate of insurance or proof of reinstatement. A model Certificate of Insurance is illustrated in Model Form A.6. in Appendix A. Coverage shall be of the following types and not less than the specified amounts:

103.4.1.1. Worker's Compensation. Workers' compensation as required by Texas law, with the policy endorsed to provide a waiver of subrogation as to the OWNER; employer's liability insurance of not less than \$100,000 for each accident, \$100,000 disease - each employee, \$500,000 disease - policy limit.

103.4.1.2. Commercial General Liability. Commercial general liability insurance, including independent CONTRACTOR'S liability, completed operations and contractual liability, covering, but not limited to, the liability assumed under the indemnification provisions of this Contract, fully insuring CONTRACTOR'S (or SUBCONTRACTOR'S) liability for injury to or death of OWNER'S employees and third parties, extended to include personal injury liability coverage with damage to property of third parties, with minimum limits as set forth in Table 103.4.1.2.(a) General Liability Insurance Minimum Coverage.

The policy shall include coverage extended to apply to completed operations, asbestos hazards (if this project involves work with asbestos) and XCU (explosion, collapse and underground) hazards. The completed operations coverage must be maintained for a minimum of one year after final completion and acceptance of the work, with evidence of same filed with OWNER.

Table 103.4.1.2.(a) General Liability Insurance Minimum Coverage

General Aggregate	\$1,000,000
Products - Components/Operations Aggregate	\$1,000,000
Personal and Advertising Injury	\$ 600,000
Each Occurrence	\$ 600,000
Fire Damage (any one fire)	\$ 50,000
Medical Expense (any one person)	\$ 5,000

103.4.1.3. Automobiles. Comprehensive automobile and truck liability insurance, covering owned, hired and non-owned vehicles, with a combined bodily injury and property damage minimum limit of \$600,000 per occurrence; or separate limits of \$250,000 for bodily injury (per person), \$500,000 for bodily injury (per accident) and \$100,000 for property damage. Such insurance shall include coverage for loading and unloading hazards.

103.4.2. OWNER'S Protective Liability Insurance. CONTRACTOR shall obtain, pay for and maintain at all times during the prosecution of the work under this Contract an OWNER'S protective liability insurance policy naming the OWNER and the Engineer as insureds for property damage and bodily injury, which may arise in the prosecution of the work or CONTRACTOR'S operations under this Contract. Coverage shall be on an "occurrence" basis, and the policy shall be issued by the same insurance company that carries the CONTRACTOR'S liability insurance with a combined bodily injury and property damage minimum limit of \$600,000 per occurrence and \$1,000,000 aggregate.

103.4.3. "Umbrella" Liability Insurance. If required by OWNER, CONTRACTOR shall obtain, pay for and maintain umbrella liability insurance during the Contract term, insuring CONTRACTOR for an amount of not less than \$1,000,000 per occurrence combined limit for bodily injury and property damage that follows form and applies in excess of the primary liability coverages required hereinabove. The policy shall provide "drop down" coverage where underlying primary insurance coverage limits are insufficient or exhausted. OWNER and Engineer shall be named as additional insureds.

103.4.4. Railroad Protective Insurance. When required in the Special Provisions, CONTRACTOR shall obtain, maintain and present evidence of railroad protective insurance (RPI). The policy shall be in the name of the railroad company having jurisdiction over the right-of-way involved. The minimum limit of coverage shall meet the specifications provided by the railroad company. The OWNER shall specify the amount of RPI necessary.

103.4.5. Policy Endorsements and Special Conditions

103.4.5.1. Endorsements. Each insurance policy to be furnished by CONTRACTOR shall include the following conditions by endorsement to the policy:

- (1) each policy shall name the OWNER as an additional insured as to all applicable coverage;
- (2) each policy shall require that 30 days prior to the cancellation, nonrenewal or any material change in coverage, a notice thereof shall be given to OWNER by certified mail. If the policy is canceled for nonpayment of premium, only 10 days written notice to OWNER is required;
- (3) the term "OWNER" shall include all authorities, boards, bureaus, commissions, divisions, departments and offices of the OWNER and individual members, employees and agents thereof in their official capacities and/or while acting on behalf of the OWNER;
- (4) the policy phrase "other insurance" shall not apply to the OWNER where the OWNER is an additional insured on the policy; and
- (5) all provisions of the Contract concerning liability, duty and standard of care together with the indemnification provision, shall be underwritten by contractual liability coverage sufficient to include such obligations within applicable policies.

103.4.5.2. Insurance Requirements. Insurance furnished by the CONTRACTOR shall be in accordance with the following requirements:

- (1) any policy submitted shall not be subject to limitations, conditions or restrictions deemed inconsistent with the intent of the insurance requirements to be fulfilled by the CONTRACTOR. The OWNER'S decision thereon shall be final;
- (2) all policies are to be written through companies duly licensed to transact that class of insurance in the State of Texas; and
- (3) all liability policies required herein shall be written with an "occurrence" basis coverage trigger.

103.4.5.3. CONTRACTOR Agreements. CONTRACTOR agrees to the following:

- (1) CONTRACTOR hereby waives subrogation rights for loss or damage to the extent same are covered by insurance. Insurers shall have no right of recovery or subrogation against the OWNER, it being the intention that the insurance policies shall protect all parties to the Contract and be primary coverage for all losses covered by the policies;
- (2) companies issuing the insurance policies and CONTRACTOR shall have no recourse against the OWNER for payment of any premiums or assessments for any deductibles, as all such premiums and deductibles are the sole responsibility and risk of the CONTRACTOR;
- (3) approval, disapproval or failure to act by the OWNER regarding any insurance supplied by the CONTRACTOR (or any SUBCONTRACTORS) shall not relieve the CONTRACTOR of full responsibility or liability for damages and accidents as set forth in the Contract documents. Neither shall the bankruptcy, insolvency or denial of liability by the insurance company exonerate the CONTRACTOR from liability; and
- (4) no special payments shall be made for any insurance that the CONTRACTOR and SUBCONTRACTORS are required to carry; all are included in the Contract price and the Contract unit prices.
- (5) approval, disapproval or failure to act by OWNER regarding any insurance supplied by CONTRACTOR or its SUBCONTRACTORS shall not relieve CONTRACTOR of full responsibility or liability for damages, errors, omissions or accidents during the term of the Contract.

103.5. EXECUTION OF CONTRACT

103.5.1. OWNER AND CONTRACTOR Responsibilities. The CONTRACTOR shall within 10 business days after receipt of the Contract sign the necessary agreements entering into the required Contract with the OWNER. No Contract shall be binding on the OWNER until all authorized signatures required by law have been affixed and the executed Contract delivered to the CONTRACTOR.

103.5.2. Failure to Execute. The failure of the CONTRACTOR to execute the Contract or provide the required statutory surety bonds within 10 business days after the Contract is received shall constitute a breach of its proposal and the OWNER may annul the award and retain the proceeds of the bid security. In the event the OWNER should re-advertise for bids, the defaulting CONTRACTOR may not be eligible to bid.

103.6. NOTICE TO PROCEED AND COMMENCEMENT OF WORK

Upon OWNER receipt of the executed Contract and the required insurance and surety bonds, a notice to proceed shall be issued by the OWNER indicating the date upon which the Contract time shall start and the projected date of completion. The OWNER will attempt to provide the notice to proceed within the time specified in the plans. The CONTRACTOR shall commence work within 10 days from the date specified in the written notice to proceed. No work shall commence before the notice to proceed has been issued. Unless otherwise specified in the contract, there shall be a preconstruction meeting between the OWNER and CONTRACTOR prior to the commencement of work.

103.7. DELAY OF CONTRACT

The CONTRACTOR shall not be entitled to any claim for damages due to delay in the award or notice to proceed. If the CONTRACTOR encounters any delay occasioned by the OWNER'S failure or inability to obtain right-of-way or is delayed by the relocation or removal of any of the utilities or other installations of similar kind, the CONTRACTOR shall not be entitled to any claim for damages by virtue of any delay. Should the OWNER unreasonably delay the issuance of the notice to proceed through no fault of the CONTRACTOR, the CONTRACTOR shall be entitled only to an extension of Contract time, the Contract amount to remain unchanged. The OWNER has the right to reject any and all bids and to accept or reject any and all schedules. At such time as actual construction has been started, the work will not be stopped or delayed without written permission of the OWNER, excluding delays caused by adverse weather conditions. The CONTRACTOR shall maintain at all times sufficient equipment and personnel on the project to produce satisfactory progress during the construction period.

103.8. ORDER OF WORK TO BE PERFORMED

After a contract has been awarded and before the "Notice to Proceed" is issued, the OWNER reserves the right to prioritize the order of the Work to be performed.

ITEM 104. SCOPE OF WORK

104.1. INTENT OF CONTRACT DOCUMENTS

The intent of the documents, unless otherwise specifically provided, is to produce complete and finished work, which the CONTRACTOR undertakes to do in full compliance with the Contract documents. It is not intended to mention every item of work in the specifications that can be adequately shown on the drawings nor to show on the drawings all items of work described or required by the specifications. All materials or labor for work shown on the drawings or reasonably inferable therefrom as being necessary to produce a finished job shall be provided by the CONTRACTOR whether or not same is expressly covered in the specifications. No verbal conversation, understanding or agreement with any officer or employee or agent of the OWNER, either before or after the execution of the Contract, shall affect or modify any of the terms, conditions or obligations contained in the Contract documents.

The CONTRACTOR shall do all work as provided in the plans, specifications, special provisions, bid and contract, and shall do such additional extra work as may be considered necessary to complete the work in a satisfactory manner acceptable to the OWNER. The CONTRACTOR shall furnish all labor, tools, materials, machinery, equipment, and incidentals necessary to the satisfactory prosecution and completion of the work.

104.1.1. Arrangement of Specifications and Headings. The inclusion of any particular specification in the various sections and divisions of these specifications does not indicate that it is applicable only to work specified within that section. For any particular item of work on any type of project, the specification describing that item shall govern regardless of the section of these specifications within which it is included. The specifications included herein are grouped together for convenience only and not for the purpose of restricting the application of any specification.

The titles and headings contained in the contract documents and the subject organization are used only to facilitate reference, and in no way define or limit the scope or intent of any of the provisions of this contract.

104.2. CHANGE OR MODIFICATION OF CONTRACT

104.2.1. Increased or Decreased Quantities of Work. The OWNER reserves the right to make changes in the quantities of the work, as may be considered necessary or desirable, and such changes shall not be considered as waiving or invalidating any conditions or provisions of the Contract or bonds. The CONTRACTOR shall perform the work as altered, whether increased or decreased, and no allowances shall be made for anticipated profits.

The OWNER reserves the right to decrease the work under this Contract. Payment to the CONTRACTOR for the Contract items shall be made for the actual quantities of work performed and material furnished at the unit prices set forth in the Contract, except as provided below.

When the quantity of work to be done or of materials to be furnished under any major item of the Contract is more than 125 percent of the quantity stated in the Contract, then either party to the Contract, upon demand, shall be entitled to negotiate for revised consideration on the portion of work above 125 percent of the quantity stated in the Contract.

When the quantity of work to be done or of materials to be furnished under any major item of the Contract is less than 75 percent of the quantity stated in the Contract, then either party to the Contract, upon demand, shall be entitled to negotiate for revised consideration on the work performed.

Any revised consideration shall be paid for as is hereinafter provided under [Item 109.3](#). Payment for Extra Work. The foregoing notwithstanding, the total original Contract amount shall not be increased more than 25 percent; the CONTRACTOR, by submission of a bid and execution of the Contract, is deemed to consent to the OWNER'S right to reduce the total original Contract amount by more than 25 percent.

The Contract amount or the Contract time can only be increased or decreased by a properly written change order.

104.2.2. Alteration of Plans and Specifications. The OWNER reserves the right to make such changes in the plans and specifications and in the character of the work as may be necessary or desirable to insure completion in the most satisfactory manner, provided such changes do not materially alter the original plans and specifications or change the general nature of the work as a whole. Such changes shall not be

considered as waiving or invalidating any condition or provision of the Contract and bonds. Such changes shall be issued by the OWNER.

104.2.3. Extra Work. When any work is necessary to the proper completion of the project and for which no prices are provided for in the proposal and Contract, the CONTRACTOR shall do such work, but only when and as ordered in writing by the OWNER. Extra Work is further explained in [Item 109.3](#). Payment for Extra Work and [Item 104.3](#). Disputed Work and Claims for Additional Compensation. Payment for Extra Work shall be made as hereinafter provided in [Item 109.3](#). Payment for Extra Work. No work shall be undertaken which requires extra payment without having an executed change order approved by the CONTRACTOR and the OWNER, except when so ordered in writing.

104.2.4. Finality of Change Orders. In addition to the OWNER, the CONTRACTOR shall sign the Change Order Documents to verify the terms and conditions established by the Change Order; however, failure or refusal of the CONTRACTOR to sign a Change Order shall not relieve the CONTRACTOR of its obligation to execute the proposed changes in accordance with this Item and the other terms and provisions of this Contract. Each Change Order shall be specific and final as to prices and the extension of time, if any, and no reservations or other provisions allowing for future additional money or time as a result of the particular changes identified and fully compensated in the Change Order.

104.2.5. General Claim Procedures. Except where otherwise provided in the Contract Documents, claims by the CONTRACTOR, whether for damages, additional compensation, additional time or other reasons must be made by written notice to the OWNER within fourteen days after occurrence of the event or events giving rise to the particular claim. Every claim, whether for damages, additional compensation, additional time or other reasons shall be signed and sworn to by an authorized corporate officer (if not a corporation, then an official of the company authorized to bind the CONTRACTOR by his or her signature) of the CONTRACTOR, verifying the truth and accuracy of the claim. Such verification shall be a condition precedent to the acceptability of any claim asserted by the CONTRACTOR. The CONTRACTOR shall be deemed to have waived any claim not made strictly in accordance with the procedure and time limits set out in this paragraph.

104.3. DISPUTED WORK AND CLAIMS FOR ADDITIONAL COMPENSATION

If the CONTRACTOR is of the opinion that:

- (1) certain work necessary or required to accomplish the result intended by this Contract or certain work ordered to be done as contract work by the OWNER is actually Extra Work and not CONTRACTOR work, or
- (2) any determination or order of the OWNER violates the terms and provisions of this Contract, then the CONTRACTOR shall promptly, either before proceeding with such work or complying with such order or determination, notify the OWNER in writing of its contentions with respect thereto and request a final determination by the OWNER. Such determination of the OWNER shall be given in writing to the CONTRACTOR. If the OWNER determines that the work in question is Extra Work and not Contract work, or that the order complained of requires performance by the CONTRACTOR beyond that required by the Contract or violates the terms and provisions of the Contract, thereupon the OWNER shall cause either (a) the issuance of a change order covering the Extra Work as provided for in [Item 104.2](#). Change or Modification of Contract hereof, or (b) the determination or order complained of to be rescinded or so modified so as to not require performance beyond that required by the terms and provisions of the Contract.

If the OWNER determines that the work in question is Contract Work and not Extra Work, or that the determination or order complained of does not require performance by the CONTRACTOR beyond that required by the Contract or violate the terms and provisions of the Contract, the OWNER shall direct the CONTRACTOR to proceed, and the CONTRACTOR must promptly comply. In order to reserve its right to claim compensation for such work resulting from such compliance, however, the CONTRACTOR must, within fourteen (14) days after receiving the OWNER's determination and direction, notify the OWNER in writing that the work is being performed, or that the determination and direction is being complied with, under protest. If the OWNER is properly notified of a protest by the CONTRACTOR, then the cost of such disputed work shall be accounted for in accordance with the force account method described in [Item 109.3.3](#). Force Account Work. Payment, if any is due, shall be made when the OWNER makes a final determination regarding the merit of the CONTRACTOR's protest. The final determination of the cost

of disputed work under this method, or of any issue regarding the merits of a protest, is not waived by the OWNER'S issuance of any Change Order providing for the funding of the disputed work.

If the CONTRACTOR fails to so appeal to the OWNER for a determination or, having so appealed, should the CONTRACTOR thus fail to notify the OWNER in writing of its protest, the CONTRACTOR shall be deemed to have waived any claim for extra compensation of damages therefore. No oral appeals or oral protests, no matter to whom made, shall be deemed even substantial compliance with the provisions of this item.

A delay of the CONTRACTOR due to a court order against the OWNER, or due to the OWNER'S failure to secure right-of-way at the time required or because of a conflict of a utility with the work, shall not be cause for additional compensation for damages sustained by the CONTRACTOR, but may be a cause for extension of Contract working time only.

In addition to the foregoing requirements, the CONTRACTOR shall, upon notice from the OWNER, produce for examination and audit at the CONTRACTOR'S office, by the representatives of the OWNER, all its books and records showing all of its acts and transactions in connection with contractual performance as well as relating to or arising by reason of the matter in dispute. At such examination a duly authorized representative of the CONTRACTOR may be present.

Unless the aforesaid requirements and conditions shall have been complied with by the CONTRACTOR, the OWNER shall be released from all claims arising under, relating to or by reason of this Contract, except for the sums to be due under the payment provisions of this Contract. It is further stipulated and agreed that no conduct on the part of the OWNER or any agent or employee of the OWNER shall ever be construed as a waiver of the requirements of this section, when such requirements constitute an absolute condition precedent to any approval of any claim for extra compensation, notwithstanding any other provisions of the Contract documents; and in any action against the OWNER to recover any sum in excess of the Contract amount, the CONTRACTOR must allege and prove strict compliance with the provisions of this section.

In connection with the examination provided for herein, the OWNER, upon demand therefore, shall also produce for inspection by the CONTRACTOR such records as the OWNER may have with respect to such disputed work or work performed under protest pursuant to order of the OWNER, except those records and reports which may have been prepared for the purpose of determining the accuracy and validity of the CONTRACTOR'S claim.

104.4. PERFORMANCE OF EXTRA OR DISPUTED WORK

While the CONTRACTOR or any SUBCONTRACTOR is performing Extra Work in accordance with [Item 109.3.3](#), Force Account Work or is performing disputed work or complying with a determination or order under protest in accordance with [Item 104.3](#), Disputed Work and Claims for Additional Compensation (the cost of which shall also be determined by the method set out in [Item 109.3.3](#), Force Account Work), the CONTRACTOR shall daily furnish the OWNER or other representative of the OWNER at the project site with three copies of verified statements showing:

- (1) the name and number of each worker, foreman, timekeeper, mechanic, or laborer employed on such work or engaged in complying with such determination or order, the character of such work each is doing and the wages paid to him or her, including the rate and amount of payroll taxes, contribution for insurance and federal social security; and
- (2) the nature, cost and quantity of any materials, supplies, tools, plant or construction equipment furnished or used in connection with the performance of such work or in complying with such determination or order, and from whom purchased or rented.

The above required statements and submittals are in addition to and not in lieu of statements or submittals required under [Item 104.3](#), Disputed Work and Claims for Additional Compensation and [Item 109.3](#), Payment for Extra Work. A copy of such statements shall be signed by the OWNER'S representative, noting thereon any items in question, and shall be returned to the CONTRACTOR within two working days after submission. This signature shall not be construed as the OWNER'S agreement and acceptance of items not questioned since all items are subject to subsequent review and audit by OWNER representatives.

The CONTRACTOR and its SUBCONTRACTORS, when required by the OWNER, must also produce for inspection and audit by designated OWNER representatives, any and all of their books, vouchers, records, daily job diaries and reports, canceled checks, etc. showing the nature and quantity of labor, materials and equipment actually used in the performance of the such Work or Disputed Work; the amounts expended therefore; and the costs

incurred for insurance premiums and other items of expense directly chargeable to such Extra Work or Disputed Work. The CONTRACTOR must permit the OWNER'S representatives to make extracts there from or copies thereof as may be desired.

Failure of the CONTRACTOR to comply strictly with these requirements shall constitute a waiver of any claim for extra compensation on account of the performance of such Extra Work or Disputed Work.

ITEM 105. CONTROL OF WORK

105.1. CONTRACT DOCUMENTS

105.1.1. Priority of Contract Documents. In case of conflict between Contract documents, priority of interpretation shall be in the following order:

- (1) signed agreement (or Contract);
- (2) performance and payment bonds;
- (3) proposal;
- (4) special provisions (or conditions);
- (5) advertisement for bids (or invitation to bidders, or request for proposals);
- (6) project (or Contract) drawings;
- (7) Standard Specifications from Public Works Construction Standards - North Central Texas, and any addendum;
- (8) Standard Drawings from Public Works Construction Standards - North Central Texas, and any addendum;
- (9) referenced specifications.

105.1.2. Correlation of Documents. The Contract documents are complementary and what is called for by any one shall be as binding as if called for by all.

105.1.3. Contract Drawings and Specifications. The OWNER shall furnish the CONTRACTOR such copies of the Contract and any supplemental drawings and specifications reasonably necessary for the proper execution of the work. At least one copy of all drawings and specifications shall be accessible at all times to the OWNER at the job site.

The plans, the specifications, the proposal, special provisions and all supplementary documents are intended to describe a complete work and are essential parts of the Contract. All requirements occurring in any of them are binding. In cases of discrepancies, figured dimensions shall govern over scaled dimensions; plans shall govern over Standard Specifications, special provisions shall govern over both plans and Standard Specifications.

All other provisions of these Standard Specifications shall remain in force.

105.1.4. Supplemental Drawings and Specifications. In order to carry out the intent of the Contract documents and to assist the CONTRACTOR in performing its work, the OWNER, after the execution of the Contract, may, by supplemental drawings, specifications or otherwise, furnish additional information or instructions as may be necessary for construction purposes.

All such supplemental drawings, specifications or instructions are intended to be consistent with the Contract documents and reasonably inferable therefrom. Therefore, no extra costs shall be allowed by the OWNER on a claim that particular supplemental drawings, specifications or instructions differ from the requirements of the Contract documents, incurring extra costs, unless the CONTRACTOR has first brought the matter, in writing, to the OWNER's attention for adjustment before proceeding with the work covered by such.

If the OWNER shall decide that there is no departure from the requirements of the Contract documents, the CONTRACTOR shall then proceed with the work as shown, specified or directed. If the OWNER shall decide that extra work is involved, OWNER shall so modify the supplemental drawings, specifications or instructions to eliminate the extra work, or cause a written change order to be issued in accordance with [Item 104.2](#). Change or Modification of Contract herein.

105.1.5. Referenced Standards. All referenced State, Federal, and National standards are the most current version in effect, unless specifically noted otherwise. Referenced standards may include, but are not limited to, the latest version of publications such as *TxDOT Standard Specifications for Construction of Highways, Streets and Bridges*, *TxDOT Manual of Testing Procedures*, Federal Specifications, ASTM designations, AWWA standards, TMUTCD, ADA, TAS, and standards of other professional societies and associations.

105.1.6. Errors and Corrections in Drawings and Specifications. The OWNER shall be permitted to make such corrections or interpretations as may be necessary for the fulfillment of the intent of the Contract documents. The CONTRACTOR shall not take advantage of any apparent errors, omissions or discrepancies in the drawings or specifications. In case of any errors, omissions or discrepancies in the drawings or

specifications, the CONTRACTOR shall promptly submit the matter to the OWNER who, in turn, shall promptly make a determination and issue the necessary instructions in writing. Any adjustment by the CONTRACTOR without this determination and instructions shall be at the CONTRACTOR'S own risk and expense. The work is to be made complete as intended by the Contract documents.

105.2. WORKMANSHIP, WARRANTIES, AND GUARANTEES

105.2.1. Workmanship. Unless otherwise expressly provided in the Contract drawings or specifications, the work shall be performed in accordance with the best modern practice with materials and workmanship of the highest quality and suitable for their purpose. The OWNER shall judge and determine the CONTRACTOR'S compliance with these requirements.

105.2.2. Special Warranty. If within one year after final acceptance of the work by the OWNER, as evidenced by the final certificate of acceptance or within such longer or shorter period of time as may be prescribed by law or by the terms of any other applicable special warranty on designated equipment or portions of work as required by the Contract documents, any of the work is found to be defective or not in accordance with the Contract documents, the CONTRACTOR shall correct it promptly after receipt of a written notice from the OWNER to do so. This obligation shall survive termination of the Contract. The OWNER shall give such notice promptly after discovery of the condition.

105.2.3. SUBCONTRACTORS' and Manufacturers' Warranties. All SUBCONTRACTORS', manufacturers' and suppliers' warranties and guarantees, express or implied, respecting any part of the work and any materials used therein, shall be obtained and enforced by the CONTRACTOR for the benefit of the OWNER without the necessity of separate transfer or assignment thereof, provided that if directed by the OWNER, the CONTRACTOR shall assign such warranties and guarantees in writing to the OWNER.

105.2.4. Corrected Work Warranty. Any work repaired or replaced shall be subject to the provisions of this section to the same extent as work originally performed.

105.2.5. Rights and Remedies. The rights and remedies of the OWNER provided in this section are in addition to, and do not limit, any rights or remedies afforded to the OWNER by law or any other provision of the Contract documents, or in any way limit the OWNER'S right to recovery of damage due to default under the Contract.

105.3. SHOP DRAWINGS, PRODUCT DATA AND SAMPLES

Shop drawings are drawings, diagrams, schedules and other data specially prepared for the work by the CONTRACTOR or any SUBCONTRACTOR, manufacturer, supplier or distributor to illustrate some portion of the work. Product data or manufacturer's data are illustrations, standard schedules, performance charts, instructions, brochures, diagrams and other information furnished by the CONTRACTOR to illustrate a material, product or system for some portion of the work. Samples are physical examples, which illustrate materials, equipment or workmanship and establish standards by which the work shall be judged.

With reasonable promptness and in such sequence as to cause no delay in the work or in the work of the OWNER or any separate CONTRACTOR, CONTRACTOR shall submit an acceptable number of copies of shop drawings, layouts, manufacturer's data and material schedules as may be required by the OWNER for review. Submittals may be checked by and stamped with the approval of the CONTRACTOR and identified as the OWNER may require. Such review by the OWNER shall include checking for general conformance with the design concept of the project and general compliance with information given in the General Contract Documents. Indicated actions by the OWNER, which may result from OWNER'S review, shall not constitute concurrence with any deviation from the plans and specifications unless such deviations are specifically identified by the method described below, and further shall not relieve the CONTRACTOR of responsibility for errors or omissions in the submitted data. The OWNER may require that certain submittals be sealed by a licensed Texas Engineer. Processed shop drawing submittals are not change orders.

If deviations, discrepancies or conflicts between submittals and the design drawings and/or specifications are discovered, either prior to or after submittals are processed, the design drawings and specifications shall govern. Any deviation from the specified criteria shall be expressly stated in writing in the submittal. The CONTRACTOR shall not be relieved of responsibility for any deviation from the requirements of the Contract documents by the OWNER'S approval of shop drawings, product data or samples unless the CONTRACTOR has specifically informed

the OWNER in writing of such deviation at the time of submission and the OWNER has given written approval to the specific deviation.

The purpose of submittals by the CONTRACTOR is to demonstrate that the CONTRACTOR understands the design concept, and that it demonstrates its understanding by indicating which equipment and materials it intends to furnish and install, and by detailing the fabrication and installation methods it intends to use. The CONTRACTOR shall be responsible for dimensions that are to be confirmed and correlated at the job site, fabrication processes and techniques of construction, coordination of its work with that of other trades and satisfactory performance of its work. The CONTRACTOR shall check and verify all measurements and review submittals prior to being submitted, and sign or initial a statement included with the submittal, which signifies compliance with plans and specifications and dimensions suitable for the application. No portion of the work requiring submission of a shop drawing, product data or sample shall be commenced until the submittal has been approved by the OWNER. All such portions of the work shall be in accordance with approved submittals.

The CONTRACTOR shall be responsible for delays caused by rejection of the submittal of inadequate or incorrect shop drawings, product data or samples. The CONTRACTOR shall be responsible for providing all copies of approved shop drawings necessary for the construction operations. Three (3) copies of the approved submittals shall be retained by the CONTRACTOR until completion of the project and presented to the OWNER in bound form.

105.4. CONSTRUCTION STAKES

Unless otherwise expressly provided in the Contract drawings or specifications, the CONTRACTOR is responsible for locating or reestablishing project survey control, construction staking, including benchmarks, centerlines, and other measurements necessary for the proper execution of the project. The OWNER shall furnish the CONTRACTOR with all necessary information relating to the lines and grades.

All surveying under this section performed by the CONTRACTOR shall be done by a Texas Registered Professional Land Surveyor (RPLS). After completion of staking, the CONTRACTOR shall furnish survey field notes and cut sheets to the OWNER for review. Review of survey field notes and cut sheets shall in no way relieve the CONTRACTOR of liability for incorrectly setting stakes. When not listed as a separate pay item in the Contract, construction staking shall be considered as incidental work, and the cost thereof shall be included in such pay items as are provided in the Contract.

105.5. MEANS AND METHODS OF CONSTRUCTION

Unless otherwise expressly provided in the Contract drawings, specifications or bulletins, the means and methods of construction shall be such as the CONTRACTOR may choose; subject, however, to the OWNER'S right to prohibit means and methods proposed by the CONTRACTOR which in the OWNER'S judgment:

- (1) shall constitute a hazard to the work, or to persons or property, or shall violate express requirements of applicable laws or ordinances; or
- (2) shall cause unnecessary or unreasonable inconvenience to the public; or
- (3) shall not produce finished work in accordance with the requirements of the Contract documents; or
- (4) shall not assure the work to be completed within the time allowed by the Contract.

The OWNER'S approval of the CONTRACTOR'S means or methods of construction, or the OWNER'S failure to exercise OWNER'S right to prohibit such means or methods, shall not relieve the CONTRACTOR of its responsibility for the work or of its obligation to accomplish the result intended by the Contract documents; nor shall the exercise or non-exercise of such rights to prohibit create a cause of action for damages or provide a basis for any claim by the CONTRACTOR against the OWNER.

Where the Contract drawings, specifications or bulletins do not require the use of specific means or methods of construction, sequencing of construction or a specific traffic control plan, the CONTRACTOR shall submit its proposed plan of procedure, sequencing or traffic control plan to the OWNER sufficiently in advance of the work affected to permit a reasonable time for review and comments. The sequence of construction and traffic control plan must be approved in advance by the OWNER before construction begins. Failure to submit the proposed plan within a reasonable time shall not create a claim for damages for resulting delay in the work or for damages, nor shall it be a cause for extension of working time to complete the work.

CONTRACTOR further agrees to defend and indemnify OWNER for any claim or cause of action brought by any third party against the OWNER provided for in [Item 107.3](#). Indemnification hereof.

105.5.1. Conformity with the Plans. All work shall conform to the lines, grades, cross-sections, and dimensions shown on the plans. Any deviation from the plans which may be required by the emergency needs of construction will be determined and authorized in writing by the OWNER.

105.5.2. Public Utilities and Other Property to be Changed. In case it is necessary to change or move the property of any OWNER or of a public utility, such property shall not be moved or interfered with until ordered to do so by the OWNER. The right is reserved to the OWNER of public utilities to enter upon the limits of the contract for the purpose of making such changes or repairs to their property that may be made necessary by performance of the contract. The OWNER reserves the right of entering upon the limits of a contract for the purpose of repairing or relaying sewer and water lines and appurtenances, repairing structures, etc. and for making other repairs, changes, or extensions to any property on the project site.

105.6. SUPERVISION BY CONTRACTOR

The status of the CONTRACTOR is that of an independent CONTRACTOR under Texas law and the work under this Contract shall be under the direct charge and superintendence of the CONTRACTOR. Except where the CONTRACTOR is an individual and gives its personal superintendence to the work, the CONTRACTOR shall provide a competent superintendent or general foreman on the work site at all times during progress with full authority to act for CONTRACTOR. The CONTRACTOR shall also provide an adequate staff for the coordination and expediting of its work.

The superintendent and staff shall be satisfactory to the OWNER. The superintendent or general foreman shall not be changed during this Contract except with the written consent of the OWNER or unless the superintendent or general foreman proves unsatisfactory to the CONTRACTOR and ceases to be in its employ.

If the superintendent or any staff should be or become unsatisfactory to the OWNER, he/she shall be removed by the CONTRACTOR upon written direction of the OWNER, and in such event, the CONTRACTOR shall not be entitled to file a claim for any additional working time or money from the OWNER.

The CONTRACTOR shall provide the OWNER a list of a minimum of three working contacts who are available 24 hours per day, seven days per week.

105.7. OWNER'S REPRESENTATIVES

Where the Contract documents indicate that determinations, directions or approvals shall be made by the OWNER or "OWNER'S representatives," this shall mean the OWNER acting directly, or through duly authorized persons acting within the limit of authority delegated to them.

105.7.1. Authority of the Engineer. All work shall be performed in a good and workmanlike manner and to the satisfaction of the Engineer. The Engineer shall decide all questions which arise as to the quality and acceptability of materials furnished, work performed, manner of performance, rate of progress of the work, sequence of the construction, interpretation of the plans and specifications, acceptable fulfillment of the Contract, compensation, mutual rights between CONTRACTORS under these specifications and suspension of the work. Engineer shall determine the amount and quality of work performed and materials furnished, and Engineer's decisions and estimates shall be final. Engineer estimate in such event shall be a condition precedent to the right of the CONTRACTOR to receive money due under the Contract.

105.7.2. OWNER'S Representative's Final Determination. The OWNER'S representative's determinations shall be final relative to the proper performance of the work and the materials used, and the CONTRACTOR is bound thereby.

It is hereby covenanted and agreed between the two parties of this Contract that the OWNER'S representative shall review and determine all disputes, controversies or claims of either party in relation to this Contract or its performance. Such determination shall be made in writing by the OWNER'S representative within a reasonable time and shall be final and conclusive upon both the CONTRACTOR and the OWNER. It is further covenanted and agreed between the two parties to the Contract that the determination by the OWNER'S representative shall be a condition precedent to the right of any legal action at law or in equity that either party may have against the other.

105.8. SERVICE OF NOTICES

The OWNER and the CONTRACTOR shall designate an address and, if available, a facsimile number, an email address, and other mutually agreeable contact methods where all notices, directions or other communications may be delivered.

Notices to the surety or sureties on Contract bonds shall be directed or delivered to the surety's home office or to the surety's designated agent for delivery of notices.

Service by mail shall be presumed complete upon deposit of the paper, enclosed in a postpaid, properly addressed envelope, in a post office or official depository under the care and custody of the United States Postal Service. Service by facsimile or email after 5:00 p.m. local time of the recipient shall be deemed delivered on the following business day.

A party may change its designated address, facsimile number, email address, or other mutually agreeable method of communication by delivering written notice of the change, properly signed, to all interested parties.

Nothing herein contained shall be deemed to preclude hand delivery of any notice, direction or communication to a party mentioned above.

105.9. INSPECTION

It is the intent of the OWNER to inspect all work on this project. The CONTRACTOR shall obtain written verification from the OWNER if an inspector is not needed before proceeding with that particular item of work. The CONTRACTOR must pay for all testing needed to determine acceptability for any work done without inspection, as directed by the OWNER.

The CONTRACTOR shall furnish the OWNER with every reasonable facility for ascertaining whether or not the work performed was in accordance with the requirements and intent of the plans and specifications. Any work done (except excavation) or materials used without suitable inspection by the OWNER may be ordered removed and replaced at the CONTRACTOR'S expense.

105.9.1. Removal of Defective and Unauthorized Work. All work which has been rejected or condemned shall be repaired, or if it cannot be repaired satisfactorily, it shall be removed and replaced at the CONTRACTOR'S expense. Defective materials shall be immediately removed from the site of the work. Work done without line and grade having been given, work done beyond the lines or not in conformity with the grades shown on the plans or as given, save as herein provided, work done without written authority and prior agreement in writing as to process, shall be done at the CONTRACTOR'S risk and shall be considered unauthorized and at the option of the OWNER may not be measured and paid for and may be ordered removed at the CONTRACTOR'S expense. Upon failure of the CONTRACTOR to repair satisfactorily or to remove and replace, if so directed, rejected, unauthorized or condemned work or materials immediately after receiving notice from the OWNER, the OWNER shall, after giving written notice to the CONTRACTOR, have the authority to cause defective work to be remedied or removed and replaced, or to cause unauthorized work to be removed and to deduct the cost thereof from any monies due or to become due the CONTRACTOR. Alternatively, the OWNER may, at its option, declare the CONTRACTOR in default, in which event the performance bond surety shall complete the Contract.

105.9.2. Final Inspection. Whenever the improvements provided for by the Contract shall have been completely performed on the part of the CONTRACTOR, the CONTRACTOR shall notify the OWNER that the improvement is ready for final inspection. If the work is not acceptable to the OWNER at the time of such inspection, OWNER shall inform CONTRACTOR as to the particular defects to be remedied before final acceptance shall be made. CONTRACTOR shall promptly remedy the identified defects. The OWNER will notify the CONTRACTOR of the time allowed for correction of the unacceptable items found during the final inspection. The OWNER shall make final inspection of all work included in the Contract as soon as practicable after remedies have been made and the work is ready for acceptance.

105.9.3. Inspection Overtime. Project inspectors must be paid via the contract. The CONTRACTOR is required to reimburse the OWNER or its designated representative for the cost of all inspection overtime which may be necessary for the successful and expeditious prosecution of the work included in this Contract. Requests for overtime inspection must be submitted to the OWNER two working days in advance and on the proper form. Payment to the OWNER or its designated representative for overtime inspection costs will be made within 10 days of receipt of invoice. Failure to submit payment for overtime inspection may result in the

OWNER withholding the next monthly partial payment. No additional compensation or time shall be granted the CONTRACTOR for withheld monthly partial payments due to nonpayment of inspector overtime.

The maximum overtime rate for construction inspectors shall be determined by the OWNER. In case of disputes, the OWNER'S decision shall be final. Model Form A.8. Inspection Overtime is included in Appendix A.

105.10. ACCEPTANCE

Once the work is satisfactory to the OWNER and in accordance with the specifications and Contract documents, the CONTRACTOR shall be issued a certificate of acceptance. The Certificate of Acceptance will not be issued until all work required by the Contract, including all water and wastewater appurtenances have been adjusted to their final position.

ITEM 106. CONTROL OF MATERIAL

106.1. SUBSTITUTION OF MATERIALS

The specifications for materials set out the minimum standard of quality that the OWNER believes necessary to procure a satisfactory project. No substitutions will be permitted until the CONTRACTOR has received written permission of the OWNER to make a substitution for the material that has been specified. Requests for substitution shall be made prior to the date of the preconstruction conference.

Where the term "or equal," or "or approved equal" is used, it is understood that if a material, product, or piece of equipment bearing the name so used is furnished it will be approvable, as the particular trade name was used for the purpose of establishing a standard of quality acceptable to the OWNER. If a product of any other name is proposed for use, the OWNER's approval thereof must be obtained before the CONTRACTOR procures the proposed substitute.

Where the term "or equal," or "or approved equal" is not used in the specifications, this does not necessarily exclude alternative items or material or equipment which may accomplish the intended purpose. However, the CONTRACTOR shall have the full responsibility of proving that the proposed substitution is, in fact, equal, and the Engineer, as the representative of the OWNER, shall be the sole judge of the acceptability of substitutions. The provisions of this sub-section as related to "Substitutions" shall be applicable to all sections of these specifications.

Should an authorized substitution require redesign of a portion of the work or alterations to the plans or specifications in order for the materials or articles which are to be substituted to properly fit or in other ways to be satisfactory, the OWNER shall accomplish such redesigns and alterations. The CONTRACTOR shall bear all reasonable costs associated with redesign and alteration efforts performed by the OWNER.

106.2. MATERIALS AND EQUIPMENT

The CONTRACTOR shall be free to obtain the approved materials, equipment and articles from sources of its own selection. However, if the OWNER finds that the work shall be delayed or adversely affected in any way because a selected source of supply cannot furnish a uniform product in sufficient quantity and at the time required and a suitable source does exist, or the product is not suitable for the work, the OWNER shall have the right to require the original source of supply changed by the CONTRACTOR. The CONTRACTOR shall have no claim for extra cost or damage because of this requirement.

The CONTRACTOR warrants to the OWNER that all materials and equipment furnished under this Contract shall be new unless otherwise specified in the Contract documents and that same shall be of good quality and workmanship, free from faults and defects and in conformance with the Contract documents. All materials and equipment not conforming to these requirements, including substitutions not properly approved and authorized, may be considered defective and shall be promptly repaired or replaced by the CONTRACTOR at the CONTRACTOR's sole cost upon demand of the OWNER. If required by the OWNER, the CONTRACTOR shall furnish satisfactory evidence as to the kind and quality of materials and equipment.

106.3. SALVAGEABLE MATERIAL

All salvageable material shall be designated by and remain the property of the OWNER. Any designated salvageable material that is destroyed or damaged due to negligence of the CONTRACTOR shall be replaced with new material by the CONTRACTOR at no expense to the OWNER. Salvage material, unless designated for reuse, shall be returned to a location designated by the OWNER.

106.4. OFF-SITE STORAGE

Materials shall be stored so as to insure the preservation of their quality and fitness for the work. When directed by the OWNER, they shall be placed on wooden platforms or other hard, clean surfaces and not on the ground, and shall be placed under cover when directed. Stored materials shall be placed and located so as to facilitate prompt inspection.

Payment for costs incurred in storage of materials or equipment away from the project site will not be made by the OWNER unless:

- (1) the OWNER has approved off-site storage in writing; and
- (2) the materials will not be incorporated into the project within the next 60 days;

- (3) the materials or equipment are stored in a bonded warehouse located in the County approved by the OWNER and identified with the project for which they are stored as evidenced by warehouse receipts and appropriate documents of title;
- (4) an official PAID receipt from the material supplier is provided; and
- (5) CONTRACTOR may invoice only for the amount actually paid for the storage of the material.
- (6) Storage in facilities of the manufacturer or CONTRACTOR will not be permitted or paid for, unless such storage is expressly approved in writing by the OWNER.

106.4.1. Early Delivery to Project Site. All materials or equipment delivered to the project site earlier than thirty (30) days prior to an approved schedule for delivery to the project site shall be classified as an "early delivery". All early delivery materials or equipment must have written permission of the OWNER to be stored on the project site. Should any unauthorized early delivery occur, CONTRACTOR shall, at the CONTRACTOR'S expense, cause such early delivery to be removed from the project site and stored off-site until required at the project site. All costs of labor, transportation and storage will be included as part of the expense. If the CONTRACTOR fails or refuses to remove unauthorized early delivery materials, the OWNER may cause such materials to be removed at the CONTRACTOR'S sole expense, and amounts may be withheld from the CONTRACTOR'S Application for Payment to reimburse the OWNER for any costs incurred in removing unauthorized early delivery materials. The OWNER will not be responsible for the protection of or risk of loss on any early delivery materials or equipment, nor will the OWNER be liable for any payment thereon.

106.5. SAMPLES AND TESTS OF MATERIALS

Unless otherwise stipulated in the Contract documents, initial testing of all materials, construction items or products incorporated in the work shall be performed at the direction and expense of the OWNER, including initial compaction and density tests deemed necessary.

In the event materials, construction items or products incorporated in the work fail to satisfy the minimum requirements of the initial test, appropriate prove out test shall be made as directed by the OWNER to determine the extent of the failure and to verify that the corrective measures have brought the item up to specification requirements. The cost of all testing necessary to determine the extent of the failure and the adequacy of the corrective measures shall be the responsibility of the CONTRACTOR.

The failure of the OWNER to make any tests of materials shall in no way relieve the CONTRACTOR of its responsibility of furnishing materials conforming to the Contract documents.

Tests, unless otherwise specified, shall be made in accordance with the latest methods of the American Society for Testing and Materials. The CONTRACTOR shall provide such facilities as the OWNER may require for collecting and forwarding samples and shall not use the materials represented by the samples until tests have been made. The CONTRACTOR shall furnish adequate samples without charge. Test materials and samples shall be stored so as to ensure the preservation of their quality and fitness for the Work. If directed by the OWNER, they shall be placed on wooden platforms or other hard, clean surfaces and shall be placed under cover when directed. Stored materials shall be placed and located so as to facilitate prompt inspection.

The inspections and tests made by the OWNER, its inspectors or agents, shall ordinarily be made without cost to the CONTRACTOR unless otherwise expressly specified in the Contract documents. The CONTRACTOR shall furnish without additional cost to the OWNER such materials for testing as may be reasonably necessary. Retesting after failure to pass tests shall be at the expense of the CONTRACTOR. Should the percentage of rejected material or equipment be unreasonably large, the additional cost of such inspection and tests resulting therefrom shall be borne by the CONTRACTOR. The OWNER shall determine what extra inspection is and shall determine the additional cost incurred thereby and payable by the CONTRACTOR, and such determination shall be final.

106.6. SURPLUS MATERIALS

Surplus materials shall be disposed of by the CONTRACTOR at his expense. Surplus materials including excavation shall be removed from the site unless specified otherwise under the performance specifications.

ITEM 107. LEGAL RELATIONS AND CONTRACTOR RESPONSIBILITIES

107.1. CONTRACTOR INDEPENDENCE

While engaged in carrying out and complying with the terms and conditions of this Contract the CONTRACTOR is, and shall be, an independent CONTRACTOR and shall not, with respect to its acts or omissions, be deemed an officer, employee or agent of the OWNER. The CONTRACTOR shall not at any time or in any manner represent that it or any of its agents or employees are in any manner agents or employees of the OWNER.

CONTRACTOR is, and shall remain, an independent CONTRACTOR, with full, complete and exclusive power and authority to direct, supervise, and control its own employees and SUBCONTRACTORS and to determine the method of the performance of the work covered under this Contract. The fact that the OWNER or the Engineer shall have the right to inspect or observe CONTRACTOR'S work during performance and to exercise the other rights and prerogatives expressly reserved to the OWNER or the Engineer under this Contract is not intended to, and shall not any time, change or affect the status of the CONTRACTOR as an independent CONTRACTOR with respect to the OWNER, the CONTRACTOR'S own employees or any other person, firm or corporation.

Nothing contained in the Contract documents shall create any contractual or agency relationship between the Engineer and the CONTRACTOR.

107.2. NO THIRD PARTY CONTRACTUAL RIGHTS

This Contract is solely for the benefit of the parties to this Contract and are not intended to create or grant any rights, contractual or otherwise, to any other person or entity.

107.3. INDEMNIFICATION

CONTRACTOR covenants and agrees to and does hereby indemnify, hold harmless and defend, at its own expense, OWNER, its officers, officials, agents and employees, from and against any and all claims or suits, judgments and costs and expenses for property loss or damage and/or personal injury, including death, to any and all persons, of whatsoever kind or character, whether real or asserted, arising out of the work and services to be performed hereunder by CONTRACTOR, its officers, officials, agents, employees, SUBCONTRACTORS, licensees or invitees, whether or not caused, in whole or in part, by the alleged negligence of the officers, agents, and employees, of the OWNER. CONTRACTOR likewise covenants and agrees to, and does hereby, indemnify and hold harmless OWNER from and against any and all injuries, damage, loss or destruction to property of OWNER during the performance of any of the terms and conditions of this contract, whether arising out of in whole or in part, any and all alleged acts or omissions of officers, agents, or employees of OWNER.

The provisions of this paragraph are solely for the benefit of the parties hereto and not intended to create or grant any rights, contractual or otherwise, to any other person or entity.

107.4. OWNER'S OFFICERS, EMPLOYEES OR AGENTS

107.4.1. Claim Against Officers, Employees or Agent of the OWNER. No claim whatsoever shall be made by the CONTRACTOR against any officer, employee, or agent of the OWNER for or on account of, anything done or omitted to be done in connection with this Contract.

107.4.2. Financial Interest in Any Contract by OWNER'S Officers, Employees or Agents. CONTRACTOR is hereby advised to comply with the OWNER'S financial interest or comparable policy. If OWNER does not implement a financial interest or comparable policy of its own, provisions of this Item shall govern matters of financial interest.

No officer, employee, or agent of the OWNER shall have a financial interest, direct or indirect, in any contract with the OWNER or be financially interested, directly or indirectly, in the sale to the OWNER of any land, materials, supplies or services, except on behalf of the OWNER as an officer or employee. Any violation of this article with the knowledge, expressed or implied, of the persons, partnership, company, firm, association or corporation contracting with the OWNER shall render the Contract involved voidable by the OWNER.

107.4.3. Conflict of Interest. CONTRACTOR shall complete and submit the State of Texas Conflict of Interest Questionnaire, form CIQ as required by Texas Local Government Code, Chapter 176.

107.5. VENUE AND GOVERNING LAW

The parties herein agree that this Contract shall be performed in the county in which the OWNER's principal office is located, and if legal action is necessary in connection therewith, exclusive venue shall lie in this county. The terms and provisions of the Contract documents shall be construed in accordance with the laws and court decisions of the State of Texas.

107.6. NO WAIVER OF LEGAL RIGHTS

Inspection by the OWNER; any order, measurement, quantity or certificate by the OWNER; any order by the OWNER for payment of money; any payment for or acceptance of any work; or any extension of time or any possession taken by the OWNER shall not operate as a waiver of any provisions of the Contract or any power therein reserved to the OWNER of any rights or damages therein provided. Any waiver of any breach of Contract shall not be held to be a waiver of any other or subsequent breach. The OWNER reserves the right to correct any error that may be discovered in any estimate that may have been paid and to adjust the same to meet the requirements of the Contract documents. The OWNER reserves the right to recover by process of law sums as may be sufficient to correct any error or make good any deficiency in the work resulting from such error, dishonesty or collusion by the CONTRACTOR or its agents that is discovered in the work by the OWNER after the final payment has been made.

Neither final acceptance of the work nor final payment shall relieve the CONTRACTOR of responsibility for faulty materials or workmanship, and the CONTRACTOR shall promptly remedy any defects due thereto and pay for any damage to other work resulting therefrom. Likewise, neither final acceptance nor final payment, nor partial or entire use or occupancy of the work by the OWNER shall constitute acceptance of work not done in accordance with the Contract documents or relieve CONTRACTOR of liability with respect to any expressed or implied warranties or responsibility for faulty materials or workmanship, whether same be patently or latently defective.

The OWNER, or any officer or agent thereof, shall not be precluded at any time, either before or after final completion and acceptance of the work and final payment therefrom:

- (1) showing the true and correct amount, classifications, quality and character of the work done and materials furnished by the CONTRACTOR or any other person under this Contract, or
- (2) from showing at any time that any determination, return, decision, approval, order, letter, payment or certification is untrue and incorrect or improperly made in any particular, or
- (3) that the work or the materials or any parts thereof do not in fact conform to the Contract requirements; and
- (4) demanding the recovery from the CONTRACTOR of any overpayments made to it, or such damages as the OWNER may sustain by reason of the CONTRACTOR's failure to perform each and every part of this Contract in strict accordance with its terms; or both.

107.7. SEVERABILITY

In the event a term, condition, or provision in this Contract is determined to be void, unenforceable, or unlawful by a court of competent jurisdiction, then that term, condition or provision, shall be deleted and the remainder of the Contract shall remain in full force and effect.

107.8. HEADINGS

The title and headings contained in the Contract documents and the subject organization are used only to facilitate reference, and in no way define or limit the scope of intent of any of the provisions of this Contract.

107.9. OBLIGATIONS TO PERFORM FUNCTIONS

Any failure or neglect on the part of OWNER, Engineer or inspectors to enforce provisions herein dealing with supervision, control, inspection, testing or acceptance and approval of the work shall never operate to relieve CONTRACTOR from full compliance with the Contract documents nor render OWNER liable to CONTRACTOR for money damages, extensions of time or increased compensation of any kind.

107.10. PERFORMANCE OF THE WORK

In addition to those matters elsewhere expressly made the responsibility of the CONTRACTOR, the CONTRACTOR shall have the full and direct responsibility for the performance and completion of the work under this Contract and for any act or neglect of the CONTRACTOR, its agents, employees or SUBCONTRACTORS. CONTRACTOR shall bear all losses, if any, resulting on account of the amount and character of the work, or because the conditions under

which the work must be done are different from what CONTRACTOR estimated or anticipated, or because of weather, floods, elements or other causes, regardless of the expected completion date set forth in the Contract Documents.

107.11. SUCCESSORS AND ASSIGNS

Subject to the limitations upon assignment and transfer herein contained, this Contract shall be binding upon and inure to the benefit of the parties hereto, their respective successors and assigns.

107.12. SUPERVISION AND CONSTRUCTION PROCEDURES

The CONTRACTOR shall supervise and direct all the work, using its best skill and attention. CONTRACTOR shall be solely responsible for all construction means, methods, techniques, sequences and procedures and for coordinating all portions of the work under the Contract.

The CONTRACTOR shall carefully study and compare the Contract documents and shall at once report to the OWNER any error, inconsistency or omission it may discover. The CONTRACTOR shall perform no portion of the work at any time without Contract documents or, where required, approved shop drawings, product data or samples for such portion of the work.

The CONTRACTOR shall be responsible to the OWNER for the acts and omissions of the OWNER's employees, SUBCONTRACTORS, and agents, as well as the CONTRACTOR's employees and SUBCONTRACTORS performing any of the work under a contract with the CONTRACTOR. The CONTRACTOR shall at all times enforce strict discipline and good order among its employees and shall not employ on the work site any unfit person or anyone not skilled in the task assigned to him or her.

The CONTRACTOR shall not be relieved from its obligations to perform the work in accordance with the Contract documents either by the activities or duties of the OWNER in its administration of the Contract, or by inspections, tests or approvals required or performed by persons other than the CONTRACTOR.

The CONTRACTOR shall give to the work the consistent attention necessary to facilitate the progress thereof, and the CONTRACTOR shall cooperate with the OWNER, and with other CONTRACTORS in every way possible.

The OWNER and the OWNER's representatives shall at all times have free access to the work whenever it is in preparation or progress and the CONTRACTOR shall provide safe, convenient and proper facilities for such access and inspection.

107.13. LABOR AND MATERIALS

Unless otherwise provided in the Contract documents, the CONTRACTOR shall provide and pay for all labor, materials, equipment, tools, construction equipment and machinery, water, heat, utilities, transportation and other facilities and services necessary for the proper execution and completion of the work, whether temporary or permanent and whether or not incorporated or to be incorporated into the work.

107.14. EQUAL EMPLOYMENT OPPORTUNITY

During the performance of this Contract the CONTRACTOR agrees as follows:

107.14.1. Nondiscrimination Toward Employees. The CONTRACTOR shall not discriminate against any employee or applicant for employment because of race, color, religion, sex, age, military or veteran status, disability unrelated to job performance, or national origin. The CONTRACTOR shall take affirmative action to insure that applicants are employed and that employees are treated during employment without regard to their race, color, sex, religion, age or national origin. Such action shall include, but not be limited to, the following: employment, upgrading, demotion or transfer; recruitment or recruitment advertising; layoff or termination, rates of pay or other forms of compensation; and selection for training, including apprenticeship. The CONTRACTOR agrees to post in conspicuous places, available to employees or applicants for employment, notices to be provided setting forth the provisions of this nondiscrimination clause.

107.14.2. Nondiscrimination Employment Practices. The CONTRACTOR shall, in all solicitations or advertisements for employees placed by or on behalf of the CONTRACTOR, state that all qualified applicants shall receive consideration for employment without regard to race, color, religion, sex, national origin or age.

107.14.3. Labor Unions. The CONTRACTOR shall send to each labor union or representative of workers with which it has a collective bargaining agreement or other contract or understanding a notice to be provided, advising the said labor union or workers' representatives of the CONTRACTOR's commitments under this

section, and shall post copies of the notice in conspicuous places available to employees and applicants for employment.

107.14.4. Provisions in Subcontracts. The CONTRACTOR shall include the provisions of this section in all subcontracts pertaining to the work.

107.14.5. Reports. During the course of the work, the CONTRACTOR shall submit to the OWNER, on a monthly basis, a breakdown by minority group of all employees at the site of the work.

107.15. STATE AND LOCAL SALES AND USE TAXES

The OWNER qualifies for exemption from the state and local sales and use taxes, pursuant to the provisions of Section 151.309 of the Texas Limited Sales, Excise and Use Tax Act. Therefore, the CONTRACTOR shall not pay such taxes which would otherwise be payable in connection with the performance of this Contract.

The CONTRACTOR shall issue an exemption certificate in lieu of the tax on the purchase of:

- (1) all materials, supplies, equipment and other tangible personal property incorporated into the real property being improved; and
- (2) all materials, supplies and other tangible personal property, other than machinery or equipment and its accessories and repair and replacement parts, necessary and essential for the performance of the Contract with the OWNER which is to be completely consumed at the job site.

Tangible personal property necessary and essential for the performance of the Contract includes only such materials, tools and supplies specifically needed and directly used to incorporate tangible personal property into the real estate being improved under the Contract. Overhead supplies and supplies used indirectly or only incidental to the performance of the Contract with the OWNER are not included in the exemption. Tangible personal property is "completely consumed" if after being used once for its intended purpose it is used up or destroyed. Any exemption certificate issued by the CONTRACTOR is subject to the existing rules and interpretation governing the exemption issued by the Comptroller of Public Accounts of the State of Texas. The OWNER will not make interpretations of the extent or applicability of the exemption in a particular case; if the CONTRACTOR, or any SUBCONTRACTOR or supplier of the CONTRACTOR, has any questions about the extent or applicability of the exemption in specific circumstances, guidance should be sought from the State Comptroller's Office.

Under "reasons said purchaser is claiming this exemption" in the exemption certificate, the CONTRACTOR must name the OWNER and the project for which the equipment, material and supplies are being purchased, leased or rented.

107.16. PATENTS

The CONTRACTOR shall pay all royalties and license fees and shall provide, by suitable legal agreement with the patentee or OWNER, for the use of any design, device, material or process covered by letters, patent or any copyright. The CONTRACTOR shall indemnify, defend, hold and save the OWNER and its officers, employees and agents harmless from all liability and claims for infringement of any patent, copyright, mark or license.

In the event that any claims, suit or action at law or in equity of any kind whatsoever is brought against the OWNER, or its officers, employees or agents involving any such patents, copyrights or license rights, then the OWNER shall have the right to and may retain from any money due or to become due to the CONTRACTOR such sum deemed necessary by the OWNER for its protection until such claim or suit shall have been settled and satisfactory evidence to that effect shall have been furnished the OWNER.

107.17. COMPLIANCE WITH LAWS

The CONTRACTOR shall fully comply with all local, state and federal laws, including all codes, ordinances and regulations applicable to this Contract and the work to be done thereunder, which exist or which may be enacted later by governmental bodies having jurisdiction or authority for such enactment. CONTRACTOR shall correct any work not in compliance with local, state or federal laws.

The CONTRACTOR shall secure and pay for all permits and licenses necessary for the execution of the work and shall fully comply with all their terms and conditions.

All work required under this Contract shall comply with all requirements of law, regulation, permit or license. If the CONTRACTOR finds that there is a variance, it shall immediately report this to the OWNER for resolution.

107.17.1. Pleas of Misunderstanding. No pleas of misunderstanding or ignorance thereof will be considered. The CONTRACTOR and the CONTRACTOR'S Sureties shall indemnify and save harmless the OWNER

against any claims or liability arising from or based on the violation of any such law, ordinance, regulation or order whether by the CONTRACTOR, its employees, or SUBCONTRACTORS.

All work required under this contract shall comply with all required documents of law, regulation, permit or license, if the CONTRACTOR finds that there is a variance, the CONTRACTOR shall immediately report such to the OWNER for resolution.

OWNER shall not be liable for interest on any progress or final payment to be made under this Contract, except as may be provided by the applicable provisions of the Prompt Payment Act, Chapter 2251, Texas Government Code, as amended.

107.18. SANITARY PROVISIONS

The CONTRACTOR shall establish and enforce among its employees such regulations in regard to cleanliness and disposal of garbage and waste as shall tend to prevent the inception and spread of infectious or contagious diseases and to prevent effectively the creation of a nuisance about the work on any property either public or private, and such regulations as are required by the OWNER shall be put into immediate force and effect by the CONTRACTOR. The necessary sanitary conveniences for the use of laborers on the work, properly secluded from public observation, shall be constructed and maintained by the CONTRACTOR in such a manner and at such points as shall be approved by the OWNER, and their use shall be strictly enforced by the CONTRACTOR. All sanitary laws and regulations of the State of Texas and the OWNER'S jurisdiction shall be strictly complied with.

107.19. PUBLIC CONVENIENCE AND SAFETY

Materials stored about the work site shall be so placed, and the work shall at all times be so conducted, as to cause no greater obstruction to the traveling public than is considered necessary by the OWNER. The CONTRACTOR shall make provisions by bridges or otherwise at all cross streets, highways, sidewalks and private driveways for the free passage of pedestrians and vehicles, provided that where bridging is impracticable or unnecessary, in the opinion of the OWNER, the CONTRACTOR may make arrangements satisfactory to the OWNER for the diversion of traffic and shall, per the Contract, provide all material and perform all work necessary for the construction and maintenance of roadways and bridges for the diversion of traffic. Sidewalks must not be obstructed except by special permission of the OWNER. The materials excavated, and the construction materials or plant used in the construction of the work, shall be placed so as not to endanger the work or prevent free access to all fire hydrants, water valves, gas valves, manholes for the telephone, telegraph signal or electric conduits, sanitary sewers and fire alarm or police call boxes in the vicinity.

The OWNER reserves the right to remedy any neglect on the part of the CONTRACTOR as regards to the public convenience and safety which may come to its attention, after 24 hours' notice in writing to the CONTRACTOR, save in cases of emergency, when it shall have the right to remedy any neglect without notice; and in either case, the cost of such work done by the OWNER shall be deducted from the monies due or to become due the CONTRACTOR. The CONTRACTOR shall notify the OWNER when any street is to be closed or obstructed; such notice shall in the case of major thoroughfares or streets upon which transit lines operate be made 48 hours in advance. The CONTRACTOR shall, when directed by the OWNER, keep any street or streets in condition for unobstructed use by emergency services. Where the CONTRACTOR is required to construct temporary bridges or to make other arrangements for crossing over ditches or streams, its responsibility for accidents shall include the roadway approaches as well as the structures of such crossings.

Where the work passes over or through private property, the OWNER shall provide such right-of-way. The CONTRACTOR shall notify the proper representatives of any public utility, corporation, any company or individual, not less than 48 hours in advance of any work which might damage or interfere with the operation of property along or adjacent to the work. The CONTRACTOR shall be responsible for all damage or injury to property of any character (except such as may be required by the provisions of the Contract documents or caused by agents or employees of the OWNER) by reason of any negligent act or omission on the part of the CONTRACTOR, its employees, agents or SUBCONTRACTORS, or at any time due to defective work or materials, or due to its failure to reasonably or properly prosecute the work, and said responsibility shall not be released by the fact that the work shall have been completed and accepted.

When and where any such damage or injury is done to public or private property on the part of the CONTRACTOR, restoration shall be completed according to [Item 107.27](#). Restoration of Property.

107.20. PROTECTION OF WORK AND PERSONS AND PROPERTY

107.20.1. Protection of Work. During performance and up to date of final acceptance, the CONTRACTOR shall be under the absolute obligation to protect all work against any damage, loss or injury. In the event of damage, loss or injury, the CONTRACTOR shall promptly replace or repair the work, whichever the OWNER shall determine to be preferable. The obligation to deliver finished work in strict accordance with the Contract prior to final acceptance shall be absolute and shall not be affected by the OWNER'S approval of or failure to prohibit means and methods of construction used by the CONTRACTOR. All risk of loss or damage to the work shall be borne solely by the CONTRACTOR until final completion and acceptance of all work by the OWNER, as evidenced by the OWNER'S issuance of a certificate of acceptance.

107.20.2. Protection of Persons and Property. The CONTRACTOR shall have the responsibility to provide and maintain all warning devices and take all precautionary measures required by law or otherwise to protect persons and property while said persons or property are approaching, leaving or within the work site or any area adjacent to said work site. Compensation shall be paid to the CONTRACTOR for the installation or maintenance of any warning devices, barricades, lights, signs or any other precautionary measures required by law or otherwise for the protection of persons or property according to [Item 801.1](#). Barriers and Warning and Detour Signs.

The CONTRACTOR shall assume all duties owed by the OWNER to the general public in connection with the general public's immediate approach to and travel through the work site and the area adjacent to said work site.

Where the work is carried on, in or adjacent to any street, alley, sidewalk, public right-of-way or public place, the CONTRACTOR shall at its own cost and expense provide such flagmen and watchmen in addition to its responsibility to furnish, erect and maintain such warning devices, barricades, lights, signs, and other precautionary measures for the protection of persons or property as are required by law. During periods when schools are in session, the CONTRACTOR will be required during the construction of the Work to:

- (1) Maintain a suitable all-weather footpath across the Work at all designated school crosswalks.
- (2) Move and reinstall pedestrian crossing warning signs as construction and routing of traffic lanes require.

The CONTRACTOR'S responsibility for providing and maintaining flagmen, watchmen, warning devices, barricades, signs, and lights, and other precautionary measures shall not cease until directed in writing by the OWNER or until final payment, whichever occurs first. If the OWNER discovers that the CONTRACTOR has failed to comply with the applicable federal and state law by failing to furnish the necessary flagmen, warning devices, barricades, lights, signs or other precautionary measures for the protection of persons or property, the OWNER may order such additional precautionary measures as required by law to be taken to protect persons and property. The CONTRACTOR shall reimburse the OWNER for any expense incurred by the OWNER in taking any additional precautionary measures as a result of the CONTRACTOR'S failure to do so.

In addition, the CONTRACTOR will be held responsible for all damage to the work and other public or private property due to the failure of warning devices, barricades, signs, lights, or other precautionary measures in protecting said property, and whenever evidence is found of such damage, the OWNER may order the damaged portion immediately removed and replaced by and at the cost and expense of the CONTRACTOR.

Minimum standards for safeguarding pedestrian and vehicular traffic are contained in the current *Texas Manual of Uniform Traffic Control Devices*, as amended, Texas Department of Transportation. Signage, barricades and other traffic control devices for detouring and maintenance of traffic on this Contract shall be as provided in above said manual and as directed by the OWNER. Costs associated with the acquisition and removal of required traffic control devices shall be considered incidental to the Work.

107.20.3. Trench Safety.

107.20.3.1. Regulations. The CONTRACTOR shall be responsible for complying with state laws and federal regulations relating to trench safety, including those which may be enacted during the performance under this Contract. The CONTRACTOR is advised that Federal Regulations 29 C.F.R. 1926.650-1926.652 have been, in their most recent version as amended, in effect since January 2, 1990.

The CONTRACTOR shall fully comply with the U.S. Department of Labor Occupational Safety and Health Administration (OSHA) regulations pertaining to excavations, trenching, and shoring and shall provide and familiarize its employees involved in excavation and trenching with the provisions in OSHA pamphlet number 2226, excavation and trenching operations.

107.20.3.2. Indemnification. In addition to any other indemnification, CONTRACTOR agrees to defend, indemnify and hold OWNER, its officers, agents and employees, completely harmless from any claims, lawsuits, judgments, costs and expenses (including attorney's fees, if any) for any personal injury (including death), property damage or other harm for which recovery of damages is sought (including any injury, death or damage suffered by the CONTRACTOR'S own employees) arising out of or occasioned by the use of any trench excavation plans, regardless of their origin, or by any negligent, grossly negligent, strictly liable or intentional act of the CONTRACTOR, a SUBCONTRACTOR or any individual employee or laborer (whether or not an employee of the CONTRACTOR or a SUBCONTRACTOR) in the performance or supervision of actual trench excavation under the contract. This indemnity applies regardless of whether OWNER'S or consulting engineer's negligence or fault in the administration of this contract or in the preparation, review or approval of the OWNER'S or CONTRACTOR'S trench excavation plan contributed to the injury, death or damage. OWNER accepts no liability whatsoever as a result of its preparation, review or approval of any trench excavation plan under this contract; OWNER makes no warranty, express or implied, concerning the adequacy or correctness of any trench excavation plan.

(The provisions of this paragraph are solely for the benefit of the parties to the contract and are not intended to create or grant any rights, contractual or otherwise, to any other person or entity. This paragraph shall not be construed to waive any governmental immunity of the OWNER. This paragraph controls in the event of a conflict with any other indemnity or OWNER- warranty provision in the specifications).

107.20.3.3. Trench Safety Plan. The CONTRACTOR shall be responsible for providing to the OWNER an acceptable trench safety plan signed and sealed by a Professional Engineer qualified to do such work and licensed/registered in the State of Texas. The CONTRACTOR shall be responsible for selecting an appropriate method of providing trench safety after due consideration of the job conditions, location of utilities, pavement conditions and other relevant factors. Slope-back methods which may result in unnecessary displacement of utilities and/or destruction of pavement shall not be used without permission from the OWNER. Plans for devices used to provide trench safety such as trench shields and shoring systems will be likewise certified by Professional Engineers licensed/registered in the State of Texas or by a Professional Engineer licensed/registered in the state of manufacture of the shield or shoring system.

107.20.3.4. Shoring and Sheeting. The sides of all excavation shall be supported in accordance with the trench safety plan. Where bracing or sheeting and bracing are used, the trench width shall be increased accordingly, shall be considered as incidental work, and shall not be paid for as a separate item. In wet, saturated or flowing materials where it is necessary to install tight sheeting or cofferdams, wood or steel sheet piling of a design and type approved by the OWNER shall be used. All sheeting, shoring and bracing shall have sufficient strength and rigidity to withstand the pressure exerted, to maintain the sides of the excavation properly in place, and to protect all persons or property from injury or damage. When excavations are made adjacent to existing buildings or other structures or in paved streets, particular care shall be taken to adequately sheet, shore and brace the sides of the excavation to prevent undermining of or settlement beneath the structures or pavement. Underpinning of adjacent structures or pavement shall be done at the CONTRACTOR'S own cost and expense and in a manner satisfactory to the OWNER, or, when required by the OWNER, the pavement shall be removed, the void satisfactorily filled, compacted and the pavement replaced by the CONTRACTOR. The entire expense of such removal and subsequent replacement thereof shall be borne by the CONTRACTOR. Wooden sheeting, shoring and bracing shall be left in place where it is adjacent to the pipe embedment for the initial lift of backfill.

The removal of all sheeting, shoring and bracing shall be done in such manner as not to endanger or damage either new or existing structures, or private or public properties; and so as to avoid cave-ins or sliding of the banks. All holes or voids left by the removal of the sheeting, shoring or bracing shall be immediately and completely filled and compacted with suitable materials. If, for any reason, the CONTRACTOR, with the approval of the OWNER, elects to leave in place the sheeting, shoring or bracing, no payment shall be allowed for such material left in place unless ordered by the OWNER to be left in place.

107.20.3.5. Inspection. The CONTRACTOR shall cause all shoring or bracing to be inspected by an OSHA competent person. According to OSHA regulations, a competent person is defined as one who is capable of identifying existing and predictable hazards in the surroundings, or working conditions which are unsanitary, hazardous, or dangerous to employees, and who has authorization to take prompt corrective measures to eliminate them.

107.20.3.6. Payment for Trench Safety and Shoring. Payment for trench safety shall be by the lineal feet of trench exceeding a depth of 4-ft. unless otherwise specified in the Contract. Excavation for slope-back methods shall be subsidiary to the trench safety pay item including replacement and re-compaction. Excess excavation for other trench safety methods is also subsidiary to the trench safety pay item. Costs relating to the preparation of the trench safety plan including geotechnical investigation, testing and report preparation fees are all subsidiary to the pay item for trench safety. Should trench safety measures be required during Contract performance where no pay item has been provided, then the CONTRACTOR shall immediately notify the OWNER and, if directed to do so, provide trench safety under the provisions of [Item 104.2.3](#). Extra Work and/or [Item 109.3](#). Payment for Extra Work. Should the OWNER fail to authorize the work as provided for in [Item 104.2.3](#). Extra Work and [Item 109.3](#). Payment for Extra Work, then the CONTRACTOR shall proceed under the provisions of [Item 104.3](#). Disputed Work and Claims for Additional Compensation and [Item 104.4](#). Performance of Extra or Disputed Work. Trench safety requirements are mandatory and shall not be waived.

107.21. PROJECT SIGNS

Project signs shall be furnished, constructed, and erected by the CONTRACTOR as directed by the OWNER. Signs shall be placed in a location selected by the OWNER and maintained in good condition until the completion of the project. Project signs shall be removed by the CONTRACTOR upon the completion and acceptance of the project by the OWNER.

107.22. WORKING AREA

The CONTRACTOR shall confine its equipment, storage of materials and construction operations to the area shown on the Contract drawings or stated in the specifications, prescribed by ordinance, laws, or permits or as may be directed by the OWNER, and shall not unreasonably encumber the site or public right-of-way with its construction equipment, plant or materials.

Such area shall not be deemed for the exclusive use of the CONTRACTOR. Other CONTRACTORS of the OWNER may enter upon and use such portions of the area and for such items as determined by the OWNER are necessary for all purposes required by its contracts. The CONTRACTOR shall give to such other CONTRACTORS all reasonable facilities and assistance to the end that the work on this and other contracts shall not be unduly or unreasonably delayed. Any additional areas desired by the CONTRACTOR for its use shall be provided at its own effort, cost and expense.

All rights-of-way and easements shown on the plans for construction will be provided by the OWNER. If private property is leased or occupied by the CONTRACTOR for use in conjunction with the Work, the CONTRACTOR shall provide to the OWNER, in writing prior to final acceptance of the Work, a release of the CONTRACTOR and OWNER from any and all claims the private property OWNER has or may have as a result of the CONTRACTOR'S use of the private property during the course of the Work. The release shall be signed by the private property OWNER or the private property OWNER'S agent.

107.23. RAILWAY CROSSINGS

Where the work encroaches upon any right-of-way of any railway, the OWNER shall secure the necessary easement for the work. Where railway tracks are to be crossed, the CONTRACTOR shall observe all the regulations and instructions of the railway company as to methods of doing the work or precautions for safety of property and the public. All negotiations with the railway company, except for right-of-way, shall be made by the CONTRACTOR. The railway company shall be notified by the CONTRACTOR not less than five days prior to commencing the work. The CONTRACTOR shall not be paid separate compensation for such railway crossing but shall receive only the compensation as set out in the proposal.

Prior to crossing or working on Railroad Right-of-Way, the CONTRACTOR will be required to contact the railroad company, or companies, and to execute CONTRACTOR'S Agreements as may be required by each railroad company involved. No work shall be permitted where railroads are involved until the OWNER is furnished sufficient correspondence from the railroad company involved to ascertain that either the agreement has been executed or a certified copy of the insurance policy furnished, or that no such action is required.

107.24. EXISTING STRUCTURES, FACILITIES AND APPURTENANCES

107.24.1. General. This [Item 107.24](#). Existing Structures, Facilities and Appurtenances addresses only matters arising from certain existing, man-made surface and subsurface structures, facilities and appurtenances, not naturally occurring conditions. **AS PROVIDED IN [ITEM 103.1](#). CONTRACTOR'S WARRANTIES AND UNDERSTANDING, THE OWNER SHALL HAVE NO LIABILITY WHATSOEVER FOR ANY CLAIM ARISING FROM A DIFFERING, NATURALLY OCCURRING SURFACE OR SUBSURFACE CONDITION, OR FROM ANY MAN-MADE CONDITION THAT IS NOT A SURFACE OR SUBSURFACE STRUCTURE, FACILITY OR APPURTENANCE.** The OWNER'S responsibility for any claim arising from existing, man-made surface and subsurface structures, facilities and appurtenances is governed solely by this [Item 107.24](#). Existing Structures, Facilities and Appurtenances, and any situation involving a differing subsurface condition not included herein shall be governed solely by [Item 103.1](#). CONTRACTOR'S Warranties and Understanding.

107.24.2. Showing Locations. The plans show the general locations of all known, existing man-made surface and subsurface structures, facilities and appurtenances. The locations of many gas mains, water and wastewater mains, storm sewers, drains, culverts, conduits and other man-made utility structures, facilities and appurtenances, however, are unknown. **THE OWNER DOES NOT WARRANT THE PLANS TO SHOW THE EXACT LOCATIONS OF ANY AND ALL KNOWN, EXISTING MAN-MADE SURFACE AND SUBSURFACE STRUCTURES, FACILITIES AND APPURTENANCES, AND DOES NOT WARRANT THAT IT KNOWS OF THE EXISTENCE OF ALL POSSIBLE EXISTING MAN-MADE SURFACE AND SUBSURFACE STRUCTURES, FACILITIES AND APPURTENANCES.** The OWNER assumes no responsibility, except as provided below, for any failure to show any or all of these structures on the plans or to show them in their exact locations.

Wherever the OWNER has caused certain test borings to be made on the site, or when any information pertaining to the character or depth of materials is found from observations, records or otherwise, such information revealed thereby may be indicated on the plans. The action of the OWNER in revealing such information shall not in any manner be construed as conclusive or as a warranty on the part of the OWNER of the exact nature of the subsurface conditions that shall be encountered during construction of the work. Although the information is shown as accurately as possible, the OWNER does not guarantee that any materials to be encountered at any point or points are even approximately the same, either in character or elevations, as those shown on the plans. The information thus furnished by the OWNER is intended only as a guide to the CONTRACTOR'S own investigations preliminary to submitting a bid for the work.

107.24.2.1. Soil Borings. Soil Borings are to be used for information only and are not warranted accurate or conclusive in any way. The OWNER accepts no responsibility for any deviation from or variance in soil types and/or depths shown on the borings.

107.24.3. Conditions for Increases to Work or Payment. The CONTRACTOR and OWNER mutually, expressly agree that the failure of the OWNER to show any existing, man-made surface or subsurface structure, facility or appurtenance on the plans, or the failure to show them on the plans in their exact locations, shall not be considered as a basis of a claim for Extra Work, damages or other compensation of

any kind, nor shall it be considered as a basis for increasing the quantities of work or unit prices on any bid item, unless:

- (1) The CONTRACTOR could not have discovered the existing, man-made surface or subsurface structure, facility or appurtenance by a reasonable review of the plans and specifications and a reasonable, careful inspection of the work site prior to bid opening or award of the Contract; and
- (2) The existing, man-made surface or subsurface structure, facility or appurtenance is in a location that necessitates a substantial change in the alignment, depth or hydraulic gradient of the work to be constructed under the Contract because the CONTRACTOR cannot, by the use of reasonable skill or care, place the work in accordance with the original alignment, depth or hydraulic gradient; or
- (3) The existing surface or subsurface structure, facility or appurtenance requires the construction of a special structure, facility, appurtenance or other special work, provisions for which are not already made in the plans and specifications, to protect either the existing, man-made surface or subsurface structure, facility or appurtenance or the work to be constructed under the Contract from damage.

If the elements of (1) and either (2) or (3) occur, the provisions of the specifications regarding claims for Extra Work apply. Otherwise, the condition is considered part of the Contract work and OWNER shall not be liable for extra compensation. Provided, however, that the OWNER will not be liable for payment of Extra Work claims under this subsection that are not timely filed in accordance with other provisions of the specifications, nor shall the OWNER be liable to pay for any additional work or additional costs arising solely from a decision of the CONTRACTOR to change the original means or methods of construction chosen because an existing, man-made surface or subsurface structure, facility or appurtenance is encountered.

107.24.4. Utility Coordination and Protection. It is the intention of the OWNER that all known conflicts between utility-owned facilities and the proposed construction will be cleared prior to the issuance of the work order. Utility information shown on the plans must be confirmed by actual field check in advance of construction. Table 107.24.4.(a) Utility Coordination lists the most frequently needed contacts.

Table 107.24.4.(a) Utility Coordination

Entity	Contact Information
Texas One Call system	811
Municipal, Governmental, or Quasi-Governmental Utility OWNER	CONTRACTOR shall contact the respective entity

It will be the CONTRACTOR'S responsibility to locate and report all utility conflicts to the OWNER promptly in order to avoid unnecessary delays, and the CONTRACTOR will cooperate with utility OWNER s in making the adjustment(s). Conflicts that are found during construction will be resolved as expeditiously as possible.

The CONTRACTOR will be required to protect adequately all utility-owned facilities from damage or displacement by its operations.

The adjustment or location of any utility-owned facility which the CONTRACTOR may desire for its own convenience or ease of construction will be its responsibility to coordinate and will be at its own expense.

CONTRACTOR shall further abide by the provisions of [Item 201.2](#). Determining Location and Protection of Existing Structures and Utilities.

107.25. PROJECT CLEAN-UP

The CONTRACTOR shall keep the project site in a neat and orderly condition as an integral part of the contracted work and as such shall be considered subsidiary to the appropriate bid items. Clean up work shall be done as needed or as directed by the OWNER as the work progresses. Clean-up shall be done on a daily basis. Clean up work shall include, but not be limited to:

- (1) Removing the trash, paper, rubbish and debris resulting from operations
- (2) Sweeping streets clean of dirt or debris
- (3) Alleviating any dust nuisance in the work area
- (4) Storing excess material in appropriate and organized manner
- (5) Keeping trash of any kind off of residents' property

The CONTRACTOR, prior to utilizing any private property, shall provide a written agreement between the CONTRACTOR and the Property OWNER to the Project Manager or Construction Superintendent. The agreement shall state what uses are allowed for the property, the length of time the CONTRACTOR is allowed to use it and the final condition the property shall be returned to once all work is completed. CONTRACTOR shall provide a written release from the Property OWNER once the area has been restored.

The work shall be so conducted as to create a minimum amount of inconveniences to the public. At any time when in the judgment of the OWNER the CONTRACTOR has obstructed or closed or is carrying on operations in a greater portion of a park, street or public way than is necessary for the proper execution of the work, the OWNER may require the CONTRACTOR to finish the sections on which work is in progress before operations are started on any additional section.

The CONTRACTOR will be required to remove spoil from the job site in a timely manner. If, in the opinion of the OWNER, the spoil is not being removed as required, the CONTRACTOR will be directed to remove the spoil. The CONTRACTOR must comply with this directive within 24 hours. There will be no additional compensation to the CONTRACTOR for removing this spoil at a time other than as planned. CONTRACTOR shall comply with all requirements and regulations for any spoil removed from the project.

The CONTRACTOR shall perform such cleanup work as deemed necessary by the OWNER. Failure of the CONTRACTOR to maintain the site in a neat and orderly condition will be cause for withholding an additional ten percent (10%) of the total payments until said condition is corrected. Storage areas, either fenced or open, shall be kept free of weeds, tall grass, and other debris. In instances of large scale irrigation and planting installation, the entire site shall be kept neat and orderly with no tall grass or weed growth allowed. It shall be the CONTRACTOR'S responsibility to see that the turf areas are kept mowed during entire progress of the work. If the CONTRACTOR fails to alleviate poorly maintained conditions upon written notice by the OWNER, the OWNER will take necessary steps to correct the poor conditions with cost of such corrections to be deducted from the Contract.

Upon completion of the work and before final acceptance and final payment shall be made, the CONTRACTOR shall completely clean and remove from the site of the work all equipment, construction materials, surplus and discarded materials, temporary structures and debris of every kind. CONTRACTOR shall leave the site of the work in a neat and orderly condition equal to that which originally existed, or as called for in the Contract documents. Surplus and waste materials removed from the site of the work shall be disposed of at locations satisfactory to the OWNER, and at the CONTRACTOR'S sole cost.

107.26. DISPOSAL OF MATERIALS

Surplus excavation and other materials removed as a part of the construction may be deposited at a legal disposal site in accordance with all applicable federal, state and local laws and regulations. In addition, if the materials are disposed of within private property, a release from the property OWNER must be obtained before final acceptance of the Work as described in [Item 107.22. Working Area](#).

Surplus excavation and other materials must not be deposited in areas designated as flood plain or along natural drainage ways. Material so deposited will be required to be removed at the CONTRACTOR'S expense and the area restored to its natural condition.

Failure to comply promptly with the requirements of this special provision will result in withholding of payments due.

107.27. RESTORATION OF PROPERTY

When and where any damage or injury is done to public or private property on the part of the CONTRACTOR, it shall restore or have restored at its own cost and expense such property to a condition equal (or improved) to that existing before such damage was done by repairing, rebuilding or otherwise restoring as may be directed, or it shall make good such damage or injury in a manner acceptable to the property OWNER or the OWNER. Replacement of previously constructed items, such as curb, gutter, sidewalks, driveways, paving, etc., shall conform to the specifications for new construction, unless directed otherwise by the OWNER.

In case of failure on the part of the CONTRACTOR to restore such property or make good such damage or injury, the OWNER may, upon 48 hours written notice, under ordinary circumstances, and without notice when a nuisance or hazardous condition results, proceed to repair, rebuild or otherwise restore such property as may be determined necessary, and the cost thereof shall be deducted from any monies due or to become due the

CONTRACTOR under its Contract; or where sufficient Contract funds are unavailable for this purpose the CONTRACTOR or its surety shall reimburse the OWNER for all such costs.

107.28. ENVIRONMENTAL COMPLIANCE

The CONTRACTOR and its SUBCONTRACTORS are deemed to have made themselves familiar with and at all times shall comply with any and all applicable federal, state or local laws, rules, regulations, ordinances, and rules of common law now in effect (including any amendments now in effect), relating to the environment, Hazardous Substances or exposure to Hazardous Substances, including but not limited to the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C.A. §§ 9601, et seq.; the Hazardous Materials Transportation Act, 49 U.S.C.A. §§ 1801, et seq.; the Resource Conservation and Recovery Act of 1976, 42 U.S.C.A. §§ 6901, et seq.; the Federal Water Pollution Control Act, 33 U.S.C.A §§ 1201, et seq.; the Clean Water Act, 33 U.S.C. § 1251, et seq., the Toxic Substances Control Act, 15 U.S.C.A. §§ 2601, et seq.; the Clean Air Act, 42 U.S.C.A. §§ 7401, et seq.; the Safe Drinking Water Act, 42 U.S.C.A. §§ 3808, et seq., and the latest judicial or administrative interpretation of these laws, rules, regulations, ordinances, or rules of common law, including but not limited to any judicial or administrative order, consent decree, or judgment affecting the Project.

In the event the CONTRACTOR encounters on the site materials reasonably believed to be a Hazardous Substance that have not been rendered harmless, and removal of such materials is not a part of the scope of work required under the contract documents, the CONTRACTOR shall immediately stop work in the affected area and report in writing the facts of such encounter to the OWNER. Work in the affected area shall not thereafter be resumed except by written order of the OWNER unless and until the material is determined not to be a Hazardous Substance or the Hazardous Substance is remediated. The OWNER may choose to remediate the Hazardous Substance with a separate CONTRACTOR or through a Change Order with the CONTRACTOR. If the OWNER determines that the Hazardous Substance exists in the affected area due to the fault or negligence of the CONTRACTOR or any of its SUBCONTRACTORS, the CONTRACTOR shall be responsible for remediating the condition at the sole expense of the CONTRACTOR in accordance with the CONTRACTOR'S Spill Prevention and Response Plan. An extension of working time for any delay in the progress schedule caused as a result of the discovery and remediation of a hazardous substance may be granted by the OWNER only if all remaining work on the project must be suspended and the delay cannot be made up elsewhere in the progress schedule. Any claim or request for an extension of working time by the CONTRACTOR in connection with the discovery and remediation of a hazardous substance is subject to the provisions of NCTCOG.

The CONTRACTOR shall be responsible for identification, abatement, cleanup, control, removal, remediation, and disposal of any Hazardous Substance brought into or upon the site by the CONTRACTOR or any SUBCONTRACTOR or supplier. The CONTRACTOR shall obtain any and all permits necessary for the legal and proper handling, transportation, and disposal of the Hazardous Substance and shall, prior to undertaking any abatement, cleanup, control, removal, remediation, and disposal, notify the OWNER so that they may observe the activities; provided, however, that it shall be the CONTRACTOR'S sole responsibility to comply with all applicable laws, rules, regulations, or ordinances governing the activities.

The CONTRACTOR shall deposit surplus or waste excavation or other materials removed as part of the work at a legal disposal site in accordance with all applicable state, federal, and local laws, rules, regulations, and ordinances. The CONTRACTOR shall submit to the OWNER for review and approval all planned disposal sites or proposed uses for the surplus or waste excavation or other materials prior to removal of any excavation or other material from the Project site. A copy of all transport manifests for surplus or waste excavation or other materials shall be obtained and retained in the CONTRACTOR'S records for reference purposes, to be provided upon request to the OWNER or any governmental regulatory agency with jurisdiction over the matter.

107.28.1. Spill Prevention Plan. At least seventy-two (72) hours prior to commencing performance of any of the work at the Project site, the CONTRACTOR shall submit to the OWNER for review and approval a Spill Prevention and Response Plan (SPRP) meeting the requirements of federal and state law, rules, and regulations. The SPRP shall be specially designed for the CONTRACTOR'S planned work methods and procedures. The SPRP shall be designed to complement all applicable safety standards, fire prevention regulations, and pollution prevention policies and procedures. The SPRP shall include estimates of the quantity and rate of flow should equipment fail, and detail containment or diversionary structures to prevent spills from leaving the site or migrating into adjacent properties or navigable waters. The SPRP shall include

methods of recovery of spilled materials and all applicable twenty-four (24) hour emergency phone numbers, including without limitation that of the OWNER. The CONTRACTOR shall not commence any fieldwork prior to approval of such plan by the OWNER. The following additional rules shall apply with respect to spills caused by the CONTRACTOR or a SUBCONTRACTOR:

- (1) The CONTRACTOR shall immediately report any spill or release at the Project site, whether or not it is associated with this contract, to the OWNER or other designated representative. Thereafter, within two (2) working days after the occurrence of such event, the CONTRACTOR shall submit a written report describing such event in a degree of detail reasonably acceptable to the OWNER.
- (2) The CONTRACTOR shall immediately respond in accordance with the SPRP in the event of a spill.
- (3) The CONTRACTOR shall dispose of spilled materials in accordance with EPA and Texas Commission on Environmental Quality (TCEQ) regulations and any other applicable federal, state, or local laws, rules, or regulations. In connection with such disposals, the CONTRACTOR shall use only those transporters and disposal facilities that are approved in advance in writing by the OWNER. A copy of all transport manifests for the spilled materials shall be obtained and retained in the CONTRACTOR'S records for reference purposes, to be provided upon request of the OWNER or any governmental regulatory agency with jurisdiction over the matter. All costs of collection, containment, and disposal of spilled materials shall be the sole responsibility of the CONTRACTOR.
- (4) The term spill includes any kind of environmental discharge or release.

107.28.2. Texas Pollutant Discharge Elimination System. The CONTRACTOR is responsible for obtaining coverage under the Texas Pollutant Discharge Elimination System (TPDES) Construction General Permit from TCEQ for construction of the Project under regulations contained in 40 CFR Part 122, as amended, pursuant to the Clean Water Act, 33 U.S.C.A. §§1251 et seq. and Chapter 26 of the Texas Administrative Code. These regulations require the filing of a Notice of Intent (NOI) to obtain and abide by the general stormwater permit for construction activities promulgated by EPA as administered by the TCEQ, including but not limited to demolition, clearing, grading, embankment, and excavation that disturb the applicable amount of total land area. In addition, the CONTRACTOR shall comply with all regulations of the OWNER relating to stormwater and stormwater runoff management at the Project site.

107.28.3. Stormwater Permit. The CONTRACTOR shall provide a Storm Water Pollution Prevention Plan (SWPPP) in accordance with the requirements of the TPDES Construction General Permit, and Storm Water Pollution Prevention Plan, of these Specifications. The CONTRACTOR is responsible for obtaining an Storm Water Discharge Permit that may be required for construction of this project under regulations contained in 40 CFR Part 122, as amended, under the authority of the Clean Water Act, 33 U.S.C. 1251 et seq. These regulations require the filing of a notice of intent to obtain and abide by the general storm water permit for construction activities, including cleaning, grading, and excavation, that disturb the applicable amount of total land area. For permitting information and requirements, contact USEPA Region VI, Fountain Place 12th Floor, Suite 1200, 1445 Ross Ave., Suite 1200, Dallas, Texas 75202-2733, (214) 665-2200 and Texas Commission on Environmental Quality.

If a permit is required, the CONTRACTOR shall provide measures to control soil erosion sediment and water pollution created by construction operations for the duration of the Contract as directed by the OWNER. These measures shall be in addition to those required of the CONTRACTOR under [Item 202](#). Temporary Erosion, Sedimentation, and Water Pollution Prevention and Control of these specifications.

107.28.4. Asbestos-Related Materials. The CONTRACTOR shall not install any materials in the performance of the work that contain asbestos or asbestos-related material such as hydrated mineral silicate, including chrysolite, amosite, crocidolite, trifoliate, anthophyllite or actinolite, whether friable or non-friable.

107.28.5. Failure to Comply. The OWNER reserves the right in its sole option to exercise the following remedies (without waiving the right to pursue the imposition of any civil or criminal fines or penalties that may be imposed under state, federal, or local laws or ordinances), at no additional cost to the OWNER and without an extension of time, in the event the CONTRACTOR fails or refuses after seven (7) days advance written notice from the OWNER to comply with these provisions, the terms of the SPRP, any environmental permit or submittal issued in connection with the work, or any applicable environmental law, rule, regulation, or ordinance:

- (1) suspend all or any portion of the work until the noncompliance is corrected, or until a detailed plan to achieve compliance within a reasonably prompt period of time is prepared by the CONTRACTOR and approved by the OWNER;
- (2) if the CONTRACTOR fails to properly address the noncompliance within the time stipulated by the OWNER, perform the necessary remediation or correction work and back charge the CONTRACTOR for the cost of the remediation or correction; or
- (3) terminate the contract for default as provided in the General Conditions and the Addendum.

ITEM 108. PROSECUTION AND PROGRESS

108.1. PROGRESS SCHEDULE

The CONTRACTOR must submit to the OWNER a detailed Construction Schedule outlining the major items of work on the project. This schedule must be approved as to form by the OWNER prior to CONTRACTOR starting work on the project. The schedule must be updated on a monthly basis unless otherwise specified by the Contract. The OWNER has the authority to stop work on the project if the CONTRACTOR fails to provide an updated schedule as requested.

108.2. PROSECUTION OF THE WORK

The CONTRACTOR shall begin the work to be performed under this Contract not later than 10 days from the date specified in the work order and shall conduct the work in such a manner and with sufficient equipment, material and labor as is necessary to insure its completion within the working time. It is the intent of this specification to provide a continuous construction operation without delay except as occasioned by unforeseeable causes beyond the control and without the fault or negligence of the CONTRACTOR, and it shall be the CONTRACTOR's responsibility to execute the work in the most expeditious manner.

Work shall be done only during the hours between 7:00 am and 6:00 pm unless the OWNER approves other hours.

CONTRACTOR may work on Saturdays if it so desires and permission of the OWNER has been granted. Work on Sundays shall be permitted only with the written permission of the OWNER. If Saturday or Sunday work is permitted, working time shall be charged on the same basis as weekdays. Where the working time is expressed as calendar days or a specific date, the concept of working days shall no longer be relevant to the Contract. Work requiring inspection will not be permitted on a legal City holiday except by special written permission of the OWNER. Any work done without proper inspection is subject to removal and replacement at the direction of the OWNER.

The rate of progress shall be such that the whole work shall be performed, including completion of all punch list items, and the premises cleaned up in accordance with the Contract within the working time established in the Contract, unless an extension of time is made in the manner as specified in [Item 108.8](#). Delays; Extension of Time; Liquidated Damages.

108.2.1. Prosecution of the Work Discontinued By CONTRACTOR. Should the prosecution of the work be discontinued by the CONTRACTOR, the CONTRACTOR shall notify the OWNER at least twenty-four hours in advance of resuming operations.

108.3. OTHER CONTRACTORS; OBLIGATION TO COOPERATE

The OWNER may award other contracts for additional work on this project, or in or near the project area, and the CONTRACTOR shall fully cooperate with such other CONTRACTOR(s) and shall coordinate and fit its work to be done hereunder to such additional work as may be contracted by the OWNER. At the time of bidding, prospective bidders shall be advised of other planned contract work, which is expected to affect the work area. The CONTRACTOR shall not commit or permit any act, which shall interfere with the performance of work by any other CONTRACTOR.

Upon receiving written notice from the CONTRACTOR that another CONTRACTOR is failing to coordinate its work with the work under this Contract as directed by the OWNER, the OWNER shall promptly investigate the charge and take such necessary action as the situation may require. However, the OWNER shall not be liable to the CONTRACTOR for damages suffered by the CONTRACTOR due to the fault or negligence of another CONTRACTOR or through failure of another CONTRACTOR to carry out the directions of the OWNER. Should any interference occur between CONTRACTORS, the OWNER may furnish the CONTRACTOR with written instructions designating priority of effort or change in methods, whereupon the CONTRACTOR shall immediately comply with such direction. In such event, the CONTRACTOR shall be entitled to an extension of working time only for unavoidable delays verified by the OWNER; however, no increase in the Contract price shall be due the CONTRACTOR.

108.4. EMPLOYEES

The CONTRACTOR shall employ only competent, efficient workpeople and shall not use on the work any unfit person or one not skilled in the work assigned to him or her and shall at all times maintain good order among its employees.

Whenever the OWNER shall inform the CONTRACTOR in writing that, in its opinion, any employee is unfit, unskilled, disobedient or is disrupting the orderly progress of the work, such employee shall be removed from the work and shall not again be employed on it.

Under urgent circumstances, the OWNER may orally require immediate removal of an employee for cause, to be followed by written confirmation.

108.5. SUBCONTRACTS

The CONTRACTOR shall not make any subcontract for performing any portion of the work included in the Contract without written notice to the OWNER. This Contract having been made pursuant to the bid submitted by the CONTRACTOR and in reliance with the CONTRACTOR's personal qualifications and responsibility, the OWNER reserves the right to withhold approval of any SUBCONTRACTOR which the OWNER may deem would not be in the OWNER's best interest.

The CONTRACTOR shall, as soon as practicable after signing the Contract, submit a separate written notice to the OWNER identifying each proposed SUBCONTRACTOR. Upon request of the OWNER, the CONTRACTOR shall promptly furnish additional information tending to establish that any proposed SUBCONTRACTOR has the necessary facilities, skill, integrity, past experience and financial resources to perform the work in accordance with the terms and conditions of this Contract.

If the OWNER determines that any proposed SUBCONTRACTOR is unacceptable, it shall so notify the CONTRACTOR, who may thereupon submit another proposed SUBCONTRACTOR unless the CONTRACTOR decides to do the work itself. Disapproval by the OWNER of any proposed SUBCONTRACTOR shall not provide a basis for any claim time extension or additional compensation of any nature, including but not limited to anticipated profit, overhead or delay, by the CONTRACTOR.

If an approved SUBCONTRACTOR fails to properly perform the work undertaken, it shall be removed from the job upon request of the OWNER, following notification to the CONTRACTOR in writing of the request for removal and the reasons therefore.

Each subcontract entered into shall provide that the provisions of this Contract shall apply to all SUBCONTRACTORS and their officers and employees in all respects as if they were employees of the CONTRACTOR. The OWNER's decision not to disapprove of any subcontract shall not relieve the CONTRACTOR of any of its responsibilities, duties and liabilities hereunder. The CONTRACTOR shall be solely responsible for the acts, omissions, negligence or defaults of its SUBCONTRACTORS and of such SUBCONTRACTOR's officers, agents and employees, each of whom shall, for this purpose, be deemed to be the agent or employee of the CONTRACTOR to the extent of its subcontract.

The CONTRACTOR agrees to bind each SUBCONTRACTOR and each SUBCONTRACTOR agrees to be bound by the terms of the Contract documents insofar as applicable to its respective work. The CONTRACTOR and each SUBCONTRACTOR jointly and severally agree that nothing in the Contract documents or otherwise shall create or be deemed to create any rights in favor of a SUBCONTRACTOR against the OWNER; nor shall be deemed or construed to impose upon the OWNER any obligation, liability or duty to a SUBCONTRACTOR; or to create any contractual relation whatsoever between a SUBCONTRACTOR and the OWNER.

The provisions contained herein shall likewise apply to any sub-subcontracts.

108.6. CONTRACTOR WORK BY ITS OWN FORCES

Except as otherwise provided, CONTRACTOR shall perform no less than 25% of the Work with its own workforce. If the CONTRACTOR proposes to perform less than 50% of the work by its own forces, then the OWNER may require additional documentation with the bid submittal regarding qualifications of SUBCONTRACTORS actually performing work.

108.6.1. Assignments. The CONTRACTOR shall not assign, transfer, convey or otherwise dispose of this Contract, or its right to execute it, or its right, title or interest in it or any part thereof without the previous written consent of the surety company and the written approval of the OWNER.

The CONTRACTOR shall not assign, either legally or equitably, by power of attorney or otherwise, any of the monies due or to become due under this Contract or its claim thereto without the prior written consent of the surety company and the written approval of the OWNER. Nothing in this paragraph is intended to conflict with Texas Business and Commerce Code.

The approval of the OWNER of a particular assignment, transfer or conveyance shall not dispense with such approval to any further or other assignments.

The approval by the OWNER of any assignment, transfer or conveyance shall not operate to release the CONTRACTOR or surety hereunder from any of the Contract and bond obligations, and the CONTRACTOR shall be and remain fully responsible and liable for the defaults, negligent acts and omissions of its assignees, its agents and employees, as if they were its own.

108.7. OWNER'S RIGHT TO TEMPORARILY SUSPEND WORK

108.7.1. Reasons for Suspension. The OWNER shall have the right by written order to temporarily suspend the work, in whole or in part, whenever, in the judgment of the OWNER, such temporary suspension is required:

- (1) in the interest of the OWNER generally,
- (2) due to government or judicial controls or orders which make performance of this Contract temporarily impossible or illegal,
- (3) to coordinate the work of separate CONTRACTORS at the job site,
- (4) to expedite the completion of a separate contract even though the completion of this particular Contract may be thereby delayed,
- (5) because of weather conditions unsuitable for performance of the work, including of designated ozone alerts as determined by the National Weather Bureau or other authorized agency; or
- (6) because the CONTRACTOR is proceeding contrary to Contract provisions or has failed to correct conditions considered unsafe for workers.

The written order of the OWNER to the CONTRACTOR shall state the reasons for suspending the work and the anticipated periods for such suspension. Upon receipt of the OWNER'S written order, the CONTRACTOR shall suspend the work covered by the order and shall take such means and precautions as may be necessary to properly protect the finished and partially finished work, the unused materials and uninstalled equipment, including the providing of suitable drainage about the work and erection of temporary structures where necessary. The CONTRACTOR shall not suspend the work without written order from the OWNER and shall proceed with the work promptly when notified by the OWNER to resume operations.

108.7.2. No Additional Compensation. No additional compensation shall be paid to the CONTRACTOR for any suspension under [Item 108.7.1.](#) (6) above or otherwise where same is caused by the fault of the CONTRACTOR. Where such temporary suspension is not due to the fault of the CONTRACTOR, it shall be entitled to:

- (1) an extension of working time for the completion of the work, not to exceed the delay caused by such temporary suspension, as determined by the OWNER; and
- (2) the actual and necessary costs of properly protecting the finished and partially finished work, unused materials and uninstalled equipment during the period of the ordered suspension as determined by the OWNER as being beyond the Contract requirements, such costs, if any, to be determined on the basis set forth in [Item 109.3.](#) Payment for Extra Work herein; and
- (3) where the CONTRACTOR elects to move equipment from the job site and then return it to the site when the work is ordered resumed, the actual and necessary costs of these moves, in an amount determined by the OWNER under the provisions of [Item 109.3.](#) Payment for Extra Work; provided, however, no compensation shall be allowed if the equipment is moved to another construction project for the OWNER.
- (4) where such temporary suspension is not due to the fault of the CONTRACTOR and is the result of a designated Ozone Alert Period, the CONTRACTOR shall be entitled to additional time as provided in (1) above, but is not entitled to additional compensation.

Other than the additional time and compensation stated above, CONTRACTOR shall not be entitled to any other time extension related to the suspension, nor any additional compensation in any way related to such suspension.

108.7.3. Emergency Contract Termination Clause. Whenever, because of a national emergency, so declared by the President of the United States, or other lawful authority, it shall be impossible for the CONTRACTOR to obtain all labor, materials, and equipment necessary for the prosecution of the work with reasonable continuity, the CONTRACTOR shall notify the OWNER. If the OWNER cannot, after a reasonable time, help obtain priorities for the materials and equipment within a reasonable effort, then the Contract shall be considered as terminated, and the CONTRACTOR shall be entitled to payment for work performed that is acceptable to OWNER based upon unit prices contained in the bid or, if the Contract is lump sum, then based upon the schedule of values submitted by the CONTRACTOR. CONTRACTOR shall not be entitled to any compensation for anticipated profit, overhead, delay damages or any other compensation for work that has not been performed.

108.8. DELAYS; EXTENSION OF TIME; LIQUIDATED DAMAGES

The CONTRACTOR shall be entitled to an extension of working time under this Contract only when claim for such extension is submitted to the OWNER in writing by the CONTRACTOR within fourteen (14) days from and after the time when any alleged cause of delay shall occur, and then only when such time is approved by the OWNER. The CONTRACTOR shall notify the OWNER immediately upon encountering any condition that the CONTRACTOR believes may cause a claim for a time extension. In adjusting the contract time for the completion of the project, unforeseeable causes beyond the control and without the fault or negligence of the CONTRACTOR, including but not restricted to inability to obtain supplies and materials when orders for such supplies and materials were timely made and materials are not available from other sources, acts of God or the public enemy, acts of the OWNER, fires, floods, epidemics, quarantine restrictions, strikes, freight embargoes, unusually severe weather conditions, ozone alerts as determined by the National Weather Bureau or other authorized agency, or delays of SUBCONTRACTORS due to such causes beyond their control shall be taken into consideration.

If the satisfactory execution and completion of the Contract should require work and materials in greater amounts or quantities than those set forth in the Contract, requiring more time for completion than the anticipated time, then the Contract time shall be increased, but not more than in the same proportion as the cost of the additional work bears to the cost of the original work contracted for. No allowances shall be made for delays or suspension of the performance of the work due to the fault of the CONTRACTOR.

No adjustment of the Contract time shall be made if, concurrently with the cause for delay, hindrance, disruption, force majeure, impact or interference, there existed a cause for delay due to the fault or negligence of the CONTRACTOR or CONTRACTOR'S agents, employees or SUBCONTRACTORS. Notwithstanding any other provisions of the Contract Documents, including the General and Special Provisions, no adjustment shall be made to the Contract price and the CONTRACTOR shall not be entitled to claim or receive any additional compensation as a result of or arising out of any delay, hindrance, disruption, force majeure, impact or interference, foreseen or unforeseen, resulting in adjustment of the Contract time to complete the project, **including but not limited to those caused in whole or in part by the acts, omissions, failures, negligence or fault of the OWNER, its officers, officials, agents, Engineer, Consulting Engineer or employees**. This provision is intended to cover all delays except as prohibited by law. If a recoverable delay is caused by the sole fault of the OWNER, compensation will be limited to an amount to be determined pursuant to Section [109.3.3](#). Force Account Work notwithstanding any other provision of the Contract documents, all claims for extension of working time must be submitted in accordance with [Item 108.8](#). Delays; Extension of Time; Liquidated Damages, and no act of the OWNER shall be deemed a waiver or entitlement of such extension.

108.8.1. Liquidated Damages for Failure to Complete on Time. The time of completion is the essence of this Contract. For each day that any work shall remain uncompleted after the time specified in the proposal and the Contract, or the increased time granted by the OWNER, or as equitably increased by additional work or materials ordered after the Contract is signed, the sum per day given in the Schedule 108.8.1. (a) Liquidated Damages, unless otherwise specified, shall be deducted from the monies due the CONTRACTOR.

Schedule 108.8.1. (a) Liquidated Damages

Amount of Contract (\$)	Amount of Liquidated Damages (\$)
Less than 25,000.00	200.00 Per Day
25,000.00 to 99,999.99	350.00 Per Day
100,000.00 to 999,999.99	500.00 Per Day
More than 1,000,000.00	1000.00 Per Day

The sum of money thus deducted for such delay, failure or noncompletion is not to be considered as a penalty, but shall be deemed, taken and treated as reasonable liquidated damages, per day that the CONTRACTOR shall be in default after the time stipulated in the Contract for completing the work. The said amounts are fixed and agreed upon by and between OWNER and CONTRACTOR because of the impracticability and extreme difficulty of fixing and ascertaining the actual damages the OWNER in such event would sustain; and said amounts are agreed to be the amount of damages which the OWNER would sustain and which shall be retained from the monies due, or that may become due, the CONTRACTOR under this Contract; and if said monies be insufficient to cover the amount owing, then the CONTRACTOR or its surety shall pay any additional amounts due.

In the event that the actual damages incurred by the OWNER exceed the amount of liquidated damages, OWNER shall be entitled to recover its actual damages.

108.9. CONTRACTOR DEFAULT: OWNER'S RIGHT TO SUSPEND WORK AND ANNUL CONTRACT

The work or any portion of the work under this Contract shall be suspended immediately on written order of the OWNER declaring the CONTRACTOR to be in default. A copy of such notice shall be served on the CONTRACTOR's surety. The Contract may be terminated by the OWNER for any good cause or causes, among others of which special reference is made to the following:

- (1) failure of the CONTRACTOR to start the work within 10 days from date specified in the written work order issued by the OWNER to begin the work;
- (2) substantial evidence that the progress of the work being made by the CONTRACTOR is insufficient to complete the work within the specified working time;
- (3) failure of the CONTRACTOR to provide sufficient and proper equipment, materials or construction forces for properly executing the work;
- (4) substantial evidence that the CONTRACTOR has abandoned the work or discontinued the performance of the work or any part thereof and failure to resume performance within a reasonable time after notice to do so;
- (5) substantial evidence that the CONTRACTOR has become insolvent or bankrupt, or otherwise financially unable to carry on the work;
- (6) deliberate failure on the part of the CONTRACTOR to observe any requirements of the Contract Documents or to comply with any orders given by the OWNER or Engineer as provided for in the Contract Documents;
- (7) failure of the CONTRACTOR to promptly make good any defects in materials or workmanship, or any defects of any nature, the correction of which has been directed in writing by the OWNER;
- (8) substantial evidence of collusion for the purpose of illegally procuring a contract or perpetrating fraud on the OWNER in the construction of work under Contract;
- (9) repeated and flagrant violations of safe working procedures;
- (10) the filing by the CONTRACTOR of litigation against the OWNER prior to final completion of the work.

When the work is suspended for any of the causes itemized above, or for any other cause or causes, the CONTRACTOR shall discontinue the work or such part thereof as the OWNER shall designate, whereupon the surety may either at its option assume the Contract or that portion thereof which the OWNER has ordered the CONTRACTOR to discontinue and perform the same or, with the written consent of the OWNER, sublet the same, provided, however, that the surety shall exercise its option within two weeks after the written notice to discontinue the work has been served upon the CONTRACTOR and upon the surety or its authorized agents. The surety in such event shall assume the CONTRACTOR's place in all respects and shall be paid by the OWNER for all work performed by it in accordance with the terms of the Contract, but in no event shall such payments exceed the Contract amount, regardless of the cost to the surety to complete the work.

All monies remaining due the CONTRACTOR at the time of its default shall thereupon become due and payable to the surety as the work progresses, subject to all terms of the Contract. In case the surety does not, within the hereinabove specified time, exercise its obligation to assume the Contract or that portion thereof which the OWNER has ordered the CONTRACTOR to discontinue, then the OWNER shall have the power to complete by contract or otherwise, as it may determine, the work herein described or such part thereof as it may deem necessary; and the CONTRACTOR hereto agrees that the OWNER shall have the right to take possession of or use any or all of the materials, plant, tools, equipment, supplies and property of every kind provided by the CONTRACTOR for the purpose of its work and to procure other tools, equipment and materials for the completion of the same and to charge to the account of the CONTRACTOR the expense of said contract for labor, materials, tools, equipment and expenses incident thereto. The expense so charged shall be deducted by the OWNER out of such monies as may be due or may at any time thereafter become due the CONTRACTOR under and by virtue of the Contract or any part thereof.

The OWNER shall not be required to obtain the lowest bid for the work of completing the contract, but the expenses to be deducted shall be the actual cost of such work. In case such expense is less than the sum which would have been payable under the Contract if the same had been completed by the CONTRACTOR, then in such case the OWNER may pay the CONTRACTOR the difference in the cost, provided that the CONTRACTOR shall not be entitled to any claim for damages or for loss of anticipated profits.

In case such expense shall exceed the amount which would have been payable under the Contract if the same had been completed by the CONTRACTOR, the CONTRACTOR and its surety shall pay the amount of the excess to the OWNER on notice from the OWNER for excess due including any costs incurred by the OWNER, such as inspection, legal fees and liquidated damages. When any particular part of the work is being carried on by the OWNER by contract or otherwise under the provisions of this section, the CONTRACTOR shall continue the remainder of the work in conformity with the terms of the Contract and in such manner as not to hinder or interfere with the performance of workers employed as above provided by the OWNER or surety.

108.10. SUSPENSION BY COURT ORDER AGAINST THE OWNER

The CONTRACTOR shall suspend such part or parts of the work pursuant to a court order issued against the OWNER and shall not be entitled to additional compensation for anticipated profits, overhead, delay damage or any other form of compensation by virtue of such court order; neither shall the CONTRACTOR be liable to the OWNER in the event the work is suspended by such court order, unless such suspension is due to the fault or negligence of the CONTRACTOR.

108.11. TERMINATION FOR CONVENIENCE OF THE OWNER

108.11.1. Notice of Termination. The performance of the work under this Contract may be terminated by the OWNER in whole or from time to time in part, in accordance with this section, whenever the OWNER shall determine that such termination is in the best interest of the OWNER. Any such termination shall be effected by serving in accordance with [Item 105.8](#). Service of Notices a notice of termination to the CONTRACTOR specifying the extent to which performance of work under the Contract is terminated, and the date upon which such termination becomes effective. Further, it shall be deemed conclusively presumed and established that such termination is made with just cause as therein stated; and no proof in any claim, demand or suit shall be required of the OWNER regarding such discretionary action.

108.11.2. CONTRACTOR Action. After receipt of a notice of termination, and except as otherwise directed by the OWNER, the CONTRACTOR shall:

- (1) stop work under the Contract on the date and to the extent specified in the notice of termination;
- (2) place no further orders or subcontracts for materials, services or facilities except as may be necessary for completion of such portion the work under the Contract as is not terminated;
- (3) (terminate all subcontracts, purchase orders or options to the extent that they relate to the performance of work terminated by the notice of termination or at the OWNER'S written request, deliver and assign to the OWNER, or any person or entity acting on the OWNER'S behalf, any or all subcontracts, purchase orders and options made by CONTRACTOR in the performance of the work, and deliver to the OWNER true and correct originals and copies of such Contract Documents;

- (4) transfer title to the OWNER and deliver in the manner, at the times, and to the extent, if any, directed by the OWNER:
 - a. the fabricated or un-fabricated parts, work in process, completed work, supplies and other material produced as a part of, or acquired in connection with the performance of, the work terminated by the notice of termination; and
 - b. the completed or partially completed plans, drawings, information and other property which, if the Contract had been completed, would have been required to be furnished to the OWNER.
- (5) complete performance of such part of the work as shall not have been terminated by the notice of termination; and
- (6) take such action as may be necessary, or as the OWNER may direct, for the protection and preservation of the property related to its Contract which is in the possession of the CONTRACTOR and in which the OWNER has or may acquire an interest.

At a time not later than 30 days after the termination date specified in the notice of termination, the CONTRACTOR may submit to the OWNER a list, certified as to the quantity and quality, of any or all items of termination inventory not previously disposed of, exclusive of items the disposition of which has been directed or authorized by the OWNER. Not later than 15 calendar days thereafter, the OWNER shall accept title to such items and remove them or enter into a storage agreement covering the same, provided that the list submitted shall be subject to verification by the OWNER upon removal of the items, or, if the items are stored, within 45 calendar days from the date of submission of the list, and provided that any necessary adjustments to correct the list as submitted shall be made prior to final settlement.

108.11.3. Termination Claim. Within 60 days after notice of termination, the CONTRACTOR shall submit its termination claim to the OWNER in the form and with the certification prescribed by the OWNER. Unless one or more extensions in writing are granted by the OWNER upon request of the CONTRACTOR, made in writing within such 60-day period or authorized extension thereof, any and all such claims shall be conclusively deemed waived.

108.11.4. Amounts. Subject to the provisions of [Item 108.11.3](#), Termination Claim, the CONTRACTOR and OWNER may agree upon the whole or any part of the amount or amounts to be paid to the CONTRACTOR by reason of the total or partial termination of work pursuant hereto, provided that such agreed amount or amounts shall never exceed the total Contract price as reduced by the amount of payments otherwise made and as further reduced by the Contract price of work not terminated. The Contract shall be amended accordingly, and the CONTRACTOR shall be paid the agreed amount. No amount shall be due for lost or anticipated profits. Nothing in [Item 108.11.5](#), Failure to Agree hereunder, prescribing the amount to be paid to the CONTRACTOR in the event of failure of the CONTRACTOR and the OWNER to agree upon the whole amount to be paid to the CONTRACTOR by reason of the termination of work pursuant to this section, shall be deemed to limit, restrict or otherwise determine or affect the amount or amounts which may be agreed upon to be paid to the CONTRACTOR pursuant to this paragraph.

108.11.5. Failure to Agree. In the event of the failure of the CONTRACTOR and the OWNER to agree, as provided in [Item 108.11.4](#), Amounts, upon the whole amount to be paid to the CONTRACTOR by reason of the termination of work pursuant to this section, the OWNER shall determine, on the basis of information available to it, the amount, if any, due to the CONTRACTOR by reason of the termination and shall pay to the CONTRACTOR the amounts determined. No amount shall be due for lost or anticipated profits. The OWNER's determination shall be final.

108.11.6. Deductions. In arriving at the amount due the CONTRACTOR under this section, there shall be deducted (a) all unliquidated advance or other payments on account theretofore made to the CONTRACTOR, applicable to the terminated portion of this Contract; (b) any claim which the OWNER may have against the CONTRACTOR in connection with this Contract; and (c) the agreed price for or the proceeds of sale of any materials, supplies or other things kept by the CONTRACTOR or sold, pursuant to the provisions of this clause, and not otherwise recovered by or credited to the OWNER.

108.11.7. Adjustment. If the termination hereunder be partial prior to the settlement of the terminated portion of this Contract, the CONTRACTOR may file with the OWNER a request in writing for an equitable adjustment of the price or prices specified in the Contract relating to the continued portion of the Contract

(the portion not terminated by the notice of termination), and such equitable adjustment as may be agreed upon shall be made in such price or prices; nothing contained herein, however, shall limit the right of the OWNER and the CONTRACTOR to agree upon the amount or amounts to be paid to the CONTRACTOR for the completion of the continued portion of the Contract when said Contract does not contain an established Contract price for such continued portion.

108.11.8. No Limitation of Rights. Nothing contained in this section shall limit or alter the rights, which the OWNER may have for termination of this Contract under [Item 108.9](#), CONTRACTOR Default: OWNER'S Right to Suspend Work and Annual Contract or any other right which OWNER may have for default or breach of Contract by CONTRACTOR.

108.12. CLAIMS AGAINST OWNER AND ACTION THEREON

No claim against the OWNER under the Contract or for breach of the Contract or additional compensation for extra or disputed work shall be made or asserted against the OWNER under the Contract or in any court action except pursuant to the provisions of [Item 109.3](#), Payment for Extra Work, [Item 104.3](#), Disputed Work and Claims for Additional Compensation, and [Item 104.4](#), Performance of Extra or Disputed Work, and unless the CONTRACTOR shall have strictly complied with all requirements relating to the giving of notice and information with respect to such claim as required under said sections. The requirements cannot be waived by the OWNER'S representative, and are not waived by a claimed breach of contract by the OWNER.

108.13. USE OF COMPLETED PORTIONS OF WORK

The OWNER may, after written notice to the CONTRACTOR, and without incurring any liability for increased compensation to the CONTRACTOR, take over and use any completed portion of the work prior to the final completion and acceptance of the entire work included in the Contract, and notwithstanding that the time allowed for final completion has not expired. The CONTRACTOR shall not object to, nor interfere in any way with, such occupancy or use after receipt of the OWNER'S written notice.

Immediately prior to such occupancy and use, the OWNER shall inspect such portion of the work to be taken over and shall furnish the CONTRACTOR a written statement of the work, if any, still to be done on such part. The CONTRACTOR shall promptly thereafter complete such unfinished work to permit occupancy and use on the date specified in the OWNER'S written order, unless the OWNER shall permit specific items of work to be finished after the occupancy and use by the OWNER.

The provisions in the last two paragraphs above shall not apply to portions of roads, streets, bridges or detours upon which traffic is diverted to enable the continuation of the Contract work.

Neither such usage, as performed under this section, nor the written statement of work still to be done shall be held in any way as an acceptance of said work or structure or any part thereof, nor as a waiver of any of the provisions of these specifications or other Contract Documents pending final completion and acceptance of the work; all necessary repairs and removals of any section of the work so put into use, due to the defective materials or workmanship or to operations of the CONTRACTOR, shall be performed by the CONTRACTOR at its own expense.

In the event the CONTRACTOR is unreasonably delayed by the OWNER exercising its rights under this section, the CONTRACTOR may submit a request for an extension of time under [Item 108.8](#), Delays; Extension of Time; Liquidated Damages; no additional compensation or delay damages will be paid.

ITEM 109. MEASUREMENT AND PAYMENT

109.1. PAYMENT FOR LABOR AND MATERIAL; NO LIENS

The CONTRACTOR shall furnish payrolls and personnel records, which pertain to this current Contract with the OWNER for the purpose of ascertaining compliance with minimum wage rates published by the OWNER. Monthly and final estimates for payment will not be processed unless the CONTRACTOR complies with this requirement in a timely manner.

The CONTRACTOR for itself or any of its SUBCONTRACTORS shall pay all indebtedness, which may become due to any person, firm or corporation having furnished labor, material or both in the performance of this Contract. It shall be the responsibility of each person, firm or corporation claiming to have furnished labor, materials or both, in connection with this Contract, to protect its interest in the manner prescribed by applicable laws of the State of Texas, provided, however, that as this Contract provides for a public works project, no lien of any kind shall ever exist or be placed against the work or any portion thereof, or any public funds or retainage held by the OWNER; and any SUBCONTRACTOR shall look solely to the CONTRACTOR and the payment bond surety, and not the OWNER, for payment of any outstanding amounts due for labor, materials or any other indebtedness in connection with the work. If the CONTRACTOR or SUBCONTRACTOR or supplier places a lien against the work or a portion thereof then the CONTRACTOR shall cause the removal of the lien. However, the OWNER may, at any time prior to making final payment, require the CONTRACTOR to furnish a Consent of Surety to any payment due the CONTRACTOR for completed work and may, at the discretion of the OWNER or the request of the Surety, make the check jointly payable to the CONTRACTOR and the Surety.

The OWNER may conduct random sampling of wage rates on each CONTRACT. The OWNER may interview the CONTRACTOR'S and CONTRACTOR'S SUBCONTRACTOR'S employees in the field to verify the employee is working in and being paid for the classification shown on the payroll. In instances of noncompliance, the OWNER MAY initiate action as outlined in the CONTRACT Documents.

109.2. PAYMENT FOR MATERIALS

109.2.1. Materials On-Hand. Materials purchased and stored more than 30 days before use may be considered materials on-hand. Payment for such materials shall be made according to [Item 109.5](#). Monthly Estimate, Partial Payments, Retainage, Final Inspection, Acceptance and Final Payment.

109.2.2. Materials Stored Off-Site. Off-site storage of such materials and payment for off-site storage may be accomplished according to [Item 106.4](#). Off-Site Storage.

109.2.3. Measurement of Quantities. The determination of quantities of work acceptably completed under the terms of the contract, or as directed by the OWNER in writing, shall be made by the OWNER, based on measurements made by the OWNER. These measurements shall be taken according to the U.S. Standard measurements used in common practice and shall be the actual length, area, solid contents, numbers and weight.

109.3. PAYMENT FOR EXTRA WORK

109.3.1. General. Extra Work done by the CONTRACTOR, as authorized and approved by the OWNER, shall be compensated for in the manner described in this [Item 109.3](#). The compensation provided for Extra Work done constitutes full and final payment for the cost of the Extra Work, which cost is limited to: (1) all reasonable costs of labor, materials, supplies, tools, equipment or machinery rental, power, fuel, lubricants, water and other similar operation expenses (but only for the time that such of the above things are employed or used on such Extra Work) incurred in the performance of the Extra Work, and a ratable proportion of premium expenses for all bonds and insurance required under the Contract, to the extent that the Extra Work would cause an increase in such bond or insurance premiums; and (2) a markup amount of not-to-exceed 15-percent of the above mentioned costs to cover and compensate the CONTRACTOR for profit, overhead, profit-and-overhead markups charged to CONTRACTOR by other SUBCONTRACTORS and suppliers, general supervision, field office expense and all other elements of cost and expense not embraced within the cost of the Extra Work as described in this [Item 109.3.1](#). General. No cost of off-site storage shall be included in the above description of cost unless off-site storage has been approved and directed by the OWNER in writing. No other claims or reservations of right as to additional costs, prices, markups, costs not permitted to be

included under this paragraph, disallowed costs or other future additional money or time shall be accepted; each change order shall be specific and final as described in [Item 104.2.4](#) Finality of Change Orders.

109.3.2. Method of Determination. The method of determination and payment of cost, or credit to the OWNER, for any Extra Work shall be one of the following:

- (1) Unit prices agreed on in writing, approved by the OWNER and executed by the OWNER and CONTRACTOR before the Extra Work is commenced, or unit prices already included in the Contract documents, subject to all other conditions of the Contract. Mutual acceptance of a not-to-exceed lump sum properly itemized and supported by sufficient substantiating data to permit evaluation before the Extra Work is commenced, subject to all other conditions of the Contract.
- (2) A not-to-exceed cost to be determined in a manner agreed upon by the parties plus a mutually acceptable fixed or percentage fee, agreed upon before the Extra Work is commenced and subject to all other conditions of the Contract.
- (3) The force account method provided in [Item 109.3.3](#). Force Account Work.

109.3.3. Force Account Work. If the CONTRACTOR and the OWNER cannot agree to one of the methods of calculating cost provided in [Item 109.3.2](#). Method of Determination above, or if the parties agree to a method but cannot agree to a final dollar figure, or if the CONTRACTOR for whatever reason fails or refuses to sign the Change Order in question, the CONTRACTOR, provided it receives a written order signed by the OWNER, shall promptly proceed with the work involved. Nothing in this paragraph shall be construed to relieve the CONTRACTOR of any obligations it has under the disputed work provisions of [Item 104.3](#). Disputed Work and Claims for Additional Compensation, and [Item 104.4](#). Performance of Extra or Disputed Work, and where applicable the CONTRACTOR is still obligated to abide with those Items as well as this [Item 109.3.3](#). Force Account Work. The cost of the work involved shall then be calculated on a force account basis, on the basis of the actual, reasonable field cost of the work attributable to the changes, plus a reasonable allowance for overhead, profit, markups of other SUBCONTRACTORS and suppliers, general supervision, field office expense and other elements of cost not embraced within the actual field cost as specified herein, such allowance in any case never to exceed 15%. In such case, the CONTRACTOR shall keep a detailed itemized account of the work involved and the actual field cost incurred, in a format acceptable to the OWNER and with such appropriate supporting data as the OWNER may prescribe. Sworn copies of the itemized accounting shall be directed to the OWNER each day during the performance of the force account work. Failure of the CONTRACTOR to submit the sworn-to itemized accounting daily as required herein shall constitute a waiver by the CONTRACTOR of any right to dispute the OWNER'S determination of the amount due the CONTRACTOR for force account work.

Actual, reasonable field cost of the work to be charged under this [Item 109.3.3](#). Force Account Work for force account work is limited to the following:

- (1) The reasonable wages of all workers, foremen, timekeepers, mechanics and laborers, plus costs of social security, old age and unemployment insurance, fringe benefits required by agreement or custom (excluding employee or executive bonuses), and worker's compensation insurance, for the time such labor is actually employed or used on force account work.
- (2) Reasonable costs of materials, tools, supplies and equipment (but not to include off-site storage unless so approved and directed in writing by the OWNER), whether incorporated or consumed into the force account work.
- (3) Reasonable rental costs of machinery and equipment, exclusive of hand tools, only for the time actually employed or used on force account work, whether rented from the CONTRACTOR or others.
- (4) A pro rata portion of premium expenses for all bonds and insurance to the extent force account work would cause an increase in such bond or insurance premiums.

Pending final determination of the cost to the OWNER, payment of undisputed amounts on force account shall be included on the monthly estimate as work is completed unless otherwise expressly provided in the written order signed by the OWNER to perform the work. Nothing in this [Item 109.3.3](#). Force Account Work shall be construed as directing the CONTRACTOR'S means and methods of performing the work in question.

109.3.4. Distinguishing Extra Work. For purposes of this Item or any other provision of the Contract documents that allows a claim for Extra Work, the term "Extra Work" means work that is not reasonably within the scope of the Contract Documents or not otherwise incidental or necessary to performance of the

Contract. The term does not include any change by the CONTRACTOR in the means and methods of performing the Work from that anticipated or bid (even if such change in means or methods is requested or directed by the OWNER), whether or not the change is due to foreseeable or unforeseeable events or conditions, if the intended result or scope of the Work is not expanded or increased. The OWNER shall not be liable for any claim due to a change in the means or methods of construction by the CONTRACTOR, resulting in additional costs, if the OWNER has not changed the plans or specifications and if the intended result and scope of the work required by and reasonably inferred from the Contract Documents remains the same. The OWNER shall also not be liable for any claim for work required in performance of the Contract, without which the Contract could not be completed, notwithstanding that the CONTRACTOR did not contemplate or foresee the degree or amount of work that would be necessary or required to complete the Contract and notwithstanding that it cost the CONTRACTOR more to complete the Contract work than the original Contract price.

109.4. PAYMENT WITHHELD

In addition to express provisions elsewhere contained in the Contract, the OWNER may withhold from any payment otherwise due the CONTRACTOR such amount as determined necessary to protect the OWNER'S interest, or, if it so elects, may withhold or retain all or a portion of any payment or refund payment on account of:

- (1) unsatisfactory progress of the work not caused by conditions beyond the CONTRACTOR'S control,
- (2) defective work not corrected,
- (3) CONTRACTOR'S failure to carry out instructions or orders of the OWNER or its representative,
- (4) a reasonable doubt that the Contract can be completed for the balance then unpaid,
- (5) work or execution thereof not in accordance with the Contract documents,
- (6) claim filed by or against the CONTRACTOR or reasonable evidence indicating probable filing of claims,
- (7) failure of the CONTRACTOR to make payments to any SUBCONTRACTOR or suppliers for material or labor used in the performance of the Work,
- (8) damage to another CONTRACTOR or OWNER,
- (9) unsafe working conditions allowed to persist by the CONTRACTOR,
- (10) failure of the CONTRACTOR to provide work schedules as required by the OWNER,
- (11) use of SUBCONTRACTORS without the OWNER'S approval or,
- (12) failure of the CONTRACTOR to keep current as-built record drawings at the job site or to turn same over in completed form to the OWNER.

When the grounds for withholding payment are removed, payment shall be made for amounts withheld because of them, and OWNER shall never be liable for interest on any delayed or late payment.

109.5. MONTHLY ESTIMATE, PARTIAL PAYMENTS, RETAINAGE, FINAL INSPECTION, ACCEPTANCE AND FINAL PAYMENT

109.5.1. Monthly Estimate. Except as otherwise provided by the Contract, between the 25th day and the last day of each month, the OWNER shall make an approximate estimate of the value of the work done during the month under the specifications. The monthly estimate may include acceptable nonperishable materials as referenced in [Item 109.2](#). Payment for Materials; such payment shall be allowed on the same percentage basis of the net invoice value as provided hereinafter. The percent retained by OWNER shall normally be up to 10 percent at completion, unless otherwise stated. At the midpoint, or at any subsequent time, if OWNER determines that the progress on the Contract is satisfactory in all respects, it may at its discretion cease to retain additional funds until the completion of the project, or until progress ceases to be satisfactory. The OWNER shall make the sole determination in this matter.

Except as otherwise provided by the Contract, between the 25th day and the last day of each month the CONTRACTOR shall make an estimate of the value of the work done during the month under the specifications. The CONTRACTOR shall prepare the estimate on a form approved by the OWNER. The CONTRACTOR shall forward the estimate required above to the OWNER by not later than the last day of the month. The monthly estimate may include acceptable nonperishable materials delivered to and stored at the work site or a storage facility accessible to the OWNER; payment for such stored materials shall be allowed on the same percentage basis of the value as provided hereinafter. The monthly estimate shall also provide such supporting documentation as the OWNER or the other applicable provisions of the specifications may require.

The OWNER shall verify that the CONTRACTOR'S estimate matches the total value of work done and acceptable non-perishable materials delivered to the work site or storage facility, based upon the bid proposal prices and quantities measured or verified by OWNER. In the event of a discrepancy between quantities of work as shown in the CONTRACTOR'S estimate and measured quantities as shown in the OWNER'S verification, the OWNER'S determination or measurement shall be final, and the CONTRACTOR'S estimate shall be adjusted to reflect the quantities of work as shown by the OWNER'S verification. Payment shall be made by OWNER about thirty (30) days after receipt of the estimate from CONTRACTOR. OWNER shall not be liable for interest on any late or delayed payment caused by any claim or dispute, any discrepancy in quantities as described above, any failure to provide supporting documentation or other information required with the estimate or as a precondition to payment under the Contract, or due to any payment the OWNER has a right to withhold under the Contract.

The CONTRACTOR shall furnish to the OWNER such detailed information as OWNER may request to assist in the preparation of monthly estimates. It is understood that the monthly estimates shall be approximate only, and all monthly estimates and partial payments shall be subject to correction in the estimate rendered following the discovery of an error in any previous estimate, and such estimate shall not in any respect be taken as an admission of the OWNER of the amount of work done or of its quality or sufficiency nor as an acceptance of the work or the release of the CONTRACTOR of any of its responsibility under the Contract.

109.5.2. Retainage. As security for the faithful completion of the work by the CONTRACTOR, the OWNER shall retain 15-percent of the total dollar amount of work done on all contracts \$25,000.00 and less; 10-percent of the total dollar amount of work done on all contracts in excess of \$25,000.00 and less than \$400,000.00; five-percent of the total dollar amount of work done on all contracts of \$400,000.00 or more. On all contracts in excess of \$400,000, the following shall apply:

- (1) on all contracts in excess when work progress is 80-percent complete, retainage may, at the OWNER'S option, be reduced to two percent of the dollar value of all work satisfactorily completed to date (not to include material on hand), provided that the CONTRACTOR is making satisfactory progress and there is no cause of greater retainage as determined by the OWNER;
- (2) when work progress is substantially complete, the retainage may be further reduced to only that amount necessary to assure completion as determined by the OWNER;
- (3) if the OWNER determines that the CONTRACTOR is not making satisfactory progress or if there is other specific cause, the OWNER may, at its discretion, reinstate up to the five percent retainage.

109.5.3. Final Inspection and Acceptance. Final inspections and acceptance shall proceed according to [Item 105.9](#). Inspection and [Item 105.10](#). Acceptance.

109.5.4. Final Payment. Whenever the improvements provided for by the Contract shall have been completely performed on the part of the CONTRACTOR, as evidenced in the certificate of acceptance obtained according to [Item 105.10](#). Acceptance, and all required submissions provided to the OWNER, a final estimate showing the value of the work shall be prepared by the OWNER as soon as the necessary measurements and computations can be made. All prior estimates upon which payments have been made are subject to necessary corrections or revisions in the final payment. The amount of the final estimate, less any sums that have been previously paid, deducted or retained under the provisions of this Contract, shall be paid to the CONTRACTOR within a reasonable period of time (not to exceed 90 days) after final acceptance and the CONTRACTOR has provided to the OWNER:

- (1) a consent of surety to final payment;
- (2) the final CONTRACTOR'S Report of SUBCONTRACTOR/Supplier Payment, evidencing that all indebtedness connected with the work and all sums of money due for any labor, materials, apparatus, fixtures or machinery furnished for or used in the performance of the work have been paid or otherwise satisfied, or that the person or persons to whom the same may be respectively due have consented to final payment; and
- (3) such other affidavits, lien waivers and other documentation as the OWNER may reasonably require to protect its interests.

In addition, the CONTRACTOR shall be required to execute the OWNER'S standard Affidavit of Final Payment and Release as a precondition to receipt of final payment.

The acceptance by the CONTRACTOR of the final payment as aforesaid shall operate as and shall be a release to the OWNER from all claims, damages or liabilities under the Contract, including all SUBCONTRACTOR claims, or claims for additional compensation, for anything done or furnished or relating to the work under the Contract or for any act or neglect of said OWNER relating to or connected with the Contract.

All warranties and guarantees shall commence from the date of the certificate of acceptance. No interest shall be due the CONTRACTOR on any partial or final payment or on the retainage.

109.5.5. Compensation and Acknowledgement of Work. The CONTRACTOR shall receive and accept compensation, as herein provided, as full payment for furnishing all labor, tools, material, equipment and incidentals; for performing all work contemplated and embraced under the Contract; for all loss or damage arising out of the nature of the work, or from the action of the elements; for any unforeseen defects or obstruction which may arise or be encountered during the prosecution of the work and before its final acceptance by the OWNER; for all risks of whatever description connected with the prosecution of the work; for all expense incurred by or in consequence of suspension or discontinuance of such prosecution of the work as herein specified; for any infringement of patents, trademarks or copyrights; and for completing the work in an acceptable manner according to the plans and specifications.

109.6. WIRE TRANSFERS

Payments to the CONTRACTOR may, at the discretion of the OWNER, be made by wire transfer to a bank of the CONTRACTOR'S choice. The CONTRACTOR must furnish the following information:

- (1) The ABA number of the bank.
- (2) The CONTRACTOR'S account number.
- (3) Or other such information as may be required by sending and receiving financial institutions.

The request must be on the CONTRACTOR'S letterhead and signed by an authorized representative of the CONTRACTOR (cannot be a copy).

ITEM 110. AIR QUALITY REQUIREMENT FOR EQUIPMENT

As of 2016, ten (10) counties in North Central Texas have been designated by the EPA as being nonattainment for the pollutant ozone, and additional counties are expected to be designated in the near future. As a result, development of an air quality plan, known as the State Implementation Plan (SIP), is required for all nonattainment areas in order to demonstrate how ozone will be reduced to levels compliant with EPA standards. The SIP for the Dallas-Fort Worth nonattainment area includes programs to implement control strategies to all emission sources, including non-road construction equipment sources. To support these efforts, air quality requirements for equipment are applicable to the Contract.

110.1. EQUIPMENT REQUIREMENTS

All construction equipment being used to perform work on the Contract shall meet EPA emissions standards of Tier 3 or equivalent, or cleaner. Model Form A.14. Schedule for Phase-In of Tier 1-Tier 4 Non-Road Engines is included in Appendix A. Compliance may be achieved through the use of equipment powered by an EPA-certified engine, through engine repowers, or through the use of retrofits which have been verified by the EPA and/or California Air Resources Board. A list of available retrofits is available online at EPA's website "Verified Technologies List for Clean Diesel."

Equipment that meets one or more of the following conditions may be exempt from these requirements:

- (1) Equipment powered by an engine that is less than or equal to ten (10) years old.
- (2) Equipment that must be used to fulfill use or reporting requirements for a grant program or other clean air initiative. Documentation of such obligations must be submitted to OWNER for verification.
- (3) Equipment that is designated as low-use equipment, which is defined as any piece of construction equipment which is used for less than ten (10) hours per week on a single public works contract. A Low-Use Exemption Weekly Reporting Form will be required for all equipment for which this exemption is claimed. Model Form A.15. Low-Use Exemption Weekly Reporting Form is included in Appendix A.
- (4) Equipment that is being used to address a critical or emergency public works need, including, but not limited to, broken water mains or sanitary sewer lines. This exemption is limited to work performed in a situation in which the procurement of construction services is performed on an emergency basis, as provided for by State law.

110.2. OPERATIONAL REQUIREMENTS

All diesel fuel used to perform work on the public works contract shall be Ultra-Low Sulfur Diesel (ULSD) fuel which also complies with Texas Low Emission Diesel (TxLED) program requirements. This may include TxLED-compliant Biodiesel blends.

The CONTRACTOR shall limit idling of equipment to no more than five (5) minutes, unless the idling is applicable to one or more of the following exceptions:

- (1) is being used for emergency response purposes;
- (2) is idling as a necessary component of mechanical operation, maintenance, or diagnostic purposes; or
- (3) is idling for the health or safety of the equipment operator.

To the greatest extent possible, CONTRACTOR shall stage equipment away from, and minimize operation near, sensitive receptors including, but not limited to, fresh air intakes, hospitals, schools, licensed day care facilities, and residences.

110.3. REPORTING TO OWNER

On or before the day construction activity commences, the CONTRACTOR shall submit to the OWNER an inventory report containing identifying data for each piece of equipment to be used on the worksite. A form for submitting such information will be provided by the OWNER. Model Form A.16. Contract Equipment Inventory is included in Appendix A. This inventory may be used by the OWNER or INSPECTOR to conduct site inspections and/or verify compliance with specification elements.

If additional equipment is brought on-site after construction begins, the CONTRACTOR shall provide this same inventory information to the OWNER for the new equipment on or before the day it begins work on-site.

Reports shall be provided for all equipment used on-site.

110.4. ENFORCEMENT

All construction equipment used on the job site is subject to inspection by the OWNER at random. CONTRACTOR is responsible for ensuring that all SUBCONTRACTORS meet the requirements of this specification.

The provisions of this specification shall be enforced as established in the Terms and Conditions of the Contract. If the provisions of this specification are not met, the OWNER may declare the CONTRACTOR to be in default of the contract.



Division 200

Site Protection and Preparation

DIVISION 200 SITE PROTECTION & PREPARATION

TABLE OF CONTENTS

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
<u>201.</u>	<u>SITE PROTECTION</u>	<u>201-1 to 201-3</u>
<u>201.1.</u>	<u>Removal, Protection, and Replacement of Trees, Shrubberty, Plants, Sod, and Other Vegetation</u>	
<u>201.2.</u>	<u>Determining Location and Protection of Existing Structures and Utilities</u>	
<u>201.3.</u>	<u>Maintenance of Streets and Rights of Way During Construction</u>	
<u>202.</u>	<u>TEMPORARY EROSION, SEDIMENTATION, AND WATER POLLUTION PREVENTION AND CONTROL</u>	<u>202-1 to 202-12</u>
<u>202.1.</u>	<u>Description</u>	
<u>202.2.</u>	<u>Items of Work and Materials</u>	
<u>202.3.</u>	<u>Preconstruction Submittals</u>	
<u>202.4.</u>	<u>Construction Requirements</u>	
<u>202.5.</u>	<u>Silt Fence</u>	
<u>202.6.</u>	<u>Interceptor Swale</u>	
<u>202.7.</u>	<u>Diversion Dike</u>	
<u>202.8.</u>	<u>Triangular Sediment Filter Dike</u>	
<u>202.9.</u>	<u>Check Dam (Rock)</u>	
<u>202.10.</u>	<u>Check Dam (Filter Tube)</u>	
<u>202.11.</u>	<u>Stabilized Construction Exit</u>	
<u>202.12.</u>	<u>Stone Outlet Sediment Trap</u>	
<u>202.13.</u>	<u>Pipe Slope Drain</u>	
<u>202.14.</u>	<u>Inlet Protection</u>	
<u>202.15.</u>	<u>Erosion Control Blankets</u>	
<u>202.16.</u>	<u>Section Held for Future Use</u>	
<u>202.17.</u>	<u>Section Held for Future Use</u>	
<u>202.18.</u>	<u>Filter Tubes</u>	
<u>202.19.</u>	<u>Measurement and Payment</u>	
<u>203.</u>	<u>SITE PREPARATION</u>	<u>203-1 to 203-5</u>
<u>203.1.</u>	<u>General Site Preparation</u>	
<u>203.2.</u>	<u>Unclassified Excavation</u>	
<u>203.3.</u>	<u>Section Held for Future Use</u>	
<u>203.4.</u>	<u>Borrow & Spoil</u>	
<u>203.5.</u>	<u>Embankment</u>	
<u>203.6.</u>	<u>Dust Control</u>	
<u>204.</u>	<u>LANDSCAPING</u>	<u>204-1 to 204-8</u>
<u>204.1.</u>	<u>Vegetation Removal and Reuse, Clearing and Grubbing</u>	
<u>204.2.</u>	<u>Topsoil</u>	
<u>204.3.</u>	<u>Soil Amendments</u>	
<u>204.4.</u>	<u>Fertilizer</u>	
<u>204.5.</u>	<u>Sodding</u>	
<u>204.6.</u>	<u>Seeding Turfgrass</u>	
<u>204.7.</u>	<u>Mulching</u>	
<u>204.8.</u>	<u>Rejection</u>	

ITEM 201. SITE PROTECTION

201.1. REMOVAL, PROTECTION, AND REPLACEMENT OF TREES, SHRUBBERY, PLANTS, SOD, AND OTHER VEGETATION

No trees shall be removed unless so noted on the plans or upon the specific approval of the OWNER. Where trees, plants, shrubbery, etc., are adjacent to the line of the work and are not to be removed or are designated on the plans to be removed and replanted, the CONTRACTOR shall protect such trees, plants, shrubbery, and etc. in accordance to the contract documents. If, in the opinion of the OWNER, such trees, plants, shrubbery, etc., would be damaged by machinery, etc., hand excavation may be required. Shrubby, plants, etc. to be relocated or reused shall be removed with a ball of dirt about their roots and shall be carefully stored and given proper attention.

Sod shall be removed in squares cut out with a sharp spade and of such sizes that they may be handled conveniently without breaking. They shall be carefully stored and given proper attention. During hot, dry weather, the stored sod shall be protected by covering with canvas or burlap.

Tree roots shall be protected by installing temporary construction fencing outside the tree's drip line. Other tree protection may be required by OWNER. No operating, parking, or storing of equipment and/or materials is allowed within the tree protection zone. The CONTRACTOR shall be responsible for all damage to trees, plants, shrubbery, etc., and any such damage shall be remedied to the satisfaction of the OWNER at the expense of the CONTRACTOR. All damaged limbs over 1-inch in diameter shall be sawed clean adjacent to the damaged area or at the trunk and dressed with acceptable tree wound treatment material, unless dressing is waived by the OWNER.

The cost of removal shall be paid for as a separate contract pay item if a separate pay item is provided; otherwise, the costs thereof shall be included in such pay items as are provided in the proposal and contract. The cost of protection shall not be paid for as a separate contract pay item; the costs thereof shall be included in such pay items as are provided for in the proposal and contract.

Where sod, shrubbery, plants, etc., are designated for removal and replacement, such areas shall have sod, shrubbery, plants, etc., of the same kind and in good condition, placed in OWNER approved locations. Trees that are to be removed and subsequently replaced shall be designated on the plans. When backfilling is completed, the sod, shrubbery, plants, etc. shall be carefully placed in OWNER approved locations and the area thoroughly wet down.

The cost of such replacement shall be paid for as a separate contract pay item if a separate pay item is provided; otherwise, the costs thereof shall be included in such pay items as are provided in the proposal and contract.

201.2. DETERMINING LOCATION AND PROTECTION OF EXISTING STRUCTURES AND UTILITIES

Determining location and protection of existing structures and utilities shall comply with this [Item 201.2](#), and with the provisions of [Item 107.24](#), Existing Structures, Facilities and Appurtenances and [Item 103.1](#), Contractor's Warranties and Understanding.

201.2.1. Determining Location. Determining the location of existing structures, utilities and appurtenances shall proceed according to the specifications herein and the provisions of [Item 107.24](#), Existing Structures, Facilities and Appurtenances.

BIDDERS must satisfy themselves as to the actual existing subsurface conditions, including but not limited to the depth, location and sizes of pipe or conduits of various kinds in place. Where the exact depth of any utility or obstruction is not shown on a plan, excavation shall be made prior to reaching the obstruction in order to determine adjustments in grade if needed to prevent interference. Redesign to eliminate conflicts may be necessary. Extra compensation shall not be paid for such delays.

201.2.1.1. Subsurface Utility Engineering. If provided by CONTRACTOR, subsurface utility engineering shall be in conformance with CI/ASCE 38-02, Standard Guideline for the Collection and Depiction of Existing Subsurface Utility Data, or as currently revised.

201.2.2. Protection. All existing structures, improvement and utilities designated to remain shall be adequately protected, at the expense of the CONTRACTOR, from damage that might otherwise occur due to construction operations. Where construction comes in close proximity to existing structures, utilities or

appurtenances, or if it becomes necessary to move services, poles, guy wires, pipe lines or other obstructions, the CONTRACTOR shall notify and cooperate with the owner of the utility, structure, or appurtenance. The utility lines and other existing structures shown on the plans are for information only and are not guaranteed by the OWNER to be complete or accurate as to location and/or depth. The CONTRACTOR shall be liable for damage to any utilities resulting from the CONTRACTOR'S operations. During construction, all fire hydrants, valve boxes, water meters/vaults, manholes, emergency call boxes and/or other existing utility controls shall be left intact, unobstructed and accessible unless noted on the plan.

All water mains, wastewater collection mains, wastewater collection laterals, storm drains, power conduits, gas mains, gas service laterals, irrigation systems, and other lines or appurtenances encountered during construction shall be supported or replaced as detailed on the plans. Water service lines shall not be removed during excavation, and the CONTRACTOR shall provide adequate support for the services across the open ditch.

201.2.2.1. Temporary Utility Supports. CONTRACTOR shall provide temporary utility support to protect existing utility lines exposed during construction. Method and type of temporary utility supports, if required, shall be approved by the utility owner.

201.2.3. Relocating or Replacing Structures, Utilities or Appurtenances. Utility locations shall be obtained prior to the commencement of work according to [Item 107.24](#), Existing Structures, Facilities and Appurtenances. Unless noted on plans that utilities are to be moved by others, any cost of temporarily or permanently relocating utilities shall be borne by the CONTRACTOR. The cost of these replacements shall be included in the CONTRACTOR'S bid price for the various items of work, and no separate payment shall be made. The OWNER shall approve all shut downs and may assist in the shut down operations.

If it is necessary to adjust another utility, a representative of that utility shall be notified to decide method and work to be done. The CONTRACTOR shall make satisfactory arrangements with the OWNER or other utilities for the required adjustments at the CONTRACTOR'S own expense, other than for items that may be provided in the contract for such work. No extra compensation shall be paid due to delays caused by removal of public utility structures.

201.2.3.1. Interrupted Utility Services. In case damage to an existing utility occurs, the CONTRACTOR shall notify the OWNER and utility owner immediately. The CONTRACTOR shall be responsible for the cost to restore the structure or utility to its original condition and position without extra compensation. Restoration of utility services shall be made as soon as practicable as directed and approved by the utility owner.

The CONTRACTOR shall notify the OWNER of any spill of wastewater. Remediation of the spill is the responsibility of the CONTRACTOR and shall be at no additional cost to the OWNER. Spill and remediation will be reported by the OWNER to the TCEQ, USEPA, or other appropriate regulatory agencies. The CONTRACTOR shall be responsible for notifying customers of temporary interruption of service.

201.2.3.2. Street Sign Posts and Signs. The CONTRACTOR shall be responsible for all damage to street sign posts and signs within the limits of the CONTRACTOR'S operations that remain in place or are removed and replaced. In the event that street sign posts and signs are damaged or destroyed by the CONTRACTOR'S operations, they shall be replaced at the CONTRACTOR'S expense.

201.2.3.3. Methods of Removal and Disposal. Materials or parts of structures which are to be broken up, dismantled or removed, and which are to be salvaged, shall be removed, loaded, cleaned and unloaded at sites designated by the OWNER. Materials that are not salvageable shall become the property of the CONTRACTOR. Disposal of such materials, in accordance with applicable local, state, and federal regulations, shall be at the CONTRACTOR'S expense.

201.2.4. Measurement and Payment. No measurement shall be made for the removal and replacement of utility pipe even if the utility pipe is replaced with a different pipe. No payment shall be made except as provided for under certain conditions in [Item 107.24](#), Existing Structures, Facilities and Appurtenances and Item 203.1.4.1. Measurement and Payment for Utility Supports, unless otherwise provided in the Contract.

201.2.4.1. Measurement and Payment for Temporary Utility Supports. No separate measurement or payment shall be made for temporary utility supports unless a separate bid item is established in the Contract. If a separate bid item for temporary utility supports is established in the Contract, it shall include all necessary labor, tools, materials, equipment and incidentals necessary to complete the work, including removal and cleanup.

201.3. MAINTENANCE OF STREETS AND RIGHTS OF WAY DURING CONSTRUCTION

The CONTRACTOR shall at all times maintain vehicular and pedestrian traffic through and adjacent to work zones in accordance with [Item 107](#). Legal Relations and Contractor Responsibilities. The maintenance required shall include but not be limited to the filling of potholes; blading or otherwise smoothing of the paved surfaces (particularly in a trench area); cleaning and removal of surplus excavation material, rubbish, etc.; and the maintenance of safe and efficient vehicular and pedestrian access. Dust control shall be in accordance with 203.6 Dust Control.

ITEM 202. TEMPORARY EROSION, SEDIMENTATION, AND WATER POLLUTION PREVENTION AND CONTROL

202.1. DESCRIPTION

This Item shall govern the use of temporary control measures necessary to prevent and control soil erosion, sedimentation, and water pollution that may degrade the MS4, adjacent properties, and/or receiving waters including rivers, streams, lakes, reservoirs, groundwater, and wetlands. The temporary control measures contained herein shall be installed and maintained throughout the construction contract and coordinated with any permanent or temporary pollution control features specified elsewhere on the plans and in the specifications to assure effective and continuous water pollution control throughout the construction and post construction periods. These control measures shall not be used as a substitute for the permanent pollution control measures unless otherwise directed by the OWNER in writing. The controls may include any of the devices listed in this item. Additional information regarding these and other controls can be found in NCTCOG's *integrated* Storm Water Management iSWM Program Manuals. In the event of conflict between these specifications and applicable Federal, State and Local laws, rules and regulations, the more restrictive requirement shall apply.

Measurement and payment for all measures called for within [Item 202](#), shall be per [Item 202.19](#) Measurement and Payment.

202.2. ITEMS OF WORK AND MATERIALS

The items, estimated quantities, and locations of the control measures will be shown on the plans; however, the OWNER may revise these items as needs arise. The materials will be shown on the plans and in the specifications. The OWNER may allow, in writing, the use of other materials and work methods as the need arises.

202.3. PRECONSTRUCTION SUBMITTALS

Prior to the start of construction, the CONTRACTOR shall submit to the OWNER a copy of the Storm Water Pollution Prevention Plan (SWPPP) and any documentation required by the Construction General Permit. Work on the project shall not begin until the submittals have been accepted by the OWNER. The CONTRACTOR shall provide the OWNER, for information purposes, proposed methods of storm water pollution control for CONTRACTOR operations in areas which are outside the limits of the erosion control plan or the SWPPP (such as construction and haul roads, field offices, equipment and supply storage areas, portable process plants, and source material storage), as well as a plan for disposal of waste materials.

202.4. CONSTRUCTION REQUIREMENTS

202.4.1. General. The CONTRACTOR shall provide control measures to prevent or minimize the impact of the CONTRACTOR'S operations to receiving waters as required by the plans or Storm Water Pollution Prevention Plan (SWPPP) and/or as directed by the OWNER in writing.

In any disturbed area where construction activities have ceased, permanently or temporarily, the CONTRACTOR shall initiate stabilization of the area by the use of seeding, mulching, soil retention blankets or other appropriate measures within 14-days, except in areas where construction activities are scheduled to resume within 21-days. The CONTRACTOR shall effectively prevent and control erosion and sedimentation on the site at the earliest practicable time as outlined in the approved schedule. Control measures, where applicable, will be implemented prior to the commencement of each construction operation. The CONTRACTOR shall limit the amount of disturbed earth to the area(s) shown on the plans or as directed by the OWNER. The OWNER has the authority to limit the disturbed surface area exposed by construction operations. If, in the opinion of the OWNER, the CONTRACTOR is not able to effectively control soil erosion and sedimentation resulting from construction operations, the OWNER will limit the amount of disturbed area to that which the CONTRACTOR is able to control.

Should the control measures fail to function effectively, the CONTRACTOR shall act immediately to bring the erosion and sedimentation under control by maintaining existing controls or by providing additional controls as directed by the OWNER. When, in the opinion of the OWNER, the site is adequately stabilized, the control measures, except mulches and soil retention blankets, will be removed and properly disposed of by the CONTRACTOR. Soil retention blankets shall be removed only when, in the opinion of the OWNER, final

permanent perennial seeding would be adversely affected by the presence of an existing soil retention blanket.

All erosion, sediment, and water pollution controls will be maintained in good working order. The CONTRACTOR and OWNER will inspect the entire project to determine the condition of the control measures using one of the following inspection schedules:

- (1) A rain gauge provided by the CONTRACTOR will be located at the project site. Inspection will occur every fourteen (14) calendar days, and also within 24-hours of a rainfall event of 0.5-in. or more as measured by the project rain gauge.
- (2) Inspection will occur at least once every seven (7) calendar days on a specifically defined day, regardless of whether or not there has been a rainfall event since the previous inspection.

Sediment will be removed and devices repaired as soon as practicable but no later than seven (7) calendar days after the surrounding exposed ground has dried sufficiently to prevent further damage from equipment operations needed for repairs.

In the event of continuous rainfall over a 24-hour period, or other circumstances that preclude equipment operation in the area, the CONTRACTOR will install additional backup devices, as determined by the OWNER, by other appropriate methods. The CONTRACTOR will remove silt accumulations and deposit the spoils in an area approved by the OWNER as soon as practical. Any corrective action needed for the control measures will be accomplished in the sequence directed by the OWNER; however, areas adjacent to receiving waters shall generally have priority, followed by devices protecting storm sewer inlets.

In the event of conflict between these requirements and storm water pollution control laws, rules or regulations of other Federal, State, or Local agencies, the more restrictive laws, rules or regulations shall apply.

202.4.2. Other Practices and Controls. The CONTRACTOR shall also conform to the following practices and controls.

202.4.2.1. Location and Construction of CONTRACTOR'S Auxiliary Areas. Disposal areas, stockpiles, and haul roads shall be constructed in a manner that will minimize and control the amount of sediment that may enter receiving waters. Disposal areas shall not be located in any floodplain or receiving waters. Construction roads may not be located in or cross any receiving waters without prior approval of the OWNER and shall be done in compliance with applicable rules and regulations. Staging areas and vehicle maintenance areas shall be constructed by the CONTRACTOR in a manner to minimize the runoff of pollutants and at a location approved by the OWNER. The CONTRACTOR shall prevent pollution of receiving waters with petroleum products or other hazardous or regulated substances.

202.4.2.2. Activity In or Near Waters. Construction operations in receiving waters shall be restricted to those areas where it is necessary to perform the work shown on the plans. Wherever streams are crossed, temporary bridges, timber mats, or other structures shall be used and approved by the OWNER. When work areas or material sources are located adjacent to a receiving water, control measures such as diversion dikes or rock berms shall be used to keep sediment and other contaminants from entering the adjacent receiving water. Care shall be taken during the construction and removal of such barriers to minimize down-gradient sedimentation.

All receiving waters shall be cleared as soon as practicable of temporary embankment, temporary bridges, matting, falsework, piling, debris, or other obstructions placed during construction operations that are not a part of the finished work.

202.4.2.3. Materials Storage. Protected storage for paints, chemicals, solvents, fertilizers, and other potentially toxic materials will be provided by the CONTRACTOR at a location approved by the OWNER.

202.4.2.4. Vegetation. Disturbance of vegetation shall be minimized and limited to only what is shown on the construction plans or as directed by the OWNER in writing. Operations shall be in accordance with [Item 204](#), Landscaping.

202.4.2.5. Keeping Roadways Clean. The CONTRACTOR shall clean paved surfaces, as necessary, to remove sediment that has accumulated on the roadway.

202.4.3. Cleaning and Stabilizing Project Area. The project will not be accepted until the CONTRACTOR has cleaned up as described in [Item 107.25](#), Project Clean-up to the satisfaction of the OWNER. The project will

also not be accepted until the CONTRACTOR provides a uniform perennial vegetative cover with a density of 70-percent of the native background vegetative cover or, if in the opinion of the OWNER, permanent measures (such as riprap, gabions, geotextiles, or other stabilization methods approved by the OWNER), supplemented by temporary measures (such as mulching with seed, silt fences, earth dams, etc.) have been employed that will control erosion, sedimentation, and water pollution until sufficient vegetative cover can be established.

202.5. SILT FENCE

202.5.1. Description. Silt Fence is a barrier consisting of geotextile fabric, steel wire fence fabric and supported by steel posts to prevent soil and sediment loss from a site. This includes all labor and materials associated with installation, maintenance, and ultimate removal of the silt fence as shown in the construction drawings or similar document.

The purpose of a silt fence is to intercept and detain water-borne sediment from unprotected areas to a limited extent. Silt fence is used during the period of construction near the perimeter of a disturbed area to intercept sediment while allowing water to percolate through. This fence shall remain in place until the disturbed area is permanently stabilized. Silt fences are to be constructed along a line of constant elevation (along contour line) where possible. Silt fence shall not be used where there is a concentration of water in a channel or drainage way or where soil conditions prevent a minimum toe-in depth of 6-inches or installation of support post to depth of 12-inches. If concentrated flow occurs after installation, corrective action shall be taken such as placing a stone overflow in the areas of concentrated flow or replacing the silt fence with a more appropriate control measure.

202.5.2. Materials.

202.5.2.1. Geotextile. Silt Fence fabric must meet the following minimum criteria:

- (1) Tensile Strength, ASTM D4632 Test Method for Grab Breaking Load and Elongation of Geotextiles, 90-lbs.
- (2) Puncture Rating, ASTM D4833 Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products, 60-lbs.
- (3) Mullen Burst Rating, ASTM D3786 Standard Test Method for Hydraulic Bursting Strength of Textile Fabrics-Diaphragm Bursting Strength Tester Method, 280-psi.
- (4) Apparent Opening Size, ASTM D4751 Test Method for Determining Apparent Opening Size of a Geotextile, U.S. Sieve No. 40 (max) to 80 (min).
- (5) Ultraviolet Resistance, ASTM D4355 standard Test Method for Deterioration of Geotextiles by Exposure to light, Moisture, and Heat in a Xenon Arc Type Apparatus, Minimum 70 percent.

202.5.2.2. Posts. Fence posts shall be steel and may be T-section or L-section, 1.3 pounds per linear foot minimum, and 4 feet in length minimum. Plastic caps to be installed in areas exposed to pedestrian traffic. Wood posts may be used if anticipated length of service is less than 90 days and provided they are 4 feet in length minimum and have a nominal cross section of 2 inches by 4 inches for pine or 2 inches by 2 inches for hardwoods. If allowed, wood posts shall be replaced if deterioration renders post ineffective.

202.5.2.3. Wire Support. Silt fence shall be supported by steel wire fence fabric as follows:

- (1) 4" x 4" mesh size, W1.4 /1.4, minimum 14-gauge wire fence fabric;
- (2) Hog wire, 12 gauge wire, small openings installed at bottom of silt fence;
- (3) Standard 2" x 2" chain link fence fabric; or
- (4) Other welded or woven steel fabrics consisting of equal or smaller spacing as that listed herein and appropriate gauge wire to provide support.

202.5.2.4. Stone. When a stone overflow is specified, the stone shall be 1½-inches washed stone containing no fines meeting the requirement for coarse crushed stone in [Section 504.2.2.1](#). (a) Coarse Crushed Stone Embedment.

202.5.3. Construction. Silt Fence shall consist of synthetic fabric supported by wire mesh and steel posts set a minimum of 1-foot depth and spaced not more than 6-feet on center. A 6-inch wide trench is to be cut 6-inches deep at the toe of the fence to allow the fabric and wire mesh to be laid below the surface and backfilled with compacted earth or gravel. This entrenchment prevents any bypass of runoff under the fence. Fabric shall overlap at abutting ends a minimum of 3-feet and shall be joined such that no leakage or bypass

occurs. Sufficient room for the operation of sediment removal equipment shall be provided between the silt fence and other obstructions in order to properly maintain the fence. The last 10 feet (or more) at the ends of a line of silt fence shall be turned upslope to prevent bypass of stormwater. Additional upslope runs of silt fence may be needed every 200 to 400 linear feet, depending on the traverse slope along the line of silt fence. A stone overflow structure constructed in accordance with Standard Drawing 1020A shall be installed at all low points or spaced approximately every 300 feet if there is no apparent low point.

202.6. INTERCEPTOR SWALE

202.6.1. Description. A temporary interceptor swale may have a V-shape, parabolic, or be trapezoidal with a flat bottom. Interceptor swales are used to shorten the length of exposed slope by intercepting runoff and can also serve as perimeter swales preventing off-site runoff from entering the disturbed area or prevent sediment-laden runoff from leaving the construction site or disturbed area. The outlet (discharge point) of the swale shall be designed to have non-erosive velocities or designed with velocity dissipation devices. Diverted runoff from a disturbed area or other construction activity shall be conveyed to a sediment control. The swales shall remain in place until the disturbed area is permanently stabilized.

202.6.2. Applications and Design Criteria. It is the responsibility of the OWNER to provide specific details and specifications of all interceptor swales.

202.7. DIVERSION DIKE

202.7.1. Description. A temporary diversion dike is a barrier created by the placement of an earthen embankment to reroute the flow of runoff to an erosion control device or away from an open, easily erodible area. A diversion dike intercepts runoff from small upland areas and diverts it away from exposed slopes to a stabilized outlet or sediment trapping device. Dikes are generally used for the duration of construction to intercept and reroute runoff from disturbed areas to prevent excessive erosion until permanent drainage features are installed and/or slopes are stabilized. The outlet (discharge point) of the diversion dike shall be designed to have non-erosive velocities or designed with velocity dissipation devices. Diverted runoff from a disturbed area or other construction activity shall be conveyed to a sediment control.

202.7.2. Materials. For grades less than 2 percent and velocities less than 6 feet per second, the minimum required channel stabilization shall be grass, erosion control blankets, or anchored mulch. For grades in excess of 2 percent or velocities exceeding 6 feet per second, stabilization is required in the form of turf reinforcement mats (or rip-rap with appropriate size, gradation, and thickness depending on flow conditions). Velocities greater than 8 feet per second will require approval by the OWNER. Dike material shall consist of in situ soils with a plasticity index greater than 25.

202.7.3. Construction and Maintenance. Diversion dikes shall be installed prior to and maintained for the duration of construction and should intercept no more than 5-acres of runoff. Maximum depth of flow at the dike shall be 1 foot based on a 2-year return period design storm peak flow. Dikes shall have a minimum top width of 2.0-ft. and a minimum height of compacted fill of 18" measured from the top of the existing ground at the upslope toe to top of the dike and having side slopes of 3:1 or flatter. The soil for the dike shall be placed in lifts of 8" or less and be compacted to 95-percent standard proctor density using ASTM D698 Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort. The channel formed by the dike must have positive drainage for its entire length to a controlled outlet.

CONTRACTOR shall inspect dikes on a regular basis, at least as frequently as required by the SWPPP. Deficiencies shall be repaired as required by the SWPPP or as directed by the OWNER. Remove temporary diversion dike at direction of OWNER or upon establishment of permanent ground cover; and establish permanent ground cover in the area disturbed by the removal.

202.8. TRIANGULAR SEDIMENT FILTER DIKE

202.8.1. Description. The work shall consist of installing a temporary triangular sediment filter dike as shown on the plans during the construction period to control sedimentation.

The purpose of a triangular sediment filter dike is to intercept and detain water-borne sediment from unprotected areas of limited extent. Triangular filter dikes are used in place of silt fence, treating sediment flow at the perimeter of construction areas and at the perimeter of the site. Also, the dikes can serve as

stream protection devices by preventing sediment from entering the streams. This measure can be effective on paved areas where installation of silt fence is not possible.

202.8.2. Materials.

202.8.2.1. Geotextile. The fabric must meet the following minimum criteria:

- (1) Tensile Strength, ASTM D4632 Test Method for Grab Breaking Load and Elongation of Geotextiles, 90-lbs.
- (2) Puncture Rating, ASTM D4833 Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products, 60-lbs.
- (3) Mullen Burst Rating, ASTM D3786 Standard Test Method for Hydraulic Bursting Strength of Textile Fabrics-Diaphragm Bursting Strength Tester Method, 280-psi.
- (4) Apparent Opening Size, ASTM D4751 Test Method for Determining Apparent Opening Size of a Geotextile, U.S. Sieve No. 30 (max) to 100 (min).
- (5) Ultraviolet Resistance, ASTM D4345 Standard Test Method for Deterioration of Geotextiles by Exposure to Light, Moisture, and Heat in a Xenon Arc Type Apparatus, Minimum 70 percent.

202.8.2.2. Wire Mesh Support. The internal support for the dike structure shall be 6-gauge 6" x 6" wire mesh or 4" x 4" welded wire fabric folded into triangular form being 18" on each side.

202.8.2.3. Filter Stone for Rock Bags. Material shall consist of 1-inch Crushed Stone conforming to [Item 504.2.2.1](#). Crushed Stone Embedment.

202.8.2.4. Bag Material for Rock Bags. Bag material shall be polypropylene, polyethylene, polyamide or cotton burlap woven fabric, minimum unit weight 4-ounces-per-square-yard, mullen burst strength exceeding 300-psi as determined by ASTM D3786 Standard Test Method for Hydraulic Bursting Strength of Textile Fabrics-Diaphragm Bursting Strength Tester Method, and ultraviolet stability exceeding 70-percent. Bag material shall be free of all defects.

202.8.3. Construction. Triangular sediment filter dikes shall be installed across exposed slopes during construction with ends of the dike tied into existing grades to prevent failure. Filter material shall lap over ends 6-inches to cover dike-to-dike junction; each junction shall be secured by shoat rings. Where the dike is placed on pavement, two rock bags shall be used to anchor the overlap to the pavement. Additional bags shall be used as needed to ensure continuous contact with the placement (no gaps). The ends of the dike shall be turned up grade to prevent bypass of stormwater.

202.9. CHECK DAM (ROCK)

202.9.1. Description. The work shall consist of constructing temporary rock check dams as shown on the plans during the construction period to control erosion and sedimentation.

202.9.2. Materials.

202.9.2.1. Stone. Stone shall be well graded with size range from 1½-inches to 3½-inches in diameter depending on expected flows. Where the channel design flow velocity will be greater than 5 feet per second the upper size limit of the stone will need to be increased by the designer and specified on the construction drawings.

202.9.2.2. Geotextile Fabric. Use geotextile filter fabric under check dams exceeding 18 inches in height. If required, the check dam shall be placed on geotextile fabric meeting the following minimum criteria:

- (1) Tensile Strength, ASTM D4632 Test Method for Grab Breaking Load and Elongation of Geotextiles, 250-lbs
 - (2) Puncture Rating, ASTM D4833 Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products, 135-lbs.
 - (3) Mullen Burst Rating, ASTM D3786 Standard Test Method for Hydraulic Bursting Strength of Textile Fabrics-Diaphragm Bursting Strength Tester Method, 420-psi.
- Apparent Opening Size, ASTM D4751 Test Method for Determining Apparent Opening Size of a Geotextile, U.S. Sieve No. 20 (max).

202.9.3. Construction and Maintenance. Check dams should be placed at a distance and height to allow small pools to form between each one. Typically, dam height should be between 12" and 36". Dams should be spaced such that the top of the downstream dam should be at the same elevation as the toe of the

upstream dam. Rock check dams should be triangular in cross section with slopes of 1:1 or flatter on the upstream side and 2:1 or flatter on the downstream side. The middle overflow section of the check dam shall be half the total depth of the channel.

The check dam shall be inspected regularly in accordance with the SWPPP. The check dams shall be reshaped or replaced as needed during inspection. When the silt reaches 1/3 the height of the berm or 1-foot, whichever is less, the accumulated silt shall be removed and disposed of at an approved site in a manner that will not contribute to additional siltation. The check dam shall be left in place until all upstream areas are stabilized and accumulated silt removed; removal shall be done by hand.

202.10. CHECK DAM (FILTER TUBE)

202.10.1. Description. The work shall consist of constructing temporary filter tube check dams as shown on the plans during the construction period to control channel velocity and erosion.

202.10.2. Materials.

202.10.2.1. Filter Tube. Filter tubes shall meet the material requirements of [Item 202.18](#) Filter Tubes.

202.10.2.2. Stakes (Metal and Wood). Galvanized or painted steel stakes in studded "T" shape or punched "U" shape, minimum filter tube diameter of 18" and a weight of 1.25 pounds per linear foot minimum. Hardwood stakes or pressure treated wood stakes nominal 2"x2"x36" minimum dimensions.

202.10.2.3. Geotextile Fabric. Section held for future use.

202.10.3. Construction and Maintenance. Filter tube check dams should be placed at a distance and diameter (i.e. height) to allow small pools to form between each one. Typically, minimum tube diameter shall be 6". The tubes should be spaced such that the top of the downstream tube should be at the same elevation as the toe of the upstream tube. The filter tube shall be placed in a bedding trench to ensure firm contact between the tube and ground.

The check dam shall be inspected regularly in accordance with the SWPPP. The check dams shall be reshaped or replaced as needed during inspection. When the silt reaches 1/3 the height of the berm or 1-foot, whichever is less, the accumulated silt shall be removed and disposed of at an approved site in a manner that will not contribute to additional siltation. The check dam shall be left in place until all upstream areas are stabilized and accumulated silt removed; removal shall be done by hand.

202.11. STABILIZED CONSTRUCTION EXIT

202.11.1. Description. The work shall consist of constructing a temporary stabilized construction in accordance with contract documents. The exit will consist of a pad of crushed stone placed on a geotextile filter cloth and remain in place for the duration of the construction period to facilitate the removal of sediment and other debris from construction equipment prior to exiting the construction site. This includes all labor and materials associated with installation, maintenance, and ultimate removal of the stabilized construction exit as shown in the construction drawings or similar document.

202.11.2. Materials.

202.11.2.1. Stone. Stone material shall consist of 3-inch to 5-inch minimum coarse aggregate and shall be placed in a layer of at least 6-inches thickness. No crushed concrete shall be allowed.

202.11.2.2. Geotextile. The geotextile fabric must meet the following minimum criteria:

- (1) Tensile Strength, ASTM D4632 Test Method for Grab Breaking Load and Elongation of Geotextiles, 300-lbs.
- (2) Puncture Strength, ASTM D4833 Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products, 120-lbs.
- (3) Mullen Burst Rating, ASTM D3786 Standard Test Method for Hydraulic Bursting Strength of Textile Fabrics-Diaphragm Bursting Strength Tester Method, 600-psi.
- (4) Apparent Opening Size, ASTM D4751 Test Method for Determining Apparent Opening Size of a Geotextile, U.S. Sieve No. 40 (max).

202.11.3. Construction and Use. A temporary stabilized construction exit shall be installed at any point where traffic will be leaving a construction site to or from a paved surface such as a street, alley, sidewalk or parking area. The purpose of a stabilized construction exit is to reduce or eliminate the tracking or flowing of sediment onto paved surfaces. The exit shall be properly graded, sloping away from offsite paved surfaces

or incorporate a drainage swale to prevent runoff from leaving the construction site. Avoid placing construction access at the lowest point on the construction site or on top of proposed utility lines. The minimum length shall be 50 feet. The minimum width shall be 20 feet for sites less than 5 acres and 30 feet for sites 5 acres and larger.

The stabilized construction exit shall be maintained in a condition that prevents tracking or flow of sediment onto paved surfaces. Periodic re-grading and top dressing with additional stone must be done to keep the efficiency of the exit from diminishing. The rock shall be re-graded when ruts appear. Additional rock shall be added when soil is showing through the rock surface.

Additional controls will be required if inspections reveal a properly installed and maintained exit, but tracking of soil outside the construction area is still evident. All sediment spilled, dropped, washed or tracked onto public rights of way shall be removed immediately by the CONTRACTOR. The use of water to wash sediment from streets is prohibited.

When necessary, vehicles must be cleaned to remove sediment prior to entrance onto paved roads, streets, or parking lots. When vehicular washing is required, it shall be done on a constructed wheel wash facility that drains into an approved sediment trap or sediment basin or other sedimentation/filtration device.

202.12. STONE OUTLET SEDIMENT TRAP

202.12.1. Description. A stone outlet sediment trap is an impoundment created by the placement of a stone embankment and filter stone to prevent soil and sediment loss from a site. The stone embankment may be confined within a gabion basket or chain link fence fabric or unconfined. This item includes all labor and materials associated with installation, maintenance and ultimate removal of the stone outlet sediment trap as shown in the construction drawings or similar document.

202.12.2. Materials.

202.12.2.1. Embankment Stone. The embankment stone shall be comprised of Type A Dry Riprap stone conforming to [Item 803.3](#). Riprap and with a size range of 6 to 12 inches in diameter.

202.12.2.2. Filter Stone. The filter stone covering the upstream face of the 6 to 12 inch Riprap shall be 1 inches washed stone containing no fines meeting the requirement for coarse crushed stone in [Section 504.2.2.1](#), Crushed Stone Embedment.

202.12.2.3. Geotextile. The embankment stone shall be place on geotextile fabric meeting the following minimum criteria:

- (1) Tensile Strength, ASTM D4632 Test Method for Grab Breaking Load and Elongation of Geotextiles, 250-lbs.
- (2) Puncture Rating, ASTM D4833 Test Method for Index Puncture Resistance of Geotextiles, Geomembranes, and Related Products, 135-lbs.
- (3) Mullen Burst Rating, ASTM D3786 Standard Test Method for Hydraulic Bursting Strength of Textile Fabrics-Diaphragm Bursting Strength Tester Method, 420-psi.
- (4) Apparent Opening Size, ASTM D4751 Test Method for Determining Apparent Opening Size of a Geotextile, U.S. Sieve No. 20 (max).

202.12.2.4. Confinement. When a confined stone outlet sediment trap is used the confinement of the embankment stone shall be by one of the following:

- (1) Gabion Basket – Gabion baskets shall meet the requirements of [Item 803.2.2.1](#), Baskets, Metallic Coated. Tie wire shall be supplied by the gabion manufacturer for use with the product selected.
- (2) Chain Link Fence Fabric – Fabric shall meet the requirements of [Item 801.4.2.1](#), Chain Link Fence Fabric, Zinc or Aluminum coated. Tie wire or metal bands for closure and anchoring shall be as recommended by the fabric supplier for use with the fence material used.

202.12.2.5. Anchor Pipe. Standard weight, 2" nominal diameter galvanized steel pipe.

202.12.3. Construction and Maintenance. The required temporary storage volume behind the stone outlet structure as shown on the construction plans shall be provided with the existing topography or can be provided by additional excavation as needed. Embankment slopes of excavated area should not be steeper than 2H: 1V to prevent slope failures into the storage area.

202.12.3.1. Stone Embankment. The maximum stone embankment height shall be 6 feet as measured from the toe of the slope on the downstream side. The minimum width of the stone

embankment at the top shall be 2 feet. Embankment slope shall be 1.5H: 1V or flatter. The embankment shall have a depressed area to serve as the overflow with a minimum width of 4 feet. The overflow width shall be designed to have a minimum freeboard of 6" at design flow.

For a confined stone outlet sediment trap the embankment stone may be enclosed in a gabion basket or chain link fence fabric and anchored to the channel bottom to prevent washing away. This type of device shall be required where the placement will be in a perennial stream channel.

202.12.3.2. Filter Stone Embankment Face. Filter stone shall be placed on the upstream face of the stone embankment to a minimum depth of 6 inches.

202.12.3.3. Maintenance. The filter stone on the upstream face shall be removed and replaced when it becomes clogged with any material that prevents the storage basin from dewatering. Also, accumulated silt shall be removed from the storage area when the depth of sediment is equal to one-third of the height of the embankment as measured from the original toe of slope to the crest of the outlet, or has reached a depth of one foot, whichever is less.

202.13. PIPE SLOPE DRAIN

202.13.1. Description. A temporary pipe slope drain is an erosion control device that combines an earthen diversion dike and a rigid or flexible pipe to carry runoff over an exposed slope to a stabilized outlet apron. This includes all labor and materials associated with installation and maintenance of the pipe slope drain as shown in the construction drawings or similar document. Maximum drainage areas for individual pipe slope drains shall be 5 acres. For areas larger than 5 acres, additional drains shall be added. Both the entrance and outfall of the pipe slope drain should be properly stabilized. Grass can normally be used at the entrance, but armor type stabilization such as stone or concrete riprap is normally required to address the high velocities of the outfall.

202.13.2. Materials.

202.13.2.1. Pipe. The drain pipe shall be made of any material, rigid or flexible capable of conveying runoff. Regardless of material, the drain pipe shall be completely water-tight so that no water leaks onto the slope to be protected.

202.13.2.2. Stabilized Outlet. The most common stabilized outlet consists of well graded stone or recycled concrete riprap. Alternate materials for stabilized outlets may be approved by the OWNER.

202.13.2.3. Stabilized Entrance. Material shall be in accordance with [Item 202.15](#) Erosion Control Blankets.

202.13.2.4. Diversion Dike. Material shall be in accordance with [Item 202.7](#) Diversion Dike.

202.13.3. Construction and Maintenance.

202.13.3.1. Pipe Slope Drain. A diversion dike shall be constructed at the top of the slope which shall be protected. Attached to the inlet end of the pipe, using water-tight fittings, shall be a standard tee fitting with a stabilized entrance apron extending a minimum of 3 feet long by 3 feet wide from the open ends of the tee staked in place per the manufacturer's recommendations. Attached to the branch end of the tee fitting shall be rigid or flexible pipe to be used for containment of the runoff from the top of the slope to the bottom. The pipe shall be secured with hold down anchors spaced 10 feet on center.

202.13.3.2. Stabilized Outlet. A stabilized outlet shall be excavated to accept the runoff from the pipe and dissipate the energy of the flow.

202.13.3.3. Maintenance. Pipe slope drains should be inspected regularly (at least as often as required by the SWPPP Construction General Permit) to locate and repair any damage to joints or clogging of the pipe. In cases where the diversion dike has deteriorated around the entrance of the pipe, it may be necessary to reinforce the dike with sandbags or to install a concrete collar to prevent failure. Signs of erosion around the pipe drain should be addressed by stabilizing the area with erosion control blanket, turf reinforcement mats, riprap, concrete, or other acceptable methods. All repairs shall be completed in a timely manner or as directed by the OWNER.

202.14. INLET PROTECTION

202.14.1. Description. Inlet protection devices vary depending on the type of inlet and whether the inlet is located at grade (i.e. on a slope) or in a sag (i.e. at a low point). The devices are normally located at the inlet, providing either detention or filtration to reduce sediment and floatable materials in storm water. Clogging can greatly reduce or completely stop the flow into the inlet.

Ensure that inlet protection is properly designed, installed and maintained to avoid flooding of the roadway or adjacent properties and structures. Inlet protection devices shall provide overflow capability to allow stormwater overflow during extreme storm events or when the filter media on the protection device has clogged. Inlet protection **shall not** be installed on inlets located on publicly traveled streets unless approved by the OWNER in writing.

The five types of inlets commonly used in public works construction are listed below with their recommended inlet protection devices. Grate inlets are installed in either paved or unpaved locations and they are therefore listed twice in the list below. These measures include all labor and materials associated with installation, maintenance and ultimate removal of the inlet protection as shown in the details or the approved construction drawings.

202.14.1.1. Curb Inlets.

- A. Filter Tube – The use of a prefabricated or site fabricated filter tube and support system at the inlet to slow the sediment laden stormwater to allow sedimentation to occur. The diameter or height of the filter tube shall be two inches shorter than the curb opening height to allow for overflow capability.
- B. Filter Fabric – The use of a geosynthetic filter fabric material and support system at the inlet to slow the sediment laden stormwater to allow sedimentation to occur. A 2-inch high gap shall be cut in the filter fabric just below the top of the curb opening to allow for overflow capability. The filter fabric and support system are held in place with filter stone anchor bags strategically placed to hold the filter fabric in contact with the pavement surface and the curb face.

202.14.1.2. Grate Inlets in Paved Areas.

- A. Filter Tube – The use of a prefabricated or site fabricated filter tube at the inlet to slow the sediment laden stormwater to allow sedimentation to occur. The diameter or height of the filter tube shall be designated on the approved construction plans and shall be small enough to prevent flood damage to on site facilities or adjacent properties. Traffic control warning devices shall be provided to prevent damage from and to vehicles.
- B. Block & Gravel – The use of filter stone with a concrete block and hardware fabric support system to slow the sediment laden stormwater to allow sedimentation to occur.

202.14.1.3. Grate Inlets or Area Inlets in Unpaved Areas.

- (1) Filter Tube – The use of a prefabricated or site fabricated filter tube surrounding the inlet to slow the sediment laden stormwater to allow sedimentation to occur. The diameter or height of the filter tube shall be designated on the approved construction plans and shall be small enough to prevent flood damage to on site facilities or adjacent properties. The filter tube shall be located in a prepared bedding trench to ensure good contact with the underside of the filter tube and shall be staked in place to prevent movement by flowing stormwater.
- (2) Block & Gravel – The use of filter stone with a concrete block and hardware fabric support system to slow the sediment laden stormwater to allow sedimentation to occur.
- (3) Excavated Impoundment – The use of an excavated impoundment at the inlet to slow the sediment laden stormwater to allow sedimentation to occur. Dewatering weep holes shall be provided in the structure walls at the bottom of the excavation to allow the impoundment to dewater after rain events.
- (4) Filter Fabric – The use of filter fabric with wire backing supported by wooden stakes at each corner of the grate and reinforced with a 2"x4" wood frame around the top perimeter of the wood posts.

202.14.1.4. Combination Inlets.

- (1) Filter Tube – The use of a prefabricated or site fabricated filter tube at the inlet to slow the sediment laden stormwater to allow sedimentation to occur. The diameter or height of the filter tube shall be

designated on the approved construction plans and shall be small enough to prevent flood damage to on site facilities or adjacent properties. Traffic control warning devices shall be provided to prevent damage from and to vehicles.

202.14.1.5. Pipe Inlets.

- (1) **Filter Tube** – The use of a prefabricated or site fabricated filter tube and support system at the inlet end of an open pipe system to slow the sediment laden stormwater to allow sedimentation to occur. The diameter or height of the filter tube shall be one half the diameter of the pipe opening to allow for overflow capability.
- (2) **Filter Stone** – The use of a confined or unconfined stone dam with a six inch thick layer of filter stone on the upstream face of the stone dam to slow the sediment laden stormwater to allow sedimentation to occur. The height of the stone dam shall be one half the diameter of the pipe opening to allow for overflow capability.

202.14.2. Materials.

202.14.2.1. Filter Tubes. Filter tubes shall meet the material requirements of [Item 202.18](#) Filter Tubes.

202.14.2.2. Concrete Blocks. Concrete blocks shall be standard 8" x 8" x 16" hollow core concrete masonry units and may be either load bearing or non-load bearing concrete masonry units.

202.14.2.3. Geotextile Filter Fabric. The fabric shall meet the material requirements of [Item 202.5](#) Silt Fence.

202.14.2.4. Filter Stone. Filter stone shall consist of 1-1/2 inch Coarse Crushed Stone conforming to [Item 504.2.2.1](#). Crushed Stone Embedment. Angular shaped stone is preferable to rounded shapes.

202.14.2.5. Stakes (Metal and Wood). Galvanized or painted steel stakes in studded "T" shape or punched "U" shape, minimum 36" long and a weight of 1.25 pounds per linear foot minimum. Hardwood stakes or pressure treated wood stakes nominal 2"x2"x36" minimum dimensions.

202.14.2.6. Wire Mesh. Wire mesh shall be standard hardware cloth or comparable wire mesh with an opening size not to exceed 1/2-inch.

202.14.2.7. Stone Riprap. The stone riprap shall be comprised of Type A Dry Riprap stone conforming to [Item 803.3](#). Riprap with a size range of 6 inches to 12 inches in diameter.

202.14.3. Construction and Maintenance. Inlet protection filter media shall be placed to intercept the flow of sediment laden water into the inlet with no gaps and shall be adequately anchored to prevent movement. When properly installed the inlet filter media will pond water during a rain event and for up to two days after the end of the rain event. If the filter media becomes clogged and will not drain, remove the standing water through another sediment control BMP before it is allowed into the storm drain or off site. **Do not remove the filter media to allow the water to drain.** Replace the filter media with new material prior to the next rain event.

Check inlet protection devices for proper construction immediately after installation, at the end of each work day, immediately prior to rain events and as required by the SWPPP. Remove trapped sediment, floatable debris and yard waste as needed to keep the filter media clear.

202.14.3.1. Curb Inlets. The filter media shall make firm contact with the pavement surface at all times, shall extend beyond the curb opening at least 24 inches along the curb and be pressed tight against the curb face on both sides of the inlet opening. The overflow gap shall be provided to prevent complete blockage of the inlet opening.

202.14.3.2. Grate Inlets in Paved Areas. The filter media shall completely surround the grate inlet with no gaps and shall make firm contact with the pavement surface at all times. The height of the filter media surrounding the grate inlet shall be shown on the approved plans and must be checked on site to ensure that when water attains the top height of the filter media it will not cause localized flooding or property damage. Grate inlets are commonly located in the middle of paved areas subject to local and construction traffic. Installations shall have adequate traffic control devices to prevent damage to vehicles and to prevent damage to the BMP.

202.14.3.3. Grate Inlets & Area Inlets in Unpaved Areas. The filter media shall completely surround the inlet with no gaps and shall make firm contact with the ground surface at all times. A bedding trench

shall be provided under filter tubes when they are used. The height of the filter media surrounding the inlet shall be shown on the approved plans and must be checked on site to ensure that when water attains the top height of the filter media it will not cause localized flooding or property damage.

202.14.3.4. Combination Inlets. The filter media shall surround the three non-curb sides of the grate, extend beyond the curb opening at least 24 inches along the curb and be pressed tight against the curb face on both sides of the inlet opening.

202.14.3.5. Pipe Inlets. The filter media shall surround the pipe opening inlet as shown on the approved plans for project. A bedding trench shall be provided under filter tubes when they are used.

202.15. EROSION CONTROL BLANKETS

202.15.1. Description. An erosion control blanket (ECB) is a temporary erosion prevention product placed over disturbed areas to limit the effects of erosion due to rainfall impact and runoff across barren soil. Erosion control blankets are manufactured by a wide variety of vendors addressing a wide variety of conditions such as slope and functional longevity. Blankets are typically constructed of natural materials such as coir (coconut husk) fibers, excelsior (wood) or straw between two layers of synthetic netting.

202.15.2. Materials.

202.15.2.1. Blanket. Erosion control blanket shall be of a type and class appropriate to site-specific requirements as determined by the OWNER. Installed materials shall meet the applicable "Minimum Performance Standards for TxDOT" as published by TxDOT in its "Erosion Control Report". Approved products may be found in the official listing on the most current annual "Approved Products List for TxDOT" applicable to TxDOT Item 169 Soil Retention Blanket and its Special Provisions.

202.15.2.2. Staples. Staples shall conform to the recommendations shown within the manufacturer's published literature for the approved soil retention blanket. In the absence of manufacturer's recommendation for staples, a minimum 11-gauge wire staples 6-inches in length and 1-inch in width shall be used.

202.15.3. Construction and Maintenance.

202.15.3.1. Erosion Control Blanket. Prior to the installation of any erosion control blankets, all rocks, dirt clods, stumps, roots, trash and any other obstructions that would prevent the mat from lying in direct contact with the soil shall be removed. Anchor trenching shall be located along the entire perimeter of the installation area, except for small areas with less than 2% slope. These trenches shall be 6-inches deep and 6-inches wide and the blanket shall be laid into the trench then backfilled with compacted soil or gravel. At a minimum, the end of each roll of ECB shall overlap the next roll by 3 feet and the sides of rolls shall overlap 4 inches. Blankets shall be fastened to the ground according to the manufacturer's instruction. Staples shall be placed parallel to the flow, at all critical channel points, and at all overlaps. If requested by the OWNER, the CONTRACTOR shall submit staple pattern to the OWNER for approval. Installations shall be in accordance with manufacturer's recommended guidelines with the exception of the minimum criteria stated herein.

202.15.3.2. Maintenance. Blankets shall be inspected for deficiencies every seven days and after each half-inch or greater rainfall event. Noted deficiencies shall be repaired or replaced prior to the next rainfall event, but no later than seven days.

202.16. SECTION HELD FOR FUTURE USE

202.17. SECTION HELD FOR FUTURE USE

202.18. FILTER TUBES

202.18.1. Description. The work shall consist of constructing temporary filter tubes consisting of a filter media confined within a roll or tube of mesh material. The filter tube is then anchored or secured to the ground or pavement surface to prevent movement during storm events. The filter tube slows the flow of

sediment laden stormwater to allow the sediment to settle out or to be filtered out as the stormwater seeps through the filter media. Installations are either for perimeter protection or slope protection.

202.18.2. Materials.

202.18.2.1. Tubes. Tubes shall be constructed out of geosynthetic material, plastic mesh, jute mesh, coir mesh or metal hardware fabric. Material used shall be of adequate strength and durability to withstand anticipated environmental conditions (Heat, cold, ultraviolet light, etc.) and construction hazards during the full term of the device installation. The mesh openings shall be large enough to allow the flow of water through the filter media, but will be small enough to contain the filter media.

202.18.2.2. Filter Media. Filter media may consist of any of the following or an approved combination of the following materials:

- (1) Compost. Erosion Control Compost (ECC) per TxDOT Specification Item 161, Compost.
- (2) Coir or Straw. Commercially produced product interwoven into the tube mesh. Loose material inserted into the tube will not be allowed.
- (3) Filter Stone. Stone shall consist of 1-1/2 inch Coarse Crushed Stone conforming to [Item 504.2.2.1. Crushed Stone Embedment](#).

202.18.2.3. Stakes. Stakes may be metal or wood. Metal stakes when used will be T-section or L-section and 1.3 pounds per linear foot minimum. Wood stakes when used shall have a nominal cross section of 2-inches by 2-inches. Stakes shall be at least six inches longer than the outside diameter of the tube being anchored.

202.18.3. Construction and Maintenance. Installations shall be of the size and material specified on the approved plans or as approved by the OWNER. Overlaps between ends of bound or sealed tubes shall be a minimum of three feet and shall be securely tied together to prevent gaps from forming between the tubes and movement of the tubes. Filter Tubes are to be placed along a line of constant elevation (along a contour line) where possible. The ends of the tube installation at the edge of the disturbed ground area shall be turned uphill to prevent the bypass of stormwater.

202.18.3.1. Perimeter Protection. For installations on soil, construct a one-inch to two-inch deep shaped bedding trench along the full length of the filter tube to ensure positive contact of the filter tube with the soil. Install the properly sized filter tube at the downstream edge of the disturbed land area and anchor in place with stakes placed on maximum eight-foot centers. For installations on pavement which typically occur along utility trenches or when there is a temporary stockpile of erodible material, the mesh with the filter media in place shall provide at least a 6-inch wide contact with the pavement to ensure that the stormwater flows through the filter media. The filter tube shall be anchored with temporary traffic control devices (i.e. vertical panel, barrels, etc.) or standard concrete masonry units to prevent movement of the filter tube during storm events.

202.18.3.2. Slope Protection. Slope protection installations are generally only installed when slopes are steeper than 5H: 1V, slopes that are longer than 30' from top to bottom, or the slope has a large amount of stormwater runoff that will flow downslope. Filter tubes shall be placed at the spacing shown on the approved plans, but generally every 25' apart along lines of constant elevation.

202.19. MEASUREMENT AND PAYMENT

If included in the Contract as a unit price item, measurement for payment will be made complete, in place and ready for use inclusive of all components necessary for a complete and working installation. This includes all labor and materials associated with installation, maintenance, and ultimate removal as shown in the construction drawings or similar document, and establishing permanent ground cover at removal.

ITEM 203. SITE PREPARATION

203.1. GENERAL SITE PREPARATION

203.1.1. Description. This Item shall consist of preparing the right-of-way and designated easements for construction operations by the removal and disposal of all obstructions from the right-of-way and from designated easements, where removal of such obstructions is not otherwise provided for in the plans and specifications. Such obstructions shall be considered to include remains of houses not completely removed by others, foundations, floor slabs, concrete, brick, lumber, plaster, septic tanks, basements, abandoned utility pipes or conduits, equipment or other foundations, fences, retaining walls, outhouses, shacks and other debris.

This item shall also include the removal and disposal of curb and gutters, driveways, paved parking areas, miscellaneous stone, brick, concrete sidewalks, drainage structures, manholes, inlets, abandoned railroad tracks, scrap iron, all rubbish and debris, whether above or below ground except live utility facilities. This Item shall also include the removal and disposal of designated trees, stumps, bushes, vegetation, roots, shrubs, brush, and logs. It is the intent of this specification to provide for the removal and disposal of all obstructions and objectionable materials not specifically provided for elsewhere in the plans and specifications. This Item does not include the removal and disposal of hazardous material.

203.1.2. Construction Methods.

The entire right-of-way, permanent and temporary easements for this project and such additional areas, including public or corporate areas and public or corporate lands, as made available for construction of this project, shall be cleared of all structures and obstructions, as defined above, except that trees or shrubs shall be protected unless specifically designated by the OWNER for removal. Unless designated for removal without replacement, trees and shrubs shall be treated according to [Item 201.1](#), Removal, Protection, and Replacement of Trees, Shrubbery, Plants, Sod, and Other Vegetation. Unless otherwise indicated on the plans, trees and stumps to be removed shall be cut off or otherwise removed as close to the natural ground as practicable on areas which are to be covered by at least 3-ft. of embankment. On areas required for borrow sites and material sources, stumps, roots, etc., shall be removed to the complete extent necessary to prevent such objectionable matter becoming mixed with the material to be used in construction. At all times during site preparation, the area shall be maintained in a manner as to prevent standing water.

Unless otherwise indicated on plans, all foundations and underground obstructions shall be removed to the following depths:

- (1) In areas to receive embankment, 2-ft. below natural ground or to bottom of structure.
- (2) In areas to be excavated, 2-ft. below the lower elevations of the excavation, or to the bottom of structure.
- (3) In all other areas, 1-ft. below natural ground or to bottom of structure.

All basement walls and floors, septic tanks and storage tanks within the limits of the right-of-way shall be removed and the resulting holes backfilled as directed by the OWNER. Holes remaining after removal of all obstructions, objectionable material, trees, stumps, etc., shall be backfilled. The CONTRACTOR shall complete the operation of preparing right-of-way so that the prepared right-of-way shall be free of holes, ditches and other abrupt changes in elevations and irregularities to contour.

The remaining ends of all abandoned-in-place storm sewers, culverts, sanitary sewers, conduits and water or gas pipes shall be plugged with an adequate quantity of concrete to form a tight closure. All materials and debris removed shall become the property of the CONTRACTOR unless otherwise provided for on the plans or in the specifications and shall be removed from the right-of-way. Unless otherwise provided, all merchantable timber removed as previously specified shall become the property of the CONTRACTOR. Gravel, brick, stone or broken concrete, when permitted by special conditions, may be used in the roadway embankment.

203.1.3. Measurement and Payment. General site preparation shall be measured on a lump sum basis, unless indicated otherwise. Measurement for payment shall be made only on areas indicated and classified on the plans as "General Site Preparation," and disposed of properly as indicated in [Item 107.26](#), Disposal of Materials. All work performed and measured as prescribed by this Item shall be paid for at the lump sum

price bid for “General Site Preparation” unless indicated otherwise, which price shall be full compensation for furnishing all labor, equipment, tools, supplies and incidentals necessary to complete the work.

203.2. UNCLASSIFIED EXCAVATION

203.2.1. Description. Unclassified excavation shall consist of required excavation for general site grading, and street and channel excavation within the limits of the OWNER’S right-of-way or designated easements and areas adjacent thereto (except excavation specifically described and provided for elsewhere in the specifications). This will include the proper removal, utilization, and/or disposal of all uncontaminated excavated materials to the required lines, grades and typical cross sections in accordance with the plans and specifications.

203.2.2. Classification. All authorized excavation shall be “unclassified” and involves removal of all materials necessary to permit carrying on the completion of the work. Any reference to rock or other material on the plans and/or in this specification is solely for the OWNER’S and CONTRACTOR’S information and is not to be taken as an indication or guarantee of classification of excavation.

203.2.3. General. In general, all excavation shall be made in open cut from the surface of the ground and shall be no greater in width or depth than is necessary to permit the proper construction of the work in accordance with the plans and specifications. Where excavation to grades established in the field by the OWNER would terminate in unstable soil, the CONTRACTOR shall remove the unstable soil and backfill to the required grade. Work shall be executed in a neat workmanlike manner. All excavation shall be to the line and grade as provided on the approved plans. The CONTRACTOR shall abide by all applicable federal, state and/or local laws governing excavation work.

The CONTRACTOR shall provide for the uninterrupted flow of storm, water and wastewater lines and surface waters during progress of the construction. The CONTRACTOR shall coordinate interruptions to gas, electric, and other services no less than two (2) days prior to construction of the planned interruptions. Completed work shall conform to the established alignment, grades and cross sections.

203.2.4. Water for Construction. The CONTRACTOR shall provide water as needed for site preparation, compaction, and other incidental activities in accordance with local requirements.

203.2.5. Dewatering. During construction, channels, trenches, pits, and other low point excavations shall be kept drained, insofar as practicable. Dewatering work shall include the installation and operation of all pumping, bailing, well-pointing, sumps, and draining necessary to keep the excavation free from groundwater, seepage water, water from storm drains, wastewater collection systems, ditches, creeks, ponds, and other sources. Construction will not be permitted in standing water. All discharges from dewatering activities shall be in conformance with all federal, state, and local requirements in a manner approved by the OWNER. Outlet velocity of discharges from dewatering activities shall be controlled to prevent erosion. Unless provided for as a separate pay item, all dewatering work shall be considered incidental to unclassified excavation.

203.2.6. Excavated Material. Excavated materials shall be handled at all times in such manner as to cause a minimum of inconvenience to the public and to permit safe and convenient access to private and public property adjacent to the line of the work.

All suitable materials removed from the excavation shall be used, insofar as practicable, in the formation of embankments as required by [Item 203.5](#). Embankment, or shall be otherwise utilized. Desirable topsoil, sod, etc. shall be carefully removed and piled separately adjacent to the work when required. Suitable excavated materials to be utilized for the project may be temporarily stockpiled adjacent to the work provided appropriate BMPs are installed.

Unclassified excavated material in excess of that needed for construction or deemed unsuitable shall be known as “waste” and, unless specified otherwise, shall become the property of the CONTRACTOR to be disposed of outside the limits of the project in accordance with federal, state, and local requirements.

203.2.7. Alternate Methods of Excavation. Prior to commencing any alternate method of excavation, the CONTRACTOR shall submit means and methods approach for approval by the OWNER. All alternate methods of excavation shall be in compliance with applicable federal, state, and local requirements. If approved by the OWNER, alternate methods of excavation shall be at no additional cost to the OWNER.

203.2.8. Measurement and Payment. All unclassified excavation shall be measured in its original position and the volume in cubic-yards determined by the average end area method. Work performed for finishing of parkways and medians shall not be measured directly, but shall be considered subsidiary to unclassified excavation.

All unclassified excavation work performed as prescribed by this Item shall be paid for at the contract bid price per cubic-yard for unclassified excavation, which price shall constitute payment in full for furnishing and operating all equipment, excavation, placement, compaction, loading, hauling, and unloading and for satisfactory disposal of unsuitable and excess materials; finishing slopes, ditches and parkways; for all maintenance blading or scarifying the ground surface; and for furnishing all labor, fuel, tools, materials, equipment, implements, and incidentals necessary to the satisfactory performance of the work.

203.3. SECTION HELD FOR FUTURE USE

203.4. BORROW & SPOIL

203.4.1. Description. Borrow shall consist of required excavation, removal, and proper utilization of materials obtained from designated or approved off-site sources. Spoil shall consist of the required excavation, removal, transportation, deposit, and storage of materials to an off-site location.

203.4.2. Classification. All authorized borrow shall be “unclassified” unless otherwise noted.

203.4.3. Construction Methods. All suitable materials removed from the excavation shall be used, insofar as practicable, in the formation of the embankment as required by the governing item for embankment; or shall otherwise be utilized as indicated on the plans or as directed. The completed work shall conform to the established alignment, grades and cross section. Site of the borrow and spoil operations shall be left so as to provide proper drainage where practicable. Where indicated on the plans, the sides and/or ends of borrow pits shall be sloped to the dimensions indicated on the plans.

203.4.4. Selection of Materials. Where shown on the plans, select material shall be utilized in the formation of embankment, embedment or backfill, or to improve the project, in which case the work shall be performed in such a manner and sequence that suitable material may be selected, removed separately and deposited in the project as shown on the approved plans. When required, acceptable borrow material, tested by standard laboratory methods, and shall meet the requirements indicated on the plans.

203.4.5. Measurement and Payment. Borrow shall be measured in a compacted condition in its final position and the volume computed in cubic-yards by the method of average end areas, or as specified otherwise. Spoil sites shall be considered part of the overall project site, and the spoil area shall contribute to the total project acreage.

All work performed as required herein and in the [Item 203.5](#), Embankment, and measured as provided in this Item shall be paid for at the unit price bid. Payment shall not be allowed for excavation for any material which is used for purposes other than those designated. The unit price shall be full compensation for furnishing all labor, for materials, tools, equipment, compaction, hauling and incidentals necessary to complete the work, as well as for any and all fees associated with disposal.

203.5. EMBANKMENT

203.5.1. Description. Embankment shall consist of the placement and compaction of all suitable materials obtained from excavation, borrow or any other approved excavation.

203.5.2. Construction Methods. Prior to the placing of any embankment, all clearing and grubbing and site preparation shall have been completed. Stump holes or other small excavations within the limits of the embankment shall have been backfilled with material with same properties as to in-situ material or specified fill material before commencing the embankment construction. The surface of the ground, including plowed or loosened ground or small ditches or washes, shall be restored to approximately its original slope.

The surface of hillsides shall be loosened by the scarifying or plowing to a depth of not less than 4-in. or cut into steps before embankment materials are placed. The embankment shall then be placed in layers as hereinafter specified, beginning at the low side in part widths as the embankment is raised. The material

which has been loosened shall be recompacted simultaneously with the embankment material placed at the same elevation.

Where embankment is to be placed over or adjacent to the existing roadbeds, the slopes shall be plowed or scarified to a depth not less than 4-in. and the embankment built up in successive layers, as hereinafter specified, to the level of the old roadbed before its height is increased. Then the old roadbed shall be scarified and recompacted with the next layer of embankment. The total depth of the scarified and added materials shall not exceed the permissible depth of the layer. All embankments for roadbeds shall be constructed in layers approximately parallel to the finished grade of the street and shall be so constructed as nearly as possible to conform to the cross section of the subgrade section.

Embankments shall be constructed to the established grade and to the shape of the typical section shown on the plans, and each section shall conform to the detailed sections of slopes. After completion of the embankment, it shall be continuously maintained to its finished section and grade until the project is accepted.

Earth embankments shall be constructed in successive layers, for the full width of specified depth or cross sections; and in such lengths as are suitable for the sprinkling and compaction methods to be used. Each layer of earth embankment shall be uniform as to material, density, and moisture content before beginning compaction. Prior to compaction, the layers shall not exceed 6-in. in depth for pneumatic tire rolling or 8-in. in depth for rolling with other types of rollers unless otherwise specified on the plans.

Earth embankment for the construction of dams and placed adjacent to and over pipes, culverts, arches and bridges shall be of material as specified on the plans and shall be placed in successive layers approximately horizontal. Layers of embankment shall be brought up uniformly on each side of the structure, and special care shall be taken to prevent any wedging action against the structure. For such distances along embankments adjacent to structures where it is impracticable to obtain compaction by rolling, the embankment material shall be placed in layers not exceeding 6-in. in depth of loose material wetted uniformly to the moisture content directed; and shall then be compacted by methods approved by the OWNER, maintaining the required moisture content by additional sprinkling, if necessary, supplemented by such hand work as is necessary to secure a uniform and thoroughly compacted fill, until each layer has been uniformly compacted to the satisfaction of OWNER.

All earth cuts, full or part width in the side of a hill, which are not required to be excavated below subgrade elevation for base or backfill, shall be scarified to a uniform depth of not less than 6-in. below grade shown on the plans, and the materials shall be mixed and reshaped by blading and then sprinkled and rolled in accordance with the hereinabove outlined requirements for earth embankments.

Rock embankments shall be composed principally of rock and shall be constructed in successive layers for the full width of the specified depths or cross sections, and each layer shall be 18-in. or less in depth. Each layer shall be constructed by starting at one end, dumping the rock on top of the layer being constructed and then pushing the dumped material ahead in such a manner that the larger rock shall be placed on the ground or preceding rock embankment layer; and the interstices between the larger stones shall be filled with smaller stones and spalls both by this operation and from the placing of succeeding loads of rock materials. Each rock layer shall be rolled or compacted as specified in the plans. The upper or final layer of rock embankment shall contain no stones larger than 4-in. in their maximum dimension, and insofar as such is available by selection of the excavation, this layer shall be composed of materials so graded that the maximum density and uniformity of the surface layer may be secured. Each rock embankment layer shall be rolled as directed by the OWNER.

In addition to the foregoing selection of materials and utilization of the materials in the embankment, the embankment shall be constructed in the proper sequence to receive select materials as specified or as shown on the plans, with any modifications as may be directed by the OWNER. The layer of embankment immediately preceding the upper layer of select material shall be constructed to the required cross section and the proper elevation within a tolerance of not more than 0.1-ft. from the established cross section or elevation after proper compaction and shall be finished as necessary to receive the select material.

203.5.3. Density. For each layer of earth embankment and select material, the relative compaction of the embankment shall be as shown on the plans. Earth embankment and select material shall be compacted to between 95 percent and 100 percent of Standard Proctor Density as determined by ASTM D-698 at, or up to

five (5) percentage points above, optimum moisture content, using mechanical compaction methods, unless otherwise specified in the plans or specifications. After each section of earth embankment or select material is completed, such tests as are necessary shall be made as specified by the OWNER, unless otherwise specified in the special provisions or in the plans.

203.5.4. Measurement and Payment. Embankment shall not be measured or paid for as a separate contract pay item, but the cost of construction of the embankment complete in place shall be included in such contract pay items as described in standard specifications [Item 203.2](#). Unclassified Excavation or [Item 203.4](#). Borrow & Spoil. The contract pay items provided shall be full compensation for the furnishing of all labor, material, tools, equipment and incidentals necessary to complete the embankment, including cost of water, sprinkling or wetting, rolling, compaction, etc., in accordance with the plans and specifications.

203.6. DUST CONTROL

203.6.1. Description. Sprinkling for dust control shall consist of the authorized application of water or other material approved by the OWNER on those portions of the projects as shown on the plans or as directed and as herein specified. It shall be the responsibility of the CONTRACTOR to take preventive measures to eliminate, reduce, or alleviate any dust nuisance in the work area. The OWNER will approve the method used. Should the CONTRACTOR fail to control dust as outlined above, the OWNER may suspend the work until corrective measures are taken.

203.6.2. Materials. Water or other material approved by the OWNER shall be furnished by the CONTRACTOR and shall be clean, free from industrial waste and other objectionable matter. Emulsions shall meet the requirements of [Item 302.3.5](#). Emulsions for Priming, Curing and Erosion Control.

203.6.3. Construction Methods. The CONTRACTOR shall use sprinkling or other methods acceptable to the OWNER to control dust in accordance with TCEQ airborne contamination requirements. When sprinkling, the CONTRACTOR shall furnish and operate a sprinkler equipped with positive and rapidly working cutoff valves and approved spray bars, which shall insure the distribution of material in a uniform and controllable rate of application.

The CONTRACTOR shall maintain all excavations, embankment, stockpiles, haul roads, and access roads within or outside the project boundaries free from dust, which would cause a hazard or nuisance to adjacent property owners. The CONTRACTOR shall effectively prevent and control erosion and sedimentation from any runoff resulting from dust control activities. It shall be the CONTRACTOR'S continuous responsibility to be on call at all times including nights, holidays, weekends, etc. and respond in a timely manner, until acceptance of the project by the OWNER, to maintain the project free of dust in a manner which shall cause the least inconvenience to the public.

203.6.4. Measurement and Payment. Sprinkling performed as provided above shall be measured by the 1,000-gallons as delivered on the project. Sprinkling provided in the proposal and the contract as a separate pay item shall be paid for in accordance with the contract unit price. Noncompliant dust control activities shall not be approved for payment by the OWNER. When sprinkling is not classified separately for payment, then such sprinkling shall be considered as incidental work and shall not be paid for as a separate item; the cost thereof shall be included in such contract pay items as are provided. In either case, such pay items shall be the total compensation for all labor, materials, tools, machinery, equipment and incidentals necessary to complete the work in accordance with the plans and this specification.

ITEM 204. LANDSCAPING

204.1. VEGETATION REMOVAL AND REUSE, CLEARING AND GRUBBING

204.1.1. Trees. No trees shall be removed unless so noted on the plans or upon the specific approval of the OWNER. Where trees are adjacent to the line of the work and are not to be removed or are designated on the plans to be removed and replaced, the CONTRACTOR shall protect such trees by substantial wooden boxes and guards and shall not permit machinery or employees to scrape, tear the limbs from, damage or attach guy cables to them. If, in the opinion of the OWNER, such trees, etc., would be damaged by machinery, etc., hand excavation may be required. The CONTRACTOR shall be responsible for all damage to adjacent trees, etc., and any such damage shall be remedied to the satisfaction of the OWNER. All damaged limbs over 1-inch in diameter shall be sawed clean adjacent to the damaged area or at the trunk and dressed with acceptable tree wound treatment material, unless dressing is waived by the OWNER. Trees that are to be removed and subsequently replaced shall be designated on the plans. The cost of protection shall not be paid for as a separate contract pay item; the costs thereof shall be included in such pay items as are provided for in the proposal and contract.

204.1.2. Shrubbery, Plants, Sod and Other Vegetation. Shrubbery, plants, sod and any vegetation noted on the plans to be removed shall be removed and disposed of. Reuse of these items, unless specifically called for by the plans, shall not be permitted. The cost of removal shall be paid for as a separate contract pay item if a separate pay item is provided; otherwise, the costs thereof shall be included in such pay items as are provided in the proposal and contract. Where shrubbery, plants, sod and any vegetation are removed in making the excavation, such areas shall have the same shrubbery, plants, sod, vegetation, etc., of the same kind, and in new condition, replaced in their prior positions or as close as possible. When backfilling is completed, the shrubbery, plants, sod, vegetation, etc. shall be carefully replaced in their original location and the area thoroughly wet down. The cost of such replacement shall be paid for as a separate contract pay item if a separate pay item is provided; otherwise, the costs thereof shall be included in such pay items as are provided in the proposal and contract.

204.2. TOPSOIL

204.2.1. Description. This Item shall consist of furnishing and placing topsoil, free from rock and foreign material, as indicated on the plans, to the lines and grades as established by the construction plans.

204.2.2. Materials and Storage. All excavated material which is suitable for topsoil shall be used before any topsoil is obtained from a borrow source. Topsoil shall be secured from borrow sources as required to supplement suitable material secured from project excavation. Topsoil material secured from excavations shall be stockpiled at locations approved by OWNER.

204.2.3. Construction Methods. Approved topsoil shall be a minimum thickness of 6-inches unless otherwise specified on the plans, and shall be placed on areas formed to the line and grade specified in the plans.

204.2.4. Measurement and Payment. Topsoil secured from borrow sources shall be measured by the square yard in place on the project site. Measurement for payment shall be made only on topsoil secured from borrow sources. All work performed as ordered and measured as provided under this Item shall be paid for at the unit price bid for topsoil. The price shall be full compensation for excavating (except as noted below), loading, hauling, placing and furnishing all labor, equipment, tools, supplies and incidentals necessary to complete the work.

All labor, equipment, tools and incidentals necessary to place salvage topsoil as specified shall be included in the price bid for [Item 203.2](#). Unclassified Excavation. All excavation required by this Item in cut section shall be measured in accordance with provisions for the various excavation items involved with the provision that excavation shall be measured and paid for once only, regardless of the manipulations involved.

204.3. SOIL AMENDMENTS

204.3.1. General. Where indicated on the plans and defined in the specifications, soil amendments shall be added as defined or as noted in these specifications.

204.3.2. Sand. All sand shall be thoroughly washed, coarse grade construction or brick sand, free of clay balls, weeds or grass. So-called cushion sand, blow sand, creek silt or water treatment solid byproducts shall not be acceptable. A quart sample of the sand proposed to be used shall be submitted for the OWNER's approval.

204.3.3. Compost. This Item shall govern for the furnishing and placing of approved compost material to the depths and area shown on the plans or as directed by the OWNER.

204.3.3.1. Materials. Compost material shall be an organic substance produced by the aerobic (biological) decomposition of organic matter. All compost is to be clean and free of visible refuse, live plants, seed, excessive cotton lint and any chemical elements harmful to plant growth. Composted matter may include, but is not limited to, brush, manure and/or other agricultural residuals, forest residues and bark, and unrecyclable paper. Mixed municipal solid waste compost, and Class B Biosolids (as defined in 40 CFR part 503) shall not be allowed. Raw organics in the finished compost shall not be allowed.

Compost materials furnished shall meet all applicable Federal (40 CFR Part 503 Standards for Class A Biosolids) and TCEQ health and safety regulations (TAC Chapter 332). All compost material supplied shall be processed to meet the time and temperature standards in TAC Chapter 332 Subchapter B Part 23 to control noxious weeds, pathogen and vector attraction; and the physical requirements shown in Table 204.3.4.1.(a) Compost Physical Requirements.

Table 204.3.3.1.(a) Compost Physical Requirements

Compost for Manufactured Topsoil	Erosion Control Compost	General Use Compost
Organic Matter Content as determined by loss on ignition (ASTM D5268 Standard Specification for Topsoil Used for Landscaping Purposes @ 824°F)		
30% (dry mass)	40-60% (dry mass)	40-60% (dry mass)
Particle Size as determined by TEX-110-E Particle Size Analysis of Soils		
100% passing 1"	100% passing 3" <70% passing 2"	100% passing 3/4" <70% passing No. 20
Soluble Salts as determined by TEX-129-E Measuring the Resistivity of Soil Materials		
5.0 max. mmhos/cm)	5.0 max. mmhos/cm	5.0 max. mmhos/cm
(1) Maturity		
Finished	Finished	Finished
pH as determined by TEX-128-E Determining Soil pH		
5.5 - 8.5	5.5 - 8.5	5.5 - 8.5

204.3.3.2. Construction Methods. After the designated areas have been completed to the lines, grades, and cross sections shown on the plans and as provided for in other items to the contract, compost of the type specified shall be placed in accordance with the requirements hereinafter described and as directed by the OWNER. Any stockpile areas shall be well drained, and shall be left in a neat and presentable condition upon completion of the removal of the materials. Where rolling is specified, the roller shall be a light corrugated drum roller of the type approved by the OWNER. Compost shall be loose and friable and not dusty at the time of application. Compost may be required to be brought to an acceptable moisture content, as directed by the OWNER. No compost materials shall be placed within 30-yards of any source of surface water or drinking water supply.

204.3.3.2.1. Compost Manufactured Topsoil. Compost manufactured topsoil shall consist of soil constituents amended with 5- to 30-percent compost, measured by volume, as shown on the plans. Any trash, stumps, roots, weeds, or other objectionable materials in the soil shall be removed and disposed of, as approved by the OWNER, prior to beginning the mixing process.

Blended On-Site. Compost shall be spread in a uniform layer over the previously prepared subgrade area and thoroughly incorporated into the soil materials, to the depths shown on the plans, by rototilling, harrowing, or other suitable methods. After the topsoil has been produced and shaped, it shall be sprinkled and rolled as directed by the OWNER.

Pre-Blended. Topsoil manufactured from sources outside the right-of-way shall be produced in accordance with the requirements for Blended On-Site topsoil, and spread over the prepared subgrade so as to form a uniform layer of loose material of the thickness shown on the plans. After the topsoil has been placed, it shall be raked carefully to remove all objectionable materials and to yield a consistent grade, and then sprinkled and rolled as directed by the OWNER.

204.3.3.2.2. Erosion Control Compost. Compost shall be spread evenly over the previously prepared subgrade or slopes so as to form a uniform layer of loose material of the thickness shown on the plans. Erosion Control Compost shall not be placed on any slope having a slope ratio steeper than 2:1. After the compost has been placed, it shall be sprinkled and rolled as directed by the OWNER.

204.3.3.2.3. General Use Compost. General use compost shall be applied as a top dressing by placing the material evenly upon established areas of turf, grass, or other ground cover growth to the depth specified on the plans or as directed by the OWNER. Compost applications shall not bury or kill existing vegetation. All stems, roots, or other debris larger than 2-inches diameter shall be removed from the ground surface.

204.3.4. Measurement and Payment. "Compost Manufactured Topsoil (Blended On-Site)", "Compost Manufactured Topsoil (Pre-Blended)", "Erosion Control Compost" and "General Use Compost" will be measured by the cubic-yard in vehicles at the point of delivery.

The work performed and materials furnished in accordance with this Item and measured as provided for shall be paid for at the unit price bid for "Compost Manufactured Topsoil (Blended On-Site)", "Compost Manufactured Topsoil (Pre-Blended)", "Erosion Control Compost" or "General Use Compost" for the depth specified. This price shall be full compensation for securing any necessary source(s) and any royalty involved; for furnishing all materials, for all excavation, loading, hauling, stockpiling, placing, rototilling, harrowing, raking, rolling and sprinkling; and for furnishing all labor, tools, equipment and incidentals necessary to complete the work.

204.4. FERTILIZER

204.4.1. General. Fertilizer shall be a commercial product, uniform in composition, free flowing, with uniform particle size, minimal dust, and suitable for application with approved equipment. Fertilizer may be a natural organic, synthetic organic or inorganic fertilizer. If requested by the OWNER, a sample label or specification of proposed fertilizer(s) to be used shall be submitted to the OWNER for approval.

All fertilizer used shall be delivered in original bags or containers clearly labeled to show analysis of the contents. Fertilizer shall be in good physical condition. Fertilizer which has been exposed to high humidity and moisture or has become caked or otherwise damaged, making it unsuitable for use, shall be rejected.

The fertilizer is subject to testing by the OWNER in accordance with the Texas Fertilizer Law. A fertilizer shall be used with an analysis as indicated below. The figures in the analysis represent the percent of nitrogen, phosphoric acid and potash nutrients, respectively, as determined by the methods of the Association of Official Agricultural Chemists. In the event it is necessary to substitute a fertilizer of a different analysis with a lower concentration, the total amount of nutrients furnished and applied per unit area shall equal or exceed that specified for each nutrient.

204.4.2. Preplanting Application. Fertilizer analysis shall be based on soil test results and the nitrogen requirements for the turfgrass specified. If the OWNER waives soil testing, fertilizer analysis shall be, by weight, in a 1-1-1 or 1-2-1 (N-P-K) ratio (such as 13-13-13 or 10-20-10,) and 10- to 15-percent sulphate and traces of iron and zinc as required and approved by the OWNER.

Preplanting application rate shall be 10-lbs.-fertilizer-per-1,000-sq.ft.

204.4.3. Post Planting Application. Fertilizer analysis shall be based on soil test results and the nitrogen requirements for the turfgrass specified. If the OWNER waives soil testing, fertilizer analysis shall be as

specified below except that for autumn applications a complete fertilizer with a 4-1-2 to 3-1-2 (N-P-K) ratio shall be applied.

Fertilizer shall contain 30- to 50-percent slow release nitrogen, unless specified otherwise by the OWNER.

204.4.3.1. Seeds or Sprigs. As soon as new growth starts after seeding or sprigging, grass shall be fertilized every 10- to 14-days with 0.75- to 1.0-lb.-nitrogen-per-1,000-sq.ft. Applications shall alternate between nitrogen only fertilizer whose analysis is, by weight, 21-0-0 or 45-0-0 (N-P-K) and a complete fertilizer with a 3-1-2 or 4-1-2 (N-P-K) ratio (such as 21-7-14.)

204.4.3.2. Sod. Fertilizer analysis shall be based on soil test results. Fertilizer shall be applied every 4- to 6-weeks at 1.0-lb.-(actual)nitrogen-per-1,000-sq.ft.

204.4.4. Measurement and Payment. Fertilizing may be paid for as a separate pay item or considered subsidiary to other pay items as specified by the OWNER.

204.5. SODDING

204.5.1. Description. Sodding shall consist of furnishing and planting grass as designated on the plans and in accordance with the requirements of this specification and special conditions.

204.5.2. Materials. Sod shall be “*Stenotaphrum secundatum*” (St. Augustine grass), “*Cynodon dactylon*” (Common Bermudagrass), “*Buchloe dactyloides*” (Buffalograss), an approved hybrid of Common Bermudagrass, or an approved hybrid of Zoysiagrass, or other as approved by the OWNER. Sod shall consist of stolons, leaf blades, rhizomes, and roots with a healthy, virile system of dense, thickly matted roots throughout the soil of the sod for a thickness not less than 0.75-in. Sod shall be alive, healthy, vigorous, free of insects, disease, stones, and undesirable foreign materials, weeds and grasses deleterious to its growth or which might affect its subsistence or hardiness when transplanted. The grass shall have been mowed prior to sod cutting so that the height of the grass shall not exceed 2-inches. St. Augustine grass sod shall have been produced on growing beds of clay or clay loam topsoil. Bermudagrasses and zoysiagrasses shall have been grown on sand or sandy loam soils. Sod shall not be harvested or planted when its moisture condition is so excessively wet or dry that its survival shall be affected. Sod shall be protected from exposure to wind, sun and freezing. If sod is stacked, it shall be kept moist and shall be stacked roots to roots and grass to grass.

Sod to be placed between curb and walk and on terraces shall be the same type grass as adjacent grass or existing lawn.

Sod to be placed during the dormant stage of these grasses shall be inspected by the OWNER to verify that the grass is acceptable.

204.5.2.1. Dimensions. All sod shall have been machine cut to uniform soil thickness of ½-in. ± ⅛-in. All sod shall be of the same thickness. Rectangular sections of sod may vary in length, but all shall be of equal width and of a size that permits the sod to be lifted, handled and rolled without breaking. Broken pads and torn, uneven ends shall be rejected.

204.5.3. Construction Methods. After the designated areas have been completed to the lines, grades and cross sections shown on the plans and as provided for in other items of the contract, sodding of the type specified shall be performed in accordance with the requirements hereinafter described. Sodding shall be either plugging or solid.

Care shall be taken at all times to retain native soil on the roots of the sod during the process of excavating, hauling and planting. Sod material shall be kept moist from the time it is dug until planted. When so directed by the OWNER, the sod existing at the source shall be watered to the extent required prior to excavating. Sod material shall be planted within 3-days after it is excavated unless preserved by techniques such as shrink wrapping and transporting in refrigerated trucks, in which case the OWNER shall approve the time interval between excavation and planting.

When necessary, the sodded areas shall be smoothed after planting has been completed and shaped to conform to the cross section previously provided and existing at the time sodding operations were begun. Any excess dirt from planting operations shall be spread uniformly over the adjacent areas or disposed of as directed by the OWNER, so that the completed surface shall present a sightly appearance.

204.5.3.1. Plugging. Furrows parallel to the curb line or sidewalk lines, 12-in. on centers or to the dimensions shown on the plans, shall be opened on areas to be sodded. In all furrows, sod approximately 3-in.-square shall be placed on 12-in. centers at proper depth so that the top of the sod shall not be more than ½-in. below finished grade. Holes of equivalent depth and spacing may be used instead of furrows. Soil shall be firm around each block; then the entire sodded area shall be carefully rolled with a heavy, hand roller developing 15- to 25-lb.-per-square-inch compression. Hand tamping may be required on terraces.

204.5.3.2. Solid Sodding. At locations on the plans, or where directed, sod blocks shall be carefully placed on the prepared areas. Sod shall be so placed that the entire designated areas shall be covered. Any voids left in the solid sodding shall be filled with additional sod and tamped. The entire sodded area shall be rolled and tamped to form a thoroughly compact solid mass. Surfaces of solid sod which, in the opinion of the OWNER, may slide due to the height or slope of the surface or nature of the soil, shall, upon direction of the OWNER, be pegged with wooden pegs driven through the sod block to the firm earth, sufficiently close to hold the sod firmly in place.

204.5.3.3. Fertilizing Sod. Fertilizing shall consist of providing and distributing fertilizer over such areas as are designated on the plans and in accordance with these specifications. The fertilizer shall be applied uniformly over the area specified to be fertilized and in the manner directed. Fertilizer for sod shall comply with applicable provisions of [Item 204.4](#). Fertilizer.

204.5.3.4. Watering and Finishing Sod. Sodded areas shall be thoroughly watered immediately after they are planted. Large areas shall be planted by irrigation zones, so areas can be watered as soon as they are planted. Sod shall be subsequently watered and mowed at such time and in a manner and quantity directed by the OWNER until completion and final acceptance of the project by the OWNER.

Sod shall not be considered finally accepted until the sod has started to peg down (roots growing into the soil), and is free from dead blocks or rolls of sod.

204.5.4. Measurement and Payment. Plugging and solid sodding shall be measured for payment in square yards of sodded area completed in accordance with the plans and specifications. Plugging or solid sodding, as the case may be, shall be paid for at the contract unit price per square yard, complete in place, as provided in the proposal and contract. The contract unit price shall be the total compensation for furnishing and placing all sod, for all rolling and tamping, for all water, for disposal of all surplus material, and for all material, labor, equipment, tools and incidentals necessary to complete the work, all in accordance with the plans and these specifications.

204.6. SEEDING TURFGRASS

204.6.1. General. Seeding shall consist of preparing the ground, providing and planting seed or a mixture of seed of the kind specified along and across such areas as may be designated on the plans and in accordance with these specifications.

204.6.2. Materials. All material for turfgrass provided shall be in accordance with these specifications and as noted in the plans and contract documents. Prior to planting, CONTRACTOR shall provide the OWNER with the State of Texas Certificate stating analysis of purity and germination of seed.

Seed shall be labeled in accordance with U.S. Department of Agriculture rules and regulations.

204.6.2.1. Bermuda Grass Seed. Turfgrass seed shall be “Cynodon Dactylon” (Common Bermuda Grass). The seed shall be harvested within 1-year prior to planting, free of Johnsongrass, field bind weed, dodder seed, and free of other weed seed to the limits allowable under the Federal Seed Act and applicable seed laws. The seed shall not be a mixture. The seed shall be hulled, extra fancy grade, and have a germination and purity that shall produce, after allowance for Federal Seed Act tolerances, a pure live seed content of not less than 85-percent. Pure Live Seed (PLS) Percent shall be determined using the formula: $\text{Percent Pure Live Seed} = \% \text{Purity} \times [(\% \text{Germination} + \% \text{Firm or Hard Seed}) \div 100]$

204.6.2.2. Ryegrass Seed. Turfgrass seed shall be “Lolium multiflorum” (Italian or Annual Ryegrass). The seed shall be harvested within 1-year prior to planting and shall be free of perennial ryegrass seed, other grass seed and weed seed to the limits allowable under the Federal Seed Act and applicable seed

laws. Seed shall be at least 95-percent pure, treated with fungicide, and shall have a 90-percent minimum germination rate.

204.6.2.3. Sprigs. Turfgrass sprigs and stolons shall be “Cynodon Dactylon” (Common Bermuda Grass) (Hybrid Bermuda Grass of the Tifway 419/ Tifton 10/Tifgreen Strain). Sprigs shall be acquired from a healthy stand of grass, free of weeds and other grasses. The source is to be inspected and approved by the OWNER. Sprigs and stolons are to be delivered and planted within 24-hours of harvest unless special precautions are taken to prevent drying of sprigs to assure optimum rooting.

204.6.3. Planting Season and Application Rates. All planting shall be done between the dates specified for each grass type except when specifically authorized in writing. The seeds planted per acre shall be of a type specified with the mixture, rate and planting dates as shown in Table 204.6.3.(a) Seeding Turfgrass, or as specified by the OWNER.

Table 204.6.3.(a) Seeding Turfgrass

Type	Planting Season	Seed and Rate
Type I	March through September	Bermuda Grass, hulled, 50-lb.-PLS ¹ -per-acre
Type II	October through February	Rye Grass, 100-lb.- PLS ¹ -per-acre combined with Bermuda Grass, unhulled, 20-lb.- PLS ¹ -per-acre
Other	specified on the plans	specified on the plans

1. Pure Live Seed (PLS) is determined by multiplying the gross weight times purity times the germination. (For example, a 100-lb. bag with 85% purity and 80% germination: PLS = pounds in bag x purity x germination = 100-lb. x 0.85 x 0.80 = 60.8-lb. of pure live seed.)

204.6.4. Construction Methods.

204.6.4.1. General. After the designated areas have been completed to the lines, grades and cross sections shown on the plans and as provided for in other items of this contract, seeding of the type specified shall be performed in accordance with the requirements hereinafter described. All seeding operations shall be performed by either “drilling” or “cultipacker” process or approved equivalent. Seed shall be covered by + ¼” topsoil.

The OWNER may reject seeded area on the basis of weed populations.

204.6.4.2. Broadcast Seeding. Area to be treated shall be rough graded and raked. Seed or seed mixture in the quantity specified shall be uniformly distributed over the areas shown on the plans and where directed. If the sowing of seed is by hand, rather than by mechanical methods, the seed shall be sown in two directions at right angles to each other. Seed and fertilizer may be distributed at the same time, provided the specified uniform rate of application for both is obtained.

204.6.4.3. Disc Seed. Soil over the area shown on the plans as directed to be seeded shall be loosened to a minimum depth of 3-in. All particles in the seedbed shall be reduced to less than 1-in. in diameter, or they shall be removed. The area shall then be finished to the line and grade as specified under [Item 204.6.4.6](#). Watering, Maintaining, and Finishing Seeded Areas.

Seed or seed mixture specified shall then be planted at the rate required, and application shall be made uniformly. If the sowing of seed is by hand rather than by mechanical methods, seed shall be sown in two directions at right angles to each other. Seed and fertilizer may be distributed at the same time, provided the specified uniform rate of application for both is obtained. After planting, the seed shall be raked or harrowed into the soil to a depth of approximately 0.125-in.

204.6.4.4. Hydraulic Mulching. All mulch shall be cellulose fiber mulch and shall be refined specifically for lawn hydraulic mulch applications. Use “Conwed” or an approved equal. Adhesive (Tacking) agents for mulch may include guar gum, polyacrylamide, or other tacking agent, as approved by the OWNER. Tacking agent shall be evenly distributed in the hydraulic mulch before land application in the proportion recommended by the mulch manufacturer.

Seed or seed mixture, in the quantity specified, shall be uniformly distributed over the areas shown on the plans or where directed. Seed and fertilizer are to be distributed as a water slurry, and the mixture shall be applied to that area to be seeded within 30-minutes after all components are placed in the

equipment. Fertilizer shall conform to the applicable requirements of [Item 204.4](#). Fertilizer. After placement is completed, the planted area shall be watered sufficiently to assure uniform moisture from the surface to a minimum 6-in. depth.

204.6.4.5. Fertilizing. Fertilizing shall consist of providing and distributing fertilizer over such areas as are designated on the plans and in accordance with applicable requirements of [Item 204.4](#). Fertilizer. The fertilizer shall be applied uniformly over the area specified to be fertilized and in the manner directed.

204.6.4.6. Watering, Maintaining, and Finishing Seeded Areas. Seeded areas shall be thoroughly watered immediately after they are planted. Seeded areas shall be watered as directed by the OWNER at least twice daily for at least 14-days after seeding in such a manner as to prevent washing of the slopes or dislodgment of the seed. Water shall be applied to the cultivated areas until a minimum depth of 6-inches is thoroughly moistened. CONTRACTOR shall re-seed washed areas. The CONTRACTOR shall be responsible for proper watering until final acceptance.

Seeded areas shall be maintained, including watering and mowing, at such time and in a manner and quantity directed by the OWNER until completion and final acceptance of the project by the OWNER. At minimum, the CONTRACTOR shall maintain the seeded area until each of the following conditions is achieved: vegetation is evenly distributed, without large bare areas, and covers 70% of the seeded area.

Where applicable, the shoulders, slopes and ditches shall be smoothed after seeding has been completed and shaped to conform to the cross section previously provided and existing at the time planting operations were begun.

204.6.5. Measurement and Payment. Acceptable material for broadcast seeding, disced seeding, and hydraulic mulching shall be measured by the square-yard or by the acre complete in place. The work performed and materials furnished and measured as provided in this Item shall be paid for at the unit price for broadcast seeding, disced seeding, or hydraulic mulching of the type specified, as the case may be. The price shall be full compensation for furnishing all materials, including water for seed-fertilizer slurry and hydraulic mulching, fertilizer, and for performing all operations necessary to complete the work.

Water for sprinkling the cultivated area or seedbed when required shall meet the requirement of and shall be measured and paid for in accordance with the provisions governing [Item 203.6](#). Dust Control.

204.7. MULCHING

204.7.1. Description. Mulching provides protection for bare soil by absorbing the energy of each raindrop prior to the point when this energy would dislodge individual soil particles and begin the erosion process. Mulching fosters plant growth by providing insulation from temperature extremes and retaining valuable moisture necessary for proper germination.

204.7.2. Materials.

204.7.2.1. Organic Mulches.

204.7.2.1.1. Straw. The best quality straw mulch comes from wheat, oats or barley and shall be free of weed and grass seed that may not be desired vegetation for the area to be protected. Straw mulch is light and therefore shall be properly anchored to the ground.

204.7.2.1.2. Wood Chips. Wood chips are suitable for areas that will not require mowing frequently and are heavy enough that they do not require anchoring. They do however deplete nitrogen from the soil, which is a necessary nutrient for all plants. To alleviate this condition wood chips must be treated with 12-pounds-ammonium-nitrate-per-ton of mulch used.

204.7.2.1.3. Bark Chips. Bark chips are popular for ornamental applications as they do not require anchoring, do not decompose very rapidly and serve as an excellent insulation material. When using bark chips, it is not necessary to treat for nitrogen deficiency or to fertilize.

204.7.2.1.4. Compost and Wood Mulch Mixture. Compost and wood mulch mixtures should be a blend of 50% untreated wood mulch with 50% compost measured by volume. Wood mulch should be less than or equal to 5 in. in length with 95% passing a 2-in. screen and less than 30% passing a

1-in. screen. The compost shall meet the Physical Requirements specified in Table 1 of TxDOT Special Specification 1058, Compost.

204.7.2.1.5. Other. Other types of organic mulches shall be approved by the OWNER.

204.7.3. Construction and Maintenance.


204.7.3.1. Organic Mulch. Prior to the placement of any mulch, the area to be protected shall be graded completely in accordance with plans. Fertilization and soil treatment shall then be done prior to placement of mulch with the exceptions of when seed is to be applied by means of hydraulic seeding or when seed is distributed following straw mulch spreading during winter months. Organic mulches may be distributed by hand or by mechanical means, so long as a complete covering is achieved. The application of straw mulch should be approximately 2 tons dry straw per acre spread uniformly across the area. Other forms of mulch, such as wood chips or chopped site vegetation, should be placed in thicknesses of two-inches or greater over the area. Straw mulch should be anchored by application of a fiber mulch binder, by the application of a synthetic liquid mulch binder, by using a tractor-drawn crimper to punch into the soil, or by placing a netting above the mulch stapled to the ground, as required.

204.7.3.2. Maintenance. All mulching materials shall be inspected on a weekly basis, and after each significant local rainfall event of ½ inch or more to locate areas of erosion. Where erosion has occurred, either additional mulch shall be applied or an alternative method shall be implemented, as required by the OWNER.

204.7.4. Measurement. If included in the Contract as a unit price item, measurement of organic mulches shall be made by the square yard of treated area, in place and ready for use as an erosion control surface treatment. Alternatively, it may be measured per pound of organic mulch.

204.8. REJECTION

Landscape materials may be rejected for failure to meet any of the requirements shown in the plans and specifications.

A photograph of a road construction site. In the background, a large yellow and black asphalt paver machine is working on a road. The machine is spreading a layer of dark asphalt. In the foreground, there is a pile of dark asphalt material on a light-colored concrete or gravel base. The scene is outdoors, and the lighting suggests it is daytime.

Division 300

Roadway Construction

DIVISION 300 ROADWAY CONSTRUCTION**TABLE OF CONTENTS**

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
301.	SUBGRADE, SUBBASE, AND BASE PREPARATION	301-1 to 301-18
301.1.	<u>General</u>	
301.2.	<u>Lime Treatment</u>	
301.3.	<u>Portland Cement Treatment</u>	
301.4.	<u>Asphalt Emulsion Treatment</u>	
301.5.	<u>Flexible Subbase or Base (Crushed Stone/Concrete)</u>	
301.6.	<u>Geotextiles Used in Paving Applications</u>	
302.	ASPHALT PAVEMENT	302-1 to 302-28
302.1.	<u>Description</u>	
302.2.	<u>Aggregates for Hot-Mix Asphalt Pavement</u>	
302.3.	<u>Bituminous Materials</u>	
302.4.	<u>Section Held for Future Use</u>	
302.5.	<u>Storage, Heating and Application Temperature Of Bituminous Materials</u>	
302.6.	<u>Emulsified Asphalt Treatment</u>	
302.7.	<u>Prime Coat</u>	
302.8.	<u>Asphalt Base Course</u>	
302.9.	<u>Hot-Mix Asphalt Pavement</u>	
302.10.	<u>Measurement and Payment</u>	
303.	PORTLAND CEMENT CONCRETE PAVEMENT	303-1 to 303-26
303.1	<u>Description</u>	
303.2.	<u>Portland Cement Concrete Pavement Materials</u>	
303.3.	<u>Mix Design and Mixing Concrete for Pavement</u>	
303.4.	<u>Equipment</u>	
303.5.	<u>Construction Methods</u>	
303.6.	<u>Alley Paving</u>	
303.7.	<u>Pavement Leaveouts</u>	
303.8.	<u>Pavement Testing and Evaluation</u>	
303.9.	<u>Measurement and Payment</u>	
304.	PAVING UNITS	304-1 to 304-3
304.1.	<u>Solid Concrete Interlocking Paving Units</u>	
305.	MISCELLANEOUS ROADWAY CONSTRUCTION	305-1 to 305-5
305.1.	<u>Concrete Curb and Gutter</u>	
305.2.	<u>Concrete Sidewalks, Driveway Approaches, and Barrier Free Ramps</u>	
305.3.	<u>Concrete Medians</u>	
305.4.	<u>Reinforced Concrete Headers</u>	

ITEM 301. SUBGRADE, SUBBASE, AND BASE PREPARATION

301.1. GENERAL

Subgrade is that portion of the roadbed upon which the subbase, base or the pavement is to be placed. It includes minimum 12-in. beyond the back of the curb for streets, which are to be paved with concrete. Subbase is that layer of specified material of plan thickness between a base and a subgrade. Base is that layer of specified material of plan thickness placed immediately below the pavement course surfacing.

301.1.1. Subgrade Preparation.

301.1.1.1. Description. These specifications shall govern for the preparation of the subgrade except as otherwise provided or specified.

301.1.1.2. Equipment. All equipment necessary for the construction of this item shall be on the project and shall be approved by the OWNER as to condition before the CONTRACTOR shall be permitted to begin construction operations on which the equipment is to be used. Any equipment that achieves the desired results in the time frame allowed is acceptable.

301.1.1.3. Construction Methods. After the excavation of embankment has been substantially completed, the subgrade shall be shaped so that after rolling as specified in [Item 301.1.2](#). Rolling of Embankment, Subgrade or Flexible Base and subsequent finishing operations, it shall conform to the correct alignment, cross section and elevation. Subgrade shall be proof rolled prior to subgrade stabilization and after final compaction after subgrade stabilization as specified in [Item 301.1.1.3.1](#). Proof Rolling. Rolling and sprinkling, as needed, shall be performed when and to the extent directed and the roadbed shall be completed to or above the plane of the typical section shown on the plans and the lines and grades established by the OWNER.

After completion of the compaction and immediately before the application of subbase, base or pavement, the subgrade preparation equipment shall be operated using approved methods in a manner to finish the subgrade to the required section. The subgrade shall then be tested with the approved template, operated and maintained by the CONTRACTOR. All irregularities which develop in excess of 1/2-in. in a length of 16-ft. measured longitudinally shall be corrected by loosening, adding or removing material; reshaping; and recompacting by sprinkling and rolling. The completed subgrade shall have a uniform density of not less than 95-percent of the maximum density determined by ASTM D698 Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lb/ft³). Moisture content shall be within minus-2- to plus-4-of-optimum.

The subgrade shall be maintained in a smooth, compacted condition, in conformity with the required section and established grade, until the subbase, base or pavement is placed, and shall be kept wetted down sufficiently in advance of placing any subbase, base or pavement to insure its being in a firm and moist condition for at least 2-in. below surface of the prepared subgrade. Only such subgrade as is necessary for the satisfactory execution of the work shall be completed ahead of the placement of base or pavement. Hauling or operating of unnecessary equipment on the completed subgrade shall be kept to a minimum. If equipment is operated on recent work, the OWNER may inspect and require subgrade replacement for such defects as fractures, rutting, or any other failure. Complete drainage of the subgrade shall be provided at all times.

Finishing of the subgrade by other methods shall be permitted on pavement widening projects, on sections where the pavement width is not uniform, at intersections and elsewhere where the operation of certain equipment would not be practical. Subgrade finished by hand or other methods shall conform to the requirements above specified. Subgrade finished by hand or other methods shall conform to the requirements above specified.

301.1.1.3.1. Proof Rolling. This Item shall govern for furnishing and operating heavy pneumatic tire compaction equipment for locating unstable areas of earthwork or base.

301.1.1.3.1.1. Proof Rolling Equipment. The proof rolling equipment shall consist of not less than four pneumatic tire wheels, running on axles carrying not more than four wheels, and mounted in a rigid frame and provided with loading platform or body suitable for ballast loading.

All wheels shall be arranged so that they will carry approximately equal loads when operating on uneven surfaces.

The proof roller under working conditions shall have a rolling width of from 8-ft. to 10-ft., and shall be so designed that, by ballast loading, the gross load may be varied uniformly from 15 tons to 25 tons. The tires shall be capable of operating under the various loads with up to 150 pounds per square inch air pressure. Tires shall be practically full of liquid. (Tires shall be considered as being practically full when liquid will flow from the valve stem of a fully inflated tire with the stem in the uppermost position.)

The operating load and tire pressure shall be within the range of the manufacturer's chart as directed by the OWNER. The CONTRACTOR shall furnish the OWNER charts or tabulations showing the contact areas and contact pressures for the full range of tire inflation pressures and for the full range of loadings for the particular tires furnished.

The proof roller shall be towed by a suitable crawler type tractor or rubber tire tractor of adequate tractive capacity, or may be of the self-propelled type. A proof roller unit shall consist of either a self-propelled roller or combination of roller and towing tractor.

There shall be a sufficient quantity of ballast available to load the equipment to a maximum gross weight of 25 tons.

Rubber tire tractive equipment shall be used on base courses and asphalt pavements. Other type tractive equipment may be used on embankment subgrade. The heavy pneumatic tire roller unit shall be capable of turning 180 degrees in the crown width or operating in forward and reverse modes.

In lieu of the rolling equipment specified, the CONTRACTOR may, upon written permission from the OWNER, operate other compacting equipment that will produce equivalent results in the same period of time as the specified equipment. The CONTRACTOR shall submit together with any proposed alternate compacting equipment, the weight (empty and with proposed loading), the wheel configuration and load distribution along with his proposed procedure to provide full width and length coverage of the subgrade area within the required period of time. If the substituted compaction equipment fails to produce the desired results within the same period of time as would be expected of the specified equipment, as determined by the OWNER, its use shall be discontinued.

301.1.1.3.1.2. Proof Rolling Construction Methods. This work shall be done when specified in the plans and specifications. The subgrade and base layer shall be proof rolled to locate unstable areas.

Within the ranges set forth in [Item 301.1.1.3.1.1](#), Proof Rolling, the load and tire inflation pressures shall be adjusted as directed by the OWNER. It is proposed to use a contact pressure corresponding as nearly as practical to the maximum supporting value of the earthwork or base. A minimum of two coverages of the proof roller will be required. Each succeeding trip of the proof roller shall be offset by not greater than one tire width. Rollers shall be operated at speeds directed by the OWNER which shall be between 2 and 6 miles per hour.

Where the operation of the proof roller unit shows an area to be unstable or non-uniform, it shall be corrected in accordance with the applicable Item of Work.

301.1.1.4. Measurement and Payment. Preparation of subgrade shall not be measured for payment as a separate contract pay item. Preparation of the subgrade or fine grading shall not be paid for as a separate contract pay item; and cost thereof shall be included in such contract items as are provided, which pay items shall be the total compensation for the furnishing of all labor, tools, materials, equipment and incidentals necessary to complete the work, including disposal or surplus material, all in accordance with the plans and these specifications.

301.1.2. Rolling of Embankment, Subgrade or Flexible Base

301.1.2.1. Description. Rolling shall consist of the compaction of embankment, subgrade or flexible base by the operation of approved power rollers, as herein specified and as directed by the OWNER.

301.1.2.2. Roller Requirements. All equipment necessary for the construction of this item shall be on the project and shall be approved by the OWNER as to condition before the CONTRACTOR shall be permitted to begin construction operations on which the equipment is to be used. Any equipment that achieves the desired results in the time frame allowed is acceptable. If equipment fails to produce the desired result within the required time frame, its use shall be discontinued and the CONTRACTOR will be required to furnish equipment, as determined by the Engineer, at no additional cost to the OWNER.

Sufficient rollers shall be provided to compact the material in a manner satisfactory to the OWNER. When operations are so isolated from one another that one roller unit cannot perform the required compaction satisfactorily, the CONTRACTOR shall provide additional roller units.

301.1.2.3. Rolling Methods. The embankment, subgrade or base course shall be sprinkled as directed by the OWNER. Rolling patterns and speeds shall be established per project and indicated on the plans.

301.1.2.4. Measurement and Payment. Rolling provided in the proposal and contract, as a separate contract pay item, shall be measured for payment by the actual hours the roller is in operation, as ordered by the OWNER. Rolling provided in the proposal and the contract, as a separate pay item, shall be paid for in accordance with the contract unit price. When rolling is not classified separate for payment, then such rolling shall be considered as incidental work and shall not be paid for as a separate item. The cost thereof shall be included in such contract pay items as are provided. In either case, such pay items shall be the total compensation for all labor, materials, tools, machinery, equipment and incidentals necessary to complete the work in accordance with the plans and this specification.

301.2. LIME TREATMENT

This item shall consist of treating subgrade, subbase, and base courses by the pulverization, addition of lime, mixing and compacting the mixed material to the required density. This item applies to natural ground, embankment, or pulverized recycled asphalt pavement base or subbase courses placed under this contract, which shall be constructed as specified herein and in conformity with the typical section, lines and grades as shown on the plans.

301.2.1. Materials.

301.2.1.1. Hydrated Lime (Slurry).

301.2.1.1.1. General. Hydrated lime slurry shall be a pumpable suspension of solids in water. The solids portion of the mixture, when considered on the basis of "solids content," shall consist principally of hydrated lime of a quality and fineness sufficient to meet the following requirements as to chemical composition and residue.

301.2.1.1.2. Chemical Composition. The "solids content" of the lime slurry shall have a hydrate alkalinity $\text{Ca}(\text{OH})_2$ of not less than 90-percent by weight.

301.2.1.1.3. Residue. The percent by weight of residue retained in the "solid content" of lime slurry shall conform to the requirements in Table 301.2.1.1.3.(a) Hydrated Lime.

Table 301.2.1.1.3.(a) Hydrated Lime

Sieve Size	Residue Retained, Percent by Weight
No. 6 (3360 micron)	None
No. 10 (2000 micron)	Max. 1.0%
No. 30 (590 micron)	Max. 2.5%

301.2.1.1.4. Slurry Grades. Type B, commercial lime slurry, shall conform to one of the following three grades:

- (1) Grade 1: The "dry solids contents" shall be at least 31-percent by weight of the slurry.
- (2) Grade 2: The "dry solids contents" shall be at least 35-percent by weight of the slurry.
- (3) Grade 3: The "dry solids contents" shall be at least 46-percent by weight of the slurry.

When Type B, commercial lime slurry, is specified, the CONTRACTOR shall select, prior to construction, the grade to be used and shall notify the OWNER in writing before changing from one grade to another.

301.2.1.2. Quicklime.

CAUTION: Handling and use of quicklime can be dangerous. Quicklime should be prescribed by a registered professional engineer familiar with its use.

301.2.1.2.1. General. Quicklime is a dry material consisting essentially of calcium oxide. It shall be furnished either in “pebble” gradation suitable for dry placing and slurry placing, or as a dry powder suitable only for slurry placing. Powdered quicklime is restricted to slurry placing, as the possibility of appreciable amounts of finely divided powdered quicklime makes it unsuitable for dry placing.

301.2.1.2.2. Chemical Composition. Quicklime shall conform to the chemical requirements of ASTM C977 Quicklime and Hydrated Lime for Soil Stabilization.

301.2.1.3. Tests. If the minimum design strength or percent lime to be used for the treated subgrade, existing base, new subbase or new base is specified, it shall be determined by preliminary laboratory tests at the OWNER’S expense. Optimum lime addition percentage shall be determined by Tex-112-E Admixing Lime to Reduce Plasticity Index of Soils (Atterberg Limits Soil-Lime Series) and/or by ASTM D6276 Test Method for Using pH to Estimate the Soil-Lime Proportion Requirement for Soil Stabilization (pH Soil-Lime Series.) The actual minimum lime dosage to be applied shall be 1% above the minimum test results.

301.2.1.4. Lime Delivery and Storage. If hydrated lime is furnished in bags, each bag shall bear the manufacturer’s certified weight. Bags varying more than 5-percent by weight may be rejected, and the average weight of the bags in any shipment, as shown by weighing 50 bags taken at random, shall not be less than the manufacturer’s certified weight. If lime is furnished in trucks, each truck shall bear the weight of lime measured on certified scales, or the CONTRACTOR shall place a set of standard platform truck scales or hopper scales at a location approved by the OWNER.

Hydrated lime and quicklime shall be stored and handled in closed, weatherproof containers until immediately before distribution on the road. If storage bins are used, they shall be completely enclosed. Hydrated lime bags shall be stored in weatherproof buildings with adequate protection from ground dampness. Quicklime, when permitted, shall be shipped only in bulk; bagged material shall not be acceptable.

301.2.1.5. Water. Water shall conform to the requirements of [Item 303.2.7. Water](#).

301.2.1.6. Soil. The soil shall consist of the in-situ soil or approved soil, free from vegetation, roots, or other objectionable matter. It may be either the material encountered in the existing section, material secured from approved sources shown on the plans or as designated by the OWNER, or a combination of existing and additional soil from approved sources, as shown on the plans, or as directed by the OWNER.

301.2.1.7. Recycled/Reclaimed Asphalt Pavement. Recycled/Reclaimed asphalt pavement is defined as a salvaged, milled, pulverized, broken or crushed asphaltic pavement uncontaminated by dirt or other objectionable materials.

301.2.1.8. Rejection. Any materials that do not conform to the requirements of this specification shall be rejected.

301.2.2. Equipment. Machinery, tools and equipment necessary for proper performance of the work shall be on the project and approved by the OWNER prior to the beginning of construction operations.

301.2.3. Lime Treatment Construction Methods.

301.2.3.1. General. It is a primary requirement of this specification to secure a completed course of treated material containing a uniform lime mixture, free from loose or segregated areas, or uniform density and moisture content, well bound for its full depth, and with a smooth surface and suitable for placing subsequent courses. It shall be the responsibility of the CONTRACTOR to regulate the sequence of work, to use the specified amount of lime, maintain the work and rework the courses as necessary to meet the above requirements.

Prior to beginning any lime treatment, the roadbed shall be constructed and shaped to conform to the typical sections, lines and grades as shown on the plans or as established by the OWNER.

In cases where groundwater is present, application of lime for stabilization shall be evaluated by the OWNER.

301.2.3.2. Section Held for Future Use.

301.2.3.3. General Construction.

301.2.3.3.1. Treatment for Materials in Place. Materials to be treated shall be excavated to the secondary grade (proposed bottom of lime treatment) and removed or windrowed to expose the secondary grade. Any wet or unstable material below the secondary grade shall be corrected by scarifying, adding lime and compacting until it is of uniform stability. The excavated material shall then be spread to the desired cross section.

If the CONTRACTOR elects to use a cutting or pulverizing machine that shall remove the subgrade material accurately to the secondary grade and to pulverize the material at the same time, CONTRACTOR shall not be required to expose the secondary grade or windrow the material. However, the CONTRACTOR shall be required to roll the subgrade before using the pulverizing machine and correct any soft areas that this rolling may reveal. This method shall be permitted only where a machine is provided which shall insure that the material is cut uniformly to the proper depth and which has cutters that shall place the secondary grade to a smooth surface over the entire width of the cut. The machine shall be of such design that a visible indication is given at all times that the machine is cutting to the proper depth.

301.2.3.3.2. Treatment for New Materials. The base and subbase materials, as provided in the governing specifications, shall be delivered, placed and spread in the required amount per station.

The material shall be manipulated as specified and thoroughly mixed prior to the addition of the lime.

301.2.3.4. Lime Application. Lime shall be spread only on that area where the first mixing operation can be completed in the same working day, except that quicklime shall be mixed at the time of application. The application and mixing of lime with the materials shall be accomplished by the methods hereinafter described unless otherwise approved by the OWNER.

301.2.3.4.1. Dry Placing Quicklime. Quicklime may be placed dry if it is in pebble form. A spreader or motor grader shall be used to spread pebble Quicklime.

301.2.3.4.2. Slurry Placing.

Hydrated Lime or Commercial Lime Slurry. Lime shall be mixed with water and applied as a thin water suspension or slurry. Type B, commercial lime slurry, shall be applied with a lime percentage not less than that applicable for the grade used. The distribution of lime at the rate shown on the plans shall be attained by successive passes over a measured surface of roadway until the proper moisture and lime content have been achieved.

Quicklime. When Quicklime is applied as a slurry, the amount of dry quicklime shall be 80-percent of the amount shown on the plans. The residue from the Quicklime slurring procedure shall be spread uniformly over the length of the roadway currently being processed unless otherwise approved by the OWNER. This residue is primarily inert material with little stabilizing value, but may contain a small amount of Quicklime particles that slake slowly. A concentration of these particles could cause the compacted stabilized material to swell during slaking.

301.2.3.5. Mixing. Mixing procedure shall be the same for “dry placing” or “slurry placing” as hereinafter described.

301.2.3.5.1. Treatment for Materials-In-Place. Material and lime shall be thoroughly mixed by approved road mixers or other approved equipment and the mixing continued until a homogeneous, friable mixture of material and lime is obtained, free from all clods or lumps. Materials containing plastic clay or other materials which shall not readily mix with lime shall be mixed as thoroughly as possible at the time of the lime application, brought to the proper moisture content, sealed with a pneumatic roller, and left to cure 1- to 4-days as directed by the OWNER. During the curing period,

the material shall be kept moist. After the required curing time, the material shall be uniformly mixed by approved methods. If the soil binder lime mixture contains clods, they shall be reduced in size by raking, blading, discing, harrowing, scarifying or the use of other approved pulverization methods so that when all nonslaking aggregates obtained on the No. 4 sieve are removed, the remainder of the material shall meet the requirements of Table 301.2.3.5.1.(a) Lime Treated Materials-In-Place when tested dry by laboratory sieves.

Table 301.2.3.5.1.(a) Lime Treated Materials-In-Place

Sieve Size	Minimum Passing
1¾-in. (45mm)	100%
No. 4 (4.75mm)	60%

1. Recycled asphalt pavement shall be pulverized so that 100-percent shall pass a 2-in. (50mm) sieve.

During the interval of time between application and mixing, hydrated lime that has been exposed to the open air for a period of 6-hours or more, or to excessive loss due to washing or blowing, shall not be accepted for payment.

In addition to the above, when pebble quicklime is used, the material and lime shall be mixed as thoroughly as possible at the time of application. Sufficient moisture shall be added during the mixing to hydrate the quicklime. After mixing, and prior to compaction, the mixture of material, quicklime and water shall be moist cured for 2- to 7-days, as approved by the OWNER. After curing, mixing shall continue until the pulverization requirements are met.

301.2.3.5.2. Treatment of New Material. The base or subbase material, lime and required water shall be thoroughly mixed and blended by approved road mixers or other approved equipment and the mixing continued until a homogeneous, friable mixture is obtained. When lime is placed as a slurry and mixed by the use of blades, the material shall be bladed as the lime water mixture is applied; after the total amount has been placed, the mixture shall be thoroughly blended to the satisfaction of the OWNER.

During the interval of time between application and mixing, hydrated lime that has been exposed to the open air for a period of 6-hours or more, or to excessive loss due to washing or blowing, shall not be accepted for payment.

301.2.3.6. Compaction. Compaction of the mixture shall begin immediately after final mixing and in no case later than 3-days after final mixing. The material shall be aerated or sprinkled as necessary to provide optimum moisture. Compaction shall begin at the bottom and shall continue until the entire depth of the mixture is uniformly compacted as shown on the plans or specified by the OWNER. The compacted mixture shall have a uniform density of not less than 95-percent of the maximum density as determined by ASTM D698 Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³). Moisture content shall be within minus 2-percent to plus 4-percent of optimum. After each section is completed, such tests as are necessary shall be made by the OWNER. If any portion fails to meet the density specified, it shall be reworked as necessary to obtain the specified density. After the mixture has been compacted, the surface shall be shaped to the required line, grades and cross sections and then rolled sufficiently to prevent hairline cracking.

301.2.3.7. Maintenance. The CONTRACTOR shall be required to maintain the completed soil lime base within the limits of its contract in good condition, satisfactory to the OWNER as to grade, crown and cross section until such time as the surface course is constructed. The surface of the compacted layer shall be kept moist until covered by other base or paving material or application of a curing seal of emulsified asphalt conforming to requirements of [Item 302.3.5](#). Emulsions for Priming, Curing and Erosion Control (PCE). If a curing seal is used, it should be applied as soon as possible after completion of final rolling, at a rate of between 0.10- and 0.20-gallons-per-square-yard, the exact rate to be determined by the OWNER. No equipment or traffic shall be permitted on lime treated material for 72-hours after curing seal is applied, unless otherwise permitted by the OWNER. In cases where subgrade treatment or subbase sets up sufficiently to prevent objectionable damage from traffic, such layers may be opened to traffic 2-

days after compaction. The CONTRACTOR shall immediately repair all irregularities or other defects that may occur at the CONTRACTOR'S expense. Repairs are to be made as directed by the OWNER and in a manner to insure restoration of a uniform surface and durability of the portion repaired.

301.2.4. Measurement and Payment. Lime treatment shall be measured for payment in square-yards for the thickness shown in the plans for the surface area of completed and accepted work. The measurement for lime shall be by the ton of 2000-pounds dry weight. The measured tonnage of (dry) quicklime shall be multiplied by the conversion factor 1.25 to give the equivalent quantity of hydrated lime (dry) which shall be the basis of payment.

Lime treatment shall be paid for at the contract unit price per square-yard, as provided in the proposal and contract. The contract unit price shall be the total compensation for preparing the roadbed; for loosening, pulverizing, application of lime, water content in the slurry mixture and the mixing water; mixing, shaping, sprinkling, compacting, finishing, curing and maintaining; for manipulations required; and for all labor, equipment, fuels, tools and incidentals necessary to complete the work, all in accordance with the plans and specifications.

Lime material measured as provided in the this item shall be paid for at the unit price bid for "lime material" which price shall be full compensation for furnishing the material; for all freight involved; for all unloading, storing and handling; and for all labor, equipment, fuels, tools and incidentals necessary to complete the work.

301.3. PORTLAND CEMENT TREATMENT

This item shall consist of the treatment of the subgrade, subbase or base course which is to be composed of a compacted mixture of soil, and/or pulverized recycled asphalt pavement, Portland cement and water and shall be constructed as herein specified and in conformity to the cross sections, lines and grades as established by the OWNER. In the event new materials are placed, rather than using in-situ soils, the subbase or base shall be constructed as herein specified and in conformity with the items governing the base or subbase courses.

301.3.1. Materials.

301.3.1.1. Portland Cement. Cement shall be ASTM C150 Type I, II or IP and conform to the requirements of [Item 303.2.2](#). Portland Cement.

301.3.1.2. Water. Water shall conform to the requirements of [Item 303.2.7](#). Water.

301.3.1.3. Soil. The soil shall consist of the in-situ soil or approved soil, free from vegetation, roots, or other objectionable matter. It may be either the material encountered in the existing section, material secured from approved sources shown on the plans or as designated by the OWNER, or a combination of existing and additional soil from approved sources, as shown on the plans, or as directed by the OWNER.

301.3.1.4. Recycled/Reclaimed Asphalt Pavement. Recycled/Reclaimed asphalt pavement is defined as a salvaged, milled, pulverized, broken or crushed asphaltic pavement uncontaminated by dirt or other objectionable materials.

301.3.2. Equipment. All equipment necessary to properly prosecute, perform and complete the work within the contract time shall be on the project and shall be approved by the OWNER as to type and condition before the CONTRACTOR shall be permitted to begin construction operations on which the equipment is to be used.

The cement-modified soil layer may be constructed with any machine or combination of machines and auxiliary equipment that shall produce the results meeting the requirements for soil pulverization, cement application, water application, mixing, incorporation of materials, compaction, finishing and curing as specified herein. The CONTRACTOR shall at all times provide sufficient equipment to enable continuous performance of the work and its completion in the required number of working days.

301.3.3. Portland Cement Treatment Construction Methods.

301.3.3.1. General. The primary requirement of this specification is to secure a complete course of treated material containing a uniform Portland cement mixture, free from loose or segregated areas, of uniform density and moisture content, well bound and compacted for its full depth with a smooth surface suitable for placing additional subbase, base or surface courses. It shall be the responsibility of the CONTRACTOR to regulate the sequence of work, to process a sufficient quantity of material so as to

provide full depth as shown on plans, to use the proper amount of Portland cement, maintain the work and to rework the courses as necessary to meet the foregoing requirements.

Cement stabilized base shall not be mixed or placed when the air temperature is below 40°F and falling, but may be mixed or placed with the air temperature is above 35°F and rising, the temperature being taken in the shade and away from artificial heat, and with the further provisions that cement stabilized base shall be mixed or placed only when weather conditions, in the opinion of the OWNER, are suitable.

301.3.3.2. Treatment for Materials-In-Place. Before other construction operations are begun, the roadbed shall be graded and shaped as required to construct the Portland cement treatment for material in place in conformance with the lines, grades, thickness and typical cross sections shown on the plans. Unsuitable soil or material shall be removed and replaced with acceptable soil. The subgrade shall be firm and able to support without displacement the construction equipment and achieve the compaction herein specified. Soft or yielding subgrade shall be corrected and made stable before construction proceeds.

The soil and/or recycled asphalt pavement shall be so pulverized that at the completion of moist-mixing, it meets the gradation in Table 301.3.3.2.(a) Cement Treated Materials-In-Place.

Table 301.3.3.2.(a) Cement Treated Materials-In-Place

Sieve Size	Minimum Passing by Dry Weight^{1,2}
1-in. (25mm)	100%
No. 4 (4.75mm)	80%

1. Exclusive of gravel or stone retained on these sieves.

2. Recycled asphalt pavement shall be pulverized so that 100-percent shall pass a 2-in. (50mm) sieve.

301.3.3.2.1. Application of Cement to Materials-In-Place. Portland cement shall be spread by an approved dry or slurry method uniformly on the soil at the rate specified on the plans or as determined by preliminary laboratory tests. If a bulk cement spreader is used, it shall be positioned by string lines or other approved method during spreading to insure a uniform distribution of cement. Cement shall be applied only to such an area that all the operations can be continuous and completed in daylight within 6-hours of such application.

The percentage of moisture in the soil at the time of cement application shall not exceed the quantity that shall permit uniform and intimate mixture of soil and cement during dry-mixing operations, and it shall not exceed the specified optimum moisture content for the soil and cement mixture. In the event of high soil-moisture contents, cement may be applied at one-half the specified rate when approved by the Engineer. The remainder of the application rate of cement shall be applied the following day(s), not to exceed 48-hours. The usual construction sequence shall then be resumed.

No equipment, except that used in the spreading and mixing, shall be allowed to pass over the freshly spread cement until it is mixed with the soil.

301.3.3.2.2. Mixing and Processing of Stabilized Materials-In-Place. Any method used to achieve the specified results is acceptable. Mixing shall continue until a homogeneous, friable mixture of the material and cement is obtained, free from all clods or lumps. The mixture shall be kept within moisture tolerances throughout the operation.

301.3.3.2.3. Compaction and Finishing of Stabilized Materials-In-Place. Compaction shall begin after mixing and after gradation and moisture requirements have been met. The material shall be compacted to at least 95-percent of the maximum density as determined by ASTM D698 Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³). At the start of compaction, the percentage of moisture in the mixture and in unpulverized soil lumps, based on oven-dry weights, shall be within 2-percentage-points of the specified optimum moisture content and shall be less than the quantity which shall cause the soil-cement mixture to become unstable during compaction and finishing. When the uncompacted soil-cement mixture is wetted by rain so that the

average moisture content exceeds the tolerance given at the time of final compaction, the entire section shall be reconstructed in accordance with this specification at the sole expense of the CONTRACTOR. The specified optimum moisture content and density shall be determined in the field on the representative samples of soil-cement mixture obtained from the area being processed. Final moisture content shall be within minus-2- to plus-4-of-optimum.

Prior to the beginning of compaction, the mixture shall be in a loose condition for its full depth. Compaction shall begin at the bottom and shall continue until the entire depth of the mixture is uniformly compacted. The loose mixture shall then be uniformly compacted to the specified density within 2-hours. After the soil and cement mixture, except the top mulch, is compacted, water shall be uniformly applied as needed and thoroughly mixed in. The surface shall then be reshaped to the required lines, grades and cross section and then lightly scarified to loosen any imprint left by the compacting or shaping equipment.

The resulting surface shall be thoroughly rolled with a pneumatic tire roller and "clipped," "skinned," and "tight-bladed" by a power grader to a depth of approximately 1/4-in., moving all loosened soil and cement from the section. The surface shall then be thoroughly compacted with the pneumatic roller, adding small increments of moisture as needed during rolling. When directed by the OWNER, surface finishing methods may be varied from this procedure, provided a dense, uniform surface, free of surface material, is maintained at its specified optimum during all finishing operations. Surface compaction and finishing shall proceed in such a manner as to produce, in not more than 2-hours, a smooth, closely knit surface, free of cracks, ridges or loose material, conforming to the drawn grade and line shown on the plans.

OWNER shall conduct in-place density tests shall as outlined in ASTM D2922 Density of Soil and Soil-Aggregate in Place by Nuclear Methods (Shallow Depth). In-place density tests shall be performed at the rate of one-per-300-linear-ft. of paving for two (2) lanes. The suitability of the modification shall be confirmed by Atterberg Limit testing at the rate of one-test-per-2,500-cubic-yards of processed material.

In addition to the requirements specified for density, the full depth of the material shown on the plans shall be compacted to the extent necessary to remain firm and stable under construction equipment. After each section is completed, tests as necessary will be made by the OWNER. If the material fails to meet the density requirements, it shall be reworked as necessary to meet these requirements. Throughout this entire operation the shape of the course shall be maintained by blading, and the surface upon completion shall be smooth and in conformity with the typical section shown on the plans and to the established lines and grades. Should the material, due to any reason or cause, lose the stability, density and finish before the next course is placed or the work is accepted, it shall be recompacted and refinished at the sole expense of the CONTRACTOR.

301.3.3.3. Plant-Mixed Cement Treated Base.

301.3.3.3.1. Subgrade Preparation. Before other construction operations are begun, the area to be paved shall be graded and shaped as required to receive the cement treated base in conformance with the grades, lines, thicknesses and typical cross-section shown on the plans. Unsuitable subgrade soil or material shall be removed and replaced with acceptable soil. The subgrade shall be firm and able to support without displacement of the construction equipment and compaction. Soft or yielding subgrade shall be corrected and made stable before construction proceeds.

301.3.3.3.2. Mixing and Processing for Plant-Mixed Cement Treated Base. The aggregate, cement and water shall be mixed in a pug mill as approved by the Engineer. The plant shall be equipped with feeding and metering devices that add the aggregate, cement and water into the mixer in the specified quantities to produce a mixture that meets or exceeds the mix design criteria. Aggregate and cement shall be mixed sufficiently to prevent cement balls from forming when the mix water is added. Mixing time shall be sufficient to assure an intimate, uniform mixture of aggregate, cement and water. The percentage of moisture in the aggregate, at the time of cement application shall be the amount that assures a uniform and intimate mixture of aggregate and cement during

mixing operations. It shall not exceed the specified moisture content required for adequate compaction.

Free access to the plant shall be provided to the OWNER for construction quality control. The mixture shall be hauled to the paving area in trucks having beds cleaned of deleterious material.

The CONTRACTOR shall submit a mix design for the proposed Cement Treated Base (CTB) to the OWNER for approval in advance of the proposed work. Unconfined compression strength test results shall be submitted with the mix design by the supplier of the CTB material. Work shall not begin until the mix design is approved by the OWNER.

301.3.3.3.3. Placement of Plant-Mixed Cement Treated Base. The mixture shall be placed on a moistened subgrade in a uniform layer by any approved method of spreading that will deposit the required quantity per lineal foot, without segregation, to produce a uniformly compacted base conforming to the grade and cross-section. Not more than 30-minutes shall elapse between placement of cement treated base in adjacent lanes at any location except at longitudinal and transverse construction joints. Compaction shall start as soon as possible after spreading. Elapsed time between the addition of water to the cement treated base mixture and the start of compaction shall not exceed 60-minutes under normal conditions. The Engineer may alter this time if environmental conditions, such as temperature, humidity or wind conditions would justify such a change. Laboratory tests may be required to verify changes in compaction time limits.

301.3.3.3.4. Compaction and Finishing of Plant-Mixed Cement Treated Base. At the start of compaction, the percentage of moisture in the mixture shall not be more than one-percentage-point-below or two-percentage-points-above the specified optimum moisture content, and shall be less than that quantity which will cause the cement treated base mixture to become unstable during compaction and finishing. The specified optimum moisture content and density shall be determined in the field by a Moisture-Density Test AASHTO T134 or ASTM D558 Test Methods for Moisture-Density Relations of Soil-Cement Mixtures, on representative samples of cement treated base mixture obtained from the area prior to compaction. Prior to compaction, the mixture shall be in a loose condition for its full depth. The loose mixture shall then be compacted uniformly to the specified density. During compaction operations, initial shaping may be required to obtain uniform compaction and required grade and cross-section.

When initial compaction is completed, the surface of the cement treated base shall be shaped to the required lines, grades and cross-section. The moisture content of the surface material shall be maintained at not less than its specified optimum moisture content during finishing operations. If any reshaping of the surface is necessary, it shall be lightly scarified to remove any compaction planes, scales or smooth surfaces left by equipment. Final compaction shall then be continued until uniform and adequate density is obtained. Cement treated base shall be uniformly compacted to a minimum of 95-percent of maximum density. Compaction and finishing shall be done in such a manner as to produce, in not longer than two-hours, a smooth, dense surface free of compaction planes, cracks, ridges, or loose material.

301.3.3.4. Finishing and Preparation for Surfacing. After the final layer or course of the cement-modified soil has been compacted, it shall be brought to the required lines and grades in accordance with the typical sections. The completed section shall then be finished by rolling as directed with a pneumatic tire or other suitable roller sufficiently light to prevent hair cracking. Preparation for final surfacing may begin immediately.

301.3.3.5. Protection and Cover. After the roadway has been finished as specified herein, it shall be immediately protected against rapid drying by applying a curing seal of emulsified asphalt at the rate of 0.2-gallon-per-square-yard. The curing seal shall consist of emulsified asphalt conforming to requirements of [Item 302.3.5](#). Emulsions for Priming, Curing and Erosion Control (PCE). Immediately prior to application of the curing seal, the section shall be wetted by the use of pressure water distributors so that all voids in the soil-cement surface are filled with water, but without free water standing on the surface. The curing seal shall be applied while this moisture condition exists so that

undue asphalt penetration of the soil-cement surface shall be prevented; and at the same time aided in complete coverage by the curing seal.

Should it be necessary for construction equipment or other traffic vehicles to pass over the section before the curing seal has dried sufficiently to prevent pickup, it shall be the responsibility of the CONTRACTOR to dust or sand the surface before such use. The CONTRACTOR shall also maintain the curing cover for 7-days so that all of the soil-cement base course shall be covered effectively with curing seal during this period. The curing seal shall remain in place for the additional asphalt-wearing surface.

301.3.3.6. Opening to Traffic. The CONTRACTOR shall not be permitted to drive heavy equipment over completed portions. Pneumatic-tired equipment required for hauling cement and water may be permitted to drive over after the surface has hardened sufficiently to prevent the equipment from marring the surface, provided that protection and cover are not impaired. The soil-cement course may be opened to local traffic as soon as the curing seal has been applied and dusted or sanded as necessary to prevent it from being picked up by traffic. Completed portions may be opened to all traffic after 7-days or as directed by OWNER.

301.3.3.7. Maintenance. The CONTRACTOR shall be required within the limits of its contract to maintain the soil-cement treatment in good condition from the time it first starts work until all work shall have been completed. Maintenance shall include immediate repairs of any defect that may occur after the cement is applied. Such maintenance work shall be done by the CONTRACTOR at the CONTRACTOR'S expense and repeated as often as necessary to keep the area continuously intact. Repairs are to be made in such a manner as to insure restoration of a uniform surface for the full depth of treatment. Any low area of treated subgrade shall be remedied by scarifying the surface to a depth of at least 2-in., filling the area with treated material and compacting. Any low area of subbase or base shall be remedied by replacing the material for the full depth of subbase or base treatment rather than adding a thin layer of stabilized material to the completed work.

301.3.4. Measurement and Payment. Portland cement treatment shall be measured by the square-yard of completed and accepted cement treated course. Measurement for cement shall be by the ton of 2000-pounds of dry weight, as determined by certified weight tickets. No allowance shall be made for any materials used or work done outside the limits as established by the OWNER.

The work performed and material furnished as prescribed by this item and measured as provided in this item shall be paid for at the unit price bid for soil-cement treated subgrade, subbase, or base course, which price shall be full compensation for pulverizing or providing the soil material; handling, hauling and spreading dry or slurry cement, mixing the cement with the soil either in-place or in a mixing plant; furnishing, hauling and mixing water with the soil-cement mixture; spreading and shaping the mixture; compacting the mixture, including all rolling required for this compaction; surface finishing; curing; and for all manipulation, labor, equipment, appliances, tools and incidentals necessary to complete the work and carry out the maintenance provisions in this specification. Cement material measured as provided in this item shall be paid for at the unit price bid for cement material, which price shall be compensation for furnishing the material, for all freight involved, for all unloading and storing, and for all labor, equipment, fuels, tools and incidentals necessary to complete the work, all in accordance with the plans and these specifications.

301.4. ASPHALT EMULSION TREATMENT

This item shall consist of treating subgrade, subbase, and base courses by the pulverization, addition of asphalt base stabilization agent, mixing and compacting the mixed material to the required density. This item applies to natural ground, embankment, base or subbase courses placed under this contract, which shall be constructed as specified herein and in conformity with the typical section, lines and grades as shown on the plans.

Asphalt stabilization of recycled material such as crushed concrete or other non-hazardous recycled materials, processed recycled asphalt pavements, bottom ash, foundry slag, glass, recycled crumb rubber to create subgrade, subbase or base courses shall conform to TxDOT Special Specification 3157 Cold Processed - Recycled Paving Material (RPM) for Use as Aggregate Base Course. Asphalt emulsion for such recycling shall conform to [Item 302.3.6](#). Specialty Emulsions or [Item 302.3.7](#). Emulsion for In-Place Asphalt Recycling, as specified by the OWNER.

301.4.1. Materials.

301.4.1.1. Asphalt Soil (Base) Stabilization Agent. The product shall be composed of petroleum of resin oil base with selective hardening and drying agents to form a stable subgrade, subbase, or base. Independent laboratory tests shall certify compliance with requirements of Table 301.4.1.1.(a) Asphalt Soil Stabilization Agent Requirements, as specified on the plans.

If the minimum design strength or percent asphalt base stabilization agent to be used for the treated subgrade, existing base, new subbase or new base is specified, it shall be determined by preliminary laboratory tests at the OWNER'S expense.

Table 301.4.1.1.(a) Asphalt Soil Stabilization Agent Requirements

Property	Test Method, Test Parameters	Required Value	
		Minimum	Maximum
Appearance	Visual Inspection	Brown Liquid	
Viscosity S.F. at 77°F Sec	ASTM D244 Emulsified Asphalts	5	175
Residue, % min	ASTM D244, modified ¹	55	65
Penetration 77°F, Sec		5	40
Miscibility Test	ASTM D244, modified ²	No coagulation	
Moisture, wt %		-	45
Volatile %		25	-
% Non-Volatile Soluble in Trichloroethylene	AASHTO T 45-56	-	8
Accelerated Weathering (2-year exposure)	Federal Spec TT C-555 B, 40 ml	No material deterioration after exposure	
Resistance To wind and Driven Rain (@ 98 mph)	Federal Spec TT C-555 B, As 4ml sealer after cure	Passes/no wt. gain	
Ash, % wt.		-	8
Polymer, % wt.		-	4
Particle Charge	ASTM D244	Positive	
Flash Point	TCC	275°F	
Shaker Test 2- to 4-hrs.	Mix Burrell Wrist Action Shaker Model 75 set on Level 7, diluted 1 part water to 4 parts soil stabilizer, Sieve #40	-	1%

1. ASTM D244 Modified Evaporation Test for percent of residue is made by heating 50-gram sample to 300°F until foaming ceases, then cool immediately and calculate results.

2. Test procedure identical with ASTM D244, except that 0.02 Normal Calcium Chloride solution shall be used in place of distilled water.

301.4.1.2. Base and Subbase Materials. Base and subbase materials shall meet the requirements shown on the plans or in the pertinent specifications.

301.4.1.3. Delivery and Storage. If asphalt base stabilization agent is furnished in trucks, each truck shall bear the weight of asphalt base stabilization agent measured on certified scales, or the CONTRACTOR shall place a set of standard platform truck scales or hopper scales at a location approved by the OWNER.

Asphalt base stabilization agent shall be stored and handled in tank, tanker or distributor truck until immediately before distribution on the road. Asphalt base stabilization agent shall be stored in freeze-proof containers.

301.4.2. Equipment. Machinery, tools and equipment necessary for proper performance of the work shall be on the project and approved by the OWNER prior to the beginning of construction operations. All machinery, tools and equipment used shall be maintained in a satisfactory and workmanlike manner.

301.4.3. Asphalt Emulsion Treatment Construction Methods.

301.4.3.1. General. It is a primary requirement of this specification to secure a completed course of treated material containing a uniform asphalt base stabilization agent mixture, free from loose or segregated areas, of uniform density and moisture content, well bound for its full depth, and with a smooth surface and suitable for placing subsequent courses. It shall be the responsibility of the CONTRACTOR to regulate the sequence of work, to use the proper amount of asphalt base stabilization agent, maintain the work and rework the courses as necessary to meet the above requirements.

Prior to beginning any asphalt base stabilization agent treatments, the roadbed shall be constructed and shaped to conform to the typical sections, lines and grades as shown on the plans or as established by the OWNER.

301.4.3.2. General Construction.

301.4.3.2.1. Treatment for Materials-In-Place. Materials to be treated shall be excavated to the secondary grade (proposed bottom of asphalt base stabilization agent) and removed or windrowed to expose the secondary grade. Any wet or unstable material below the secondary grade shall be corrected by scarifying, adding asphalt base stabilization agent and compacting until it is of uniform stability. The excavated material shall then be spread to the desired cross section.

If the CONTRACTOR elects to use a cutting or pulverizing machine that shall remove the subgrade material accurately to the secondary grade and to pulverize the material at the same time, CONTRACTOR shall not be required to expose the secondary grade or windrow the material. However, the CONTRACTOR shall be required to roll the subgrade before using the pulverizing machine and correct any soft areas that this rolling may reveal. This method shall be permitted only where a machine is provided which shall insure that the material is cut uniformly to the proper depth and which has cutters that shall place the secondary grade to a smooth surface over the entire width of the cut. The machine shall be of such design that a visible indication is given at all times that the machine is cutting to the proper depth.

301.4.3.2.2. Treatment for New Materials. The base and subbase material, as provided in the governing specifications, shall be delivered, placed and spread in the required amount per station. The material shall be manipulated as specified and thoroughly mixed prior to the addition of the asphalt base stabilization agent.

301.4.3.3. Asphalt Base Stabilization Agent Application. Asphalt base stabilization agent shall be spread only on that area where the mixing can be completed in the same working day. Asphalt base stabilization agent shall be mixed with water and applied as a thin water suspension. The distribution of asphalt stabilization agent at the rate shown on the plans shall be attained by successive passes over a measured surface of roadway until the proper moisture content and asphalt base stabilization agent content has been achieved.

The asphalt base stabilization agent shall be distributed at a uniform rate and in such a manner as to reduce heavy or light areas to a minimum. A motor grade can be used to cover the exposed asphalt base stabilization agent. If necessary, the material shall be sprinkled until a proper moisture content has been achieved.

301.4.3.4. Mixing. The application and mixing of asphalt base stabilization agent with the material shall be thorough. During the interval of time between application and mixing, asphalt base stabilization agent that has been exposed to the open air for a maximum time of 2-hours, or a shorter period when the breaking of the emulsion has occurred, shall not be accepted for payment. *(Breaking of the emulsion is when the emulsion is over exposed on the surface without mixing, thus turning it from a brown color to black. The color change is due to the evaporation of the water from the emulsion, thus rendering it ineffective in mixing in the soil, base or subbase material).* The CONTRACTOR is responsible for monitoring the application and the mix time of the asphalt stabilization agent with the soil, base or subbase material. The overexposed area shall be retreated with another application of asphalt base stabilization agent and mixed.

301.4.3.4.1. Treatment for Materials-In-Place. Material and asphalt base stabilization agent shall be thoroughly mixed by approved road mixers or other approved equipment and the mixing

continued until a homogeneous, friable mixture of material and asphalt base stabilization agent is obtained, free from all clods or lumps. Materials containing plastic clay or other materials which shall not readily mix with asphalt base stabilization agent shall be mixed as thoroughly as possible, and meet the requirements of Table 301.4.3.4.1.(a) Asphalt Emulsion Treated Materials-In-Place when tested dry by laboratory sieve at the time of the asphalt base stabilization agent application, brought to the proper moisture content, sealed with a pneumatic roller, and left to cure 1 to 2 days as directed by the OWNER. During the curing period, the material shall be kept moist.

Table 301.4.3.4.1.(a) Asphalt Emulsion Treated Materials-In-Place

Sieve Size	Minimum Passing by Dry Weight^{1,2}
1¾-in. (45mm)	100%
No. 4 (4.75mm)	60%

301.4.3.4.2. Treatment of New Material. The base or subbase material, asphalt base stabilization agent and required water shall be thoroughly mixed and blended by approved road mixers or other approved equipment and the mixing continued until a homogeneous, friable mixture is obtained. When the asphalt base stabilization agent is placed and mixed by the use of blades, the material shall be bladed as the asphalt base stabilization agent water mixture is applied; after the total amount has been placed, the mixture shall be thoroughly blended to the satisfaction of the OWNER.

301.4.3.4.3. Central Mixing Plant. The soil, asphalt base stabilization agent and water shall be mixed in a pugmill either of the batch or continuous-flow type. The plant shall be equipped with feeding and metering devices which shall add the soil, asphalt base stabilization agent and water into the mixer in the specified quantities. Soil and asphalt base stabilization agent shall be mixed sufficiently to prevent asphalt base stabilization agent balls from forming when water is added. Mixing shall continue until a uniform and intimate mixture of soil, asphalt base stabilization agent and water is obtained. The mixture shall be placed on the moistened subgrade in a uniform layer by an approved spreader or spreaders.

After mixing asphalt stabilization agent with the base or subbase material the following conditions shall be met:

- (1) Not more than 3-hours shall elapse between the placement of soil-asphalt emulsion mixture in adjacent lanes and placement at any location except at longitudinal construction joints.
- (2) Not more than 3-hours shall elapse between the start of spreading the soil-asphalt emulsion mixture and start of compaction.
- (3) Not more than 4-hours shall elapse between the start of mixing and the start of compaction.

The layer of soil-asphalt base stabilization agent shall be uniform in thickness and surface contour, and in such quantity that the completed base shall conform to the required grade and cross section. Dumping of the mixture in piles or windrows upon the subgrade shall be permitted.

301.4.3.5. Compaction. Compaction of the mixture shall begin immediately after final mixing and in no case later than 2-days after final mixing. The material shall be aerated or sprinkled as necessary to provide optimum moisture content. At the start of compaction, the moisture in the mixture and in unpulverized soil lumps, based on oven-dry weights, shall be within minus-2- to plus-2-percent-of-optimum. The specified optimum moisture content and density shall be determined in the field on the representative samples of soil-asphalt base stabilization agent mixture obtained from the area being processed. Prior to the beginning of compaction, the mixture shall be in a loose condition for its full depth. The loose mixture shall be uniformly compacted to the specified density within 4-hours. Compaction shall begin at the bottom and shall continue until the entire depth of the mixture is uniformly compacted as shown on the plans or specified by the OWNER.

The compacted mixture shall have a uniform density of not less than 95-percent of the maximum density as determined by ASTM D698 Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³). Final moisture content shall be within minus-2- to plus-4-percent-of-optimum. If the soil-asphalt base stabilization agent mixture is wetted by rain so that the average moisture content

exceeds the tolerance given at the time of final compaction, the entire section shall be reconstructed in accordance with this specification at the sole expense of the CONTRACTOR. After the soil and asphalt base stabilization agent mixture, except the top layer, is compacted, water shall be uniformly applied as needed and thoroughly mixed in with a spike tooth harrow or equal. The surface shall then be reshaped to the required lines, grades and cross sections and then lightly scarified to loosen any imprint left by the compacting or shaping equipment. After each section is completed, such tests as are necessary shall be made by the OWNER. If any portion fails to meet the density specified, it shall be reworked as necessary to obtain the specified density at the sole expense of the CONTRACTOR.

301.4.3.6. Finishing, Curing and Preparation for Surfacing. The resulting surface shall be thoroughly rolled with a pneumatic tire roller and “clipped”, “skinned”, and “tight-bladed” by a power grader to a depth of approximately 1/4-in., moving all loosened soil and asphalt base stabilization agent from the section. The surface shall then be thoroughly compacted with the pneumatic roller, adding small increments of moisture as needed during rolling. When directed by the OWNER, surface finishing methods may be varied from this procedure, provided a dense, uniform surface, free of surface material, is maintained at its specified optimum during all finishing operations. Surface compaction and finishing shall proceed in such a manner as to produce, in not more than 4-hours, a smooth, closely knit surface, free of cracks, ridges or loose material, conforming to the drawn grade and line shown on the plans.

The completed section shall then be moist-cured for a minimum of 2-days before further courses are added, unless otherwise directed by the OWNER. In cases where, in the opinion of the OWNER, subgrade treatment or subbase sets up sufficiently to prevent objectionable damage from traffic, such layers may be opened to traffic after compaction. The surface of the compacted layer shall be kept moist until covered by other base or paving material or application of a curing seal of emulsified asphalt. If a curing seal is used, it shall be applied as soon as possible after completion of final rolling, at a rate of between 0.10- and 0.20-gallons-per-square-yard, the exact rate to be determined by the OWNER. No equipment or traffic shall be permitted on asphalt base stabilization agent treated material for 12-hours after curing seal is applied, unless otherwise permitted by the OWNER.

301.4.3.7. Maintenance. The CONTRACTOR shall be required to maintain the completed asphalt stabilized base within the limits of its contract in good condition, satisfactory to the OWNER as to grade, crown and cross section until such time as the surface course is constructed. The CONTRACTOR shall immediately repair all irregularities or other defects that may occur at the CONTRACTOR’S expense. Repairs are to be made as directed by the OWNER and in a manner to insure restoration of a uniform surface and durability of the portion repaired.

301.4.4. Measurement and Payment. Asphalt base stabilization agent treatment shall be measured for payment in square-yards for the thickness shown in the plans for the surface area of completed and accepted work. The measurement for asphalt base stabilization agent shall be by the gallon.

Asphalt base stabilization agent treatment shall be paid for at the contract unit price per square yard, as provided in the proposal and contract. The contract unit price shall be the total compensation for preparing the roadbed; for loosening, pulverizing, application of asphalt base stabilization agent, water content in the asphalt base stabilization agent mixture and the mixing water; mixing, shaping, sprinkling, compacting, finishing, curing and maintaining; for manipulations required; and for all labor, equipment, fuels, tools and incidentals necessary to complete the work, all in accordance with the plans and specifications. Asphalt base stabilization agent material measured as provided in this item shall be paid for at the unit price bid for “asphalt emulsion base stabilizer” which price shall be full compensation for furnishing the material; for all freight involved; for all unloading, storing and handling; and for all labor, equipment, fuels, tools and incidentals necessary to complete the work.

301.5. FLEXIBLE SUBBASE OR BASE (CRUSHED STONE/CONCRETE)

This item shall consist of a foundation course for a surface course or for other subbase or base courses; shall be constructed as herein specified in one or more courses in conformity with the typical section shown on the plans and to the lines and grades as established by the OWNER.

301.5.1. Material.

301.5.1.1. General. Should the CONTRACTOR elect to produce the material from local pits, the material shall be secured from sources approved by the OWNER. The pits as utilized shall be opened up in such a manner as to immediately expose the vertical faces of all the strata of acceptable material in the depth mined. Unless otherwise directed, the material shall be secured in successive vertical cuts extending through all of the exposed strata, in order that a uniform mixed material shall be secured. Should OWNER allow crushed concrete, materials shall meet the requirements in Table 301.5.1.2.(a) Flexible Base or Subbase Material Requirements, according to specified grade. Additionally, this material shall be free of thin, laminated, or elongated pieces, reinforcing steel, or an excess of shale, dirt, organic matter or other objectionable materials as determined by the OWNER that could be harmful to the production of a homogenous base coarse.

301.5.1.2. Tests and Physical Requirements. Tests shall be performed in accordance with ASTM D4318 Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils. The preparation of samples for testing according to ASTM D4318 shall be in accordance with the requirements of ASTM D2217 Practice for Wet Preparation of Soil Samples for Particle-Size Analysis and Determination of Soil Constants. The material shall also be tested under TxDOT Test Method Tex-116-E The Wet Ball for Determining the Disintegration of Flexible Base Materials. When a magnesium soundness value is shown on the plans the material shall be tested in accordance with Test Method Tex-411-A Soundness of Aggregate Using Sodium Sulfate or Magnesium Sulfate. Physical properties shall meet the requirements in Table 301.5.1.2.(a) Flexible Base or Subbase Material Requirements, according to specified grade.

Table 301.5.1.2.(a) Flexible Base or Subbase Material Requirements

Property	Grade 1		Grade 2	
Triaxial Class	1		1 to 2.3	
Minimum Compressive Strength at lateral pressure 0-psi at lateral pressure 15-psi	45-psi 175-psi		35-psi 175-psi	
Master Grading	Sieve	Percent Retained	Sieve	Percent Retained
	1 $\frac{3}{4}$ "	0	2 $\frac{1}{2}$ "	0
	$\frac{7}{8}$ "	10-35	1 $\frac{3}{4}$ "	0-10
	$\frac{3}{8}$ "	30-50	No. 4	45-75
	No. 4	45-65	No. 40	60-85
	No. 40	70-85		
Maximum Liquid Limit	35		40	
Maximum Plasticity Index	10		12	
Maximum Wet Ball Mill ¹	40		45	
Maximum increase in passing No. 40	20%		20%	
Maximum foreign material allowed	1%		1%	

1. When lightweight aggregates are used, the wet ball mill requirements shall not apply; lightweight aggregate shall meet the Los Angeles Abrasion, Pressure Slaking and Freeze Thaw requirements of TxDOT Item 303 Aggregate for Surface Treatment (Lightweight).

301.5.1.3. Rejection. Aggregate that fails to meet the requirements of these specifications may be rejected by the OWNER. Such rejection shall incur no cost to the OWNER. Aggregate sources from which materials are delivered with properties not meeting these specifications may be rejected as further supply sources to the project by the OWNER.

301.5.2. Construction Methods.

301.5.2.1. Preparation of Subgrade. Preparation of the subgrade shall be in conformity with the requirements of [Item 301.3.3.3.1. Subgrade Preparation](#).

301.5.2.2. Placing. Immediately before placing the subbase or base course material, the subgrade shall be checked as to conformity with grade and section.

The material shall be delivered in approved vehicles of a uniform capacity. It shall be the charge of the CONTRACTOR that the required amount of specified material shall be delivered to secure the proper thickness of the completed subbase or base course. Material deposited on the subgrade shall be spread and shaped the same day. All material shall be moved at least once from the original position in which it is deposited. In the event of inclement weather or other unforeseen circumstances which render impracticable the spreading of the material during the first 24-hour period, the material shall be scarified and spread as directed by the OWNER. The material shall be sprinkled, if directed, and shall then be bladed, dragged and shaped to conform to the typical section as shown on the plans.

All areas and "nests" of segregated coarse or fine material shall be corrected or removed and replaced with well-graded material as directed by the OWNER. If additional binder is considered desirable or necessary after the material is spread and shaped, it shall be furnished and fully incorporated with the material in place by scarifying, harrowing, brooming or by other approved methods. The course shall be sprinkled as required and compacted to the extent necessary to provide not less than the percent density as specified in [Item 301.5.2.3. Density](#). In addition to the requirements specified for density, the full depth of flexible subbase or base shown on the plans shall be compacted to the extent necessary to remain firm and stable under construction equipment. After each course is completed, tests as necessary shall be made by the OWNER unless otherwise specified in the special provisions or in the plans. If the material fails to meet the density requirements, it shall be reworked as necessary to meet these requirements.

Throughout the entire operation, the shape of the course shall be maintained by blading. The surface, upon completion, shall be smooth and in conformity with the typical sections shown on the plans to the established lines and grades. On the surface on which pavement is to be placed, any deviation in excess of 1/2-in. in cross section in a length of 16-ft. measured longitudinally shall be corrected by loosening, adding or removing material, reshaping and recompacting by sprinkling and rolling. All fractures, settlement, or segregation that develops shall be corrected immediately by scarifying the areas affected, adding suitable material as required, reshaping and recompacting by sprinkling and rolling.

Should the subbase or base course, due to any reason or cause, lose the required stability, density and finish before the surfacing is complete, it shall be recompacted and refinished at the sole expense of the CONTRACTOR.

301.5.2.3. Density. The density required under this item shall not be less than 92-percent compaction as determined by ASTM D1557, Test Method for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³). Moisture content shall be within minus-2- to plus-4-of-optimum.

301.5.2.4. Courses. Non full depth asphalt pavements, paving types with flexible base under the curb and gutter, shall be placed and compacted at the same time and in the same operation as the flexible base under the pavement. Where the subbase or base course exceeds 6-in. in thickness, it shall be constructed in two or more courses of equal thickness as indicated on the typical section. A minimum course depth of 3-in. is recommended. The first course shall be placed and compacted under the curb and gutter and under the pavement. The curb and gutter shall then be built upon the first course. The final course of the flexible base shall be placed following the curing time as specified in [Item 305.1. Concrete Curb and Gutter](#).

301.5.3. Measurement and Payment. Work and accepted materials as specified for this item shall be measured by the square-yard of the required depth from plans and specifications completed flexible base as follows:

- (1) Where no curb and gutter is in place or is to be constructed in connection with the flexible base, measurement shall be made to the lines shown on the plans or established as the edge of the base to be constructed.
- (2) Where curb and gutter is in place or is proposed to be constructed in connection with the placing of the flexible base, measurement shall be made to the lip of the gutter. Material placed under the curb and gutter or behind the curb shall not be measured as flexible base but shall be considered as foundation courses for the curb and gutter.

The work performed and material placed (including additional binder if required) as prescribed for this item, measured as provided in this item, shall be paid for at the unit price bid per square-yard for flexible base, which price shall be full compensation for preparation of subgrade, furnishing of material, hauling, blading, sprinkling, compacting and furnishing all of labor and equipment necessary to complete the work.

301.6. GEOTEXTILES USED IN PAVING APPLICATIONS

301.6.1. Materials.

301.6.1.1. Physical Properties. The fabric properties shall conform to those shown in Table

301.6.1.(a) Geotextiles for Paving, as determined by the Federal Highway Administration Task Force 25 Guidelines using ASTM Test Methods, except where noted.

301.6.1.2. Certification. The manufacturer, if required by the OWNER, shall provide documents stating the name and manufacturer, the chemical composition of the filaments or yarns and test values of the properties of the geotextile. The manufacturer must certify that the material meets or exceeds these specifications.

301.6.1.3. Rejection. Geotextile may be rejected for failure to meet any of the requirements of this specification.

Table 301.6.1.(a) Geotextiles for Paving

Designation (Test Method)	Characteristic	Average Roll Minimum Value
ASTM D4632 Grab Breaking Load and Elongation of Geotextiles	Grab Strength	80-lbs. @ 12-in.-per-minute
ASTM D4632	Elongation @ Break	50% @ 12-in.-per-minute
Tex-616-J, Construction Fabrics	Asphalt Retention	0.5-oz.-per-sq.-ft.
ASTM D276 Identification of Fibers in Textiles	Melting Point	300°F

301.6.2. Construction Methods. Construction methods for each type unit shall be provided by the manufacturer and approved by the OWNER based on the site-specific use.

301.6.3. Measurement and Payment. If provided as a separate contract item, geotextile shall be measured by the square-yard, complete in place.

Geotextile, when provided as a separate pay item, shall be paid for by the square-yard, complete in place, which price shall include materials, hauling, placing, anchoring, and all other work necessary to achieve a functional geotextile layer(s) in the subbase or base layer. If not provided as a separate contract item, geotextile shall be considered subsidiary to those items provided for subbase or base preparation.

ITEM 302. ASPHALT PAVEMENT

302.1. DESCRIPTION

This Item establishes the requirements for asphalt construction. This Item includes material requirements and construction methods for emulsified asphalts, hot-mix asphalt pavement, performance graded (PG) asphalts and other miscellaneous asphaltic materials and polymer additives. Alternately, the use of warm-mix asphalt may be permitted with the OWNER'S approval in accordance with the Texas Department of Transportation Pavement Design Guide - Section 5: Hot-Mix Asphalt Concrete Pavement Mixtures.

302.2. AGGREGATES FOR HOT-MIX ASPHALT PAVEMENT

302.2.1. General Requirements. Aggregates shall conform to the requirements contained in this [Item 302.2](#). Aggregates for Hot-Mix Asphalt Pavement and shall be approved by the OWNER prior to use. The integrity of the aggregate shall be such as to produce a workable material within the limits contained in this specification.

302.2.1.1. Deleterious Substances. Aggregates shall be free from loam, clay balls or other injurious foreign matter occurring either free or as a coating on the aggregates.

302.2.1.2. Storage. Prior to stockpiling of aggregates, the area shall be cleaned of trash, weeds and grass and be relatively smooth. Aggregates shall be stockpiled in such a manner as to prevent mixing of one aggregate with another. Coarse aggregates shall be separated into stockpiles of different gradation, such as a large coarse aggregate and a small coarse aggregate stockpile and such that the grading requirements of the specified type shall be met when the piles are combined in the asphaltic mixture. No coarse aggregate stockpile shall contain more than 15-percent by weight of material that shall pass a No. 10 (2.0mm) sieve except as noted on the plans. Fine aggregate stockpiles may contain coarse aggregate in the amount of up to 20-percent by weight; however, the coarse aggregate shall meet the quality tests specified in [Item 302.2.2](#). Coarse Aggregates. Suitable equipment of acceptable size shall be furnished by the CONTRACTOR to work the stockpiles and prevent segregation of the aggregates.

302.2.1.3. Quality and Testing Requirements. Test of aggregates, when required, shall be made in accordance with applicable Texas Department of Transportation tests or ASTM Test Methods, as shown in the tables below or as required by OWNER.

Requirements for hot-mix asphalt pavement aggregates are shown in Table 302.2.2.(a) Coarse Aggregate Quality Requirements.

302.2.1.4. Aggregate Rejection. Aggregates that fail to meet the requirements of these specifications may be rejected by the OWNER. Such rejection shall incur no cost to the OWNER. The OWNER may reject sources from which materials are delivered with properties not meeting these specifications. Such rejection shall incur no cost to the OWNER.

302.2.2. Coarse Aggregates. Coarse aggregates shall be that portion of the total aggregates retained on the No. 10 sieve (2.0mm). Coarse aggregates shall consist of clean, tough, durable fragments of crushed stone, crushed gravel, or steel slag as specified herein, of uniform quality throughout.

All coarse aggregates shall meet the requirements listed in Table 302.2.2.(a) Coarse Aggregate Quality Requirements.

Table 302.2.2.(a) Coarse Aggregate Quality Requirements¹

Characteristic	Test Method	Value
Deleterious Material	Tex-217-F, Part I, Determining Deleterious Material in Coarse Aggregates (Bituminous Mixtures)	1.5% Max.
Decantation	Tex-217-F, Part II, Decantation Test for Coarse Aggregate (Bituminous Mixtures)	1.5% Max.
Los Angeles Abrasion	Tex-410-A, Abrasion of Coarse Aggregate Using the Los Angeles Machine (ASTM C131)	35% Max.
Magnesium Sulfate Soundness Loss, 5 Cycle	Tex-411-A, Soundness of Aggregate Using Sodium Sulfate or Magnesium Sulfate	30% Max. (lower value may be shown on plans)
Coarse Aggregate Angularity Two Crushed Faces	Tex-460-A, Part I, Determining Crushed Face Count	90% Min.
Flat Elongated Particles	ASTM D4791 Flat Particles, Elongated Particles, or Flat and Elongated Particles in Coarse Aggregate	20% Max. @ 3:1

1. Sampled during delivery to the plant or from the stockpile, unless otherwise shown on the plans.

302.2.3. Fine Aggregate. Fine aggregate may consist of crushed stone, crushed gravel, sand, and/or limestone or steel slag screenings.

Fine aggregate shall meet the requirements listed in Table 302.2.3.(a) Fine Aggregate Quality Requirements.

Table 302.2.3.(a) Fine Aggregate Quality Requirements¹

Characteristic	Test Method	Value
Linear Shrinkage	Tex-107-E, Determining the Bar Linear Shrinkage of Soils	3% Max.
Sand Equivalent Value	Tex-203-F, Sand Equivalent Test	45% Min.

1. Sampled during delivery to the plant or from the stockpile, unless otherwise shown on the plans.

302.2.3.1. Sand. Sand material may constitute a part of the fine aggregates for hot-mix asphalt pavement. The fine aggregate portion of the sand passing the No. 40 (425- μ m) sieve shall meet the Linear Shrinkage requirement listed in Table 302.2.3.(a) Fine Aggregate Quality Requirements.

302.2.3.1.1. Gradation. Fine aggregate sand shall be that portion of the sand in the total aggregate passing the No. 10 (2.0mm) sieve. It shall be well graded and composed of sound, durable sand particles.

302.2.3.2. Limestone or Steel Slag Screenings. Limestone or steel slag screenings may constitute part or all of the fine aggregates for hot-mix asphalt pavement. Screenings shall be of the same or similar material for coarse aggregates. Where limestone rock screenings are specified for use, they shall be screenings resulting from crushing operation.

The fine aggregate portion passing the No. 40 (425- μ m) sieve shall meet the Linear Shrinkage requirement listed in Table 302.2.3.(a) Fine Aggregate Quality Requirements. Fine aggregates from each source shall meet Linear Shrinkage requirements.

302.2.3.2.1. Gradation. The limestone or steel slag screening shall meet the grading requirements in Table 302.2.3.2.1.(a) Limestone or Steel Slag Screenings Gradation unless otherwise shown on the plans.

When authorized by the OWNER, stone or steel slag screenings containing particles larger than $\frac{3}{8}$ -in. (9.5-mm) may be used but only that portion of the material passing the $\frac{3}{8}$ -in. (9.5-mm) sieve shall be considered as fulfilling the requirements for screenings when a minimum percent of screenings is specified for a particular mixture.

Table 302.2.3.2.1.(a) Limestone or Steel Slag Screenings Gradation

Sieve Size	Percent Passing by Weight
3/8-in. (9.5-mm)	100
Passing No. 200 (75-μm)	0 to 30

302.2.4. Mineral Filler. Mineral filler shall consist of a thoroughly dry stone dust Portland cement or other mineral dust approved by the OWNER. All mineral filler shall meet the requirements listed in Table 302.2.4.(a) Mineral Filler Quality Requirements.

Table 302.2.4.(a) Mineral Filler Quality Requirements¹

Characteristic	Test Method	Value
Linear Shrinkage	Tex-107-E, Determining the Bar Linear Shrinkage of Soils	3% Max.

1. Sampled during delivery to the plant or from the stockpile, unless otherwise shown on the plans.

302.2.4.1. Gradation. When tested by the method outlined in TxDOT Test Method Tex-200-F Sieve Analysis of Fine and Coarse Aggregates (Part 1 Dry Sieve Analysis (Based on Weight) or Part 3 Volumetric Sieve Analysis, as applicable), it shall meet the requirements of Table 302.2.4.1.(a) Mineral Filler Gradation.

Table 302.2.4.1.(a) Mineral Filler Gradation

Sieve Size	Percent Passing by Weight
No. 30 sieve (600-μm)	95 to 100
No. 80 sieve (180-μm)	Not Less Than 75
No. 200 sieve (75 μm)	Not Less Than 55

302.3. BITUMINOUS MATERIALS

302.3.1. General. This Item consists of bituminous material, including performance graded asphalts, modified performance graded asphalts, asphalt cement, emulsified asphalt, and other miscellaneous asphaltic materials. Asphalt for use in paving shall be a refined asphalt produced from crude petroleum. The base asphalt shall be homogeneous and free from water and residue from distillation of coal, coal tar or paraffin oil and shall not foam when heated to 347°F.

302.3.1.1. Tests and Certification of Bituminous Materials. When tested according to ASTM or AASHTO test methods, the various materials shall meet the applicable requirements of this specification. At the time of delivery of each shipment of asphalt, the vendor supplying the material shall deliver to the CONTRACTOR certified copies of the test report. Two copies of the test reports shall be furnished to the OWNER. Test reports shall indicate the name of the vendor, type and grade of bituminous material delivered, date and point of delivery, quantity delivered, delivery ticket number, purchase order number, and results of the specified tests. The test report, signed by an authorized representative of the vendor, shall certify that the product delivered conforms to the specifications for the type and grade indicated. The certified test reports and the testing required in connection with the reports shall be at no cost to the OWNER.

Until the certified test reports and samples of the material have been checked by the OWNER to determine their conformity with the prescribed requirements, the material to which such report relates and any work in which it may have been incorporated as an integral component, shall be only tentatively accepted by the OWNER. Final acceptance shall be dependent upon the determination by the OWNER that the material involved fulfills the prescribed requirements.

302.3.1.2. Rejection. Any material specified in this section may be rejected for failure to meet any of the provisions for this specification, or for any defect causing it to be unsuitable for its intended use.

302.3.2. Performance Graded (PG) Asphalt Binders. Performance graded asphalt binders shall be smooth and homogeneous, shall be free from water, shall not foam when heated to 347°F and shall meet the

requirements for performance graded asphalt binders shown in Table 302.3.2.(a) Performance Graded Asphalt Binders.

PG binders shall show no separation when tested according to Tex-540-C Measurement of Polymer Separation on Heating in Modified Asphalt Systems. Separation testing is not required if one of the following conditions is met:

- (1) The modifier is introduced separately at the mix plant either by injection in the asphalt line or mixer; or
- (2) The binder is blended on site in continuously agitated tanks; or
- (3) Binder acceptance is based on field samples taken from an in-line sampling port at the hot-mix plant after the addition of modifiers.

302.3.2.1. Modified Performance Graded Asphalt Binders. In addition to meeting the requirements in Table 302.3.2.(a) Performance Graded Asphalt Binders, modified performance graded asphalt binders shall also meet the requirements listed herein according to grade.

302.3.2.1.1. SBR Latex Rubber Modified Performance Graded Binders. Available grades include PG 64-28L, PG 70-28L, PG 70-22L, PG 76-22L, and PG 82-22L. The manufacturer shall provide certification that SBR latex rubber was used in production of the binder. Ductility tested according to AASHTO T51: 39.2°F, 1-cm/min, cm, 70-cm minimum.

302.3.2.1.2. SBS Rubber Modified Performance Graded Binders. Available grades include PG 64-28S, PG 70-28S, PG 70-22S, PG 76-22S, and PG 82-22S. The manufacturer shall provide certification that SBS rubber was used in production of the binder. Elastic recovery tested according to Tex-539-C Measurement of Elastic Recovery of Tensile Deformation Using a Ductilometer: 50°F, 55% minimum.

302.3.2.1.3. Tire Rubber Modified Performance Graded Binders. Available grades include PG 64-28TR, PG 70-28TR, PG 70-22TR, PG 76-22TR, and PG 82-22TR. The manufacturer shall provide certification that tire rubber was used in production of the binder. Elastic recovery tested according to Tex-539-C Measurement of Elastic Recovery of Tensile Deformation Using a Ductilometer: 50°F, 40% minimum.

Table 302.3.2.(a) Performance Graded Asphalt Binders

Performance Grade	PG 58			PG 64				PG 70				PG 76				PG 82		
	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28
Average 7-day maximum Pavement Design Temperature, °C ¹	58			64				70				76				82		
Minimum Pavement Design Temperature, °C ¹ (i.e. design temperature shall be greater than shown)	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28	-34	-16	-22	-28
Original Binder																		
Flash Point Temperature, AASHTO T48: Minimum °C	230																	
Viscosity, AASHTO TP48 ^{2,3} Maximum, 3.0 Pa*s, Test Temp, °C	135																	
Dynamic Shear, AASHTO TP5: ⁴ G*/sinδ, Minimum, 1.00-kPa Test Temperature @ 10-rad/s, °C	58			64				70				76				82		
Rolling Thin Film Oven (Tex-541-C)																		
Maximum Loss, percent	1.0																	
Dynamic Shear, AASHTO TP5: G*/sinδ, Minimum, 2.20-kPa Test Temperature @ 10-rad/s, °C	58			64				70				76				82		
Pressure Aging Vessel Residue (AASHTO PP1)																		
PAV Aging Temperature, °C	100																	
Dynamic Shear, AASHTO TP5: G*/sinδ, Maximum, 5000-kPa Test Temperature @ 10-rad/s, °C	25	22	19	28	25	22	19	28	25	22	19	28	25	22	19	28	25	22
Creep Stiffness, AASHTO TP1: ^{5,6} S, Maximum, 300-Mpa <i>m</i> -value, Minimum, 0.300 Test Temp @60s, °C	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18
Direct Tension, AASHTO TP3: ⁶ Failure Strain, Minimum, 1.0% Test Temp @ 1.0-mm/min, °C	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18	-24	-6	-12	-18

1. Pavement temperatures are estimated from air temperatures using an algorithm contained in the PGEXCEL3.XLS software program, may be provided by the specifying agency, or by following the procedures as outlined in AASHTO MP2 and PP28.

2. This requirement may be waived at the discretion of the specifying agency if the supplier warrants that the asphalt binder can be adequately pumped, mixed and compacted at temperatures that meet all applicable safety, environmental and constructability requirements. At test temperatures where the binder is a Newtonian fluid, any suitable standard means of viscosity measurement may be used, including capillary (AASHTO T201 or T202) or rotational viscometry (AASHTO TP48).

3. Viscosity at 135°C is an indicator of mixing and compaction temperatures that can be expected in the lab and field. High values may indicate high mixing and compaction temperatures. Additionally, significant variation can occur from batch to batch. CONTRACTORS should be aware that variation could significantly impact mixing and compaction operations. CONTRACTORS are therefore responsible for addressing any constructability issues which may arise.

4. For quality control of unmodified asphalt cement production, measurement of the viscosity of the original asphalt cement may be substituted for dynamic shear measurements of G*/sin(δ) at test temperatures where the asphalt is a Newtonian fluid. Any suitable standard means of viscosity measurement may be used, including capillary (AASHTO T201 or T202) or rotational viscometry (AASHTO TP48).

5. Silicone beam molds as described in AASHTO TP1-93 are acceptable for use.

6. If the creep stiffness is below 300-Mpa, the direct tension test is not required. If the creep stiffness is between 300- and 600-Mpa, the direct tension failure strain requirement can be used in lieu of the creep stiffness requirement. The m-value requirement must be satisfied in both cases.

302.3.2.2. Acceptance of Performance Graded (PG) Asphalt Binders.

302.3.2.2.1. Location of Manufacture. Performance graded binder acceptance procedures are dependent on where the binder is manufactured. The requirements are as follows.

Manufactured at the Source. PG binders manufactured at the source are normally approved at the source according to the applicable requirements of the OWNER. The OWNER may acquire field samples at any time, particularly if material quality is suspect.

Manufactured at the Job Site. If PG binders are manufactured at the job site, for example where SBR latex is injected at the hot mix plant, the following quality measures are required. Antistrip agents are not considered asphalt modifiers.

- (1) Preconstruction. The CONTRACTOR shall provide the OWNER with a 1-quart sample of the proposed binder and a test report showing compliance with the required performance grade. The sample and test report will be forwarded to OWNER for verification testing. If the OWNER chooses to verify that the sample meets specifications, the OWNER will complete verification testing within ten (10) working days after receipt of the sample. If the OWNER chooses to verify the sample, then the sample shall be verified before mixture production is allowed to begin.
- (2) Construction. A sampling port is required which meets the requirements of AASHTO T40 Practice for Sampling Bituminous Materials, Section 9, "Sampling From Pipelines During Loading or Unloading". This sampling port shall be located on the asphalt line before introduction of the asphalt into the mix plant and shall be downstream from the addition of any modifiers and any dispersing or mixing equipment associated with their introduction.

Sample containers shall be provided by the CONTRACTOR and shall be clean, double friction top round 1-quart cans. All samples shall be taken by the CONTRACTOR, and witnessed by the Engineer.

All samples shall be taken from the sampling port after a sufficient amount of asphalt is run out and wasted, in order to clear any residual asphalt that builds up in the sampling port. All samples shall be taken in a clean, 1-gallon can, immediately stirred and used to fill three (3) 1-quart sample cans. The cans shall be delivered to the OWNER. The OWNER will choose one sample can for testing and the other cans are retained until testing is complete, in case the original sample is lost or damaged.

302.3.2.2.2. Sampling Frequency. A sample of the PG binder may be taken from each mixture production day, at a time determined by the OWNER. The sample from the first day's production may be subjected to verification testing. Additionally, throughout the duration of the project, the OWNER may randomly select binder samples for verification testing.

302.3.2.2.3. Verification Testing. OWNER may perform verification testing on all construction samples. The OWNER will complete verification testing within 10 working days after receipt of the sample.

For verification testing which fails to confirm the required performance grade, the CONTRACTOR shall review the manufacturing process to locate the source of the problem. The OWNER may stop production until the CONTRACTOR can show that the next binder produced will meet the specifications. The OWNER may require materials not meeting the specification requirements to be removed and replaced at the CONTRACTOR's expense.

302.3.3. Asphalt Cement. Asphalt cement is bituminous liquid binder. The material for asphalt cement shall be homogeneous, shall be free from water, shall not foam when heated to 347°F and shall meet the requirements of Table 302.3.3.(a) Requirements for Asphalt Cement.

Table 302.3.3.(a) Requirements for Asphalt Cement

Property, Test Parameters	Value According to Grade							
	AC-3		AC-5		AC-10		AC-20	
	Min	Max	Min	Max	Min	Max	Min.	Max
Viscosity, 140°F, Stokes	250	350	400	600	800	1200	1600	2400
Viscosity, 275°F, Stokes	1.1	—	1.4	—	1.9	—	2.5	—
Penetration, 77°F, 100-g, 5-sec.	210	—	135	—	85	—	55	—
Flash point C.O.C., °F	425	—	425	—	450	—	450	—
Solubility in trichloroethylene (%)	99.0	—	99.0	—	99.0	—	99.0	—
Tests on residues from thin film oven test: Viscosity, 140°F, Stokes	—	900	—	1500	—	3000	—	6000
Ductility, 77°F 5-cms-per-min, cms.	100	—	100	—	70	—	50	—
Spot Test	Negative for all grades							

302.3.3.1. Polymer Modified Asphalt Cement. For surface treatment applications, a polymer additive consisting of an anionic emulsion of styrene-butadiene low-temperature copolymer shall be added to the AC-5 or AC-10 asphalt when specified on the plans or in the specifications in the contract. The polymer additive shall consist of two-percent (by weight) polymer additive (solids basis) which has good storage stability. Polymer additive shall possess the properties specified in [Item 302.3.3.1.1](#). Polymer Additive Properties. The manufacturer shall furnish the actual styrene-butadiene rubber (SBR) content for each batch of polymer emulsion. This information shall accompany all shipments to facilitate proper addition rates.

The finished polymer modified asphalt cement blend shall be smooth, homogeneous, and comply with the requirements in Table 302.3.3.1.(a) Polymer Modified Asphalt Requirements.

Table 302.3.3.1.(a) Polymer Modified Asphalt Requirements

Property	Test Method, Test Parameters	Value According to Grade	
		AC-5 + 2% Polymer Solids	AC-10 + 2% Polymer Solids
Minimum SBR Content	Tex-533-C Determining Polymer Additive Percentages in Polymer Modified Asphalt Cements, IR Determination ¹	2.0% Solids By Wt.	2.0% Solids By Wt.
Penetration	AASHTO T49, 100-G, 5-Sec, 77°F	120 Min	80 Min
Minimum Viscosity	AASHTO T202, 140°F	700-Poise	1300-Poise
Maximum Viscosity	AASHTO T202, 275°F	7.0-Poise	8.0-Poise
Ductility	AASHTO T51, 39.2°F, 5-cm/Min	70-cm, Min	60-cm, Min
Separation of Polymer	Tex-540-C Measurement of Polymer Separation on Heating in Modified Asphalt Systems, After 48-Hrs. at 325°F	None	None

1. The asphalt supplier shall furnish the OWNER samples of the asphalt cement and polymer emulsion used in making the finished product.

302.3.3.1.1. Polymer Additive Properties.

The polymer additive shall be an emulsion of styrenebutadiene low-temperature copolymer in water. The emulsion shall have good storage stability and possess the properties in Table 302.3.3.1.1.(a) Polymer Additive Requirements.

Table 302.3.3.1.1.(a) Polymer Additive Requirements

Property	Value
Monomer Ratio of Polymer (butadiene to styrene)	73 ± 5 27 ± 5
Minimum Solids Content (percent by weight)	45
Viscosity of Emulsion at $77 \pm 1^\circ\text{F}$, cps, max (No.3 spindle, 20-rpm, Brookfield RVT Viscometer)	2000

302.3.4. Emulsified Asphalt. Emulsified asphalt shall be composed of a paving asphalt base uniformly emulsified with water. It shall be homogeneous throughout and, when stored, shall show no separation within 30-days after delivery. Emulsified asphalt shall meet the requirements for the specified type and grade shown in Tables 302.3.4.(a) through (d).

302.3.4.1. Testing Requirements. Test reports and certification shall be made for emulsified asphalt in accordance with [Item 302.3.1.1](#). Tests and Certification of Bituminous Materials.

302.3.4.2. Temperature. Emulsified asphalt may be reheated, but at no time after loading for transportation from refinery to the purchaser shall the temperature of the emulsion be raised above 160°F . During reheating, the emulsified asphalt shall be agitated to prevent localized overheating. Emulsified asphalt shall not be permitted to cool to a temperature of less than 40°F . Unless otherwise specified, emulsified asphalt shall be applied at a temperature within the limits specified in Table 302.5.(a) Requirements for Storage, Heating and Application Temperature. CONTRACTOR shall furnish and keep on the site an accurate thermometer suitable for determining the temperature of the emulsified asphalt.

Table 302.3.4.(a) Tests and Properties of Anionic Emulsions

Property	Rapid Setting				Medium Setting		Slow Setting			
	Type - Grade									
	RS-2		RS-2h		MS-2		SS-1		SS-1h	
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol at 77°F, sec	-	-	-	-	-	-	20	100	20	100
at 122°F, sec	150	400	150	400	100	300	-	-	-	-
Sieve Test, %	-	0.10	-	0.10	-	0.10	-	0.10	-	0.10
Miscibility (Standard Test)	-	-	-	-	-	-	Passing		Passing	
Cement Mixing, %	-	-	-	-	-	-	-	2.0	-	2.0
Demulsibility, 35-ml of 0.02 N CaCl ₂ , %	60	-	60	-	-	30	-	-	-	-
Storage Stability, 1-day, %	-	1	-	1	-	1	-	1	-	1
Freezing Test, 3 cycles ¹	-	-	-	-	Passing		Passing		Passing	
Distillation Test:										
Residue by Distillation, % by weight	65	-	65	-	65	-	60	-	60	-
Oil Distillate, % by volume of emulsion	-	½	-	½	-	½	-	½	-	½
Tests on Residue from Distillation:										
Penetration at 77°F, 100 g, 5 sec	120	160	80	110	120	160	120	160	70	100
Solubility in Trichloroethylene, %	97.5	-	97.5	-	97.5	-	97.5	-	97.5	-
Ductility at 77°F, 5 cm/min, cm	100	-	80	-	100	--	100	-	80	-

1. Applies only when the Engineer designates material for winter use.

Table 302.3.4.(b) Tests and Properties of High Float Anionic Emulsions

Property	Rapid Setting		Medium Setting	
	Type - Grade			
	HFRS-2		AES-300	
	Min	Max	Min	Max
Viscosity, Saybolt Furol at 77°F, sec	-	-	75	400
at 122°F, sec	150	400	-	-
Sieve Test, %	-	0.10	-	0.10
Coating Ability and Water Resistance:				
Coating, dry aggregate	-	-		good
Coating, after spraying	-	-		fair
Coating, wet aggregate	-	-		fair
Coating, after spraying	-	-		fair
Demulsibility 35-ml of 0.02 N CaCl ₂ , %	50	-	-	-
Storage Stability Test, 1-day, %	-	1	-	1
Distillation Test:				
Residue by Distillation, % by weight	65	-	65	-
Oil Distillate, by volume of emulsion, %	-	1/2	-	5
Tests on Residue from Distillation:				
Penetration at 77°F, 100 g, 5 sec	100	140	300	-
Solubility in Trichloroethylene, %	97.5	-	97.5	-
Ductility at 77°F, 5 cm/min, cm	100	-	-	-
Float Test at 140°F, sec	1200	-	1200	-

Table 302.3.4.(c) Tests and Properties of Cationic Emulsions

Property	Rapid Setting				Medium Setting				Slow Setting			
	Type - Grade											
	CRS-2		CRS-2h		CMS-2		CMS-2s		CSS-1		CSS-1h	
	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max	Min	Max
Viscosity, Saybolt Furol at 77°F, sec	-	-	-	-	-	-	-	-	20	100	20	100
at 122°F, sec	150	400	150	400	100	300	100	300	-	-	-	-
Sieve Test, %	-	0.10	-	0.10	-	0.10	-	0.10	-	0.10	-	0.10
Cement Mixing, %	-	-	-	-	-	-	-	-	-	2.0	-	2.0
Demulsibility, 35 ml 0.8 percent sodium dioctyl sulfosuccinate, %	40	-	40	-	-	-	-	-	-	-	-	-
Storage Stability, 1 day, %	-	1	-	1	-	1	-	1	-	1	-	1
Coating Ability and Water Resistance:												
Coating, dry aggregate	-	-	-	-	good		good		-	-	-	-
Coating, after spraying	-	-	-	-	fair		fair		-	-	-	-
Coating, wet aggregate	-	-	-	-	fair		fair		-	-	-	-
Coating, after spraying	-	-	-	-	fair		fair		-	-	-	-
Particle Charge Test	positive		positive		positive		positive		positive		positive	
Distillation Test:												
Residue by Distillation, % by wt	65	-	65	-	65	-	65	-	60	-	60	-
Oil Distillate, % by volume of Emulsion	-	½	-	½	-	7	-	5	-	½	-	½
Tests on Residue from Distillation:												
Penetration at 77°F, 100-g, 5-sec	120	160	80	110	120	200	300	-	120	160	80	110
Solubility in Trichloroethylene, %	97.5	-	97.5	-	97.5	-	97.5	-	97.5	-	97.5	-
Ductility at 77° F, 5 cm/min, cm	100	-	80	-	100	-	-	-	100	-	80	-

Table 302.3.4.(d) Tests and Properties of Polymer Modified Emulsions

Property	High Float Anionic Rapid Setting		Cationic Rapid Setting	
	Type - Grade			
	HFRS-2P		CRS-2P	
	Min	Max	Min	Max
Polymer Content, percent by weight of the distillation residue ¹	3.0	-	3.0	-
Viscosity, Saybolt Furol at 122°F, sec	150	400	150	400
Storage Stability Test, 1-day, %	-	1	-	1
Demulsibility, 35-ml of 0.02 N CaCl ₂ , %	40	-	-	-
Demulsibility, 35-ml 0.8-percent sodium dioctyl sulfosuccinate, %	-	-	40	-
Sieve Test, %	-	0.10	-	0.10
Particle Charge Test	-		Positive	
Distillation Test: ²				
Oil distillate, by volume of emulsion, %	-	½	-	½
Residue, % by wt	65	-	65	-
Tests on Residue from Distillation:				
Float Value at 140°F, sec	1200	-	-	-
Penetration, 77°F, 100-g, 5-sec	100	140	110	150
Ductility, 39.2°F, 5-cm/min, cm	50	-	50	-
Viscosity at 140°F, poises	1500	-	1300	-
Solubility in Trichloroethylene, %	97	-	97	-

1. The CONTRACTOR shall provide the OWNER samples of the asphalt cement and polymer used in making the finished emulsion with a certified statement from the Emulsion Supplier stating that the provided asphalt cement and polymer used in the finished product are the same as provided.

2. The temperature on the lower thermometer shall be brought slowly to 350°F plus or minus 10°F and maintained at this temperature for 20-minutes. The total distillation shall be completed in 60-minutes plus or minus 5-minutes from the first application of heat.

302.3.5. Emulsions for Priming, Curing and Erosion Control (PCE).

302.3.5.1. General Use Emulsions. The emulsion shall be a slow curing anionic or cationic emulsion of a petroleum based material in water. The supplier must state whether the material supplied is cationic or anionic. Such emulsions may be used for priming of base materials, curing seal for stabilized base materials, and erosion control applications such as dust control, soil surface stabilization, or mulch binder.

Emulsion properties shall fall within the ranges as shown in Table 302.3.5.1.(a) Tests and Properties of PCE (General Use) Emulsions. The base emulsion material may be diluted with water to achieve the desired concentration of residual with maximum dilution rates as indicated in Table 302.3.5.1.(b) Maximum Dilution Rate.

Table 302.3.5.1.(a) Tests and Properties of PCE (General Use) Emulsions

Property	Test Methods, Test Parameters	Minimum	Maximum
Viscosity	Saybolt Furol, 25°C	10-seconds	100-seconds
Sieve Test	Sieve Test	-	0.1%
Miscibility	ASTM D244 Emulsified Asphalts, modified ¹	Passing	-
Residue by Evaporation	ASTM D244, modified ²	60% by weight	-
Tests on Residue from Evaporation	Flash Point, C.O.C. Kinematic Viscosity, 60°C	200°C 100-cSt	- 350-cSt

1. Except the dilution shall use 350-ml of distilled or deionized water and a 100-ml beaker.

2. Except the sample shall remain in the oven until foaming ceases, then cooled and weighed.

Table 302.3.5.1.(b) Maximum Dilution Rate

Use	Maximum Dilution Rate
Priming of Base Materials	(1) part PCE to (3) parts water
Curing Seal	(1) part PCE to (3) parts water
Erosion Control	(1) part PCE to (7) parts water

302.3.5.2. Emulsions Specifically for Priming and Curing. Product shall be a water-based emulsion composed of petroleum of resin oil base with selective hardening and drying agents to form a road prime and sealer. Emulsions may be provided either concentrated or pre-diluted. Concentrated prime and/or road sealing emulsions specified in this [Item 302.3.5.2](#). Emulsions Specifically for Priming and Curing shall meet the requirements of Table 302.3.5.2.(a) Requirements for MCS-600-C – Concentrated. Diluted prime and/or road sealing emulsions specified in this [Item 302.3.5.2](#). Emulsions Specifically for Priming and Curing shall meet the requirements of Table 302.3.5.2.(b) Requirements for MCS-600-D – Dilute.

Table 302.3.5.2.(a) Requirements for MCS-600-C – Concentrated

Property	Test Methods, Test Parameters	Required Value	
		Minimum	Maximum
Appearance	Visual Inspection	Brown Liquid	
Viscosity S.F. at 77°F Sec	ASTM D244 Emulsified Asphalts	15	200
Residue, % min	ASTM D244, modified ¹	56	65
Miscibility Test	ASTM D244, modified ²	No coagulation	
Moisture, wt %		-	48
Volatile %		35	-
% Non-Volatile Soluble in Trichloroethylene	AASHTO T 45-56	-	6
Accelerated Weathering (2-year exposure)	Federal Spec TT C-555 B, 40 ml	No material deterioration after exposure	
Resistance To wind and Driven Rain (@ 98 mph)	Federal Spec TT C-555 B, As 4ml sealer after cure	Passes/no wt. gain	
Ash, % wt.		-	8
Polymer, % wt.		-	4
Freeze Test (Concentrated Form)	3-cycle	Pass	
Particle Charge	ASTM D244	Positive	
Shaker Test 2- to 4-hrs.	Mix Burrell Wrist Action Shaker Model 75 set on Level 7, diluted 1 part water to 4 parts road prime, Sieve #40	-	1%

1. ASTM D244 Modified Evaporation Test for percent of residue is made by heating 50-gram sample to 300°F until foaming ceases, then cool immediately and calculate results.

2. Test procedure identical with ASTM D244, except that 0.02 Normal Calcium Chloride solution shall be used in place of distilled water.

Table 302.3.5.2.(b) Requirements for MCS-600-D – Dilute

Property	Test Methods, Test Parameters	Required Value	
		Minimum	Maximum
Appearance	Visual Inspection	Brown Liquid	
Viscosity S.F. at 77°F Sec	ASTM D244 Emulsified Asphalts	5	70
Residue, % min	ASTM D244, modified ¹	10	20
Miscibility Test	ASTM D244, modified ²	No coagulation	
Moisture, wt %		-	90
Volatile %		90	-
% Non-Volatile Soluble in Trichloroethylene	AASHTO T 45-56	0	2
Accelerated Weathering (2-year exposure)	Federal Spec TT C-555 B, 40 ml	No material deterioration after exposure	
Resistance To wind and Driven Rain (@ 98 mph)	Federal Spec TT C-555 B, As 4ml sealer after cure	Passes/no wt. gain	
Ash, % wt.		-	2
Polymer, % wt.		-	1
Freeze Test (Concentrated Form)	3-cycle	Pass	
Particle Charge	ASTM D244	Positive	
Shaker Test 2- to 4-hrs. (non-diluted)	Mix Burrell Wrist Action Shaker Model 75 set on Level 7, Sieve #40	-	1%

1. ASTM D244 Modified Evaporation Test for percent of residue is made by heating 100-gram sample to 300°F until foaming ceases, then cool immediately and calculate results.

2. Test procedure identical with ASTM D244, except that 0.02 Normal Calcium Chloride solution shall be used in place of distilled water.

302.3.6. Specialty Emulsions. Specialty emulsions shall be slow setting emulsions of a petroleum-based material in water. Specialty emulsions may be used for purposes such as tack coat, fog seals, priming base materials, curing seal for stabilized base materials, recycled/reclaimed asphalt pavement (RAP) rejuvenator, repairing surface deficiencies, and erosion control applications. Specialty emulsions are classified as either Restorative Seal or Maltene Rejuvenator and shall meet the requirements for the specified type shown in Table 302.3.6.(a) Requirements for Restorative Seal or Table 302.3.6.(b) Requirement for Maltene Rejuvenator, respectively. Specialty emulsions shall be freeze stabilized and if freezing has occurred a homogeneous mixture shall be obtained when the material has thawed and been thoroughly mixed.

Table 302.3.6.(a) Requirements for Restorative Seal

Properties	Test Methods	Requirements
Test on Emulsion		
Viscosity @77°F, SES	ASTM D244 Emulsified Asphalts	25 - 150
Sieve Test, % by Wt.	ASTM D244, modified ¹	0.1 Max.
Particle Charge Test	ASTM D244	Positive
Cement Mixing Test, % by Wt.	ASTM D244	2.0 Max.
Pumping Stability	See Note 2.	Pass
5-day Settlement Test, % by Wt.	ASTM D244	5.0 Max.
Residue, % Wt.	ASTM D244, modified ³	64 Min.
Test on Residue from Distillation		
Viscosity @ 140°F, cSt	ASTM D2170 Kinematic Viscosity of Asphalts (Bitumens)	1,000 – 4,000
Maltene Distribution Ratio ⁴	ASTM D2006-70 Method of Test for Characteristic Groups in Rubber Extender and Processing Oils by the Precipitation Method (Discontinued 1975)	0.7 – 1.1
PC/S Ratio ⁴	ASTM D2006-70	0.5 Min.
Asphaltenes, % Wt.	ASTM D2006-70	11.00 Max.

1. Test procedure identical with ASTM D244 except that distilled water shall be used in place of two-percent sodium oleate solution.

2. Pumping stability is determined by charging 15-ounces (450-ml) of emulsion into 30-ounce (one-liter) beaker and circulating the emulsion through a gear pump (Roper 29.B22621) having ¼" inlet and outlet. The emulsion passes if there is not significant oil separation after circulating ten-minutes.

3. ASTM D244 Evaporation Test for percent of residue is modified by heating 2-ounces (50-gram) sample to 300°F until foaming ceases, then cooling immediately and calculating results.

4. In the Maltene Distribution Ratio Test by ASTM Method D2006-70:

$$(PC + A_1) \div (S + A_2)$$

PC=Polar Compounds

A₁=First Acidaffins

A₂= Second Acidaffins

S= Saturated Hydrocarbons

Table 302.3.6.(b) Requirement for Maltene Rejuvenator

Properties	Test Methods		Requirements	
	ASTM	AASHTO	Min.	Max.
Test on Emulsion				
Viscosity @77°F, SES	D244 Emulsified Asphalts	T-59	15	40
Residue, % Wt.	D244 (Mod) ¹	T-59 (Mod)	60	65
Miscibility Test	D244 (Mod) ²	T-59 (Mod)	No Coagulation	
Sieve Test, % by Wt.	D244 (Mod) ³	T-59 (Mod)	-	0.1
Particle Charge Test	D244	T-59	Positive	
Percent Light Transmittance	See Note 4.		-	30
Test on Residue from Distillation				
Flash Point, COC, °F	D92 Flash and Fire Points by Cleveland Open Cup	T-48	385	-
Viscosity @ 140°F, cSt	D445 Kinematic Viscosity of Transparent and Opaque Liquids (the Calculation of Dynamic Viscosity)	-	100	200
Asphaltenes, % Wt.	D2006-70 Method of Test for Characteristic Groups in Rubber Extender and Processing Oils by the Precipitation Method (Discontinued 1975)	-	-	1.0
Maltene Distribution Ratio ⁵	D2006-70		0.3	0.6
PC/S Ratio ⁵	D2006-70	-	0.5	-
Saturated Hydrocarbons, S ⁵	D2006-70	-	21	28

1. ASTM D244 Modified Evaporation Test for percent of residue is made by heating 2-ounces sample to 300°F until foaming ceases, then cool immediately and calculate results.

2. Test procedure identical with ASTM D244 except that 0.02 Normal Calcium Chloride solution shall be used in place of distilled water.

3. Test procedure identical with ASTM D244 except that distilled water shall be used in place of two-percent sodium oleate solution.

4. Test according to Attachment "Standard Procedure for Determining Percent Light Transmittance of Maltene Rejuvenator, Restorative Seal, and PCE Material" in TxDOT Special Provision to Item 300 for Maltene Rejuvenator (Waco District).

5. Chemical composition by ASTM Method D2006-70:

$$(PC + A_1) \div (S + A_2)$$

PC=Polar Compounds A₁=First Acidaffins

A₂= Second Acidaffins S= Saturated Hydrocarbons

302.3.7. Emulsion for In-Place Asphalt Recycling. Emulsion shall be designed to be a recycling agent to be mixed at ambient temperature with existing in-place asphalt, native or selective material and or Recycled Asphalt Pavement (RAP) material. Product shall be a water miscible emulsion. Asphaltene, Resins, Cyclics, Saturates content must be specifically formulated based on laboratory data of existing material in relation to rejuvenation demand and any added RAP material. Product shall meet minimums and fall within the ranges specified in Table 302.3.7.(a) Emulsion Requirements for In-Place Asphalt Recycling.

Table 302.3.7.(a) Emulsion Requirements for In-Place Asphalt Recycling

Properties	Test Methods, Test Parameters	Requirements	
		Min.	Max.
Test on Emulsion			
Viscosity	Saybolt Furol, 122°F	-	185
Sieve %		-	1.0
Particle Charge		Positive	
Specific Gravity @ 77°F	ASTM D244	0.910	1.16
Cement Mixing Test		Passing	
Distillation			
Residue; % from Distillation @ 325°F		60	68
Test on Residue from Distillation			
Penetration, 77°F Extrapolation function		1400	-
Asphaltene, %		3.1	10.1
Resins, % wt.		1.2	8.9
Cyclics		65.0	95.0
Saturates		2.8	18.3
Flash Point C.O.C.		400°F	-

302.4. SECTION HELD FOR FUTURE USE**302.5. STORAGE, HEATING AND APPLICATION TEMPERATURE OF BITUMINOUS MATERIALS**

Asphalt materials should be applied at the temperature that provides proper and uniform distribution. Within practical limits, higher temperatures than necessary should be avoided. Satisfactory application should be obtained within the recommended ranges shown in Table 302.5.(a) Requirements for Storage, Heating and Application Temperature. No material shall be heated above the maximum temperature shown. Performance graded asphalt binders containing particulate or polymer modifiers may be susceptible to separation of the modifier. Appropriate circulation or agitation in storage shall be provided if separation of the modifier is expected or suspected, and in every case when the modified binder will be stored at elevated temperatures for more than one day before use.

WARNING TO CONTRACTOR: Attention is called to the fact that asphaltic materials are highly flammable. Heating of asphaltic materials constitutes a fire hazard to various degrees. The utmost care shall be taken to prevent open flames of any kind from coming in contact with the asphaltic material or the gases of same. Proper precautions should be used in all cases. The CONTRACTOR shall be responsible for any fires or accidents which may result from heating the asphaltic materials.

Binder or modifier supplier instructions regarding recommended application and storage temperatures shall supersede the guidelines below.

Table 302.5.(a) Requirements for Storage, Heating and Application Temperature

Material Type-Grade	Application and Mixing		Heating and Storage
	Recommended Range °F	Maximum Allowable °F	Maximum °F
All PG Binders	275-375	375	400
AC-3, 5, 10, 20	275-325	350	400
Emulsions			
SS-1, SS-1h, SS-1P, CSS-1h	50-130	140	140
RS-2, RS-2h, MS-2, CRS2h, CRS-2P, CMS-2, CMS-2s, HFRS-2, HFRS-2P, AES-300	110-160	170	170
PCE, Restorative Seal or Maltene Rejuvenator	Ambient = 72-130	140	140

302.6. EMULSIFIED ASPHALT TREATMENT

302.6.1. Description. Emulsified asphalt treatment shall consist of one or more applications of a mixture of emulsified asphalt of the proportion and type specified on the plans and water. The mixture shall be applied at the rate specified on the plans. It is to be used as a base treatment, earthwork seal, prime coat or dust preventative. This mixture may be applied to the base course, subgrade, shoulders or detours at the locations and to the extent shown on plans or as directed by the OWNER.

302.6.2. Materials. The amount of emulsified asphalt in the mixture, expressed as a percent by volume of the total mixture, shall be within the limits specified on the plans. When tested by approved laboratory methods, the emulsified asphalt used shall meet the requirements of [Item 302.3.4](#), Emulsified Asphalt or [Item 302.3.5](#), Emulsions for Priming, Curing, and Erosion Control (PCE) or [Item 302.3.6](#), Specialty Emulsions.

The water used shall be clear, free from industrial wastes and other objectionable matter.

302.6.3. Construction Methods. Asphalt materials shall be handled in accordance with [Item 302.5](#), Storage, Heating and Application Temperature of Bituminous Materials.

The emulsified asphalt and water mixture shall be applied by a self-propelled sprinkler meeting the requirements of [Item 203.6](#), Dust Control so operated as to uniformly distribute the mixture in the quantity determined by the OWNER.

The emulsion and water may be mixed in the sprinkler tank. The CONTRACTOR shall make suitable provisions for agitating the two materials sufficiently to produce a uniform blend. The sprinkler tank shall have been recently calibrated, and the OWNER shall be furnished an accurate and satisfactory record of such calibration. After beginning the work, should the yield on the emulsion applied appear to be in error, the distributor shall be recalibrated in a manner satisfactory to the OWNER, before proceeding with the work.

302.6.4. Measurement and Payment. Emulsified asphalt shall be measured by the gallon prior to mixing with water. The work performed and the emulsified asphalt furnished as prescribed by this Item and measured as provided in this Item shall be paid for at the unit price bid of the type specified, which price shall be full compensation for furnishing all required materials including mixing water for application; all freight involved; all hauling, mixing, and distributing the mixture as specified; and all manipulation, labor, tools, equipment and incidentals necessary to complete the work.

302.7. PRIME COAT

302.7.1. Description. This Item shall consist of application of asphaltic materials on the completed base course and/or other approved area, which shall be applied in accordance with these specifications and as shown of the plans.

302.7.2. Materials. The asphaltic material used for the prime coat shall be of the type and grade as stated in the contract and when tested by approved laboratory methods shall meet the requirements of [Item 302.3.4](#), Emulsified Asphalt or [Item 302.3.5](#), Emulsions for Priming, Curing, and Erosion Control (PCE) or [Item 302.3.6](#), Specialty Emulsions.

302.7.3. Equipment. All storage tanks, piping, retorts, booster tanks and distributors used in storing and handling asphaltic material shall be kept clean and in good condition at all times. Equipment shall be operated in such a manner that there shall be no contamination of the asphaltic material with foreign material. It shall be the responsibility of the CONTRACTOR to provide and maintain in good working order a recording thermometer at the storage heating unit at all times. The distributor shall have been recently calibrated and the OWNER shall be furnished an accurate and satisfactory record of such calibration. After beginning the work, should the yield on the asphaltic material applied appear to be in error, the distributor shall be recalibrated in a manner satisfactory to the OWNER before proceeding with the work.

302.7.4. Construction Methods. Asphalt materials shall be handled in accordance with [Item 302.5](#). Storage, Heating and Application Temperature of Bituminous Materials.

Prime coat shall not be applied when the air temperature is below 50°F and falling, but it may be applied when the air temperature is above 40°F and rising, the air temperature being taken in the shade and away from artificial heat. Asphaltic material shall not be placed when general weather conditions, in the opinion of the OWNER, are not suitable.

When, in the opinion of the OWNER, the base is thoroughly dry and is satisfactory to receive the prime coat, the surface shall be cleaned by sweeping or other methods approved by the OWNER. The asphaltic material shall be applied to the cleaned base at the approximate rate of 0.15- to 0.25-gallons-per-square-yard of surface area. The application shall be made with an approved type of self-propelled pressure distributor so constructed and operated as to distribute the material evenly and smoothly in the quantity specified or directed. The CONTRACTOR shall provide all necessary facilities for determining the temperature of the asphaltic material in all of the heating equipment and in the distribution, for determining the rate at which it is applied, and for securing uniformity at the junction of two distributor loads.

The OWNER shall select the temperature of application within the limits recommended in [Item 302.5](#). Storage, Heating and Application Temperature of Bituminous Materials based on the temperature-viscosity relationship that shall permit application of the asphalt. The CONTRACTOR shall apply the asphalt at a temperature within 15°F of the temperature selected.

No traffic, hauling or placing of subsequent courses shall be permitted over the freshly applied prime coat until authorized by the OWNER.

The CONTRACTOR shall be responsible for the maintenance of the surface until the work is accepted by the OWNER.

302.7.5. Measurement and Payment. The asphaltic material for prime coat will be measured at the point of delivery on the road in gallons at the applied temperature. The quantity to be measured for payment shall be the number of gallons used, as directed, of the specified prime coat.

The work performed and materials furnished in accordance with this Item and measured as provided will be paid for at the unit prices bid for "Asphaltic Material," of the type and grade specified. Price shall be full compensation for cleaning the area to be primed; for furnishing, preparing, hauling and placing all required materials; for all freight and heating involved; for spreading, dragging, brooming, finishing and maintaining under traffic until accepted; and for all manipulation, labor, tools, equipment and incidentals necessary to complete the work.

302.8. ASPHALT BASE COURSE

302.8.1. Description. Asphalt base course shall consist of a compact mixture of mineral aggregates and asphaltic material mixed hot in a mixing plant. It may be a base course, subbase course, or foundation course. It is made of larger aggregate than Hot-Mix Coarse Base (A) as shown in Table 302.9.3.(a) Dense Graded Hot Mix Master Grading.

302.8.2. Materials.

302.8.2.1. Asphaltic Cement. Asphalt for the mixture shall be of the types of asphalt cement as determined by the OWNER and shall meet the requirements of [Item 302.3.2](#). Performance-Graded (PG) Asphalt Binders or [Item 302.3.3](#). Asphalt Cement. The grade of asphalt to be used shall be determined by the OWNER after design tests have been made using the mineral aggregate approved for use in the construction. If more than one type of asphaltic cement mixture is specified for the project, only one grade of asphalt shall be required for all types of mixture unless otherwise shown on the plans. The

CONTRACTOR shall notify the OWNER of the source of asphaltic material prior to production of the asphaltic mixture, and this source shall not be changed during the course of the project, except by written permission of the OWNER.

302.8.2.2. Tack Coat. The liquid asphalt material used for tack coat should be MS-2 or SS-1 in [Item 302.3.4](#). Emulsified Asphalt, Restorative Seal in [Item 302.3.6](#). Specialty Emulsions or one of the other various grades of materials (selected by the OWNER) listed under [Item 302.3.4](#). Emulsified Asphalt.

302.8.2.3. Mineral Aggregate. The material shall be crushed and screened as necessary to meet the requirements hereinafter specified and shall consist of durable coarse aggregate particles mixed with approved binding materials.

Unless otherwise specified, the grading of the mineral aggregate shall conform to the limitations as shown in Table 302.8.2.3.(a) Asphalt Base Course Aggregate Grades.

Table 302.8.2.3.(a) Asphalt Base Course Aggregate Grades

Sieve Size	Grade			
	1	2	3	4
1 ³ / ₄ -inch		100.0	100.0	As Shown on Plans
1 ¹ / ₂ -inch	100.0	90.0-100.0		
1-inch	90.0-100.0			
³ / ₈ -in.	45.0-70.0			
No. 4	30.0-55.0	25.0-55.0		
No. 40	15.0-30.0	15.0-40.0	15.0-40.0	

Testing of the mineral aggregate shall be in accordance with the test methods in Table 302.8.2.3.(b) Aggregate Tests.

Table 302.8.2.3.(b) Aggregate Tests

Property	Test
Preparation of Soil Constants	Tex-101-E Preparing Soil and Flexible Base Materials for Testing
Liquid Limit	ASTM D4318 Liquid Limit, Plastic Limit, and Plasticity Index of Soils
Plastic Limit	ASTM D4318 Liquid Limit, Plastic Limit, and Plasticity Index of Soils
Plasticity Index	ASTM D4318 Liquid Limit, Plastic Limit, and Plasticity Index of Soils
Sieve Analysis	ASTM C136 Sieve Analysis of Fine and Coarse Aggregates
Wet Ball Mill	Tex-116-E Ball Mill Method for Determining the Disintegration of Flexible Base Material
Sand Equivalent	ASTM D2419 Sand Equivalent Value of Soils and Fine Aggregate

Unless otherwise specified on the plans, the mineral aggregate for Grades 1, 2 and 3 shall meet the limits of Table 302.8.2.3.(c) Aggregate Physical Requirements. Mineral aggregate for Grade 4 shall meet the physical requirements shown on the plans.

Table 302.8.2.3.(c) Aggregate Physical Requirements

Property	Limit
Wet Ball Mill	50 Max.
Plasticity Index	15 Max.
Liquid Limit	40 Max.
Sand equivalent	≥ 40

302.8.3. Construction Methods. Asphalt materials shall be handled in accordance with [Item 302.5](#). Storage, Heating and Application Temperature of Bituminous Materials.

Mixing plants may be either the weight-batching type plant, the continuous mixing type plant, or the drum mixing type plant as described in [Item 302.9.5](#). Mixing Plants except that requirements for Type “B” and “D” mixtures of fine graded surface course are deleted.

Equipment for storage, weighing and heating of materials shall be as described in [Item 302.9.4](#). Equipment.

The OWNER shall designate the asphalt content to be used in the mixture after design tests have been made with the aggregates to be used in the project. When tests as determined by the OWNER are made, samples of the mixture shall not vary from the asphalt content designated by the OWNER by more than 0.5-percent dry weight (based on total mixture). The asphaltic material will form typically 4- to 9-percent of the mixture by weight.

The mixture shall consist of a uniform mixture of mineral aggregates and asphaltic material.

The asphaltic mixtures for the weight-batching type plant and from the continuous mixing type plant, when tested in accordance with the current methods outlined in TxDOT Test Method Tex-208-F Test for Stabilometer Value of Bituminous Mixtures (Part I or Part III as applicable), shall have laboratory density and stability as indicated in Table 302.8.3.(a) Stability of Asphalt Base Course. If the mixture produced does not have the specified qualities, the mixture shall be changed until it conforms to the specified qualities.

Table 302.8.3.(a) Stability of Asphalt Base Course

Property	Value
Density (%)	96 ±2
Stability (%) Hveem Stabilometer	Not less than 40 except when otherwise shown on the plans

302.8.4. Measurement and Payment. Asphalt base course shall be measured and paid for in accordance with [Item 302.10](#). Measurement and Payment.

302.9. HOT-MIX ASPHALT PAVEMENT

302.9.1. Description. This Item shall govern pavement consisting of a binder course, a leveling up course, a surface course or any combination of these courses as shown on the plans. Each course shall be composed of a compacted mixture of mineral aggregate and asphaltic material mixed hot in a mixing plant; and shall be constructed on the previously completed and approved subgrade, subbase course, base course, existing pavement, or in the case of a bridge, on the prepared floor slab, all in accordance with these specifications and in conformity with the lines, grades, quantities and typical sections as stated in the contract, plans and/or established in the field by the OWNER.

302.9.2. Materials. The materials proposed to be used may be inspected and tested at any time during the preparation of the work.

302.9.2.1. Aggregates. Mineral aggregates shall consist of a fine aggregate, coarse aggregate and, when required, a mineral filler all in accordance with [Item 302.2](#). Aggregates for Hot-Mix Asphalt Pavement and approved by the OWNER. Representative samples of the materials proposed to be used in the mixture shall be submitted for tests in the quantities required by the OWNER. No material that has in any way become unfit for use after approval shall be used in the work. Approval of both the materials and sources of supply must be obtained from the OWNER prior to delivery of the material.

302.9.2.2. Asphaltic Materials. Material shall conform to the applicable paragraphs of [Item 302.3](#). Bituminous Materials. Only one grade of asphalt shall be required for all the types of mixtures unless otherwise shown on the plans or required by the OWNER.

302.9.2.2.1. Paving Mixture. Asphaltic materials for the paving mixture shall be the type and grade specified, shown on the plans, or as designated by the OWNER after design tests have been made, using the mineral aggregates proposed to be used in the mixture, and shall meet the requirements of [Item 302.3.2](#). Performance Graded (PG) Asphalt Binders or [Item 302.3.3](#). Asphalt Cement. If more than one type of asphaltic pavement mixture is specified for the project, only one grade of asphalt

shall be required for all types of mixtures, unless otherwise shown on the plans. The CONTRACTOR shall notify the OWNER of the source of asphaltic material prior to production of the asphaltic mixture and prior to the paving of this course of the project except on written permission of the OWNER.

302.9.2.2.2. Prime Coat. Prime coat shall conform to the provisions of [Item 302.7](#). Prime Coat.

302.9.2.2.3. Track Coat. The liquid asphalt material used for tack coat should be MS-2 or SS-1 in [Item 302.3.4](#). Emulsified Asphalt, restorative seal in [Item 302.3.6](#). Specialty Emulsions or one of the other various grades of materials (selected by the OWNER) listed under [Item 302.3.4](#). Emulsified Asphalt.

302.9.3. Paving Mixture. The paving mixture shall consist of a uniform mixture of coarse aggregate, fine aggregate, mineral filler, when required, and asphaltic material, accurately proportioned by weight. The grading of each constituent shall be such as to produce, when properly proportioned, a mixture conforming to the following limitations for grading the type specified. The exact proportions of each constituent producing the total aggregate within these limits shall be as directed by the OWNER, and when tested by standard laboratory methods, the mixture shall meet the requirements listed in Tables 302.9.3.(a) through (f). The OWNER shall specify or approve a mixture within the specified limits for all types of mixtures, which shall be suitable for the work in which the asphaltic pavement shall be used. The percentages of asphalt shall not vary more than 0.4-percent from the proportions established by the OWNER.

Table 302.9.3.(a) Dense Graded Hot Mix¹ Master Grading

Sieve Size	Type of Mixture						
	A Coarse Base	B Fine Base	C Coarse Surface	D Fine Surface	F Fine Mixture	CMHB – C Coarse Surface	CMHB – F Fine Surface
	Percent Passing by Weight						
1½"	100						
1¼"	95-100						
1"		100					
¾"	70-90	95-100	100			98 – 100	
⅝"		75-95	95-100			95 – 100	
½"	50-70			100			98 – 100
⅜"		60-80	70-85	85-100	100	50-70	85 - 100
¼"					95-100		
No. 4	30-50	40-60	43-63	50-70		30 - 45	40 - 60
No. 10	20-34	27-40	30-40	32-42	32-42	15 - 25	15 - 25
No. 40	5-20	10-25	10-25	11-26	9-24	6 – 20	6 – 20
No. 80	2-12	3-13	3-13	4-14	3-13	6 – 18	6 – 18
No. 200	2 - 8	2 - 8	2 - 8	2 - 8	2 - 8	5 - 8	5 - 8
VMA % minimum	11	12	13	14	15	14	15

1. These mixtures shall be designed using a Texas Gyratory Compactor (TGC) and in accordance with Test Method Tex-204-F Design of Bituminous Mixtures. Design must be researched and based on intended use.

Table 302.9.3.(b) Superpave Hot Mix¹ Master Grading

Sieve Size, inches (centimeters)	Nominal Maximum Aggregate Size, inches (centimeters)				
	1½ (3.81)	1 (2.54)	¾ (1.90)	½ (1.27)	⅜ (0.95)
	Coarse Base	Fine Base	Coarse Surface	Fine Surface	Fine Mixture
Percent Passing By Weight					
2 (5.08)	100.0				
1½ (3.81)	90.0 – 100.0	100.0			
1 (2.54)		90.0 – 100.0	100.0		
¾ (1.90)			90.0 – 100.0	100.0	
½ (1.27)				90.0 – 100.0	100.0
⅜ (0.95)					90.0 – 100.0
No. 4					
No. 8	15.0 - 41.0	19.0 – 45.0	23.0 - 49.0	28.0 – 58.0	32.0 – 67.0
No. 16					
No. 30					
No. 50					
No. 100					
No. 200	0.0–6.0	1.0 – 7.0	2.8 - 8.0	2.0 - 10.0	2.0 – 10.0
VMA % minimum	11	12	13	14	15

1. These mixtures shall be designed using a Superpave Gyratory Compactor (SGC) and in accordance with the AASHTO Standard Practice for Designing Superpave Hot Mix Asphalt (PP28-99). Design must be researched and based on intended use.

Table 302.9.3.(c) Superpave – Plant Produced Mixture Requirements

VMA (MIN)	VFA	Dust/Asphalt Ratio
11.0%	64 – 77 %	0.6 – 1.8 %
12.0%	67 – 77 %	0.6 – 1.6 %
13.0%	69 – 80 %	0.6 – 1.6 %
14.0%	71 – 80 %	0.6 – 1.6 %
15.0%	73 – 80 %	0.6 – 1.6 %

Table 302.9.3.(d) Cellulose Modified Mixtures¹ Master Grading

Sieve Size	Stone Mastic Asphalt (SMA)		Permeable Friction Course (PFC)	
	¾"	½"	½"	½" Modified
	Coarse Surface	Fine Surface	Coarse Surface	Fine Surface
	Percent Passing By Weight			
¾"	100.0			
½"	99.0-100.0	100.0	90.0-100.0	85.0-100.0
⅜"	70.0-85.0	70.0-90.0	35.0-60.0	55.0-75.0
No. 4	30.0-42.0	30.0-50.0	10.0-25.0	15.0-25.0
No. 8	20.0-33.0	20.0-30.0	5.0-10.0	5.0-10.0
No. 16		21.0 max		
No. 30		18.0 max		
No. 50		15.0 max		
No. 100				
No. 200	8.0-11.0	8.0-12.0	1.0 - 4.0	2.0 - 4.0

1. These mixtures shall be designed using a Superpave Gyratory Compactor (SGC) and in accordance with the AASHTO Standard Practice for Designing Superpave Hot Mix Asphalt (PP28-99). Design must be researched and based on intended use.

Table 302.9.3.(e) Cellulose Modified Mixture Properties

Property	Requirements	
	Stone Mastic Asphalt (SMA)	Permeable Friction Course (PFC)
Air Voids, %	4.0 (Lab Molded)	20.0 Min. (Lab Molded)
Cellulose Fibers, %	0.4	0.4
VMA, Percent (Min.)	17.0 (Plant); 17.5 (Design)	
VCA ¹ (Mix), Percent	Less Than VCA (DRC)	
TSR, Percent	80.0 Min. (Tex-531-C)	
Draindown @ Production Temp., %	0.30 Max. (T305)	0.30 Max. (T305)
Asphalt Content, Percent	6.0 Min.	6.0 Min.
N(Des)	100	20

1. See NCHRP Report 425 for definition and calculation of VCA (Voids in Coarse Aggregate).

302.9.3.1. Extraction Test. When required by the OWNER, samples of the asphaltic mixture may be taken from the plant, trucks or finished pavement for check tests. The minimum weight of the test specimen in grams shall be 3000 times the maximum size of aggregate in inches, and when tested in accordance with Recovery of Asphalt from Solution by Abson Method and Quantitative Extraction of Bitumen from Bituminous Paving Mixtures, ASTM Designations D1856 and D2172, respectively, it shall not vary from the grading proportions specified for the mixture being used by more than 5-percent.

302.9.3.2. Stability. The asphaltic mixture from the weight-batching plant and from the continuous mixing type plant, when tested in accordance with the current methods outlined in the TxDOT Test Method Tex-208-F Test for Stabilometer Value of Bituminous Mixtures, shall have the laboratory density and stability indicated in Table 302.9.3.(f) Asphalt Pavement Mixture Stability. If the mixture produced does not have the specified qualities, the mixture shall be changed until it conforms to the specified qualities.

Table 302.9.3.(f) Asphalt Pavement Mixture Stability

Property	Value
Density (%)	96 ±1
Stability (%) Hveem Stabilometer	Unless otherwise shown on the plans, Not less than 40 applied on arterials with truck traffic, and Not less than 35 for residential applications

302.9.4. Equipment. All equipment necessary for the construction of the hot-mix asphalt pavement shall be on the project and shall be approved by the OWNER as to condition before the CONTRACTOR shall be permitted to begin construction operations on which the equipment is to be used. All equipment shall be maintained in good repair and operating condition.

302.9.4.1. Bins. Bin storage shall be provided with tight cut-off gates to prevent leakage of aggregates or mineral filler into the weight box. The weight box for aggregates shall be of sufficient capacity to hold a complete batch of aggregates and mineral filler without wasting or leveling and shall be so designed that it shall quickly discharge the entire batch into the mixer. The weight box shall be provided with a close fitting and quick operating cut-off gate so that there shall be no leakage of the aggregates into the mixer and shall be satisfactorily attached to the batching scales.

302.9.4.2. Scales. Scales used for weighing different grades of mineral aggregates may be either the springless dial type or the multi-beam type. All scales must be a tare beam for balancing. The beam scales must also be equipped with a telltale indicator of the springless dial type indicating over-and-under loads of at least 50-pounds. Scales shall be accurate within 4-pounds-per-1000-pounds. If plant vibration interferes with accurate weighing, the scales shall be insulated against shock or vibration.

302.9.4.3. Material Bucket. The asphaltic material bucket shall be of sufficient size to hold the necessary asphaltic material for one batch. If the material is measured by weight, the bucket shall be properly attached to the scales herein specified. If the proportioning is by volume based on weight, the measuring bucket used shall be of the overflow type and shall meet the requirements of the OWNER.

302.9.4.4. Asphalt Storage. Asphalt storage shall be sufficient to meet the requirements of the plant. Asphalt in storage shall be heated by steam coils, absolutely tight to prevent leakage of moisture into the asphalt; the steam for heating shall not be at a temperature in excess of 400°F; direct fire heating of the asphalt shall not be permitted. Agitating asphalt with steam or air shall not be permitted.

302.9.4.5. Steam Heating Systems. The steam heating system shall insure the maintaining of the asphalt at a uniform draw-off temperature at the asphalt bucket of between 275°F and 375°F. The temperature shall be maintained with an efficient positive control of heat at all times as directed or approved by the OWNER. Asphalt heated beyond 375°F either before or during mixing with the mineral aggregate shall be rejected. The draw-off at the asphalt bucket shall be of a quick cut-off type which shall not leak. The asphalt supply line shall be of circulating type, and equipped with a recording thermometer indicating the temperature of the asphalt at the draw-off valve. This thermometer may be combined with the one used in recording the temperature of the aggregate.

302.9.4.6. Weight Bucket. The asphalt weight bucket shall be of an approved type. The scales of weighing the asphalt shall be either the springless dial type or the multi-beam type. The dial type shall be arranged for rapid adjustment at zero and shall be provided with a pointer to indicate the weight of the asphalt required in one batch. The beam type shall have a tare beam for balancing and shall be equipped with a telltale indicator of the springless dial type. If plant vibration interferes with accurate weighing, the scales shall be insulated against shock or vibration. The asphalt shall be sprayed into the mixer through an approved spray bar that shall distribute the asphalt uniformly throughout the length of the mixer.

302.9.4.7. Mixer. The mixer shall be of the pugmill type and shall have a capacity of not less than 1,000-pounds in a single batch. The number of blades and their positions shall give a uniform and complete circulation of the batch. A mixer that segregates mineral aggregate or fails to secure a thorough and uniform mixing with the asphalt and mineral filler shall not be permitted to be used. The

adequacy of the mixer to produce a successful mix shall be determined by mixing the standard batch for the required time, then dumping the batch, and taking samples from different parts of the batch; the samples shall be tested by the extraction test and shall show that the batch is uniform throughout.

All mixers shall be provided with an automatic time lock on the discharge gates of the mixer and the weigh box; and shall be locked for a period of 45-seconds after all the mineral aggregates have been introduced into the mixer. When discharged, the mixture shall have a temperature of 225°F to 350°F. The dump doors of the mixer shall be tight to the dry mineral aggregate or dust so that there shall be no spilling from the pugmill or drum. In introducing the batch into the mixer, all mineral aggregates shall first be introduced. Aggregates shall be thoroughly mixed for a period of 5- to 10-seconds before the asphalt is added; then the total mixture shall be mixed for the time required to produce a homogeneous mixture, in which all particles of the aggregates are uniformly coated.

302.9.4.8. Spreading and Finishing Machine. The spreading and finishing machine shall be of a type approved by the OWNER and capable of producing a surface that shall meet the requirements of the typical cross section and surface test.

302.9.4.9. Rollers. Rollers shall meet the governing specifications for [Item 301.1.2](#). Rolling of Embankment, Subgrade or Flexible Base. The use of vibratory roller on overlay thickness less than 1.5 inches will not be permitted.

302.9.4.10. Straightedges. The CONTRACTOR shall provide acceptable 16-ft. straightedges for the surface testing. Satisfactory templates shall be provided as required by the OWNER.

302.9.4.11. Vehicles for Transporting Mixture. Asphaltic concrete shall be transported from the plant to the site of the work in tight vehicles with metal bottoms previously cleaned of all foregoing substances. The OWNER may require that the vehicles be suitably insulated, and each load shall be covered with canvas or other suitable material of sufficient size to protect the asphaltic concrete from the weather and to prevent loss of material.

302.9.5. Mixing Plants. Mixing plants may be either the weight-batching plant, the continuous mixing type plant or the drum mixing type plant as hereinafter described. All types of plants shall be equipped with satisfactory conveyors, power units, aggregates handling equipment, hot-aggregates screens and bins and dust collectors.

Temporary storing or holding of the asphaltic mixture by a surge-storage system is permitted during the normal day's operation. Overnight storage shall not be permitted.

302.9.5.1. Weight Batching Plant. The proportioning of the various materials entering into the asphaltic mixture shall be as approved or directed by the OWNER. The OWNER shall have access at all times to all parts of the paving plant. The plant shall be of the batch type provided with separate storage bins and chambers for heating and mixing the materials.

The various sizes of mineral aggregates as received shall be stored or stockpiled separately, and the feeding of all sizes of mineral aggregates to the dryer shall be done by mechanical means that shall give a uniform and continuous feed to each of the sizes incorporated in order to give a control of the temperature and grading of the mineral aggregates.

The drying of the mineral aggregates shall be done in such a manner that the finer particles shall not escape with the furnace gases. If forced draft is used, a dust collector system shall be installed. If natural draft is used, the OWNER may require a dust collector system to prevent loss of the finer particles. The aggregate shall be heated in a suitable apparatus that continuously agitates the aggregate during the heating and in which the temperature can be efficiently and positively controlled so that the aggregates shall not be damaged and the mixture produced shall have a temperature between 225°F and 350°F.

A recording thermometer shall be provided which shall record the temperature of the aggregates as they leave the dryer. The recording thermometer shall be provided with a 24-hour chart and may be so equipped that it shall record both the temperature of the aggregates and the temperature of the asphalt incorporated into the batch. The drying apparatus shall be of sufficient size to dry and heat the amount of aggregates required to maintain the plant in continuous operation.

The screening capacity and size of the bins shall be sufficient to screen and store the amount of aggregates required to properly operate the plant and keep the plant in continuous operation at full capacity. Provisions shall be made to enable inspection forces to have easy and safe access to the proper location on the mixing plant where representative samples may be taken from the hot bins for testing. The aggregates shall be separated into at least four bins when producing Type “B” mixtures and at least three bins when producing Type “D” mixtures. If mineral filler is needed, an additional bin shall be provided. These bins shall contain the sizes of aggregates as shown in Table 302.9.3.(a) Dense Graded Hot Mix Master Grading.

302.9.5.2. Continuous Mixing Plant. Cold-aggregates bin and proportioning devices, dryer, and screening and proportioning shall conform to the requirements hereinabove for the weight-batching type of plant. The hot-aggregates proportioning device shall be so designed that when properly operated, a uniform and continuous flow of aggregates into the mixer shall be maintained.

An accurate asphaltic material meter shall be installed in the asphalt line leading to the spray bar, so that the amount of asphalt being used can be accurately determined. The asphaltic material spray bar shall be so designed that the asphalt shall be uniformly and continuously sprayed into the mixture.

The mixer shall be of the pugmill continuous type and shall have a capacity of not less than 40-tons-per-hour of mixture. Any mixer that segregates the aggregates or fails to secure a thorough and uniform mixing of the aggregates or fails to secure a thorough and uniform mixing of the aggregates with the asphaltic material shall not be used. This shall be determined by taking samples from different parts of a truckload and testing by the extraction test. These tests must show that the load is uniform throughout.

The amount of aggregates and asphaltic material entering the mixer and the rate of travel through the mixer shall be so coordinated that a uniform mixture of the specified grading and asphalt content shall be produced. The mixture shall not vary from the specified mixture by more than the specified tolerances.

The asphaltic mixture shall be at a temperature of between 225°F and 350°F when dumped from the mixer. The OWNER shall determine the lowest temperature, within the above limitations, at which the material can be satisfactorily dried, mixed, transported, spread and compacted, and the mixture furnished by the CONTRACTOR shall be between this determined temperature and 30°F higher.

302.9.5.3. Drum Mixing Plant. The plant shall be adequately designed and constructed for the process of mixing aggregates and asphalt in the drum mixer. The plant shall be equipped with satisfactory conveyors, power units, aggregates-handling equipment, and feed controls and shall consist of the following essential pieces of equipment.

The number of compartments in the cold-aggregates bin shall be equal to or greater than the number of stockpiles of individual materials to be used. The bin shall be of sufficient size to store the amount of aggregates required to keep the plant in continuous operation and of proper design to prevent overflow of material from one compartment to another. The feed system shall provide a uniform and continuous flow of aggregates in the desired proportion to the drum mixer.

A surge-storage system shall be required. It shall be adequate to minimize the production interruptions during the normal day's operations and shall be constructed to minimize segregation. A device such as gob hopper or other similar device approved by the OWNER to prevent segregation in the surge-storage bin shall be required.

The system shall provide positive weight measurement of the combined cold-aggregates feed by use of belt scales or other approved devices. Provisions of a permanent nature shall be made for checking the accuracy of the measuring device as required by [Item 302.9.4. Equipment](#). When a belt scale is used, mixture production shall be maintained so that the scale normally operates between 50-percent and 100-percent of its rated capacity. Belt scale operation below 50-percent of the rated capacity may be allowed by the OWNER if accuracy checks show the scale to meet the requirements of [Item 302.9.4. Equipment](#) at the selected rate, and it can be satisfactorily demonstrated to the OWNER that the mixture uniformity and quality have not been adversely affected.

An asphaltic material measuring device meeting the requirements of [Item 302.9.4](#). Equipment shall be placed in the asphalt line leading to the drum mixer so that the cumulative amount of asphalt used can be accurately determined. Provisions of a permanent nature shall be made for checking the accuracy of measuring device output. The asphalt measuring device and line to the measuring device shall be protected with a jacket of hot oil or other approved means to maintain the temperature of the line and measuring device near the temperature specified for the asphaltic material. Unless otherwise shown on the plans, the temperature of the asphaltic material entering the measuring device shall be maintained at $\pm 10^{\circ}\text{F}$ of the temperature at which the asphalt measuring device was calibrated and set.

The asphaltic material feed-control shall be coupled with the total aggregate weight measuring device in such manner as to automatically vary the asphalt-feed rate as required to maintain the required proportion. A scalping screen shall be required, unless otherwise shown on the plans, and shall be located ahead of any weighing device.

The asphaltic mixture shall be at a temperature of between 225°F and 350°F when dumped from the mixer. The OWNER shall determine the lowest temperature, within the above limitations, at which the material can be satisfactorily dried, mixed, transported, spread and compacted, and the mixture furnished by the CONTRACTOR shall be between this lowest determined temperature and 30°F higher. The drum mix system shall be of the type that continually agitates the aggregates and asphalt mixture during heating and in which the temperature can be so controlled that aggregates and asphalt shall not be damaged in the necessary drying and heating operations required to obtain a mixture of the specified temperature. A continuously recording thermometer shall be provided which shall indicate the temperature of the mixture as it leaves the drum mixer.

Scales may be standard platform truck scales, belt scales or other equipment such as weigh hopper (suspended) scales approved by the OWNER. All scales shall conform to [Item 302.9.4](#). Equipment. If truck scales are used, they shall be placed at a location approved by the OWNER. If other weighing equipment is used, the OWNER may require weight checks by truck scales for the basis of approval of the equipment.

302.9.5.4. Special Instructions for Cellulose Fiber. A separate dry storage area or silo shall be required for cellulose fiber. All equipment used in the storage and handling of cellulose fibers shall be kept a clean condition at all times and shall be operated in such a manner that there will be no contamination with foreign matter.

Cellulose fibers shall be added at $0.3\% \pm 0.1\%$ by mass of the mixture. Drainage shall be tested according to Tex-235-F Determination of Draindown Characteristics in Bituminous Materials. Draindown shall not exceed 0.3%-per-hour.

The cellulose fiber feed system shall supply the proper amount of cellulose fiber to the weigh box. Feeding of the cellulose fiber shall be performed in a manner such that the fibers are not damaged during the feeding and mixing processes and in a manner such that a uniform and constant flow of materials in the required proportions is maintained. The cellulose fiber storage capacity shall be ample to meet the requirements of the plant. Cellulose fiber shall not be allowed in the hot bins.

Mixing system shall control temperature so that the cellulose fiber will not be damaged in drying, heating and mixing operations.

302.9.5.4.1. Weight Batching Plant. Cellulose fiber shall be introduced into the pugmill during the dry mixing of the aggregates, prior to injection of the asphalt.

In introducing the batch into the mixer, all aggregates and then all cellulose fiber shall be introduced first and shall be mixed thoroughly for a minimum period of 5-seconds to uniformly distribute the various sizes of the aggregate and cellulose fiber throughout the batch before asphaltic material is added. The asphaltic material shall then be added and the mixing continued for a wet mixing period of not less than 15-seconds. The mixing period shall be increased if, in the opinion of the Engineer, the mixture is not uniform or the aggregates are not properly coated.

302.9.5.4.2. Continuous Mixing Plant. The mixing requirements shall be the same as is required for a standard Weigh-Batch Plant.

302.9.5.4.3. Drum-Mix Plant. Cellulose fiber shall be added to the mixture during the dry mixing process, unless otherwise approved by the Engineer. Cellulose fiber shall be uniformly dispersed in the mixture. Engineer may require that fiber be introduced into the drum dryer at the recycle port by use of a vane feeder.

The amount of aggregate, cellulose fiber and asphaltic material entering the mixer and the rate of travel through the mixing unit shall be so coordinated that a uniform mixture of the specified grading, cellulose fiber content and asphalt content is produced.

302.9.6. Construction Methods. Asphalt materials shall be handled in accordance with [Item 302.5](#). Storage, Heating and Application Temperature of Bituminous Materials.

The prime coat, tack coat or the asphaltic mixture shall not be placed when the air temperature is below 50°F and is falling but may be placed when the air temperature is above 40°F and is rising, the temperature being taken in the shade and away from artificial heat; with the provision that the asphaltic mixture shall be placed only when the humidity, general weather conditions and temperature and moisture condition of the base, in the opinion of the OWNER, are suitable. Mat thickness of 2 inches and less shall not be placed when the temperature of the surface on which the mat is to be placed is below 50°F.

302.9.6.1. Prime Coat. If required, a prime coat shall be applied to the completed subgrade, subbase or base, in accordance with [Item 302.7](#). Prime Coat. The type and grade of asphaltic material and the application rate shall be as shown on the plans or as directed by the OWNER.

302.9.6.2. Tack Coat. A tack coat shall be applied when the surface to be paved is Portland cement concrete, brick or asphaltic pavement. When a tack coat is required, it shall consist of an application of the asphaltic material indicated and shall be at the rate specified on the plans or as directed by the OWNER, but not to exceed 0.10 gallons-per-square-yard of surface area. The surfaces of curbs, gutters, vertical faces of existing pavements and all structures in actual contact with asphaltic mixes shall be painted with a thin, complete coating of asphaltic material to provide a closely bonded, watertight joint.

302.9.6.3. Compacted Thickness of Hot-Mix Asphalt Pavement Surface Courses and Base Courses.

302.9.6.3.1. Base Courses. The compacted thickness or depth of each base course shall be as shown on the plans. Where the plans require a depth or thickness of the course greater than 4-in., same shall be accomplished by constructing multiple lifts of approximately equal depth, each of which shall not exceed 4-in. compacted depth. If, in the opinion of the OWNER, an additional tack coat is considered necessary between any of the multiple lifts, it shall be applied as in [Item 302.9.6.2](#). Tack Coat and at the rate as directed.

302.9.6.3.2. Surface Courses. The compacted thickness or depth of the asphalt pavement surface course shall be as shown on the plans. Where the plans require a depth or thickness of the surface course greater than 2-in. compacted depth, same shall be placed in multiple courses of equal depth, each of which shall not exceed 2-in. compacted depth. If, in the opinion of the OWNER, an additional tack coat is considered necessary between any of the multiple courses, it shall be applied as in [Item 302.9.6.2](#). Tack Coat and at the rate as directed.

302.9.6.4. Transporting Hot-Mix Asphalt Pavement Material. The mixture shall be hauled to the job site in tight vehicles previously cleaned of all foreign material. The dispatching of vehicles shall be arranged so that all material delivered shall be placed and all rolling shall be completed during daylight hours. In cool weather, or for long hauls, canvas covers may be required. The inside of the truck body may be given a light coating of an approved release agent, if necessary, to prevent the mixture from adhering to the body.

302.9.6.5. Temperature. The hot-mix asphalt mixture shall be at a temperature between 275° and 350°F when dumped from the mixer. The OWNER shall determine the temperature, within the above limitations. The mixture when dumped from the mixer shall not vary from this selected temperature more than 30°F. Restrictions on maximum mixture temperatures placed by environmental regulatory agencies supersede the maximum temperature listed above.

302.9.6.6. Placing. The hot-mix asphalt mixture shall be placed on the approved base course with the specified spreading and finishing machine in such manner that, when properly compacted, the finished course shall comply with the maximum thickness requirements, be smooth and of uniform density, and meet the requirements of the typical cross sections and the surface test. During the placing and spreading of the hot-mix asphalt material, care shall be taken to prevent the spilling of the material onto adjacent pavement, gutters or structures.

302.9.6.7. Compaction. Rolling with a tandem or vibratory roller shall start longitudinally at the sides and proceed toward the center of the surface course, overlapping on successive trips by at least half the width of the rear wheels. Alternate trips of the roller shall be slightly different in length. Rolling with the pneumatic tire roller shall be done as directed by the OWNER. Rolling shall continue until no further compression can be obtained and all roller marks are eliminated. The motion of the rollers shall be slow enough at all times to avoid displacement of the asphaltic surface material. If displacement should occur, it shall be corrected at once by the use of rakes and fresh asphaltic mixtures where required. The roller shall not be allowed to stand on the surface course when it has not been fully compacted and allowed to cool. To prevent adhesion of the surface course to the roller, the wheels shall be kept thoroughly moistened with water, but an excess of water shall not be permitted. All rollers must be in good mechanical condition. All necessary precautions shall be taken to prevent the dripping of gasoline, oil, grease or other foreign matter on the surface course while the rollers are in motion or when standing. In areas where the surface course cannot be compacted with the rollers, hand tamps, lightly oiled, shall be used to secure the required compaction.

Each course, after final compaction, shall have a relative density of not less than 92-percent. The relative density will be determined using Tex-207-F Determining Density of Compacted Bituminous Mixtures and Tex-227-F Theoretical Maximum Specific Gravity of Bituminous Mixtures.

302.9.6.8. Surface Tests. The finished surface of the pavement after compression shall be smooth and true to the established line, grade and cross section. When tested with a 16-ft. straightedge placed parallel to the centerline of the roadway, the finished surface shall have no deviation in excess of $\frac{1}{16}$ -in-per-foot from the nearest point of contact. The maximum ordinate measured from the face of the straightedge shall not exceed $\frac{1}{4}$ -in. at any point. Any point in the pavement surface not meeting these requirements shall be immediately corrected.

302.9.6.9. Pavement Thickness Test. Upon completion of the work and before final acceptance and final payment shall be made, pavement thickness test shall be made by the OWNER or its authorized representative unless otherwise specified in the special provisions or in the plans. The number and location of tests shall be at the discretion of the OWNER. The cost for the initial pavement thickness test shall be at the expense of the OWNER. In the event a deficiency in thickness of pavement is revealed during normal testing operations, subsequent tests necessary to isolate the deficiency shall be at the CONTRACTOR'S expense. The cost for the additional coring test shall be at the same rate charged by commercial laboratories.

302.10. MEASUREMENT AND PAYMENT

Prime coat and tack coat shall not be measured for direct payment but shall be considered as subsidiary work pertaining to the placing of hot-mix asphalt mixtures of the type specified.

Hot-mix asphalt pavement material shall be measured complete in place by the ton (2,000-lb.) computed at 110-lb. per S.Y. surface area per inch thickness of course, or by the S.Y. of the type(s) and grade(s) used in the completed and accepted work. Weight shall be determined by a certified scale approved by the OWNER and recorded on serially numbered weight tickets, identifying the vehicle and presented to the OWNER'S representative on the job. Work performed and materials furnished as prescribed by this Item and measured as specified in this Item shall be paid for at the contract unit price bid for the type or types of courses and mixtures as shown in the proposal, which price shall be payment in full for quarrying, furnishing all materials, heating, mixing, hauling, cleaning existing base course or pavement, placing asphaltic mixtures, rolling and finishing, and all labor, tools, equipment and incidentals necessary to complete the work, including the work and materials involved in the application of prime coat and tack coat.

ITEM 303. PORTLAND CEMENT CONCRETE PAVEMENT

303.1. DESCRIPTION

This item shall consist of finished pavement constructed of Portland cement concrete on the prepared subgrade or other base course, in conformity with the plans, as herein specified and as supplemented and/or amended by special provisions and to the lines and grades as established by the OWNER. Concrete shall be considered of satisfactory quality, provided it is:

- (1) Made of materials acceptable to the job and meeting the requirements of [Item 303.2](#). Portland Cement Concrete Pavement Materials and special provisions and amendments thereto;
- (2) In the proportions approved by the OWNER; and
- (3) Mixed, placed, finished and cured in accordance with the requirements of these specifications and any special provisions.
- (4) No concrete shall be placed where the temperature of the mix exceeds 95 degrees Fahrenheit or where the time from being batched to placed exceeds the times shown in Table 303.5.5.(a) Concrete Placement.
- (5) All concrete utilized for street, alley, drive approach and sidewalk pavement shall be batch mixed unless another method is specifically approved by the OWNER.

303.2. PORTLAND CEMENT CONCRETE PAVEMENT MATERIALS

303.2.1. Aggregates for Portland Cement Concrete Pavement.

303.2.1.1. General Requirements. Aggregates for Portland cement concrete shall conform to the requirements contained in this Item and shall be approved by the OWNER prior to use. Aggregates shall be of such character that it shall be possible to produce workable concrete within the limits contained in this specification.

303.2.1.1.1. Storage. The manner of handling and storage of aggregates shall be such as to prevent intrusion of foreign materials and segregation of sizes. If materials are stored on the ground, the stockpile sites shall be grubbed, cleaned of all vegetation and leveled. In this case, the bottom six-in. layer of aggregate shall not be disturbed and shall not be used in the work.

Where two or more sizes or types of aggregates are delivered to the job, each size or type shall be stored separately.

Aggregates shall be stockpiled on the job or at a central batching plant for a minimum of 24-hours prior to use in the project. At the plant, the aggregate shall be wetted to a uniform moisture content of not less than three-percent below saturated surface dry condition before or while being loaded for shipment. Care shall be exercised to maintain this uniformity of moisture until the aggregates are used in the mix. Wetting of stockpiles to maintain the required percent moisture shall be performed at least 12-hours prior to use.

At the time of use, the aggregates shall be free from frozen material and foreign matter. All grass, wood, sticks, burlap, paper or other material which may have become mixed with the aggregates while stockpiled or in handling shall be removed.

303.2.1.1.2. Aggregate Measuring.

The fine and coarse aggregates shall be measured loose and separately.

By Weight. Aggregate weighing equipment shall conform to the requirements of ASTM C94 Standard Specification for Ready-Mixed Concrete and shall be approved by the OWNER prior to use.

By Volume. The volume measuring equipment shall consist of approved boxes, pans or mechanical devices, which, while in operation, shall give the required volumes of the different kinds of aggregates required for the several classes of concrete. Equipment shall also be so marked and designed that the OWNER can accurately and conveniently check the quantities of each aggregate being used.

Concrete made by continuous mixing shall conform to ASTM C685 Concrete Made by Volumetric Batching and Continuous Mixing.

303.2.1.1.3. Tests. Test of aggregates shall be made in accordance with the applicable current ASTM standards, listed in Table 303.2.1.1.3.(a) Aggregate Tests.

Table 303.2.1.1.3.(a) Aggregate Tests

ASTM Designation	Standard Specification or Standard Test Method (Title)
C29	Bulk Density ("Unit Weight") and Voids in Aggregate
C33	Concrete Aggregates
C40	Organic Impurities in Fine Aggregates for Concrete
C88	Soundness of Aggregates by Use of Sodium Sulfate or Magnesium Sulfate
C123	Lightweight Particles in Aggregate
C125	Terminology Relating to Concrete and Concrete Aggregates
C127	Density, Relative Density (Specific Gravity) and Absorption of Coarse Aggregate
C128	Density, Relative Density (Specific Gravity) and Absorption of Fine Aggregate
C131	Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
C136	Sieve Analysis of Fine and Coarse Aggregates
C142	Clay Lumps and Friable Particles in Aggregates
C330	Lightweight Aggregates for Structural Concrete
C535	Resistance to Degradation of Large-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine
C641	Staining Materials in Lightweight Concrete Aggregates
D8	Terminology Relating to Materials for Roads and Pavements
D75	Sampling Aggregates
D422	Particle-Size Analysis of Soils
D4318	Liquid Limit, Plastic Limit, and Plasticity Index of Soils
D2217	Wet Preparation of Soil Samples for Particle-Size Analysis and Determination of Soil Constants

303.2.1.2. Fine Aggregates. Fine aggregate shall consist of natural sand, manufactured sand or a combination of the two, with or without mineral filler. The sand, or mixture of sand, comprising a single fine aggregate, shall consist of clean, hard, durable, uncoated grains and shall be essentially free from clay lumps.

303.2.1.2.1. Foreign Material and Deleterious Substances. The maximum permissible percentage, by weight, of deleterious substances shall not exceed the amounts in Table 303.2.1.2.1.(a) Deleterious Substances in Fine Aggregates.

The fine aggregate shall be free from an excess amount of salt or alkali and at the time of use shall be free from frozen and/or all foreign material.

Table 303.2.1.2.1.(a) Deleterious Substances in Fine Aggregates

Substance	Maximum % by Weight
Material removed by decantation	3.0% ¹
Other deleterious substances such as coal, shale, coated grains and soft flaky particles	3.0%

1. An additional loss of two-percent by decantation may be allowed, provided this new additional loss is material of the same quality as specified for fine aggregate or mineral filler.

303.2.1.2.2. Gradation. The fine aggregate shall be well graded from fine to coarse and when tested by standard laboratory sieves shall meet the requirements of Table 303.2.1.2.2.(a) Grading Requirements for Fine Aggregates.

Table 303.2.1.2.2.(a) Grading Requirements for Fine Aggregates

Sieve	Percent Passing by Weight
$\frac{3}{8}$ -in. sieve (9.5mm)	100%
No. 4 sieve (4.75mm)	95 to 100%
No. 8 sieve (2.36mm)	80 to 100%
No. 16 sieve (1.18mm)	50 to 85%
No. 30 sieve (600 μ m)	25 to 65%
No. 50 sieve (300 μ m)	10 to 30%
No. 100 sieve (150 μ m)	0 to 10%
No. 200 sieve (75 μ m)	0 to 3%

303.2.1.2.3. Mineral Filler. Stone dust or crushed sand may be added as a mineral filler, if so directed by the OWNER. Amounts of mineral filler shall not exceed 5-percent of the fine aggregate to improve the workability or quality specified for fine or coarse aggregates. When tested by standard laboratory sieves shall meet the requirements of Table 303.2.1.2.3.(a) Fine Aggregate Mineral Filler.

Table 303.2.1.2.3.(a) Fine Aggregate Mineral Filler

Sieve	Percent Passing
No. 30 sieve (600 μ m)	95 to 100%
No. 100 sieve (150 μ m)	70 to 100%

303.2.1.2.4. Rejection. Fine aggregates which fail to meet the requirements of these specifications may be rejected by the OWNER. Such rejection shall incur no cost to the OWNER.

Fine aggregates sources, from which materials with properties not meeting these specifications are delivered, may be rejected as further supply sources to the project by the OWNER. Such rejection shall incur no cost to the OWNER.

303.2.1.3. Coarse Aggregates. Coarse aggregates shall consist of durable particles of crushed gravel, crushed stone, crushed blast furnace slag meeting the requirements of ASTM C989 (Standard Specification for Ground Granulated Blast-Furnace Slag for Use in Concrete and Mortars) Grade 100 or 120, recycled crushed Portland cement concrete, or a combination of these.

303.2.1.3.1. Foreign Material and Deleterious Substances. The maximum permissible percentage, by weight, of deleterious substances shall not exceed the amounts in Table 303.2.1.3.1.(a) Deleterious Substances in Coarse Aggregates.

Aggregates shall be free from injurious amounts of salt, alkali, vegetable matter, or other objectionable material either free or as an adherent coating. At the time of their use, aggregates shall be free from frozen and/or all foreign material that may have become mixed with them in the stockpile.

Table 303.2.1.3.1.(a) Deleterious Substances in Coarse Aggregates

Substance	Maximum % by Weight
Material removed by decantation	1.0%
Shale, slate or other similar material	1.0%
Clay lumps	0.25%
Soft fragments	3.0%
Other deleterious substances, including friable, thin, elongated or laminated pieces	3.0%
The sum of all deleterious substances, exclusive of material removed by decantation	5.0%

303.2.1.3.2. Gradation. Coarse aggregates shall be well graded in size from coarse to fine. When tested by standard laboratory methods, coarse aggregates shall meet the requirements in Table 303.2.1.3.2.(a) Grading Requirements for Coarse Aggregates for percentage passing each sieve by weight.

Coarse aggregates of different characteristics, though tested and approved, shall not be mixed with other aggregates; but shall be stored, batched and weighed separately.

The difference in percent passing between two adjacent sieve sizes shall not exceed 20%.

Maximum Size Aggregate. The maximum size aggregate is defined as the clear space between the sides of the smallest square openings through which 95-percent of the weight of the aggregate can be passed. The maximum size of aggregates for paving concrete shall not exceed 1½-inches, and shall be reduced in size to meet the following conditions:

- (1) one-fifth of the least dimension between forms of that part of the structure in which concrete is to be placed;
- (2) three-fourths of the clear space between reinforcement; and
- (3) one-third the depth of the slab.

Table 303.2.1.3.2.(a) Grading Requirements for Coarse Aggregates

Size No.	Nominal Size (Sieve with Square Openings)	Amounts Finer than Each Laboratory Sieve (Square-Opening), Mass Percent													
		100 mm (4 in.)	90 mm (3½ in.)	75 mm (3 in.)	63 mm (2½ in.)	50 mm (2 in.)	37.5 mm (1½ in.)	25.0 mm (1 in.)	19.0 mm (¾ in.)	12.5 mm (½ in.)	9.5 mm (¾ in.)	4.75 mm (No. 4)	2.36 mm (No. 8)	1.18 mm (No. 16)	0.30 mm (No. 50)
1	90 to 37.5 mm (¾ to 1½ in.)	100	90 to 100	—	25 to 60	—	0 to 15	—	0 to 5	—	—	—	—	—	—
2	63 to 37.5 mm (2½ to 1½ in.)	—	—	100	90 to 100	35 to 70	0 to 15	—	0 to 5	—	—	—	—	—	—
3	50 to 25.0 mm (2 to 1 in.)	—	—	—	100	90 to 100	35 to 70	0 to 15	—	0 to 5	—	—	—	—	—
357	50 to 4.75 mm (2 in to No. 4)	—	—	—	100	95 to 100	—	35 to 70	—	10 to 30	—	0 to 5	—	—	—
4	37.5 to 19.00 mm (1½ to ¾ in.)	—	—	—	—	100	90 to 100	20 to 55	0 to 15	—	0 to 5	—	—	—	—
467	37.5 to 4.75 mm (1½ in to No. 4)	—	—	—	—	100	95 to 100	—	35 to 70	—	10 to 30	0 to 5	—	—	—
5	25.0 to 12.5 mm (1 to ½ mm)	—	—	—	—	—	100	90 to 100	20 to 55	0 to 10	0 to 5	—	—	—	—
56	25.0 to 9.5 mm (1 to ¾ in.)	—	—	—	—	—	100	90 to 100	40 to 85	10 to 40	0 to 15	0 to 5	—	—	—
57	25.0 to 4.75 (1 to No. 4)	—	—	—	—	—	100	95 to 100	—	25 to 60	—	0 to 10	0 to 5	—	—
6	19.0 to 9.5 mm (¾ to ¾ in.)	—	—	—	—	—	—	100	90 to 100	20 to 55	0 to 15	0 to 5	—	—	—
67	19.0 to 4.75 mm (¾ in to No. 4)	—	—	—	—	—	—	100	90 to 100	—	20 to 55	0 to 10	0 to 5	—	—
7	12.5 to 4.75mm (½ in to No. 4)	—	—	—	—	—	—	—	100	90 to 100	40 to 70	0 to 15	0 to 5	—	—
8	9.5 to 2.36 mm (¾ in to No. 8)	—	—	—	—	—	—	—	—	100	85 to 100	10 to 30	0 to 10	0 to 5	—
89	9.5 to 1.18 mm (¾ in to No. 16)	—	—	—	—	—	—	—	—	100	90 to 100	20 to 55	5 to 30	0 to 10	0 to 5
9 ¹	4.75 to 1.18 mm (No. 4 to No. 16)	—	—	—	—	—	—	—	—	—	100	85 to 100	10 to 40	0 to 10	0 to 5

1. Although size 9 aggregate is defined in ASTM C125 Standard Terminology Relating to Concrete and Concrete Aggregates as a fine aggregate, it is included as a coarse aggregate when it is combined with a size 8 material to create a size 89, which is a coarse aggregate as defined by ASTM C125.

303.2.1.3.3. Tests. Results of tests performed according to the applicable standard test methods listed in Table 303.2.1.1.3.(a) Aggregate Tests shall meet the criteria specified by the OWNER. Coarse Aggregates shall have a percent wear of not more than 45 when tested by abrasion and impact in the Los Angeles machine, ASTM C131 and C535.

303.2.1.3.4. Rejection. Coarse aggregates which fail to meet the requirements of these specifications may be rejected by the OWNER. Such rejection shall incur no cost to the OWNER.

Coarse aggregate sources, from which materials with properties not meeting these specifications are delivered, may be rejected as further supply sources to the project by the OWNER. Such rejection shall incur no cost to the OWNER.

303.2.2. Portland Cement. Cement shall be of a standard brand of Portland cement which shall conform to the requirements of ASTM C150 Portland Cement, ASTM C595 Blended Hydraulic Cements, or other applicable test methods of the ASTM and shall be as approved by the OWNER.

303.2.2.1. Delivery. Cement delivered in bags shall be legibly marked on the bag with brand and name of the manufacturer, shall be in good condition at the time of delivery, and shall contain 94-pounds net. Bags of cement varying more than 5-percent from the specified weight may be rejected, and if the average net weight in any shipment, as determined by weighing 50 bags taken at random, is less than 94-pounds, the entire shipment may be rejected. Cement salvaged from discarded or used bags shall not be used.

Cement delivered in bulk may be used, provided the manner and method of handling is approved by the OWNER. When delivered in bulk, the brand name of the manufacturer contained in the shipping information accompanying the shipment shall be furnished to the OWNER prior to the use of the cement. Bulk cement shall be weighed on approved scales.

Cement from different manufacturers, although tested and approved, shall not be mixed, except as approved by the OWNER.

The CONTRACTOR, when required, shall furnish to the OWNER, with each shipment of cement, a statement as the specific surface of the cement expressed in square-centimeters-per-gram.

303.2.2.2. Cement Weighing Equipment. Bulk cement shall be batched by weight. The scales shall be either the beam or springless dial type, of substantial construction with a maximum allowable error of 0.5-percent of the net load and with minimum gradations of not greater than 5-pounds. Provisions shall be made for indicating to the operator that the required load in the weight box or container is being approached, which device shall indicate at least the last 50-pounds of the load. Dial type scales shall be provided with a pointer to the dial.

When a closed-type cement box is used, the cement-weighing scales shall be provided with a springless dial indicator or tare beam to indicate when the weigh box is empty. This indicator for the empty condition of the weigh box shall be in continuous operation. The weigh box shall be fitted with an approved vent and a tightly covered inspection opening of not less than 12-sq.in. The weigh box and scales shall be maintained in a satisfactory condition to meet the requirements for accuracy for weight.

303.2.2.3. Volume and Weight of Bag of Cement. A bag of cement as packed by the manufacturer and weighing 94-pounds shall be considered 1-cubic-foot.

303.2.2.4. Storage. Cement shall be stored in a suitable weathertight building which shall protect the cement from dampness, and placed in such manner that shall permit easy access for proper inspection and identification of each shipment.

303.2.2.5. Rejection. Cement may be rejected for failure to meet any of the requirements of this specification and shall be rejected under the following specific conditions:

- (1) any bag of cement which has partially set or which contains any lumps or cakes;
- (2) all cement salvaged from torn, discarded or used bags; or
- (3) bulk cement which has partially set or which contains any lumps or cakes.

303.2.3. Chemical Admixtures. Unless otherwise provided in the plans or special provisions, approved types of chemical admixtures to minimize segregation, to improve workability or to reduce the amount of mixing water may be used in the rate of dosage specified by the OWNER and in accordance with the manufacturer's recommendations.

Admixtures shall be dispensed in a form by an accurate mechanical dispenser designed for convenient confirmation of the accuracy of measurement. Dispensers shall have sufficient capacity to measure at one time the full quantity required for each batch. Two or more admixtures of different types, such as a water-reducing and air-entraining admixture, may not be compatible when mixed together. Where different admixtures are used, they should be added to the batch separately unless it is known that they can be mixed together satisfactorily. Dosage of admixtures shall not vary from the dosage order by the OWNER by more than 5-percent. In addition:

- (1) Chemical admixtures shall conform to ASTM C494 Chemical Admixtures for Concrete, Types “A”, “D”, “F” and “G” for concrete dosages in accordance with manufacturer’s recommendations as specified by the OWNER.

Water-reducing admixtures conforming to ASTM C494, Types “A” and “F”, shall be used to improve quality of concrete by obtaining specified strength at lower cement content and to increase slump without increasing water-cement ratio and may also be utilized in improving properties of concrete containing aggregates that are harsh or poorly graded.

Water-reducing, set retarding admixtures, conforming to ASTM C494, Type “D” and “G”, may be used during hot weather concrete placement, so as to keep concrete workable during the entire placing period, in order that succeeding placements may be made without development of cold joints or discontinuities in the structural unit.

- (2) OWNER’S option: High range water-reducing admixtures, super-plasticizers conforming to ASTM C494, Type “F” and “G”, may be used to greatly reduce water content to obtain dense concrete with higher early strengths and maintain high slump or flowing concrete while maintaining low water-cement ratio for concrete that must be placed under difficult conditions such as pump or tremie methods, etc.
- (3) Air-entraining admixtures shall conform to ASTM C260 Air-Entraining Admixtures for Concrete.

Dosage shall conform to recommendations of manufacturer, as specified by OWNER, and determined by field testing of concrete mixture by qualified testing personnel in accordance with ASTM C94 Ready-Mixed Concrete.

The CONTRACTOR shall secure the approval of the OWNER for the particular admixture which it proposes to incorporate into the concrete prior to actual use of the admixture. The CONTRACTOR shall furnish such information and evidence that the OWNER may require in its determination of the acceptability of the proposed admixture. When the CONTRACTOR proposes to use an air-entraining admixture which has been previously approved by the OWNER, it shall submit a certification stating that the admixture is the same as that previously approved.

Either prior to or at any time during construction, the OWNER may require that the air-entraining admixture selected by the CONTRACTOR be tested to determine its effect upon the strength of the concrete. When so tested, a 7-day compressive strength of concrete, made with cement and aggregates in proportions to be used in the work and containing the admixture in an amount sufficient to produce from 3- to 6-percent entrained air in the plastic concrete, shall be no less than 85-percent of the strength of concrete, made with the same materials and with the same cement content and consistency but without the admixture.

Any other admixtures for whatever purpose shall have the approval of the OWNER prior to incorporation into the concrete mix.

303.2.4. Mineral Admixtures. Fly ash shall conform to the requirements of ASTM C618 Coal Fly Ash and Raw or Calcined Natural Pozzolan for Use as a Mineral Admixture in Concrete, with the exception that the “Loss on Ignition” requirements shall be a maximum of 3-percent. Fly ash shall be sampled and tested at a frequency schedule in accordance with the requirements of ASTM C311 Test Methods for Sampling and Testing Fly Ash or Natural Pozzolans for Use as a Mineral Admixture in Portland-Cement Concrete. All sources of fly ash for use in Portland cement concrete shall conform to the requirements of Texas Department of Transportation (TxDOT) Material Specification DMS-8900 Fly Ash.

With the approval of the OWNER, fly ash may be used in all classes of concrete to replace a portion of the Portland cement in a mix design. Unless otherwise approved by the OWNER, the maximum cement reduction shall not exceed 25-percent by weight per cubic-yard of concrete. If historical data and general practice in locality of usage substantiates fly ash concrete using higher percentages, CONTRACTOR may submit written request to OWNER for review. Fly ash replacement shall be on a weight basis. The minimum replacement ratio shall be 1.0-pounds of fly ash per 1.0-pounds of cement replaced.

The water-cement ratio of the concrete mix shall be based on total cementitious (cement plus fly ash) materials. Proposed concrete mix designs with materials certification data and laboratory or field mix test results on the properties of the fresh or hardened concrete shall be submitted to the OWNER for approval.

303.2.5. Mineral Filler. Mineral filler shall consist of stone dust, crushed sand or other inert material approved by the OWNER. Mineral filler may be added in amounts not to exceed 10-percent of the weight of

the sand or mixture of sands to improve the workability or plasticity of the concrete mix. Such mineral filler shall be of the quality specified for fine or coarse aggregate, and when tested by laboratory methods shall meet the requirements of Table 303.2.5.(a) Mineral Filler.

Where mineral filler is used, it shall be measured by volume or weighed and batched separately.

Table 303.2.5.(a) Mineral Filler

Sieve	Percent Retained on Sieve
No. 30 sieve (600µm)	0%
No. 200 (75 µm)	0% to 35%

303.2.6. Fibrous Reinforcement. At the OWNER'S option, fibrous reinforcement in concrete may be used unless otherwise shown on the plans or in the contract documents. Fibrous reinforcement shall not be used as a replacement for any reinforcement required for structural purposes.

303.2.6.1. Material. Fibers for reinforcement of concrete shall be in accordance with materials specified in ASTM C1116 Fiber-Reinforced Concrete and Shotcrete.

303.2.6.2. Length and Size. The fibers shall be length and size as specified in ASTM C1116.

303.2.6.3. Testing. Test methods ASTM C995 Time of Flow of Fiber-Reinforced Concrete Through Inverted Slump Cone, and ASTM C1018 Flexural Toughness and First-Crack Strength of Fiber-Reinforced Concrete (Using Beam With Third-Point Loading) in addition to applicable ASTM methods for the testing of concrete shall be used to test the fiber-reinforced concrete. Performance of fiber-reinforced concrete shall meet all requirements as specified in Section 21 of ASTM C1116.

303.2.6.4. Rejection. Fibrous reinforcement or fiber-reinforced concrete may be rejected for failure to meet any of the requirements of this specification or ASTM C1116.

303.2.7. Water. Water for use in concrete shall be reasonably clean and free of oil, acid, alkali, organic matter or other deleterious substances. Water which is suitable for drinking or ordinary household uses may be accepted for use without being tested.

303.2.7.1. Source. Water shall be obtained preferably from a domestic water supply. Where other source of supply is proposed, the approval of the OWNER must be obtained prior to using the water.

303.2.7.2. Measuring Devices. The device for measuring the quantity of water shall indicate the quantity in gallons or pounds and fractions thereof. The operating mechanism shall regulate the quantity required for any given batch within one-percent. The supply inlet shall be cut off automatically when the water is discharged into the mixer.

Upon approval of the OWNER, the water for any one batch in the mixer may be measured in approved cans, buckets or other containers, and no more than the required amount of water shall be introduced into the mixer. The measuring devices shall be checked at the beginning of each job.

303.2.7.3. Tests. If the water is of questionable quality, it shall be tested in accordance with the standard Method of Test of Quality of Water to be used in concrete, AASHTO T26.

303.2.7.4. Rejection. Water for use with cement may be rejected for failure to meet any of the requirements of this specification.

303.2.8. Dowel Bars. Dowel and tie bars shall be either straight or bent, smooth or deformed, as shown on the plans and shall conform to the requirements of [Item 303.2.9. Steel Reinforcement](#). The dowel bars shall be coated with either hot asphalt or an alternate coating, as designated on the plans, to the extent shown on the plans.

303.2.8.1. Dowel Caps. Caps for slip dowel bars shall be of the length shown on the plans and shall have an internal diameter sufficient to permit the cap to freely slip over the bar. In no case shall the internal diameter exceed the bar diameter by more than 1/8-in., and one end of the cap shall be closed. The cap shall be installed to allow the bar to move not less than 1 1/4-in. in either direction.

303.2.9. Steel Reinforcement. Concrete reinforcement is the metal (rods or fabric) imbedded in concrete in such a manner that the reinforcement and concrete act together in resisting forces.

303.2.9.1. Material. Unless otherwise specified or designated on the plans, the metal for all bar reinforcement shall be one of the following:

303.2.9.1.1. New Billet Steel. New billet steel shall meet the requirements of ASTM A615/A615M Deformed and Plain Billet-Steel Bars for Concrete Reinforcement.

303.2.9.1.2. Axle Steel. Axle steel shall meet the requirements of ASTM A996/A996M Rail-Steel and Axle-Steel Deformed Bars for Concrete Reinforcement.

303.2.9.1.3. Rail Steel. Axle steel shall meet the requirements of ASTM A996/A996M Rail-Steel and Axle-Steel Deformed Bars for Concrete Reinforcement.

The use of rail steel or axle steel shall not be permitted where bending of the bar is required.

Unless otherwise designated on the plans, all reinforcement steel bars shall be deformed in accordance with the requirements of ASTM A615/A615M or A996/A996M, as appropriate. Twisted bars are not considered deformed and shall not be used. The deformed bars shall provide a net sectional area at all points equivalent to that of plain square or round bars of equal nominal size.

Bars for spiral reinforcement shall be plain bars rolled from billets directly reduced from ingots and shall conform to the requirements of ASTM A615/A615M.

303.2.9.2. Sizes and Weights. The size and weight of reinforcing bars shall conform to the requirements of ASTM A615/A615M.

303.2.9.3. Bending. Reinforcement bars shall be bent cold to the shapes indicated on the plans. All bending of hard grade new billet steel shall be done in the shop. Bends shall be true to the shapes indicated, and irregularities shall be cause for rejection. Unless otherwise shown on the plans, bends for stirrups and ties shall be made around a pin having a diameter not less than two times the minimum thickness of the bar. Other bends shall be made according to the latest code of Standard Practice of the Reinforcing Steel Institute.

303.2.9.4. Storage. Reinforcement shall be stored above the ground surface upon skids, platforms or other supports, and shall be protected from mechanical injury and surface deterioration caused by exposure to the conditions producing rust. When placed in the work, the reinforcement shall be free from dirt, loose rust, scale, painting, oil or other foreign material.

303.2.9.5. Rejection. Reinforcement may be rejected for failure to meet any of the requirements of this specification. Additionally, reinforcement may be rejected for the following:

- (1) reinforcement exceeding the allowable variations,
- (2) reinforcement not bent in accordance with the details,
- (3) reinforcement with a coating of dirt, loose scale, paint, oil or other foreign substances which shall prevent bonding of the concrete and reinforcement,
- (4) twisted bars, or
- (5) reinforcement subjected to construction traffic.

303.2.10. Steel Wire Reinforcement. At the OWNER'S option the use of welded wire fabric may be used in lieu of deformed reinforcement bars unless otherwise shown on the plans or in the contract specifications.

Welded wire fabric shall be delivered to the job site in sheets. Rolls of wire fabric shall not be permitted.

The size of welded wire fabric shall be 12 x 12- W 4 x W 4 with a nominal diameter in inches of 0.225 and a nominal weight 0.136 lbs/linear foot.

303.2.10.1. Material. Wire for fabric reinforcement shall be cold-drawn from rods hot-rolled from billets and shall conform to the requirements of ASTM A82 Steel Wire, Plain, for Concrete Reinforcement. Welded wire fabric shall conform to the requirements of ASTM A185 Steel Welded Wire Reinforcement, Plain, for Concrete.

303.2.10.2. Sizes and Weights. The properties of wire fabric shall conform to the requirements of ASTM A82 or ASTM A185, as appropriate.

303.2.10.3. Storage. Reinforcement shall be stored above the ground surface upon skids, platforms or other supports, and shall be protected from mechanical injury and surface deterioration caused by exposure to the conditions producing rust. When placed in the work, the reinforcement shall be free from dirt, loose rust, scale, paint, oil or other foreign materials.

303.2.10.4. Rejection. Reinforcement may be rejected for failure to meet any of the requirements of this specification, and specifically for the following:

- (1) reinforcement exceeding the allowable variations,
- (2) reinforcement not bent in accordance with the details,
- (3) reinforcement with a coating of dirt, loose scale, paint, oil or other foreign substances which shall prevent bonding of the concrete and reinforcement, or
- (4) twisted bars.

303.2.11. Reinforcement Bar Chairs. Reinforcement bar chairs or supports shall be of adequate strength (if specified) to support the reinforcement bars and shall not bend or break under the weight of the reinforcement bars or CONTRACTOR'S personnel walking on the reinforcing bars.

Bar chairs may be made of metal (free of rust), precast mortar or concrete blocks or plastic. Pre-cast mortar or concrete blocks must be approved by the OWNER; and the CONTRACTOR shall supply test data showing the strength of the mortar or concrete blocks.

For approval of plastic chairs, representative samples of the plastic shall show no visible indications of deterioration after immersion in a 5-percent solution of sodium hydroxide for 120-hours.

303.2.11.1. Rejection. Bar chairs may be rejected for failure to meet any of the requirements of this specification.

303.2.12. Joint Filler. Joint filler is the material placed in concrete pavement and concrete structures to allow for the expansion and contraction of the concrete.

303.2.12.1. Material. Expansion joint materials shall consist of boards or a premolded asphalt board tested in accordance with ASTM D545 Test Methods for Preformed Expansion Joint Fillers for Concrete Construction (Nonextruding and Resilient Types).

Boards for expansion joint filler shall be of the required size, shape and type indicated on the plans or required in the specifications. Boards shall be of selected stock of redwood, cypress, gum, southern yellow pine, or Douglas fir timber. The boards shall be sound heartwood and shall be free from sapwood, knots, clustered birdseyes, checks and splits. Occasional sound or hollow birdseyes, when not in clusters, shall be permitted, provided the board is free from any other effects that shall impair its usefulness as a joint filler. With the exception of redwood and cypress, all boards shall be preservative treated according to American Wood-Preservers' Association (AWPA) Standards.

Asphalt boards for expansion joint filler shall be of the required size and uniform thickness and, when used in transverse joints, they shall conform approximately to the shape of the pavement crown shown on the plans and details. Asphalt boards shall consist of two liners of 0.016 asphalt impregnated kraft paper filled with a mastic mixture of asphalt and vegetable fiber and/or mineral filler. Boards shall be smooth, flat and straight throughout, and shall be sufficiently rigid to permit ease of installation. Boards shall be furnished in lengths equal to the width between longitudinal joints, and may be furnished in strips or scored sheet of the required shape.

Asphalt boards, when tested in accordance with the following described methods, shall not deflect from the horizontal more than $\frac{3}{4}$ -inches in $3\frac{1}{2}$ -inches. A sample of the board, 2-in. wide and 6-in. long, flat, straight and cut with its length parallel to the lay of the fiber, shall be clamped between two blocks in the direction of its thickness in such manner that $3\frac{1}{2}$ -in. length of the sample shall extend unsupported and at right angles from the common plane of the block faces. The samples and clamp so assembled shall be maintained at a temperature of 180°F for 2-hours, with the length and width of the clamped portion of the sample horizontal after which the deflection from the horizontal of the unclamped portion shall be immediately measured.

303.2.12.2. Dimensions. The thickness of the expansion joint filler shall be shown on the plans; the width shall be not less than that shown on the plans, providing for the top seal space.

303.2.12.3. Rejection. Expansion joint filler may be rejected for failure to meet any of the requirements of this specification.

303.2.13. Curing Materials. This specification shall govern the materials to be used in the curing of concrete. The materials when applied as elsewhere specified shall retain the moisture, present in the concrete at the time of application of curing material, within specified limits for the curing period.

303.2.13.1. Material. Materials for the curing of concrete shall conform to the following requirements:

303.2.13.1.1. Membrane-Forming Compounds. The membrane curing compound shall conform to the requirements of ASTM C309 Liquid Membrane-Forming Compounds for Curing Concrete, Type 2, white pigmented compound, unless otherwise specified or indicated. It shall be of such nature that it shall not produce permanent discoloration of concrete surfaces nor react deleteriously with the concrete.

The compound shall produce a firm, continuous uniform moisture-impermeable film free from pinholes and shall adhere satisfactorily to the surfaces of damp concrete. It shall, when applied to the damp concrete surface at the specified rate of coverage, dry to touch in 1-hour and dry through in not more than 4-hours under normal conditions suitable for concrete operations. It shall adhere in a tenacious film without running off or appreciably sagging. It shall not disintegrate, check, peel or crack during the required curing period.

The compound shall not peel or pick up under traffic and shall disappear from the surface of the concrete by gradual disintegration.

The compound shall be delivered to the job site in the manufacturer's original containers only, which shall be clearly labeled with the manufacturer's name, the trade name of the material and a batch number or symbol with which test samples may be correlated.

When tested in accordance with ASTM C156 Water Retention by Concrete Curing Materials, the liquid membrane-forming compound shall restrict the loss of water present in the test specimen at the time of application of the curing compound to not more than 0.01-oz.-per-in² of surface.

303.2.13.1.2. Cotton Mats. The cotton mats used for curing shall meet the following requirements:

Each mat shall have a finished width of approximately 5-ft. 6-in.; and after shrinkage shall be at least 6-in. longer than the width of the concrete to be cured.

The mats shall be composed of a single layer of cotton filler, completely enclosed in a cover of cotton cloth. The cotton filler shall be of low-grade cotton, cotton linters of such shall contain not less than $\frac{3}{4}$ -pound of cotton filler per square-yard of mat, uniformly distributed. The cotton cloth used for covering material shall be Osnaburg, weighing not less than $6\frac{3}{10}$ -ounces-per-square-yard.

All mats shall be stitched longitudinally with continuous parallel rows of stitching at intervals of not more than 4-in. or shall be tufted both transversely and longitudinally at intervals of not more than 3-in. The sewing or tufting shall not be done so tightly that the mat shall not contact the surface of the concrete at all points when saturated with water.

To insure the complete covering of the concrete where the mats fit together, there shall be a flap extending all along one side of each mat. This flap shall be composed of two thicknesses of the cover material and shall be at least 6-in. in width.

303.2.13.1.3. Waterproof Paper. Waterproof paper shall consist of two sheets of plain kraft paper cemented together with a bituminous material in which are imbedded cords or strands of fiber running in both directions of the paper, not more than 1 $\frac{1}{4}$ -in. apart. The paper shall be light in color; shall be free of visible defects; and shall have a uniform appearance. It shall be sufficiently strong and tough to permit its use under the conditions existing on streets and structural work without tearing or otherwise becoming unfit for the use for which it is intended. The paper shall conform to specifications for ASTM C171 Sheet Materials for Curing Concrete.

When tested in accordance with ASTM C156 Water Retention by Concrete Curing Materials, the paper shall restrict the loss of water present in the test specimen at the time of application of the waterproof paper to not more than 0.055-grams-per-square-centimeter of surface.

303.2.13.1.4. Polyethylene Film. Polyethylene film shall be opaque pigmented white in color; and shall be manufactured from virgin resin without additives or scrap. The film shall have a minimum thickness of 4-mils. The permissible moisture loss from the concrete, when tested in accordance with ASTM C156 Water Retention by Concrete Curing Materials, shall not exceed 0.055-grams-per-square-centimeter of surface. The film shall be sufficiently strong and tough to permit its use under the conditions existing on paving or structural projects without being torn or otherwise rendered unfit

for the use intended during the curing period. It shall be of uniform thickness throughout, free of pinholes and other blemishes.

303.2.13.2. Rejection. Concrete curing materials may be rejected for failure to meet any of the requirements of this specification.

303.2.14. Joint Sealant. Joint sealing compound shall consist of hot poured polymer or ready-mixed cold-applied sealant, silicone joint sealant or other material approved by the OWNER. It shall not crack or break when exposed to low temperatures. The cured sealant must not pick up or “track” at elevated road temperature.

303.2.14.1. Materials.

303.2.14.1.1. Hot Poured Polymer. The joint sealing compound shall melt to the proper consistency for pouring and shall solidify on cooling to atmospheric temperatures. At no time shall the material be heated to temperature exceeding 450°F; any material heated above 450°F shall be rejected.

Hot poured polymer shall be tested in accordance with TxDOT Test Method Tex-525-C Tests for Asphalt and Concrete Joint Sealers and shall meet the requirements in Table 303.2.14.1.1.(a) Hot Poured Polymer Sealant Requirements.

Table 303.2.14.1.1.(a) Hot Poured Polymer Sealant Requirements

Property	Test Parameters	Required Result
Penetration	32°F , 7-oz. , 60-sec.	Minimum 0.1-in.
	77°F , 5-oz., 5-sec.	0.45- to 0.3-in.
Flow	5-hours, 140°F, 75° incline	Maximum 0.2-in.
Bond extension	15°F, 5-cycles	No cracking of the joint sealing material or break in the bond between the joint sealer material and the mortar pieces.

303.2.14.1.2. Ready-Mixed Cold-Applied. This sealant shall be a single component and shall consist of a homogeneous blend of asphalt emulsion, polymer, and inert filler. The material shall be a resilient, adhesive compound capable of effectively sealing properly cleaned joints and cracks in concrete and asphalt pavements against infiltration of moisture throughout repeated cycles of contraction and expansion and which shall not be picked up by vehicle tires, particularly at summer temperatures.

This Item covers an emulsion composed principally of a semi-solid asphalt base, water and emulsifying agent suitable for sealing cracks at ambient temperatures of 40°F and higher. The emulsion shall be modified with a polymer and shall be smooth and homogeneous, with no evidence of polymer separation.

The cold-applied crack sealant shall meet the requirements in Table 303.2.14.1.2.(a) Cold-Applied Sealant Requirements. Material shall be free-flowing down to 40°F, such that routine pavement joints and cracks are filled to a depth of 1½-in. without the addition of heat.

The material shall be furnished in 55-gallon drums.

Table 303.2.14.1.2.(a) Cold-Applied Sealant Requirements

Property	Test Method	Required Result	
		Minimum	Maximum
Viscosity ¹ , Brookfield, 77°F	ASTM D2196 Rheological Properties of Non-Newtonian Materials by Rotational (Brookfield type) Viscometer; Method A	6,000 Centipoise	25,000 Centipoise
Storage Stability Test, One-Day	AASHTO T59	-	1-Percent
Sieve Test	AASHTO T59	-	0.10-Percent
Evaporations ² and Tests on Residue			
Residue	See Note 2.	65-Percent	-
Penetration test on Residue, 77°F, 100g, 5-seconds	AASHTO T49	35 (0.1-mm)	75 (0.1-mm)
Softening Point test on Residue, R.&B.	AASHTO T53	140°F	-
Ductility test on Residue, 39.2°F, 5 cm/Min	AASHTO T51	100-cm	-

1. OWNER may require Viscosity Profile in lieu of single-spindle viscosity test, in which case the apparent viscosity shall be 10,000.

2. Residue may be obtained by the following evaporation procedure: Mass 200g of sealant into a 1000-ml beaker or a 1-quart can and place in a heating mantle designed for a 1000-ml beaker. During the evaporation the sealant should be stirred frequently to prevent foam-over or local overheating. The temperature shall be maintained between 260°F and 300°F for 3- to 5-minutes after the material is water free. Pour required specimen.

303.2.14.1.3. Thermoplastic Cold-Applied. If approved by the OWNER, thermoplastic cold-applied jointing material may be used according to manufacturer's recommendations.

303.2.14.2. Rejection. Materials may be rejected for failure to meet any of the requirements of this specification.

303.2.15. Elastomeric Materials. This material shall conform to the requirements of the TxDOT Item 435 Elastomeric Materials. This item shall govern for the materials, testing and fabrication of elastomeric materials, except as otherwise covered in other specifications or on the plans.

303.2.15.1. Rejection. Elastomeric materials may be rejected for failure to meet any of the requirements of this specification.

303.3. MIX DESIGN AND MIXING CONCRETE FOR PAVEMENT

303.3.1. Description. This section shall govern for the concrete in pavements.

303.3.2. Equipment. All machinery and equipment necessary for the prosecution of the work specified herein shall be on the project and shall be approved by the OWNER as to condition before the CONTRACTOR shall be permitted to begin operations on which the machinery or equipment is to be used. All machinery and equipment shall be maintained in good condition to insure the completion of the work without excessive delays for repairs and replacements.

303.3.3. Concrete Mix Design and Control. At least 10-days prior to the start of concrete paving operations, the CONTRACTOR shall submit to the OWNER a design of the concrete mix it proposes to use together with samples, if requested, of all materials to be incorporated into the mix and a full description of the source of supply of each material component. The proposed batch designs must be submitted to the OWNER on the approved form.

The design of the concrete mix shall produce a quality concrete complying with these specifications and meet the requirements of ACI 318 (most recent edition) - PART 3 Construction Requirements, CHAPTER 5, Concrete Quality, except as amended by these provisions. The concrete mix design shall include the following information:

- (1) Design Requirements and Design Summary
- (2) Material source
- (3) Dry weight of cement/cu. yd. and type
- (4) Dry weight of fly ash/cu. yd. and type, if used
- (5) Saturated surface dry weight of fine and coarse aggregates/cu. yd.
- (6) Design water/cu. yd.
- (7) Quantities, type, and name of admixtures with manufacturer's data sheets
- (8) Current strength tests or strength tests in accordance with ACI 318
- (9) Current Sieve Analysis and -200 Decantation of fine and coarse aggregates and date of tests
- (10) Fineness modulus of fine aggregate
- (11) Specific Gravity and Absorption Values of fine and coarse aggregates
- (12) L.A. Abrasion of coarse aggregates

All material samples submitted to the OWNER shall be sufficiently large to permit laboratory batching for the construction of test specimens to check the adequacy of the design. When the OWNER has approved the design mix, there shall be no change or deviation from the proportions thereof or sources of supply except as hereinafter provided. No concrete may be placed on the job site until the mix design has been approved by the OWNER in writing to the CONTRACTOR.

303.3.4. Quality of Concrete.

303.3.4.1. Consistency. In general, the consistency of concrete mixtures shall be such that:

- (1) the mortar shall cling to the coarse aggregate,
- (2) the aggregate shall not segregate in concrete when it is transported to the place of deposit,
- (3) the concrete, when dropped directly from the discharge chute of the mixer, shall flatten out at the center of the pile, but the edges of the pile shall stand and not flow,
- (4) the concrete and mortar shall show no free water when removed from the mixer,
- (5) the concrete shall slide and not flow into place when transported in metal chutes at an angle of 30° with the horizontal,
- (6) the surface of the finished concrete shall be free from a surface film or laitance, and
- (7) the concrete shall be uniform and workable.

The consistency of the concrete as placed should allow the completion of all finishing operations without the addition of water to the surface. When field conditions are such that additional moisture is needed for the final concrete surface finishing operation, the required water shall be applied to the surface by fog spray only; and shall be held to a minimum amount. The concrete shall be workable, cohesive, possess satisfactory finishing qualities and be of the stiffest consistency that can be placed and vibrated into a homogeneous mass. Excessive bleeding shall be avoided.

If the strength or consistency required for the class of concrete being produced is not secured with the minimum cement specified or without exceeding the maximum water/cement ratio, the CONTRACTOR may use, or the OWNER may require, an approved cement dispersing agent (water reducer); or the CONTRACTOR shall furnish additional aggregates, or aggregates with different characteristics, or the CONTRACTOR may use additional cement in order to produce the required results. The additional cement may be permitted as a temporary measure, until aggregates are changed and designs checked with the different aggregates or cement dispersing agent.

The CONTRACTOR is solely responsible for the quality of the concrete produced. The OWNER reserves the right to independently verify the quality of the concrete through inspection of the batch plant, testing of the various materials used in the concrete and by casting and testing concrete cylinders or beams on the concrete actually incorporated in the pavement.

303.3.4.2. Standard Classes. Unless otherwise shown on the plans or detailed specifications, the Standard Classes of Pavement Concrete shown in Table 303.3.4.2.(a) shall be used.

Streets, alleys, driveways, and inlets shall be constructed in accordance with these specifications using the classes of concrete, machine or hand finished, whichever is appropriate. Mass pour medians, noses, and islands shall use hand-finished concrete.

The testing does not in any way change the penalties imposed on the CONTRACTOR for deficient strength outlined elsewhere in these specifications.

Table 303.3.4.2.(a) Standard Classes of Pavement Concrete.

Class of Concrete ¹	Minimum Cementitious Lb./CY	28 Day Min. Compressive Strength ² psi	28 Day Min. Beam Strength ^{2,3} psi	Maximum Water/ Cementitious Ratio	Coarse Aggregate Maximum Size ⁴
A ⁵	470	3000	500	0.58	1½"
C	564	3600	600	0.53	1½"
P1 ⁶	517	4000	N/A	0.49	1½"
P2 ⁷	564	4500	N/A	0.45	1½"
M	As directed by the OWNER or as shown on the plans				

1. All exposed horizontal concrete shall have entrained – air.
2. Minimum Strength Required by OWNER [Compressive or Flexural]
3. ASTM C78 (Third-Point); Reduce by 10% when Type II Cement is Used
4. Smaller nominal maximum size aggregate may be used if strength requirement is satisfied
5. Sidewalks, separate curb and gutter, and 4-inch thick median pavement
6. Machine Finished
7. Hand Finished

303.3.4.3. Performance Classes. Performance Classes of structural concrete shall meet the requirements in Table 303.3.4.3.(a) Performance Classes of Pavement Concrete.

Table 303.3.4.3.(a) Performance Classes of Pavement Concrete

Class of Concrete ¹	Minimum Cementitious Lb./CY	28-Day Compressive Strength psi	28-Day Flexural Strength ^{2,3} psi	Maximum Water/ Cementitious Ratio ⁴	Coarse Aggregate Maximum Size ⁵
PA	423	3000 ⁶	425	0.58	1½"
PC	517	3600 ⁶	510	0.53	1½"
PP1 ⁷	517	4000	N/A	0.48	1½"
PP2 ⁸	564	4500	N/A	0.44	1½"
PM	As directed by the OWNER or as shown on the plans				

1. All exposed horizontal concrete shall have entrained – air.
2. ASTM C78 (Third-Point); Reduce by 10% when Type II Cement is used
3. For early form removal
4. Consistent with ACI 211.1 Table 6.3.4(a) Relationship between water-cementitious materials ratio and compressive strength of concrete
5. Smaller nominal maximum size aggregate may be used if Strength requirement is satisfied
6. Calculated Average Required Compressive Strength Considering ACI 318 - Sec. 5.3.2.1 shall be strength shown times 1.15
7. Machine Finish
8. Hand Finish

303.3.4.4. Slump. Slump requirements for pavement and related concrete shall be as specified in Table 303.3.4.4.(a) Pavement Concrete Slump Requirements. No concrete shall be permitted with slump in excess of the maximums shown. Any concrete mix failing to meet the above consistency requirements, although meeting the slump requirements, shall be considered unsatisfactory, and the mix shall be changed to correct such unsatisfactory conditions.

Table 303.3.4.4.(a) Structural Concrete Slump Requirements.

Concrete Use	Avg. Slump (in.)	Max. Slump (in.)
Slip Form Paving	3	4
Hand formed paving	4	5
Sidewalk, Separate Curb and Gutter, and Other Miscellaneous Concrete	As specified by OWNER	

303.3.5. Mixing and Delivery. The concrete shall be produced in an approved method conforming to the requirements of this specification and ASTM C94/C94M Standard Specification for Ready-Mixed Concrete or National Ready-mixed Concrete Association (NRMCA). Ready-mix concrete shall be permitted in lieu of the paver-mixer. When ready-mix concrete is used, sampling provisions of ASTM C94 Alternate Procedure 2 shall govern. If fiber-reinforced concrete is used, mixing shall be in accordance with ASTM C1116 Fiber-Reinforced Concrete and Shotcrete. All materials for concrete placed in pavements shall conform to the requirements of the governing item of this specification.

303.3.5.1. Batch Mixing. The concrete shall be mixed in a batch mixer and only in such quantities as are required for immediate use. The mixing of each batch, after all materials are in the drum, shall continue until it produces a thoroughly mixed concrete of uniform mass as determined by established mixer performance ratings and inspection, or appropriate uniformity tests as described in ASTM C94. The entire contents of the drum shall be discharged before any materials are placed therein for the succeeding batch. Retempering or remixing shall not be permitted.

303.3.5.1.1. Mixer. The mixer shall produce concrete of uniform consistency and appearance.

303.3.5.1.2. Cleaning. The mixer shall be cleaned thoroughly each time when out of operation for more than 30 minutes.

303.3.5.2. Transit Mixing. When transit mixing is used, the transit mixer shall be of an approved revolving drum or revolving blade type so constructed as to produce a thoroughly mixed concrete with a uniform distribution of the materials throughout the mass and shall be equipped with a discharge mechanism which shall insure the discharging of the mixed concrete without segregation.

303.3.5.2.1. Prevention of Leaking. The mixer drum shall be watertight when closed and shall be equipped with a locking device that shall automatically prevent the discharging of the mixer prior to receiving the required number of revolutions.

303.3.5.2.2. Mixing. The entire quantity of mixing water shall be accurately measured by a visible calibrated mechanism. Leaking water valves shall be considered as ample reason for condemnation of the mixer unit and removal from the job by the OWNER. Each batch shall be mixed not less than 70 nor more than 100 revolutions at the rate of rotation specified by the manufacturer as mixing speed. Any additional mixing shall be done at a slower speed specified by the manufacturer for agitation and shall be continuous until the batch is discharged.

303.3.5.2.3. Counters. Truck mixers shall be equipped with actuated counters by which the numbers of revolutions of the drum may be readily verified. The counters shall be actuated at the time of starting mixing at mixing speeds.

303.3.5.2.4. Delivery. The rate of delivery of the mixed concrete shall be such that the interval between loads shall not exceed 10-minutes. The concrete shall be delivered to the site of the work and discharged from the mixer before the drum has been revolved 300 revolutions, after the introduction of the mixing water with the dry materials.

303.3.5.3. Central Mixing Plant. A central mixing plant shall be allowed, provided the method of mixing and handling has first been approved by the OWNER.

303.3.5.4. Commercial Concrete Plants. In the event the CONTRACTOR elects to use concrete produced by a commercial concrete plant, an agreement shall be drawn and executed by the responsible executive management of said plant granting the OWNER ingress and egress to all parts of the plant with full authority to make any and all required tests of aggregates and to regulate and control

all batching plant and/or central mixing plant operations. This regulatory control shall be applicable only to the concrete produced by the commercial plant for the payment herein specified.

303.3.5.5. Delivery Tickets. For transit mix operations, the manufacturer of the concrete shall, before unloading, furnish to the purchaser with each batch of concrete at the site a delivery ticket on which is printed, stamped, or written, the following information to determine that the concrete was proportioned in accordance with the approved mix design:

- (1) Name of concrete supplier
- (2) Serial number of ticket
- (3) Date
- (4) Truck number
- (5) Name of purchaser
- (6) Specific designation of job (name and location)
- (7) Specific class, design identification and designation of the concrete in conformance with that employed in job specifications
- (8) Amount of concrete in cubic yards (or cubic meters)
- (9) Time loaded or of first mixing of cement and aggregates
- (10) Water added by receiver of concrete and his/her initials
- (11) Weight of cement
- (12) Weight of fly ash
- (13) Type and amount of admixtures
- (14) Information necessary to calculate the total mixing water added by the producer (total mixing water includes free water on the aggregates, water and ice batched at the plant, and water added by the truck operator from the mixer tank);
- (15) Maximum size of aggregate
- (16) Weights of fine and coarse aggregate

For on-site concrete plant operations, the CONTRACTOR shall supply to the OWNER a batch ticket with the following information and for each continuous paving operation, provide receipts and invoices to substantiate the amounts of cement and fly ash used in the placement.

- (1) At the beginning of each day's placement, a list of the actual batch weights to be used shall be given to the OWNER.
- (2) When any changes are made, a new list of weights shall be given to the OWNER.

303.4. EQUIPMENT

303.4.1. General. All equipment necessary for the construction of this item shall be on the project and shall be approved by the OWNER as to condition before the CONTRACTOR shall be permitted to begin construction operations on which the equipment is to be used.

303.4.2. Field Laboratory. A field laboratory structure shall be required only when specifically required and provided for in the special provisions.

303.4.3. Slip Form Paver. Slip form paving equipment shall be provided with traveling side forms of sufficient dimensions, shape and strength so as to support the concrete laterally for a sufficient length of time during placement to produce pavement of the required cross section. The equipment shall spread, consolidate, screed and float-finish the freshly placed concrete in such a manner as to provide a dense and homogeneous pavement.

303.4.4. Forms. The side forms shall be metal, of approved cross section and bracing, of a height not less than the prescribed edge thickness of the concrete section, and a minimum of 10-ft. in length for each individual form. Forms shall be of ample strength and shall be provided with adequate devices for secure setting so that when in place they shall withstand the impact and vibration of equipment imposed thereupon without appreciable springing or settlement. In no case shall the base width be less than 8-in. for a form 8-in. or more in height. The forms shall be free from warps, bends or kinks and shall show no variation from the true plane for face or top. Each 10-ft. length of forms shall be provided with at least 3 pins for securely staking in position. Sufficient forms shall be provided for satisfactory prosecution of the work. 10-ft. metal

form sections shall be used in forming curves with a 250-ft., and larger radius. For curves with a radius of less than 250-ft., acceptable flexible metal forms or wood forms may be used upon approval by the OWNER.

303.4.5. Mechanical Vibratory Equipment. All concrete placed for pavement shall be consolidated by approved mechanical vibrators operated ahead of the transverse finishing machine and designed to vibrate the concrete internally and/or from the surface. Unless otherwise shown on the plans, vibrators of the surface-pan type shall be used for full-depth placement. Both types of vibrators shall be furnished and may be used concurrently at the discretion of the OWNER. Vibratory members shall extend across the pavement practically to, but shall not come in contact with, the side forms. Mechanically-operated vibrators shall be mounted in such a manner as not to interfere with the transverse or longitudinal joints.

The internal-type vibrators shall be spaced at not more than 24-in. and shall be equipped with synchronized vibratory units. Separate Vibratory units shall be spaced at sufficiently close intervals to provide uniform vibration and consolidation to the entire width of the pavement. The frequency in air of the internal spud-type Vibratory units shall be not less than 8,000-cycles-per-minute and not less than 5,000-cycles-per-minute for tube types. The method of operation shall be as directed by the OWNER. The CONTRACTOR shall have a satisfactory tachometer available for checking the vibratory elements.

The pavement vibrators shall not be used to level or spread the concrete but shall be used only for purposes of consolidation. The vibrators shall not be operated where the surface of the concrete, as spread, is below the elevation of the finished surface of the pavement, except for the first lift of concrete where the double strike-off method of placement is employed. The vibrators shall not be operated for more than 15-seconds while the machine upon which they are installed is still.

The pan-type vibrator units shall apply the vibrating impulses directly to the surface of the concrete. The operating frequency shall not be less than 3,500-cycles- nor more than 4,200-cycles-per-minute in air. The CONTRACTOR shall have a satisfactory tachometer available for checking the speed of the vibratory elements.

Approved hand manipulated mechanical vibrators shall be furnished in the number required for provision of proper consolidation of the concrete along the forms, at joints and in areas not covered by mechanically controlled vibrators. These vibrators shall be sufficiently rigid to insure control of the operating position of the vibrating head.

Complete and satisfactory consolidation of the concrete pavement is a most important requirement of this specification. Cores taken as required by [Item 303.8](#). Pavement Testing and Evaluation shall be carefully examined for voids, honeycombing or other evidence of incomplete consolidation. If such evidence is present, changes in the consolidation procedures and/or equipment shall be made to insure satisfactory consolidation.

303.4.6. Vibrating Screed. The mechanically vibrated screed shall be provided with a template adjusted to the crown of the concrete section. The template shall be power vibrated, adjustable in height and mounted to ride on the forms. The mechanical vibration of one of the screeds on the transverse finishing machine specified in [Item 303.4.7](#). Transverse Finishing Machine shall be acceptable.

303.4.7. Transverse Finishing Machine. The transverse finishing machine shall be provided with two screeds accurately adjusted to the crown of the pavement, shall be power driven and mounted in a substantial frame equipped to ride on the forms. The machine shall be so designed and operated as to strike off and consolidate the concrete.

Finishing machines shall be maintained in a tight and good operating condition, accurately adjusted to the required crown or profile and free from deflection, wobble or vibration tending to affect the surface finish. Machines failing to meet these requirements shall be rejected by the OWNER, and the CONTRACTOR shall provide approved equipment.

303.4.8. Miscellaneous Finishing Equipment. The CONTRACTOR shall furnish a broom of the push broom type not less than 18-in. in width with stiff bristles for the final surface finish of concrete base or as the OWNER directs.

The CONTRACTOR shall furnish a sufficient number of bridges equipped to ride on the forms and span the pavement for finishing operations and for the installation and finishing of joints. The CONTRACTOR shall furnish, operate and maintain at least two standard 10-ft. steel straightedges and all necessary finishing and edging tools as may be required to complete the pavement in accordance with the plans and specifications.

303.5. CONSTRUCTION METHODS

303.5.1. Subgrade. When manipulation or treatment of subgrade is required on the plans, the work shall be performed in proper sequence with the preparation of the subgrade for pavement.

The roadbed shall be excavated and shaped in conformity with the typical sections and to the lines and grades shown on the plans or established by the OWNER. Material excavated in the preparation of the roadbed in excess of that needed to properly construct the subgrade, shoulders, slopes or parkway shall be wasted. If additional material is required, it shall be secured from sources indicated on the plans or designated by the OWNER. All holes, ruts and depressions shall be filled with suitable material and, if required, the subgrade shall be thoroughly wetted and reshaped. Irregularities of more than ½-in., as shown by straightedge or template, shall be corrected. The subgrade shall be uniformly compacted to at least 95-percent of the maximum density as determined by ASTM D698 Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³). Moisture content shall be within minus-2%- to plus-4%-of-optimum. The prepared subgrade shall be wetted down sufficiently in advance of placing the pavement to insure its being in a firm and moist condition for at least 2-in. below the surface. Sufficient subgrade shall be prepared in advance to insure satisfactory prosecution of the work. No hauling or equipment shall be permitted on the finished subgrade.

The CONTRACTOR shall notify the OWNER at least three working days in advance of its intention to place concrete pavement.

Density tests must be taken no more than 72-hours prior to placement of concrete. After the specified moisture and density are achieved, the CONTRACTOR shall maintain the subgrade moisture and density in accordance with [Item 301](#). Subgrade, Subbase, and Base Preparation until the pavement is placed. In the event that rain or other conditions may have adversely affected the condition of the subgrade or base, additional tests may be required as directed by the OWNER.

303.5.2. Placing and Removing Forms. Forms shall be set to line and grade at least 200-ft., where practicable, in advance of the paving operations. Forms shall be adequately staked with at least three pins per 10-ft. section and capable of resisting the pressure of concrete placed against them and the thrust and the vibration of the construction equipment operating upon them without appreciable springing or settlement. Forms shall be jointed neatly and tightly and set with exactness to the established grade and alignment. Forms must be in firm contact with the subgrade throughout their length and base width. If the subgrade becomes unstable, forms shall be reset, using heavy stakes, or other additional supports may be necessary to provide the required stability.

303.5.2.1. Settling. When forms settle over ¼-in. under finishing operations, paving operations shall be stopped, the forms reset to line and grade and the pavement then brought to the required section and thickness.

303.5.2.2. Cleaning and Oiling. Forms shall be thoroughly cleaned after each use and well-oiled before reuse.

303.5.2.3. Removal. Forms shall remain in place a minimum of twelve hours or more as required by the OWNER. At the time the forms are removed, any honeycomb shall be rubbed with grout and sealed with a curing compound.

303.5.2.4. Curb. Superimposed or monolithic curb shall be formed from the flowline of the gutter to the top of the curb. All expansion joints in the curbs shall conform to the joint locations in the slab.

303.5.3. Placing Reinforcing Steel, Tie, and Dowel Bars. When reinforcing steel, welded wire mesh, tie bars, dowels, etc., are required, they shall be placed as shown on the plans. All reinforcing shall be clean, free from rust in the form of loose or objectionable scale, and of the type, size and dimensions shown on the plans. Reinforcing bars shall be securely wired together at the alternate intersections and all splices and shall be securely wired to each intersection dowel and load-transmission unit intersected. All bars shall be installed in their required position as shown on the plans.

The storing of reinforcing or structural steel on completed roadway slabs generally shall be avoided and, where permitted, such storage shall be limited to quantities and distribution that shall not induce excessive stresses.

303.5.3.1. Installation. All reinforcing bars and bar mats shall be installed in the slab at the required depth below the finished surface and supported by and securely attached to bar chairs installed on prescribed longitudinal and transverse centers as shown by sectional and detailed drawings on the plans. After the reinforcing steel is securely installed above the subgrade, as specifically required by plans and as herein prescribed, there shall be no loading imposed upon (or walking upon) the bar mats or individual bars before or during the placing or finishing of the concrete.

303.5.3.2. Welded Wire Mats. Where welded wire fabric reinforcement mats are required by the plans, or permitted as an alternate by the OWNER, the concrete shall be placed and struck off by means of a template to the depth below the finished surface as specified for the location of the mesh. Welded wire mats, conforming to the specified side lap and end splice requirements as detailed on the plans, shall be placed upon the struck surface. The remainder of the concrete shall be placed thereupon with finishing operations proceeding immediately. There shall be no loading imposed upon the mesh mats after installation in the slab concrete.

303.5.3.3. Assembly. Expansion joints or dummy joints which may require an assembly of parts supported by special devices shall be completely assembled and rigidly supported in the correct position well in advance of the placing of concrete.

303.5.4. Joints.

303.5.4.1. Joint Dimensions. The width of the joint shall be shown on the plans, creating the joint sealant reservoir. The depth of the joint shall be shown on the plans. Dimensions of the sealant reservoir shall be in accordance with manufacturer's recommendations. Normal width/depth ratios are 1 to 1, not to exceed 1 to 1½. After curing, the joint sealant shall be ⅛-in. to ¼-in. below the pavement surface at the center of the joint.

303.5.4.2. Expansion Joints. Expansion joints shall be installed perpendicularly to the surface and to the centerline of the pavement at the locations shown on the plans.

Refer to [Item 702.5.4.1](#). Expansion Joints for more information.

303.5.4.2.1. Joint Filler. Joint filler shall be as specified in [Item 303.2.12](#). Joint Filler, as approved by OWNER, of the size and shape shown on the plans.

Board joint material with less than 25-percent of moisture at the time of installation shall be thoroughly wetted on the job. Green lumber of much higher moisture content is desirable and acceptable.

The joint filler shall be appropriately drilled to admit the dowel bars when required. The bottom edge of the filler shall extend to or slightly below the bottom of the slab. The top edge shall be held approximately ½-in. below the finished surface of the pavement in order to allow the finishing operations to be continuous. Where the joint filler is of a premolded asphaltic type, the top edge shall be protected, while the concrete is being placed and finished, by a metal cap of at least 10 gauge material having flanges not less than 1½-in. in depth. The channel cap may remain in place during the joint finishing operations to serve as a guide for tooling the edges of the joint. After the removal of the side forms, the ends of the joints at the edges of the slab shall be carefully opened for the entire depth of the slab.

303.5.4.2.2. Curb. Where a superimposed curb or a separate curb and gutter may be used, the expansion joints therein shall coincide and be continuous with the pavement joint and of the same size and type.

303.5.4.2.3. Proximity to Existing Structures. When the pavement is adjacent to or around existing structures, expansion joints shall be constructed in accordance with the details shown on the plans.

303.5.4.2.4. Dowel Bars. Dowel bars, where required on the plans, shall be installed through the predrilled joint filler and rigidly supported in true horizontal and vertical positions by an assembly of bar chairs and dowel holders welded to transverse bars extending across the slab and placed on each side of the joint. The chair assembly shall be similar and equal to that shown on the plans and shall be approved by the OWNER prior to extensive fabrication.

303.5.4.3. Contraction Joints. Contraction or dummy joints shall be installed at the locations and at the intervals shown on the plans in accordance with this section and [Item 402.3](#), Sawing. The joints shall be constructed by sawing to a ¼-in. width and to a depth of ¼ of the pavement thickness, or deeper if so indicated on the plans. Unless otherwise specified on the plans, joints shall be sawed into the completed pavement surface as soon after initial concrete set as possible so that some raveling of the green concrete is observed in order for the sawing process to prevent uncontrolled shrinkage cracking. If sharp edge joints are being obtained, the sawing process shall be sped up to the point where some raveling is observed. Damage by blade action to the slab surface and to the concrete immediately adjacent to the joint shall be minimized. Any portion of the curing membrane which has been disturbed by sawing operations shall be restored by spraying the areas with additional curing compound. The sawed groove shall immediately be thoroughly cleaned for the full depth and width of the joint and filled. The type of equipment and method for performing this work shall be approved by the OWNER.

303.5.4.4. Construction Joints. Construction joints formed at the close of each day's work or when the placing of concrete has been stopped for 30-minutes or longer shall be constructed by use of metal or wooden bulkheads cut true to the section of the finished pavement and cleaned and oiled. Wooden bulkheads shall have a thickness of not less than 1½-in. Longitudinal bars shall be held securely in place in a plane perpendicular to the surface and at right angles to the centerline of the pavement. Edges shall be rounded to ¼-in. radius. Any surplus concrete on the subgrade shall be removed upon the resumption of the work.

In no case shall an emergency construction joint be placed within 8-ft. following a regular installation of expansion or contraction joint. If the emergency construction joint should fall within this limitation, the concrete shall be removed back to the previously installed joint.

Refer to [Item 702.5.4.2](#), Construction Joints for more information.

303.5.4.5. Longitudinal Parting Strips. Longitudinal parting strips or planes of weakness, when required, shall be accurately placed as shown on the plans.

303.5.4.6. Longitudinal Construction Joints. Longitudinal construction joints shall be of the type shown on the plans. Longitudinal joints shall be constructed accurately to required lines in order to coincide with traffic lane lines. No width between longitudinal construction joints shall exceed 24-ft., unless specifically authorized or directed by the OWNER in writing.

303.5.4.7. Joint Sealing. Routine pavement joints shall be filled to a depth of 1½-in. Materials shall generally be handled and applied according to the manufacturer's recommendations, with additional requirements as stated herein.

303.5.4.7.1. Hot Poured Polymer. The sealing filler shall be melted in an approved oil-batch kettle with continuous mechanical agitation. The kettle shall be equipped with temperature indicators. The OWNER shall determine the optimum temperature for proper pouring fluidity, and the CONTRACTOR shall maintain the material within close range of optimum temperature. At no time shall the temperature exceed 450°F. Joint sealing compound shall not be poured at atmospheric temperatures below 32°F.

303.5.4.7.2. Ready-Mixed Cold-Applied. Permeation of joints shall principally be achieved without the task of squeegeeing. However, squeegeeing is recommended to assist permeation and to allow sealant to become rapidly tack-free. Sealant shall "set" in a fixed position within 40-minutes after application, to where traffic may be restored to the pavement without the effects of "tracking." "Tracking" shall be averted without the use of topping materials such as sand.

303.5.5. Placing Concrete. Unless otherwise shown on the plans, the concrete shall be placed using either forms or slipform paver. The concrete shall be rapidly deposited on the subgrade in successive batches and shall be distributed to the required depth and for the entire width of the pavement by shoveling or other approved methods. Any concrete not placed as herein prescribed within the time limits specified in Table 303.5.5.(a) Concrete Placement will be rejected.

**Table 303.5.5.(a) Concrete Placement
Temperature –Time Requirements**

Concrete Temp (at point of placement)	Max Time - minutes (no retarding agent)	Max Time – minutes (with retarding agent) ¹
Non-Agitated Concrete		
All temperatures	30	45
Agitated Concrete		
Above 90°F	45	75
Above 75 F thru 90°F	60	90
75°F and Below	90	120

1. Normal dosage of retarder.

Where bar mats or wire mesh reinforcing is specified, method of concrete placement shall be in accordance with [Item 303.5.3](#), Placing Reinforcing Steel, Tie, and Dowel Bars. Rakes shall not be used in handling concrete. The placing operation shall be continuous. At the end of the day, or in case of unavoidable interruption or delay of more than 30-minutes, a transverse construction joint shall be placed in accordance with [Item 303.5.4.4](#), Construction Joints.

303.5.5.1. Honeycombing. Special care shall be taken in placing and spading the concrete against the forms and at all joints and assemblies so as to prevent honeycombing. Excessive voids and honeycombing in the edge of the pavement, revealed by the removal of the side forms, may be cause for rejection of the section of slab in which the defect occurs.

303.5.5.2. Weather Conditions. Except by specific written authorization of the OWNER, no concrete shall be placed when the air temperature is less than 40°F and falling but may be placed when the air temperature is above 35°F and rising, the temperature being taken in the shade away from artificial heat. When and if such permission is granted, the CONTRACTOR shall furnish sufficient protective material and devices to enclose and protect the fresh concrete in such a way as to maintain the temperature of the air surrounding the fresh concrete at not less than 50°F for a period of at least 5-days.

Except by specific written authorization of the OWNER, no concrete shall be placed when the concrete temperature is higher than 95°F. CONTRACTOR shall take appropriate measures including chilling and reduction of time intervals between batching and placing.

It is to be distinctly understood that the CONTRACTOR is responsible for the quality and strength of the concrete placed under any weather conditions. No concrete shall be placed on a frozen subgrade.

303.5.5.3. Time. Concrete shall not be placed before the time of sunrise and the surface finishing shall be completed prior to sunset unless otherwise authorized by the OWNER.

303.5.6. Finishing.

303.5.6.1. Machine. When the concrete has been deposited, it shall be approximately leveled and then struck off to such elevation that, when mechanically screeded and tamped, the concrete shall be thoroughly compacted and finished to the required line, grade and section with all surface voids filled. Where bar mats or wire mesh reinforcing is specified, method shall be in accordance with [Item 303.5.3](#), Placing Reinforcing Steel, Tie, and Dowel Bars.

303.5.6.1.1. Tolerance Limits. While the concrete is still workable, it shall be tested for irregularities with a 10-ft. straightedge placed parallel to the centerline of the pavement so as to bridge depressions and to touch all high spots. Ordinates measured from the face of the straightedge to the surface of the pavement shall at no place exceed $\frac{1}{16}$ inch-per-foot from the nearest point of contact. In no case shall the maximum ordinate to a 10-ft. straightedge be greater than $\frac{1}{8}$ -in. Any surface not within the tolerance limits shall be reworked and refinished.

303.5.6.1.2. Edging. The edges of slabs and all joints requiring edging shall be carefully tooled with an edger of the radius required by the plans at the time the concrete begins to take its "set" and becomes non-workable. All such work shall be left smooth and true to lines.

303.5.6.1.3. Stamp or Die. All concrete including curbs, curb with gutter, sidewalks, alleys, driveways and structures shall be marked by means of a substantial stamp or die so designed to make an impression in the finish of the concrete. The stamp or die shall designate the firm name or CONTRACTOR and the month and year in which the work was done. The design of the stamp or die shall be approved by the OWNER.

303.5.6.2. Hand. Hand finishing shall be permitted only in intersections and areas inaccessible to a finishing machine. The addition of one-sack of cement per cubic-yard shall be required for all hand finish concrete.

When the hand method of striking off and consolidating is permitted, the concrete, as soon as placed, shall be approximately leveled and then struck off and screeded to such elevation above grade that, when consolidated and finished, the surface of the pavement shall be at the grade elevation shown on the plans. The entire surface shall then be tamped and the concrete consolidated so as to insure maximum compaction and a minimum of voids. For the strike off and consolidation, both a strike template and tamping template shall be provided on the work. In operation the strike template shall be moved forward with a combined longitudinal and transverse motion and so manipulated that neither end of the template is raised from the forms during the striking-off process. A slight excess of material shall be kept in front of the cutting edge at all times.

The straightedge and joint finishing shall be as hereinabove prescribed.

303.5.7. Curing. The curing of concrete pavement shall be thorough and continuous throughout the entire curing period. Failure to provide proper curing as herein prescribed shall be considered as sufficient cause for immediate suspension of the paving operations. The curing method as herein specified does not preclude the use of any of the other commonly used methods of curing, and the OWNER may approve another method of curing if so requested by the CONTRACTOR. If any selected method of curing does not afford the desired results, the OWNER shall have the right to order that another method of curing be instituted. Immediately after the finishing of the surface, the pavement shall be covered with a continuous, uniform water-impermeable coating of the type specified in [Item 303.2.13](#). Curing Materials. After removal of the side forms, the sides of the slab shall receive a like coating before earth is banked against them. The solution shall be applied, under pressure with a spray nozzle, in such a manner as to cover the entire surfaces thoroughly and completely with a uniform film.

The rate of application shall be such as to insure complete coverage and shall not exceed 200-square-feet-per-gallon of curing compound. When thoroughly dry, it shall provide a continuous and flexible membrane, free from cracks or pinholes, and shall not disintegrate, check, peel or crack during the curing period. If for any reason the seal is broken during the curing period, it shall be immediately repaired with additional sealing solution.

When tested in accordance with ASTM C156 Water Retention by Concrete Curing Materials, the curing compound shall provide a film which shall have retained within the test specimen a percentage of the moisture present in the specimen when the curing compound was applied according to Table 303.5.7.(a) Water Retention by Curing Materials.

Table 303.5.7.(a) Water Retention by Curing Materials

Time	Minimum Retained Moisture
After 24-hours	97%
After 3-days	95%
After 7-days	91%

303.5.8. Opening Pavement to Traffic. All traffic shall be excluded from the pavement for a period of not less than 14-days or until field cured test specimens indicate concrete meets at least 75% of design strength, or as otherwise approved by the OWNER. In all cases the pavement shall be cleaned and joints shall be filled and trimmed before being opened to traffic.

303.5.8.1. Traffic Access. When it is necessary to provide for traffic across the pavement, the CONTRACTOR shall, at its own expense, construct suitable and substantial crossings over the concrete which shall be adequate for the traffic using same.

303.5.8.2. Time. Opening pavement to traffic shall not relieve the CONTRACTOR of responsibility for the work and shall not in any way affect the time charge on the entire project. The number of days stated in the contract shall govern for the completion of the entire work covered by the contract.

303.5.9. Monolithic Curb. Concrete for monolithic curb shall be the same as for the pavement and, if carried back from the paving mixer, shall be placed within 20-minutes after being mixed. Concrete may be placed from the separate mixer if desired but in any case must be placed while the pavement concrete is still plastic. After the concrete has been struck off and sufficiently set, the exposed surfaces shall be thoroughly worked with a float. The exposed edges shall be rounded by the use of an edging tool to the radius indicated on the plans. When the concrete in the curb has been sufficiently set, the inside form shall be carefully removed and the surface may be plastered with a mortar consisting of one part of Portland cement and two parts fine aggregate. The mortar shall be applied with a template or "mule" made to conform to curb dimensions. All exposed surfaces of curb shall be brushed to a smooth and uniform surface.

303.5.10. Superimposed Curb. When sawed joints are used, curbs shall be doweled as shown on the plans and poured after sawing. Doweled curbs which are placed with an extrusion machine shall have a mixture that conforms to [Item 303.3](#). Mix Design and Mixing Concrete for Pavement.

303.5.11. Slip Form Paving. At the option of the CONTRACTOR, and with the approval of the OWNER, concrete pavement may be constructed by the use of slip form paving equipment.

The concrete, for the full paving width, shall be effectively consolidated by internal vibration with transverse vibrating units or with a series of longitudinal vibrating units loaded with the specified thickness of pavement section and at a minimum distance ahead of the screed equal to the pavement thickness.

When concrete is being placed adjacent to an existing pavement, that part of the equipment which is supported on the existing pavement shall be equipped with protective pads on crawler tracks or rubber-tired wheels offset to run a sufficient distance from the edge of the pavement to avoid breaking or cracking the pavement edge.

Final finishing for slip form pavement construction shall be to the tolerance as specified in [Item 303.5.6](#). Finishing.

303.6. ALLEY PAVING

Alley paving shall be constructed in accordance with the specifications for street paving hereinbefore described, in accordance with the details shown on the plans, and with the following additional provisions:

Alley paving shall be constructed to one of the typical cross sections shown on the plans.

Transverse expansion joints of the type shown on the plans shall be constructed at the property line on each end of the alley with a maximum spacing of 600-ft. Transverse contraction and dummy joints shall be placed at the spacing shown on the plans. Contraction and dummy joints shall be formed in such a manner that the required joints shall be produced to the satisfaction of the OWNER. All joints shall be filled with top seal in accordance with the requirements of [Item 303.5.4](#). Joints.

303.7. PAVEMENT LEAVEOUTS

Pavement leaveouts as necessary to maintain and provide for local traffic shall be provided at location indicated on the plans or as directed by the OWNER. The extent and location of each leaveout required and a suitable crossover connection to provide for traffic movements shall be determined in the field by the OWNER. Left or right-turn lanes and median openings shall not be considered as pavement leaveouts.

303.8. PAVEMENT TESTING AND EVALUATION

303.8.1. Testing of Materials. Samples of all materials for test shall be made at the expense of the OWNER, unless otherwise specified in the special provisions or in the plans. In the event the initial sampling and testing does not comply with the specifications, all subsequent testing of the material in order to determine if the material is acceptable shall be at the CONTRACTOR'S expense at the same rate charged by the

commercial laboratories. All testing shall be in accordance with applicable ASTM Standards and concrete testing technician must be ACI certified or equivalent.

303.8.2. Pavement Thickness Test. Upon completion of the work and before final acceptance and final payment shall be made, pavement thickness test shall be made by the OWNER. The number of tests and location shall be at the discretion of the OWNER, unless otherwise specified in the special provisions or on the plans. The cost for the initial pavement thickness test shall be the expense of the OWNER. In the event a deficiency in the thickness of pavement is revealed during normal testing operations, subsequent tests necessary to isolate the deficiency shall be at the CONTRACTOR'S expense. The cost for additional coring test shall be at the same rate charged by commercial laboratories.

Where the average thickness of pavement in the area found to be deficient in thickness by more than 0.20-in., but not more than 0.50-in., upon discretion of the OWNER payment shall be made at an adjusted price as specified in Table 303.8.2.(a) Concrete Pavement Deficiency.

Table 303.8.2.(a) Concrete Pavement Deficiency

Deficiency in Thickness Determined By Cores	Proportional Part of Contract Price
Inches	Allowed
0.00 — 0.20	100 percent
0.21 — 0.30	80 percent
0.31 — 0.40	70 percent
0.41 — 0.50	60 percent

Any area of pavement found deficient in thickness by more than 0.50-in. but not more than 0.75-in. or $\frac{1}{10}$ of the plan thickness, whichever is greater, shall be evaluated by the OWNER. If, in the judgment of the OWNER, the area of such deficiency should not be removed and replaced, there shall be no payment for the area retained. If, in the judgment of the OWNER, the area of such deficiency warrants removal, the area shall be removed and replaced, at the CONTRACTOR'S entire expense, with concrete of the thickness shown on the plans. Any area of pavement found deficient in thickness by more than 0.75-in. or more than $\frac{1}{10}$ of the plan thickness, whichever is greater, shall be removed and replaced, at the CONTRACTOR'S entire expense, with concrete of the thickness shown on the plans.

No additional payment over the contract unit price shall be made for any pavement of a thickness exceeding that required by the plans.

303.8.3. Pavement Strength Test.

303.8.3.1. For Standard Classes of Concrete. During the progress of the work, the CONTRACTOR shall cast test cylinders, in accordance with ASTM C31 Standard Practice for Making and Curing Concrete Test Specimens in the Field, to maintain a check on the compressive strengths of the concrete being placed.

In accordance with ASTM C31 and ASTM C172 Standard Practice for Sampling Freshly Mixed Concrete, four test cylinders shall be taken from a representative portion of the concrete being placed for every 150-cubic yards of concrete pavement placed, but in no case shall less than 2 sets of cylinders be taken from any one day's placement. For smaller placements, the testing frequency may be adjusted at the OWNER'S discretion.

After the cylinders have been cast, they shall remain on the job site and then transported, moist cured, and tested by the OWNER in accordance with ASTM C31 and ASTM C39 Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens.

In each set, one of the cylinders shall be tested at 7-days, two cylinders shall be tested at 28-days, and one cylinder shall be held or tested at 56-days, if necessary.

If the 28-day test results indicate deficient strength, the CONTRACTOR may, at its option and expense, core the pavement in question and have the cores tested by an approved laboratory, in accordance with ASTM C42 Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of

Concrete and ACI 318 protocol, except the average of all cores must meet 100% of the minimum specified strength, with no individual core resulting in less than 90% of design strength, to override the results of the cylinder tests.

The CONTRACTOR shall be responsible for the proper storage, maintenance, and any required curing of concrete test samples made by the OWNER. The CONTRACTOR shall provide and maintain curing facilities for the purpose of curing concrete test specimens on site in accordance with ASTM C31. The cost of all materials used in test specimens and the cost of storing, maintaining and of providing and maintaining curing facilities will not be paid for as a separate contract pay item, and the costs thereof shall be considered incidental to the contract pay items provided.

Cylinders and/or cores must meet minimum specified strength. Pavement not meeting the minimum specified strength shall be subject to the money penalties or removal and replacement at the CONTRACTOR'S expense as shown in Table 303.8.3.1.(a) Standard Class Concrete Deficiency Penalties.

Table 303.8.3.1.(a) Standard Class Concrete Deficiency Penalties.

Percent Deficient	Percent of Contract Price Allowed
Greater Than 0% — Not More Than 5%	95-percent
Greater Than 5% — Not More Than 10%	90-percent
Greater Than 10% — Not More Than 15%	80-percent
Greater Than 15%	60-percent or removed and replaced at the entire cost and expense of CONTRACTOR as directed by OWNER.

The amount of penalty shall be deducted from payment due to CONTRACTOR; such penalty deducted is to defray the cost of extra maintenance.

These requirements are in addition to the requirements of [Item 303.9](#). Measurement and Payment.

The strength requirements for structures and other concrete work are not altered by this special provision.

No additional payment over the contract unit price shall be made for any pavement of strength exceeding that required by plans and/or specifications.

303.8.3.2. For Performance Classes of Concrete. During the progress of the work, the CONTRACTOR shall cast test cylinders, in accordance with ASTM C31 Standard Practice for Making and Curing Concrete Test Specimens in the Field, to maintain a check on the compressive strengths of the concrete being placed.

In accordance with ASTM C31 and ASTM C172 Standard Practice for Sampling Freshly Mixed Concrete, four test cylinders shall be taken from a representative portion of the concrete being placed for every 150-cubic yards of concrete pavement placed, but in no case shall less than 2 sets of cylinders be taken from any one day's placement.

After the cylinders have been cast, they shall remain on the job site and then transported, moist cured, and tested by the OWNER in accordance with ASTM C31 and ASTM C39 Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens.

In each set, one of the cylinders shall be tested at 7-days, two cylinders shall be tested at 28-days, and one cylinder shall be held or tested at 56-days, if necessary.

If the 28 day test results indicate deficient strength, the CONTRACTOR may, at its option and expense, core the pavement in question and have the cores tested by an approved laboratory, in accordance with ASTM C42 Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of Concrete and ACI 318 protocol, to override the results of the cylinder tests.

The CONTRACTOR shall be responsible for the proper storage, maintenance, and any required curing of concrete test samples made by the OWNER. The CONTRACTOR shall provide and maintain curing facilities for the purpose of curing concrete test specimens on site in accordance with ASTM C31. The cost of all materials used in test specimens and the cost of storing, maintaining and of providing and maintaining curing facilities will not be paid for as a separate contract pay item, and the costs thereof shall be considered incidental to the contract pay items provided.

Cylinders and/or cores must meet the specified strength in accordance with ACI 318 protocol. Pavement not meeting the specified strength shall be subject to the money penalties or removal and replacement at the CONTRACTOR'S expense as shown in Table 303.8.3.2.(a) Performance Class Concrete Deficiency Penalties.

Table 303.8.3.2.(a) Performance Class Concrete Deficiency Penalties.

Percent Deficient	Percent of Contract Price Allowed
Greater Than 0% — Not More Than 5%	95-percent
Greater Than 5% — Not More Than 10%	90-percent
Greater Than 10% — Not More Than 15%	80-percent
Greater Than 15%	60-percent or removed and replaced at the entire cost and expense of CONTRACTOR as directed by OWNER.

The amount of penalty shall be deducted from payment due to CONTRACTOR; such penalty deducted is to defray the cost of extra maintenance.

These requirements are in addition to the requirements of [Item 303.9](#), Measurement and Payment.

The strength requirements for structures and other concrete work are not altered by this special provision.

No additional payment over the contract unit price shall be made for any pavement of strength exceeding that required by plans and/or specifications.

303.8.4. Random Drying Shrinkage Cracks and Stress Cracks. Random drying shrinkage cracks or stress cracks of widths greater than 0.025-inches in recently placed reinforced Portland cement concrete pavement placed on stabilized subbase or slabs on grade are subject to being removed and replaced at the discretion of the OWNER. Random drying shrinkage cracks or stress cracks of any nature in recently placed non-reinforced Portland cement concrete pavement placed on non-stabilized subbase or slabs on grade are subject to being removed and replaced at the discretion of the OWNER. Recently placed concrete pavement or slabs on grade are those for which the one-year maintenance bond has not expired. Routing, by any means, and sealing random cracks will not be permitted. When Portland cement concrete pavement or slabs on grade must be removed and replaced, the area of removal must extend from the nearest contraction or dummy joint or construction joint a minimum distance of 10-feet, measured parallel to the longitudinal axis of the pavement, and include that portion of the concrete pavement or slab on grade containing the random crack. A sawed dummy joint will be required to be sawed across the opposing, non-damaged, slab in line with the saw cut made for the removal of the damaged slab. The area of removal and replacement of slabs containing longitudinal random cracks will be determined by the OWNER. Randomly cracked Portland cement concrete sidewalks will require removal and replacement of only the five-foot long section or sections containing random cracks.

303.9. MEASUREMENT AND PAYMENT

Portland cement concrete pavement shall be measured by the square-yard of completed and accepted pavement. Measurement for reinforced concrete pavement shall be by the square-yard measured in its final position.

The work performed and material furnished as prescribed by this item and measured as provided in this item shall be paid for at the unit price bid per square-yard for concrete pavement or the adjusted unit price for pavement of deficient thickness as provided under Pavement Thickness Test and Pavement Strength Test, which price shall be full compensation for shaping and fine grading the roadbed, including furnishing and applying all water required; for furnishing, loading and unloading, storing, hauling and handling all concrete ingredients, including all freight and royalty involved; for mixing, placing, finishing and curing all concrete; for furnishing and installing all reinforcing steel; for furnishing all materials and placing longitudinal, warping, expansion, and contraction joints, including all steel dowels, dowel caps and load transmission units required, wire and devices for placing, holding and supporting the steel bar, load transmission units, and joint filler material in the proper position; for coating steel bars where required by the plans; for all manipulations, labor, equipment, appliances, tools, traffic provisions and incidentals necessary to complete the work.

ITEM 304. PAVING UNITS

304.1. SOLID CONCRETE INTERLOCKING PAVING UNITS

This item shall govern the construction of concrete pavements and medians utilizing interlocking paving units according to lines, grades, locations, and designs as indicated on the plans and specifications, or as established by the OWNER.

304.1.1. General. Concrete Interlocking Paving Units are to be used on a site-specific basis only. The OWNER shall specify the special material and construction requirements for each location. Each site-specific application requires proper engineering design for the anticipated traffic volumes and vehicle loads.

304.1.2. Materials.

304.1.2.1. Concrete Paving Units. Interlocking paving unit construction shall conform to ASTM C936 Solid Interlocking Concrete Paving Units.

Pigment in concrete paving units shall conform to ASTM C979 Pigments for Integrally Colored Concrete.

All units shall be sound and free of defects that would interfere with the proper placing of unit or impair the strength or permanence of the construction.

304.1.2.1.1. Sampling and Testing Units. Manufacturer shall provide access to lots ready for delivery to the OWNER for testing in accordance with ASTM C936 for sampling of material prior to commencement of paving unit placement.

Manufacturer shall provide data showing manufactured products meet or exceed ASTM C936 when tested in compliance with ASTM C140 Sampling and Testing Concrete Masonry Units.

304.1.2.2. Base. The OWNER shall specify the site-specific requirements for each use. Base for pavements may consist of a reinforced concrete base, asphalt, flexible base, or stabilized subgrade. Base for medians shall be site specific and according to design parameters of the OWNER.

304.1.2.3. Bedding and Joint Sand. Bedding and joint sand shall be clean, non-plastic, and free from deleterious or foreign matter. The sand shall be natural or manufactured from crushed rock. When concrete paving units are subject to vehicular traffic, the sands shall be as hard and angular as practically available. Limestone screenings or stone dust shall not be used. Unevenly graded sand with an excess amount of material passing the No. 200 sieve shall not be used.

Sand that is suitable for the manufacturing of concrete is typically suitable for bedding. Grading of sand samples for the bedding course and joints shall be done according to ASTM C136 Method for Sieve Analysis for Fine and Coarse Aggregate. Bedding sand shall conform to the grading requirements of ASTM C33 Concrete Aggregates as shown in Table 304.1.2.3.(a) Bedding Sand Gradation.

Table 304.1.2.3.(a) Bedding¹ Sand Gradation

Sieve Size	Percent Passing
3/8-in.	100
No. 4	95 to 100
No. 8	85 to 100
No. 16	50 to 85
No. 30	25 to 60
No. 50	10 to 30
No. 100	2 to 10

1. Bedding sand may be used for joint sand. However, extra effort in sweeping and compacting the paving units shall be required to fill the joints completely.

If joint sand other than bedding sand is used, it shall conform to the grading requirements of ASTM C144 Aggregate for Masonry Mortar as shown in Table 304.1.2.3.(b) Joint Sand Gradation(Natural Sand). Joint sand shall not be used for bedding sand. Mason sands are typically acceptable only for

joint sand provided they meet grading requirements as shown in Table 304.1.2.3.(b) Joint Sand Gradation (Natural Sand).

Table 304.1.2.3.(b) Joint Sand Gradation (Natural Sand)

Sieve Size	Percent Passing
No. 4	100
No. 8	95 to 100
No. 16	70 to 100
No. 30	40 to 75
No. 50	10 to 35
No. 100	2 to 15
No. 200	0

304.1.2.4. Curbs and Gutters. Edge restraint is a critical design component of interlocking unit pavement. Curbs and gutters for concrete pavement units shall meet the requirements of [Item 305.1](#). Concrete Curb and Gutter with any deviations indicated on the plans or instructed by the OWNER.

304.1.3. Construction Methods. Construction methods for each type unit shall be provided by the manufacturer and approved by the OWNER based on the site-specific use. Delivery and paving schedule shall be coordinated to minimize interference with normal use of buildings adjacent to paving.

304.1.3.1. Delivery, Storage and Handling. Concrete paving units shall be delivered to the site in steel banded, plastic banded, or plastic wrapped cubes capable of transfer by fork lift or clamp lift. Paving units shall be unloaded at job site in such a manner that no damage occurs to the product.

Sand shall be covered with waterproof covering to prevent exposure to rainfall or removal by wind. The covering shall be secured in place.

304.1.3.2. Environmental Conditions. Paving units shall not be installed during heavy rain or snowfall over frozen base materials. Sand shall not be wet or frozen.

304.1.3.3. Construction Procedure.

304.1.3.3.1. Base. Construction methods shall follow the requirements of the selected base as contained in these specifications with any deviations indicated on the plans or instructed by the OWNER.

304.1.3.3.2. Bedding. Sand shall be spread evenly over the base course and screed to a nominal 1-in. thickness, not exceeding 1.5-in. thickness. The secreted sand shall not be disturbed. Sufficient sand shall be placed to stay ahead of the laid paving units. Bedding sand shall not be used to fill depressions in the base surface. The material shall be of uniform moisture content when spread.

304.1.3.3.3. Paving Units and Joints. Paving units shall be free of foreign materials before installation. Paving units shall be laid in the pattern(s) as shown on the drawings. Straight pattern lines shall be maintained.

Joints shall be made according to manufacturer recommendations. Typically, joints between the paving units will be between $\frac{1}{16}$ -in. and $\frac{3}{16}$ -in. wide except where paving unit shapes require a larger joint.

Gaps at the edges of the paved area shall be filled with cut paving units or edge units. Cuts shall be made with a mounted masonry saw. Units cut no smaller than one-third of a whole paving unit when feasible are recommended along edges subject to vehicular traffic. Areas not feasible shall be neatly grouted and pointed up.

A low amplitude, high frequency plate vibrator shall be used to vibrate the paving units into the sand. The size of compaction equipment shall be selected according to Table 304.1.3.3.3.(a) Compaction Equipment.

Table 304.1.3.3.3.(a) Compaction Equipment

Paving Unit Thickness	Minimum Centrifugal Compaction Force
2.4-in.	3000-lbs.
3.1-in.	5000-lbs.

Dry joint sand shall be swept into the joints and vibrated until joints are full. This will require at least two or three passes with the vibrator. All work to within 3-ft. of the laying face must be left fully compacted with sand-filled joints at the completion of each day. Excess sand shall be swept off and removed when the job is complete.

The final surface elevation of paving units after removal of excess sand shall conform to the plans, shall not deviate more than $\frac{3}{8}$ -in. under a 10-ft. long straightedge, and shall be $\frac{1}{8}$ -in. to $\frac{1}{4}$ -in. above adjacent drainage inlets, curb and gutters, concrete collars or channels.

The CONTRACTOR shall resand paving unit joints as necessary for a period of 90-days after completion of work.

304.1.4. Measurement and Payment. Concrete paving units shall be measured by the square-yard of completed and accepted pavement. Payment shall include all labor, equipment, materials, tools, and incidentals necessary to complete the work.

ITEM 305. MISCELLANEOUS ROADWAY CONSTRUCTION

305.1. CONCRETE CURB AND GUTTER

305.1.1. Description. Curb and gutter shall be of the type specified and shall be constructed to the size, shape, lines and grade as shown on the plans or as directed by the OWNER. Variations in size and shape may be made to fit individual special conditions.

305.1.2. Materials. All materials used in concrete herein specified shall conform to the requirements of the applicable sections of [Item 303](#). Portland Cement Concrete Pavement of these specifications and to additional requirements herein included.

305.1.3. Construction Methods.

305.1.3.1. Excavation. Excavation shall be as provided in [Item 203.2](#). Unclassified Excavation, and as shown on the plans. Asphalt millings or extra depth concrete shall be used to correct grade deficiencies identified after subgrade has been checked.

305.1.3.2. Reinforcing Steel. All steel reinforcement shall be accurately placed as shown on the plans and held in place during progress of concreting by such effective means that it shall not be moved out of true position. All bars shall be wired at their intersections and at all laps or splices. All bars at splices shall be lapped a minimum of 20-diameters of the bar or 12-in., whichever is greater.

All reinforcement necessary for a section of concrete shall be placed and approved by the OWNER before any concrete is deposited in the section. All steel must be free from paint and oil and all loose scale, rust, dirt and other foreign substances shall be completely removed before using.

305.1.3.3. Forms. All forms shall be of wood or steel, straight, free of warp and framed, braced or staked in a substantial and approved manner so as to insure perfect alignment and grade. All forms shall be clean and shall be oiled immediately before concreting. Care shall be taken in removing forms to prevent marring or spalling of the concrete. Forms shall extend the full depth of concrete and be a minimum of 1⁵/₈-in. in thickness or equivalent when wooden forms are used, or be of a gauge that shall provide equivalent rigidity and strength when metal forms are used.

For curves with a radius of less than 250-ft., acceptable flexible metal or wood forms shall be used.

All forms showing a deviation of 1/8-in. in 10-ft. from a straight line shall be rejected.

305.1.3.4. Expansion Joints. Expansion joints shall be constructed using expansion joint material of an approved type. Expansion joints shall be placed in the curb and gutter at 200-ft. intervals and at intersection returns and other rigid structures, or as otherwise specified by the OWNER. Tooled joints shall also be placed at 15-ft. intervals or matching abutting sidewalk joints and pavement joints to a depth of 1/4 the thickness of the curb. Expansion joints shall also be placed at all intersections with concrete driveways, curbs, buildings and other curbs and gutters. All expansion joints shall be not less than 1/2-in. in thickness, extending the full depth of the concrete and shall be perpendicular and at right angles to the face of the curb. Any expansion material extending above the finished work shall be neatly trimmed to the surface of the finished work. The expansion joints in concrete pavement shall coincide with the expansion joints in the curb and gutter and sidewalk. Longitudinal dowels, across the expansion joints in the curb and gutter, shall be required. There shall be three No. 4 round, smooth bars for dowels at each expansion joint, spaced in accordance with standard reinforcement steel specifications. The dowel shall be a minimum of 24-in. in length. One-half of the dowel shall be coated with asphalt and terminated with an expansion cap. The cap shall provide a minimum of 1-in. free expansion. Dowels shall be supported by an approved method to provide a true horizontal and longitudinal alignment.

In the event that concrete pavement is to be placed in the street, the contraction (dummy) joints in the curb, gutter and/or combined curb and gutter shall be in strict alignment with the contraction (dummy) joints in the pavement and may be marked with an approved tool to the depth designated by the OWNER. If the joints are not constructed by marking, they shall be sawed at the time of sawing joints in the concrete slab and to the same depth as those in the slab. Expansion joints of the size of those in the pavement shall be placed through the curb and gutter at the point of, and in strict alignment with, expansion joints in the pavement.

All joints through the gutters (not curb) shall be sealed with hot-poured polymer sealer unless otherwise specified.

All joints shall be constructed in a neat and workmanlike manner, with edges rounded, in conformity with the plans and specifications and at location as shown on the plans or as designated by the OWNER.

305.1.3.5. Concrete Placement. Concrete shall be placed in accordance with [Item 303](#). Portland Cement Concrete Pavement.

Concrete shall be deposited so as to maintain a horizontal surface and shall be thoroughly and continuously worked into all spaces and around any reinforcement so as to form a dense voidless mass. The coarse aggregate shall be worked away from contact with the forms so as to form a smooth, hard exposed concrete surface.

The concrete for curb and gutter shall preferably be placed continuously between expansion joints. If construction joints are allowed at other locations by the OWNER, they shall be properly constructed with wooden bulkheads so as to completely separate adjacent concrete sections.

Integral curb, with or without gutter, when designated in the plans or specifications, shall be placed while the concrete in the base or pavement is still plastic and shall be spaded and consolidated with the concrete slab in order that a thorough bond shall be obtained.

Integral curb, with or without gutter, shall be placed in sections equal to the adjoining concrete slab length, with expansion joints provided as specified herein.

Where curb and gutter is not adjacent to new pavement, 2-in. of sand cushion shall be used. After the fine grading has been completed, a 2-in. layer of sand or suitable gravel cushion shall be evenly spread over the subgrade for curb and gutter, thoroughly wetted and tamped into place to the satisfaction of the OWNER. The forms shall be placed upon this sand or gravel base. A screed shall be used to shape the sand cushion to fit a plane parallel to the top of gutter. A curb and gutter machine may be used, if approved by the OWNER.

305.1.3.6. Finishing. After the concrete has been struck off and while it is still plastic, the exposed surfaces may be plastered with ¼-in. mortar topping. The mortar topping shall be applied with a steel “mule,” or a finishing tool or method which produces results equivalent to that obtained with the mule. All exposed surfaces shall then be floated or troweled and lightly brushed as required by the OWNER to produce a smooth and uniform finish. Excess working of the surfaces shall be avoided. Excess water, laitance and inert materials shall be removed from the surfaces.

The top of all the work and the face of all curbs shall be checked for irregularities as soon as the surface is finished, using a 10-ft. straightedge, and the maximum distance from the straightedge to the concrete shall not exceed ¼-in. All variations greater than ¼-in. shall be immediately corrected. All honeycombed areas disclosed by removal of forms shall be immediately chipped out and patched with Portland cement mortar.

305.1.3.7. Curing. After finishing operations are completed, the concrete surface shall be sprayed with concrete curing compound. The surface of the concrete shall be kept thoroughly damp between the completion of the finishing operations and the application of the curing compound. The curing compound shall be applied under pressure, by means of a spray nozzle, at a rate not to exceed 200-sq.-ft.-per-gallon. A minimum of 72-hours curing time shall be required.

Forms shall remain in place at least 12 hours after completion of the concrete placement for the curb and gutter. Should the CONTRACTOR elect to remove the forms before the minimum curing time has elapsed, it shall apply curing compound to the newly exposed vertical faces. Forms for inside curb faces may be removed in approximately 3-hours, provided that the concrete has set sufficiently to permit form removal without curb damage.

305.1.3.8. Finishing Exposed Surfaces. Exposed surfaces of curb and gutter shall receive the type of finish as specified by the OWNER in accordance with [Item 702.5.13](#). Finishing Exposed Surfaces.

305.1.4. Measurement and Payment. Curb and gutter shall be measured by the linear foot in place complete.

The work performed and materials furnished as prescribed in this item, measured as provided in this item, shall be paid for at the contract unit prices bid for curb and gutter, which shall be full compensation for

preparing the subgrade; furnishing and placing all materials, including foundation course, reinforcing steel and expansion joint material; and for all manipulation, labor, tools, equipment and incidentals necessary to complete the work.

305.2. CONCRETE SIDEWALKS, DRIVEWAY APPROACHES, AND BARRIER FREE RAMPS

305.2.1. Description. This item shall govern the construction of barrier free access ramps, concrete sidewalks, driveways and approaches conforming to the lines, grades, locations and designs as indicated on the plans and specifications or as established by the OWNER.

305.2.2. Materials.

305.2.2.1. Concrete. All materials and requirements for concrete shall conform to the requirements of [Item 303](#). Portland Cement Concrete Pavement.

305.2.2.2. Reinforcement. Driveway approaches and walk reinforcing, when required, shall be No. 3 bars on 24-in. centers or No. 4 bars on 30-in. centers. No. 6 gauge, 6-in. x 6-in. wire fabric conforming to [Item 303.2.10](#). Steel Wire Reinforcement may be used only as approved by the OWNER. Sidewalk reinforcing (except in driveway approach) may be No. 3 bars on 24-in. centers or No. 10 gauge, 6-in. x 6-in.

305.2.3. Construction Methods.

305.2.3.1. General. Concrete sidewalks shall have a minimum thickness of 4-in., except that sidewalks constructed in driveway approach sections shall have a minimum thickness equal to that of driveway approach or as called for by plans and specifications within the limits of the driveway approach. Standard slope for walks shall be 1/4-in.-per-ft. in the direction of the curb or street with a tolerance of 1/8-in.-per-ft. The construction of the driveway approach shall include the variable height radius curb in accordance with the plans and details. The drive approach shall have a minimum thickness equal to the thickness of the adjacent street or 6-in., whichever is greater.

Ramps shall comply with provisions of Texas Accessibility Standards including location, slope, width, shapes, texture and coloring.

At the locations shown on the plans or at locations designated by the OWNER, the separate curb, integral curb or curb and gutter shall be laid down to a uniform width of not less than the specified height of the curb from the back of the curb line for access to future driveways. The return radii and partial curb return shall be built from the face of the curb to the back of the curb lay-down.

Where a driveway approach or ramp is to be constructed at a location where there exists a separate curb and gutter, said curb and gutter shall be removed for the full width of the gutter to the nearest joint or to a sawed point at the point of radius. On concrete pavement with monolithic curb, the breakout line shall be 12-in. from the face of the curb line and shall be parallel to it and form a right angle with the concrete surface. The breakout line shall be a sawed groove in accordance with the requirements of [Item 402.3](#). Sawing. Alternately, the OWNER may approve use of equipment designed to cut concrete curbs. All faces and edges exposed as a result of cutting shall be smoothed.

305.2.3.2. Excavation. Excavation required for the construction of sidewalks and driveways shall be to the lines and grades as established by the OWNER or as shown on the plans.

305.2.3.3. Fine Grading. The CONTRACTOR shall do all necessary filling, leveling and fine grading required to bring the subgrade to the exact grades specified and compacted to at least 90-percent of maximum density as determined by ASTM D698 Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³). Moisture content shall be within minus-2- to plus-4-of-optimum. Any over-excavation shall be repaired to the satisfaction of the OWNER.

305.2.3.4. Forms. Forms shall be of wood or metal, of a section satisfactory to the OWNER, straight, free from warp and of a depth equal to the thickness of the finished work. Forms shall be securely staked to line and grade and maintained in a true position during the depositing of concrete.

305.2.3.5. Reinforcement. Steel bar reinforcement, when required, shall be placed according to the methods in [Item 303.2.9](#). Steel Reinforcement. If wire fabric is permitted, it shall be placed in accordance with [Item 303.2.10](#). Steel Wire Reinforcement.

305.2.3.6. Concrete Placement. Concrete placement shall be in accordance with the relevant provisions of [Item 303](#). Portland Cement Concrete Pavement.

305.2.3.7. Finishing. Concrete sidewalks and driveway approaches shall be finished to a true, even surface. They shall be troweled and then brushed transversely to obtain a smooth uniform brush finish. Joint and sides shall be edged with suitable tools.

305.2.3.8. Joints. Expansion joints for sidewalks and driveways shall be formed using expansion joint material of an approved type and shaped to the section. Expansion joints shall be placed in the sidewalk at 40-ft. intervals or as otherwise specified by the OWNER. Expansion joints shall also be placed at all intersections, sidewalks with concrete driveways, curbs, formations, other sidewalks and other adjacent old concrete work. Similar material shall be placed around all obstructions protruding into or through sidewalks or driveways. All expansion joints shall be ½-in. in thickness. Edges of all construction and expansion joints and outer edges of all sidewalks shall be finished to approximately a ½-in. radius with a suitable finishing tool. Sidewalks shall be marked at intervals equal to the width of the walk with a marking tool. When sidewalk is against the curb, expansion joints and tooled grooves shall match those in the curb.

305.2.3.9. Curing. Sidewalks and driveways shall be cured in accordance with the requirements of [Item 303](#). Portland Cement Concrete Pavement.

305.2.4. Measurement and Payment. Measurement for sidewalks, driveway approaches and ramps complete and in place shall be by the square-yard. Measurement of driveway approaches shall start at the back of the laydown curb line and shall include the area of the curb radii. Curbs on driveways shall not be measured separately but shall be included as a part of the driveway concrete. Concrete sidewalks and driveways shall be paid for at the contract unit price bid, which price shall be full compensation for excavating and preparing the subgrade; furnishing and placing all materials, including gravel base and expansion joint materials; and for all manipulation, labor, tools, equipment and incidentals necessary to complete the work.

305.3. CONCRETE MEDIANS

305.3.1. Description. This item shall consist of concrete medians in accordance with these specifications and in conformance with the lines and grades established by the OWNER and details shown on the plans.

305.3.2. Materials. All material requirements for constructing concrete medians shall conform to the requirements of [Item 303](#). Portland Cement Concrete Pavement. Where a monolithic concrete median is indicated, concrete and reinforcement shall match the adjacent pavement.

305.3.3. Construction Methods.

305.3.3.1. Excavation. Excavation and fine grading shall be done according to [Item 203.2](#). Unclassified Excavation, and shall be subsidiary to the item.

305.3.3.2. Forms. Forms, where required, shall conform to the requirements of [Item 303](#). Portland Cement Concrete Pavement and shall be of a depth equal to the depth of the required section. Forms shall be securely staked to line and grade and maintained in a true position during the depositing of concrete.

305.3.3.3. Concrete Placement. Concrete placement shall be in accordance with the relevant provisions of [Item 305.1](#). Concrete Curb and Gutter.

305.3.3.4. Finishing. The surface shall be finished with a float and lightly brushed to obtain a uniform finish. Tooled joints shall be placed longitudinally and transversely at intervals not to exceed 6-ft. center to center, as shown on the plans, or as directed by the OWNER. Joints in the median shall coincide with joints in curb and gutter. Expansion joint material shall be placed between the median and the back of curb and around all obstructions protruding through the concrete median.

305.3.4. Measurement and Payment. Concrete median shall be measured by the square-yard complete in place.

The work performed and materials furnished as prescribed by this item, measured as provided for in this item, shall be paid for at the contract unit price bid for "concrete median," which price shall be full compensation for constructing concrete median and for preparing the subgrade; furnishing and placing all

materials, including sand cushion, reinforcement and expansion materials; and for all manipulation, labor, tools, equipment and incidentals necessary to complete the work.

305.4. REINFORCED CONCRETE HEADERS

This item shall govern the construction of reinforced concrete header to the size, shape and at the location shown on the plans.

Material requirements shall be the same as those for [Item 303](#). Portland Cement Concrete Pavement.

Concrete header shall be constructed at the location(s) shown on the plans and shall be constructed as shown on the plans in accordance with [Item 303](#). Portland Cement Concrete Pavement.

Concrete header shall be paid by the linear-foot complete in place.

The work performed and materials furnished as prescribed by this item, measured as provided for in this item, shall be paid for at the contract unit price bid for concrete header. This payment shall be full compensation for necessary excavation, reinforcing steel, furnishing and placing concrete, and for all labor, tools, equipment and incidentals necessary to complete the work.

An aerial, high-angle photograph of a paved road surface. The road is marked with white lines, including a series of parallel lines forming a lane on the left and a solid line on the right. Several circular manholes are visible, some with metal covers and others with dark, possibly open, centers. The pavement shows signs of wear, including cracks and patches. A solid blue rectangular area is overlaid on the right side of the image, containing white text.

Division 400

Roadway Maintenance and Rehabilitation

DIVISION 400 ROADWAY MAINTENANCE & REHABILITATION

TABLE OF CONTENTS

<i>Item #</i>	<i>Subject</i>	<i>Pages</i>
401.	CRACK SEALING	401-1
401.1.	General	
401.2.	Materials	
401.3.	Methods	
401.4.	Measurement and Payment	
402.	PAVEMENT CUT, EXCAVATION, AND REPAIR	402-1 to 402-5
402.1.	General Requirements	
402.2.	Minimum Size of Repair	
402.3.	Sawing	
402.4.	Replacing Paved Surfaces	
403.	ASPHALTIC PAVEMENT REPAIR	403-1 to 403-3
403.1.	Description	
403.2.	Materials and Mixing	
403.3.	Methods	
403.4.	Measurement and Payment	
404.	SURFACE TREATMENTS	404-1 to 404-9
404.1.	Description	
404.2.	General	
404.3.	Slurry Seals and Micro- (Re) Surfacing	
404.4.	Bituminous Surface Treatment (Chip Seal)	
405.	ULTRA THIN CONCRETE PAVING (WHITETOPPING)	405-1 to 405-3
405.1.	Description	
405.2.	Materials	
405.3.	Construction Methods	
405.4.	Measurement	
405.5.	Payment	

ITEM 401. CRACK SEALING

401.1. GENERAL

Crack sealing compound shall consist of hot poured polymer or ready-mixed cold-applied sealant, or other material approved by the OWNER. It shall not crack or break when exposed to low temperatures. The cured sealant must not pick up or “track” at elevated road temperature.

401.2. MATERIALS

401.2.1. Hot Poured Polymer. The sealing compound shall meet the requirements of [Item 303.2.14.1.1.](#) Hot Poured Polymer.

401.2.2. Ready-Mixed Cold-Applied. This sealant shall meet the requirements of [Item 303.2.14.1.2.](#) Ready-Mixed Cold-Applied.

401.2.3. Thermoplastic Cold-Applied. If approved by the OWNER, thermoplastic cold-applied jointing material may be used according to manufacturer’s recommendations.

401.2.4. Rejection. Materials may be rejected for failure to meet any of the requirements of this specification.

401.3. METHODS

Routine pavement cracks shall be filled to a depth of 1½-in. Materials shall generally be handled and applied according to the manufacturer’s recommendations, with additional requirements as stated herein. CONTRACTOR shall clean all cracks prior to installation of crack sealant materials.

401.3.1. Hot Poured Polymer. The sealing compound shall be melted in an approved oil-batch kettle with continuous mechanical agitation. The kettle shall be equipped with temperature indicators. The OWNER shall determine the optimum temperature for proper pouring fluidity, and the CONTRACTOR shall maintain the material within close range of optimum temperature. At no time shall the temperature exceed 450°F. The sealing compound shall not be poured at atmospheric temperatures below 32°F.

401.3.2. Ready-Mixed Cold-Applied. Permeation of cracks shall principally be achieved without the task of squeegeeing. However, squeegeeing is recommended to assist permeation and to allow sealant to become rapidly tack-free. Sealant shall “set” in a fixed position within 40-minutes after application, to where traffic may be restored to the pavement without the effects of “tracking.” “Tracking” shall be averted without the use of topping materials such as sand.

401.4. MEASUREMENT AND PAYMENT

Crack sealing shall be measured and paid for on a lump-sum basis for the amount specified in contract documents under “Crack Sealing.”

ITEM 402. PAVEMENT CUT, EXCAVATION, AND REPAIR

402.1. GENERAL REQUIREMENTS

Also refer to Standard Drawings 3070A – 3070D for more information.

402.1.1. Marking All pavement cut repairs shall be marked with the CONTRACTOR'S name if required by the OWNER.

402.1.2. Thoroughfares. No interference with traffic flow on the thoroughfares shall be permitted during the hours of 6:30 a.m. to 9:30 a.m. and 3:30 p.m. to 6:30 p.m., Monday through Friday, unless directed otherwise by the OWNER. Emergency closures during these hours shall be with the approval of the OWNER. Notice of street closures should be provided to the appropriate emergency and/or other department personnel.

Streets shall be maintained in accordance with [Item 201.3](#), Maintenance of Streets and Rights of Way During Construction. When work is stopped for the day, all lanes of arterial or collector streets shall be opened to traffic in accordance with the traffic control plan. A traffic lane shall be considered satisfactorily open if it is paved with hot-mix or cold-mix asphalt paving, or paved with another suitable material approved by the OWNER, or covered.

If the cut is to be covered, the CONTRACTOR shall use steel plates of sufficient strength and thickness to support all the traffic. A transition of hot-mix or cold-mix asphalt conforming to the requirements of [Item 302](#), Asphalt Pavement shall be constructed from the top of the steel plate to the existing pavement to create a smooth riding surface.

Exceptions to these specifications must be approved by the OWNER.

402.2. MINIMUM SIZE OF REPAIR

The following dimensions are minimums and may be superseded by site-specific factors or OWNER requirements. Exact pavement removal locations must be approved by the OWNER prior to construction.

If multiple repairs are closer than 10-ft. apart from edge of one repair to the edge of a second repair, a continuous section shall be replaced.

402.2.1. Sidewalk, Driveway, and Curb and Gutter. Sidewalks shall be removed and replaced to the nearest existing joint.

No sidewalk or driveway section to be replaced shall be smaller than 30-in. in either length or width unless otherwise approved by the OWNER.

A gutter of at least 12-in. may remain, provided that the curb and gutter is not damaged by the construction activity. Damaged curbs shall be replaced at the expense of the CONTRACTOR.

402.2.2. Dimension Parallels the Centerline (Along the Street/Alley). In a concrete paved street or alley, no horizontal dimension of any cut along the street path shall be less than 3-ft. or no less than 1-ft. from the edge of the trench on each end, whichever is greater. In an asphalt paved street or alley, no horizontal dimension of any cut along the street path shall be less than 4-ft. or no less than 2-ft. from the edge of the trench on each end, whichever is greater. Where saw-cut locations coincide with or fall within 3-ft. of the present location of either dummy joints, cold joint, construction joints, expansion joints, or edge, removal shall be to the existing joint or edge. See Standard Drawings 3070C and 3070D.

402.2.3. Dimension Perpendicular to the Centerline (Across the Street) – Multiple Lanes. See Standard Drawing 3070D.

402.2.3.1. Concrete. If the trench edge or point repair is located greater than 1-ft. from a lane line on the side of the line closest to the curb, pavement shall be removed and replaced from the curb to the lane line. If the edge of a trench or point repair is located less than 1-ft. from a lane line on the side of the line closest to the curb, pavement shall be removed and replaced from the curb to the 2nd lane line beyond the trench edge or point repair.

402.2.3.2. Asphalt. If the edge of a trench or point repair is located less than or equal to ½-lane-width but greater than 2-ft. from a lane line, the lane-width of pavement shall be removed and replaced. If the edge of a trench or point repair is located less than 2-ft. from a lane line, the pavement shall be removed and replaced to ½-lane-width on each side. In the lane along the curb, if the trench edge or

point repair plus 2-ft. toward the lane line is less than $\frac{1}{2}$ -lane-width, pavement shall be removed and replaced from the curb to $\frac{1}{2}$ -lane-width.

402.2.4. Dimension Perpendicular to the Centerline (Across the Street/Alley) – Residential Street or Alley. See Standard Drawing 3070C.

402.2.4.1. Concrete. In any concrete residential street or alley, if the trench edge or point repair is less than 1-ft. from the street or alley centerline, pavement shall be removed and replaced on each side from the trench edge or point repair to a distance 10-ft. from curb, and a minimum of 1-ft. from the trench edge or point repair. If the 1-ft. minimum causes the repair to be closer than 10-ft. from a curb, replace to the curb.

In a concrete residential street or alley less than 30-ft. wide, if the trench edge or point repair is between 1-ft. and 5-ft. from the street or alley centerline, the pavement shall be removed and replaced from the curb to the centerline.

In a concrete residential street or alley 30-ft. wide or greater, if the trench edge or point repair is greater than 5-ft. from the centerline, the pavement shall be removed and replaced from the curb to a distance 10-ft. from the curb. If the trench edge or point repair is more than 1-ft. but less than 5-ft. from the centerline, pavement shall be removed and replaced from the centerline to a distance 10-ft. from the curb.

402.2.4.2. Asphalt. In any asphalt residential street or alley, if the trench edge or point repair is less than 2-ft. from the street or alley centerline, pavement shall be removed and replaced on each side from the trench edge or point repair to a distance 10-ft. from curb, and a minimum of 2-ft. from the trench edge or point repair. If the 2-ft. minimum causes the repair to be closer than 10-ft. from a curb, replace to the curb.

In an asphalt residential street or alley less than 30-ft. wide, if the trench edge or point repair is between 2-ft. and 5-ft. from the street or alley centerline, the pavement shall be removed and replaced from the curb to the centerline.

In a concrete residential street or alley 30-ft. wide or greater, if the trench edge or point repair is greater than 5-ft. from the centerline, the pavement shall be removed and replaced from the curb to a distance 10-ft. from the curb. If the trench edge or point repair is more than 2-ft. but less than 5-ft. from the centerline, pavement shall be removed and replaced from the centerline to a distance 10-ft. from the curb.

402.3. SAWING

402.3.1. Description. This item shall apply in the removal of bituminous or concrete pavement, curb, gutter, sidewalk or driveways. This item shall also govern for the sawing of weakened plane joints (contraction joints). Sawing shall be in accordance with the requirements of this item unless otherwise shown on the plans or in the special provisions.

The removal and replacement of portions of permanent pavement (Portland cement concrete or hot-mix asphalt), drives, slabs, sidewalks, etc. shall require a full-depth of pavement cut to be sawed by the use of an approved power-driven concrete saw in accordance with this specification or as directed by the OWNER.

402.3.2. Equipment. The saw shall be power driven, shall be manufactured especially for the purpose of sawing pavement, shall be suitable for the work to be performed including dust control and shall be maintained in good operating condition.

Saw blades shall make a clean, smooth cut, producing a groove $\frac{1}{8}$ -in. to $\frac{1}{4}$ -in. wide and to the full depth required by these specifications or as shown on the plans.

The saw, with its control devices, shall be mounted on a sturdy frame supported on rubber-tired wheels.

402.3.3. Construction Methods. Dust and residues from sawing shall be prevented from entering the atmosphere or storm drain.

The edge of pavements, curb, gutter, sidewalk and/or driveways shall be neatly sawed. Saw cuts shall be made perpendicularly to the surface to full pavement depth or as directed by the OWNER. The edges of pavement and appurtenances damaged subsequent to sawing shall again be saw cut to neat straight lines for the purpose of removing the damaged areas. Such saw cuts shall be parallel to the original saw cut.

Concrete sidewalk or driveway to be removed shall be neatly sawed in straight lines either parallel to the curb or at right angles to the alignment of the sidewalk.

402.3.4. Measurement and Payment. Sawing shall be considered subsidiary to the items requiring sawing if no pay item exists in the Contract.

If a pay item exists in the contract for “Saw Cuts,” it shall be measured and paid in linear feet of groove actually cut in accordance with the specifications and as directed by the OWNER.

402.4. REPLACING PAVED SURFACES

402.4.1. General. Repairs are to be made as rapidly as possible. Use of fast setting concrete and similar techniques are encouraged. Completion of the job, including replacement of pavement and cleanup, shall normally be accomplished within 10-working-days after the repair work involving the cut is made.

Removal of unsatisfactory work shall begin within 15-days and replacement shall be completed within 30-days of written notification by the OWNER.

The existing pavement shall be sawed in accordance with [Item 402.3](#). Sawing.

The OWNER shall approve embedment specified in accordance with [Item 504.5](#). Embedment, or the embedment standards of the utility owner. The OWNER shall approve embedment compaction. Final backfill shall meet the requirements of [Item 504.2.3.4](#). Flowable or Stabilized Backfill or [Item 504.2.3.3](#). Type “B” Backfill, as determined by the OWNER. Type “B” Backfill shall be compacted to 95% Standard Proctor density.

Parkways shall be treated in accordance with [Item 204](#). Landscaping, including a minimum of 6-in. topsoil and protection and replacement of plants in areas disturbed by construction.

402.4.2. Temporary Pavement Repair. In the event it is necessary to place a temporary surface on any cut opening, it shall be composed of permanent type paving material, specifically excluding gravel or flexible base as the surface material, unless approved by the OWNER. Temporary surfaces shall be adequately compacted and sealed to prevent degradation of the repair during the temporary period. Any temporary surface that fails to provide a nondegraded riding surface shall be removed and replaced at the CONTRACTOR’S expense.

402.4.3. Replacing Curb, Gutter, Sidewalks, Driveways, Etc. Curb, curb with gutter, sidewalks, drives, etc. shall be replaced with Class A or Class PA concrete (Class determined by the OWNER), unless specified otherwise by the OWNER. Replacement shall meet current OWNER standards.

402.4.3.1. Measurement for Replacement of Curb, Gutter, Sidewalks, Driveways, Etc. Removed curb, curb with gutter, sidewalks, drives, etc. shall be measured for payment in square-yard or linear feet as specified in the bid item. The removal or replacement of curbs, curbs and gutters, sidewalks, driveways, etc. in excess of that specified or approved by the OWNER shall be at the expense of the CONTRACTOR.

402.4.4. Replacing Reinforced Concrete Pavement. Pavement shall be removed to a line 12-in. back of the firm banks of the trench or, if within 3-ft. of an existing joint, to the joint. The concrete replacement shall be reinforced with like-size bars as the existing pavement, #4 minimum, drilled 12-in. deep and epoxied in place, spaced on a minimum of 24-in. centers each way.

The concrete shall be Class P2 or Class PP2 (as determined by the OWNER), unless another class is specified by the OWNER. The replacement concrete shall match the thickness of the existing concrete pavement, minimum of 6-in. thick or the minimum thickness of current OWNER standard for the street type.

The new concrete pavement shall be protected from vehicular traffic for a minimum of 7 days or until a minimum flexural strength of 500-psi is obtained or until a compressive strength of 3000-psi is obtained.

402.4.4.1. Measurement of Reinforced Concrete Pavement. Replacement of the reinforced concrete pavement shall be measured at the specified trench width plus 2-ft., thickness in inches, and length in linear feet. Additional reinforced concrete pavement ordered by the OWNER to be placed will be measured as the thickness in inches, and length and width in linear feet.

402.4.5. Replacing Concrete Pavement and Asphalt Overlay. The existing pavement shall be removed to a neat line at least 12-in. back of the firm banks of the trench or, if within 3-ft. of an existing joint, to the joint.

The concrete replacement shall be reinforced with like-size bars as the existing pavement, #4 minimum, drilled 12-in. deep and epoxied in place, spaced on a minimum of 24-in. centers each way.

The asphalt surface course shall be hot-mix asphalt pavement of the type and class indicated on the plans meeting the requirements of [Item 302](#). Asphalt Pavement. Thickness shall match existing pavement or meet the minimum thickness of current OWNER standard for the street type. The joint formed at the interface of the existing pavement and the repair shall be sealed with a material approved by the OWNER.

402.4.5.1. Measurement of Concrete Pavement and Asphalt Overlay. Replacement of the reinforced concrete pavement shall be measured at the specified trench width plus 2-ft., thickness in inches, and length in linear feet. Additional reinforced concrete pavement ordered by the OWNER to be placed will be measured as the thickness in inches, and length and width in linear feet.

Hot-mix asphalt pavement shall be measured at the specified trench width plus 2-ft., thickness in inches, and the length measured in linear feet. Additional asphalt pavement ordered by the OWNER to be placed will be measured as the thickness in inches, and length and width in linear feet.

If paid for, crack sealer shall be measured as indicated on the plans.

402.4.6. Replacing Full Depth Hot-Mix Asphalt Pavement. Unless otherwise specified by the OWNER, the existing hot-mix asphalt shall be cut back to produce a vertical edge for the full depth of the paving. The cut shall extend 24-in. back of the firm banks of the trench.

All courses of hot-mix asphalt pavement shall be of the types and classes as indicated on the plans. Thickness of each course shall match existing courses or meet the minimum thickness of each course of current OWNER standard for the street type. The joint formed at the interface of the existing pavement and the repair shall be sealed with a material approved by the OWNER.

402.4.6.1. Measurement for full depth Hot-Mix Asphalt Pavement. Hot-mix asphalt pavement shall be measured at the specified trench width plus 4-ft., thickness in inches, and the length measured in linear feet. Additional asphalt pavement ordered by the OWNER to be placed will be measured as the thickness in inches, and length and width in linear feet.

If paid for, crack sealer shall be measured as indicated on the plans.

402.4.7. Replacing Hot-Mix Asphalt Pavement on a Flexible Base. Unless otherwise specified by the OWNER, the existing hot-mix asphalt shall be sawed 24-in. back from the firm banks of the trench. The cut shall be replaced with a compacted flexible base, as specified in [Item 301.5](#). Flexible Subbase or Base (Crushed Stone/Concrete), to match the existing thickness of the base, 6-in. minimum.

All courses of hot-mix asphalt pavement shall be of the types and classes as indicated on the plans.

402.4.7.1. Measurement for Hot-Mix Asphalt Pavement on a Flexible Base. Hot-mix asphalt pavement shall be 2-in. thick, specified ditch width plus 4-ft., and the length measured in linear feet. The flexible base shall be measured at the specified trench width only, 6-in. thick or the depth of the existing flexible base, and the length measured in linear feet.

402.4.8. Replacing One- or Two-Course Surface Treatment or Penetration Type Pavement. The pavement shall be replaced as specified by the OWNER in accordance with [Item 404](#). Surface Treatments.

402.4.9. Replacing Gravel Pavement on a Dirt Base. The existing gravel pavement shall be replaced with compacted flexible base, as specified in [Item 301.5](#). Flexible Subbase or Base (Crushed Stone/Concrete). The minimum thickness of flexible base shall be 8-in. unless otherwise specified by the OWNER.

402.4.9.1. Measurement. The flexible base shall be measured at specific trench width only, 8-in. thick, and the length measured in linear feet.

402.4.10. Payment for Pavement Replacement. If paid for by the OWNER, replacement curb, curb with gutter, sidewalks, drives, etc. shall be paid at the contract unit price per square-yard or linear feet as specified in the bid item, complete in place.

If paid for by the OWNER, replacement of pavement(s) and base(s) shall be paid at the contract unit price per square-yard of respective thickness, complete in place.

If paid for by the OWNER, replacement of one- or two-course surface treatment or penetration type pavement surface shall be paid in accordance with [Item 404](#). Surface Treatments.

The contract unit price shall be total compensation for furnishing and placing all materials, including excavation, compaction, rolling and finishing, for disposal of all surplus material, and for all labor, tools, equipment and incidentals necessary to complete the work, all in accordance with the plans and specifications.

ITEM 403. ASPHALTIC PAVEMENT REPAIR

403.1. DESCRIPTION

Asphaltic Pavement Repair shall be used only for patching utility cuts, potholes and temporary pavement repairs.

403.2. MATERIALS AND MIXING

403.2.1. Performance Guaranty. The supplier of the material shall guarantee the performance of the patching mix to meet the following requirements:

- (1) The material shall remain workable, in an uncovered stockpile, if applicable, for a period of not less than 12-months.
- (2) Containerized material, if applicable, shall have a shelf life and remain workable for a period of not less than 12-months.
- (3) Repaired potholes shall not show any significant signs of shoving, rutting, tracking, kick-up, or ravel-out within a period of 12-months from the time of repair.

403.2.2. Rejection. In the event a material furnished does not meet all of the specified requirements (regardless of weather, test's acceptability, methods of repair, or other conditions), the material shall be removed and replaced at no cost to the OWNER.

The OWNER shall determine the quantity of unacceptable material and the CONTRACTOR shall be required to deliver an equal quantity of acceptable material. The material shall be delivered to the location(s) designated by the OWNER within 14-days from the date of written notification from the OWNER.

In the event that the material CONTRACTOR cannot provide acceptable material, the OWNER shall determine the quantity of the unacceptable material and the CONTRACTOR shall reimburse the OWNER based on the unit bid price. The reimbursement shall be submitted to the OWNER in the form of a cashier's check or other form of payment as approved by the OWNER within 28-days from the date of written notification from OWNER.

403.2.3. Hot-Mix, Cold-Laid Asphaltic Concrete (Cold Mix). Hot-Mix, Cold-Laid Asphaltic Concrete shall consist of surface mix.

403.2.3.1. Asphaltic Mixture. The asphaltic material shall form from 4% to 7.5% of the mixture by weight. Asphalt for the mixture shall be a bituminous material in accordance with [Item 302.3.](#) Bituminous Materials as determined by the mix manufacturer and OWNER. The grade of asphalt to be used shall be determined by the OWNER after design tests have been made using the mineral aggregate approved for use in the construction. The CONTRACTOR shall notify the OWNER of asphaltic material source prior to production of the asphaltic mixture, and this source shall not be changed during the course of the project except by written permission of the OWNER.

403.2.3.2. Tack Coat. The liquid asphalt material used for tack coat should be MS-2 or SS-1 in [Item 302.3.4.](#) Emulsified Asphalt, Restorative Seal in [Item 302.3.6.](#) Specialty Emulsions or one of the other various grades of materials (selected by the OWNER) listed under [Item 302.3.4.](#) Emulsified Asphalt.

403.2.3.3. Primer. When approved by the OWNER, the use of an asphaltic primer will be permitted. When used, the primer shall be added as directed by the OWNER during the mixing.

403.2.3.4. Mineral Aggregate. The material shall be crushed and screened as necessary to meet the requirements hereinafter specified and shall consist of durable coarse aggregate particles mixed with approved binding materials.

Unless otherwise specified, the grading of mineral aggregate shall conform to the limitations as shown in Table 403.2.3.4.(a) Aggregate Grading for Cold Mix Asphalt Repair.

Table 403.2.3.4.(a) Aggregate Grading for Cold Mix Asphalt Repair

Sieve	% Aggregate by Weight
Passing 3/8-in. sieve	100%
Passing 1/4-in. sieve	80 to 100%
Passing 1/4-in. sieve, retained on No. 10 sieve	27 to 58%
Total retained on No. 10 sieve	42 to 58%
Passing No. 10 sieve, retained on No. 40 sieve	6 to 32%
Passing No. 40 sieve, retained on No. 80 sieve	4 to 32%
Passing No. 80 sieve, retained on No. 200 sieve	3 to 32%
Passing No. 200 sieve	1 to 8%

403.2.3.5. Water. Water in an amount not to exceed 3% by weight of the mixture may be used in preparing the mixture. In the event water is used in the mixing operation, adequate measuring devices as approved by the OWNER shall be used, and the water shall be administered to the mix through an approved spray bar.

When used, the water shall be added as directed by the OWNER during the mixing.

403.2.3.6. Mixture Preparation. The materials may be mixed on the job or at a central mixing plant and shipped ready for use. Mixtures that do not remain workable a sufficient period of time to permit unloading by normal means, proper spreading, blading and rolling shall not be acceptable.

403.2.3.6.1. Mixing Plants. Mixing plants may be either the weight-batching type plant, the continuous mixing type plant, or the drum mixing type plant as described in [Item 302.9.5](#). Mixing Plants.

403.2.3.6.2. Equipment. Equipment for storage, weighing and heating of materials shall be as described in [Item 302.9.4](#). Equipment.

403.2.4. High Performance Cold Mix Asphaltic Concrete. This specification shall govern for asphaltic concrete mixture intended primarily as a cool to cold wet-weather, high-performance, pothole-patching mix for maintenance. It is primarily crushed stone, asphaltic concrete with asphalt additives.

When shown on the plans or requisition, the mixture shall be provided in airtight, resealable plastic buckets of 4- to 5-gal. capacities.

403.2.4.1. Mixture Performance Criteria. The patching mix shall not require the use of a tack coat or a primer for adherence to the patch area. The mix shall be capable of being placed in air temperatures from -15°F to 100°F and shall maintain adhesive qualities in areas that are damp or wet at the time of application. The repaired areas shall remain flexible and cohesive to an air temperature of -15°F and shall have the capability of immediately being opened to traffic with no kick-up or ravel-out.

403.2.4.2. Mixture Properties. The mixture shall comply with the following requirements.

403.2.4.2.1. Aggregate. Aggregate shall have a maximum particle size of 1/2-in.

403.2.4.2.2. Resistance to Water Damage. Tests shall be conducted according to TxDOT methods. The as-received mix shall be evaluated for resistance to water damage by soaking a 3.5-oz. representative sample of the total mixture in 7-fluid-ounces of distilled or deionized water at 140 ± 2°F for 24 ± 2 hours. The soaking test shall be accomplished in a glass beaker of approximately 14-fluid-ounces. Upon completion of the 24-hour period, the mixture shall be evaluated while submerged in the testing water. The material shall show no visible evidence of stripping.

403.3. METHODS

If OWNER requires base, subbase, and/or subgrade repair by a separate method than the asphaltic patch, the base, subbase, and/or subgrade shall be repaired as specified by the OWNER. Otherwise, repair of the base, subbase, and/or subgrade may be accomplished using the asphaltic patch material when it is specifically designed to do so.

CONTRACTOR shall use all repair material(s) as instructed by its respective manufacturers.

403.4. MEASUREMENT AND PAYMENT

Repair of base, subbase, and/or subgrade if by a separate method than the asphaltic patch shall be measured as specified by the OWNER. Asphaltic patches shall be measured per each, which repair shall include all materials, work, equipment and incidentals necessary to accomplish patching as instructed by the manufacturers.

Payment for Asphaltic Pavement Repair, measured as provided for, shall be paid for at the unit price bid.

ITEM 404. SURFACE TREATMENTS

404.1. DESCRIPTION

This Item provides specifications for the construction and quality control required for the proper application of pavement surface treatments.

404.2. GENERAL

404.2.1. Environmental Conditions. Surface treatments shall not be applied when the air temperature is below 60°F and is falling but may be applied when the air temperature is above 50°F and is rising, the air temperature being taken in the shade and away from artificial heat. If the air temperature does not meet these criteria, the OWNER shall evaluate the asphaltic material for applicability. Surface treatments shall not be applied when the temperature of the surface to which the surface treatment is to be applied is below 60°F. When latex modified asphalt cement is specified, surface treatments shall not be applied when the air temperature is below 80°F and is falling, but may be applied when the air temperature is above 70°F and is rising and shall not be applied when the temperature of the surface on which the surface treatment is to be applied is below 70°F. Asphaltic material shall not be placed when, in the opinion of the OWNER, general weather conditions are not suitable.

Slurry seal or micro-surfacing shall only be applied between March 1st and December 1st. Neither treatment shall be applied under any of the following conditions:

- (1) In the period following precipitation with water remaining on the surface to be coated
- (2) In foggy conditions
- (3) If there is a threat of rain before the treatment can fully cure
- (4) If there is danger that the finished product will freeze within 24-hours of application
- (5) If weather conditions could delay opening to traffic beyond the time specified by the OWNER.

404.2.2. Storage and Stockpiling. Precautions shall be taken to insure aggregate does not become contaminated with over-sized rock, clay, silt or excessive amounts of moisture during storage. The stockpile shall be kept in areas that have good drainage. Segregation of aggregates proposed for use and as supplied to the mixing plant shall be avoided.

The CONTRACTOR shall be required to provide a suitable storage facility for all equipment and materials needed to perform the work. This site should be located as close as possible to the area of work being done to reduce turnaround time and insure an acceptable rate of work. The OWNER shall subject any site selected to final approval.

Temporary stockpiling of aggregates on the roadways shall be permitted, provided the stockpiles are spaced not less than 1,000-ft. apart and are so placed that they neither obstruct traffic nor interfere with roadway drainage. The CONTRACTOR shall be responsible for the proper preparation of all stockpile material necessary for protection of the aggregate and to prevent any contamination thereof.

404.3. SLURRY SEALS AND MICRO- (RE) SURFACING

The surface treatment shall consist of a mixture of an approved emulsified asphalt, mineral aggregate, mineral filler, water, and specified additives, proportioned, mixed and uniformly spread over a properly prepared surface. The completed slurry seal shall leave a homogenous mat, adhere firmly to the prepared surface and have a skid resistant surface texture.

404.3.1. Laboratory Evaluation. Before work commences, the CONTRACTOR shall submit a signed original of a mix design containing the test results and proportioning of the specific materials to be used on the project. A qualified laboratory must have performed this design. Previous lab reports covering the exact materials to be used may be accepted provided they were made during the calendar year. This initial mix design shall be done at the CONTRACTOR'S expense. Upon receipt of the original mix design, an independent qualified laboratory selected by the OWNER shall perform tests using the same materials as used in the initial mix design for verification of the results. This testing shall be done at the OWNER'S expense. No work shall begin until all materials and/or mix design proportions have met the specifications as required. Once the materials are approved, no substitution shall be permitted unless first tested and approved by the methods stated above.

404.3.2. Materials.

404.3.2.1. Mineral Filler. Mineral filler shall be a recognized brand of non-air-entrained Type I or II Portland that meets the requirements of ASTM D242 Mineral Filler For Bituminous Paving Mixtures, if required by the mix design. 0.5% to 2% by dry weight of aggregate shall be the range of mineral filler in the mix design. The mineral filler shall be considered as part of the dry aggregate.

404.3.2.2. Water. All water shall be potable and compatible with the slurry mix. The CONTRACTOR must insure compatibility. The percent of water in the mix design shall be as required to produce proper mix consistency.

404.3.2.3. Additives. The mix design laboratory as part of the mix design shall approve any additive used to accelerate or retard the break-set of the surface treatment materials. The amount and type of additive (if needed) shall be shown on the mix design and approved by the OWNER.

404.3.2.4. Aggregate. The mineral aggregate shall consist of natural or manufactured crushed stone such as granite, slag, limestone or other high quality aggregates or a combination thereof that conforms to the quality requirement of ASTM D1073 Fine Aggregate for Bituminous Paving Mixtures, and shall be free of dirt, organic matter, clay balls, adherent films of clay, dust or other objectionable material. If the OWNER accepts aggregate that is not free of dirt, organic matter, clay balls, adherent films of clay, or dust, the OWNER shall have the option to evaluate and accept or reject chemical modifiers of the asphaltic material. The aggregate shall contain no free water. Smooth textured sands of less than 1.25-percent water absorption shall not exceed 50-percent (by weight) of the total aggregate blend. For heavy-duty surface requirements, 100% crushed material is required.

The aggregate shall meet the gradations as shown in the Table 404.3.2.4.(a) Slurry Seal Aggregate Requirements or Table 404.3.2.4.(b) Micro-Surface Aggregate Requirements, as appropriate, and shall not vary from the low limit on one sieve to the high limit on the adjacent sieves or vice versa. The gradation type to be used shall be as designated by the OWNER.

Table 404.3.2.4.(a) Slurry Seal Aggregate Requirements

Sieve Size	Percent Passing
3/8-in.	100
No. 4	70-90
No. 8	45-70
No. 16	28-50
No. 30	19-34
No. 50	12-25
No. 100	7-8
No. 200	5-15

Table 404.3.2.4.(b) Micro-Surface Aggregate Requirements

Sieve Size	Percent Passing
3/8-in.	99-100
No. 4	86-94
No. 8	45-65
No. 16	25-46
No. 30	15-35
No. 50	10-25
No. 100	7-18
No. 200	5-15

404.3.2.5. Emulsified Asphalt. The asphalt emulsion shall be homogeneous and show no separation after mixing.

404.3.2.5.1. Slurry Seal. As directed by the OWNER, one of the following two grades of emulsion shall be selected. Grade CQS-1h (Quick Set) shall be specified on streets where the amount of time the street can be closed is restricted.

Grade SS-1h: Conforming to the requirements specified in ASTM D977 for Emulsified Asphalt.

Grade CQS-1h: Conforming to the requirements specified in ASTM D2397 for Cationic Emulsions (Quick Set).

Any emulsion used for slurry will be with 4% polymer modifier content based on bitumen weight, certified by the emulsion supplier, which shall be milled into the emulsion or blended into the asphalt prior to the emulsification process. It shall pass all applicable storage and settlement tests. The cement-mixing test shall be waived.

404.3.2.5.2. Micro-Surface. Emulsified asphalt for micro-surfacing shall be a quick-set polymer modified cationic type CSS-1h emulsion and conform to the requirements specified in AASHTO M208 and ASTM D2397 Cationic Emulsified Asphalt. It shall pass all applicable storage and settlement tests. A minimum of 3% polymer modifier content based on bitumen weight content, certified by the emulsion supplier, along with special quick-setting emulsifier agents, shall be milled into the asphalt emulsion. The cement mixing test shall be waived. The emulsified asphalt shall be so formulated that when the paving moisture is applied with the relative humidity at no more than 50% and ambient air temperature of at least 75°F, it will cure sufficiently such that rolling traffic can be allowed in one-hour with no damage to the surface.

404.3.2.6. Mixture Tests. Mixtures shall meet the requirements in Table 404.3.2.6.(a) Slurry Seal Mixture Requirements or Table 404.3.2.6.(b) Micro-Surface Mixture Requirements, as appropriate when tested by the given methods.

Table 404.3.2.6.(a) Slurry Seal Mixture Requirements

Characteristic	Test Method	Value
Consistency test	ASTM D3910 Standard Practices for Design, Testing, and Construction of Slurry Seal	2- to 3-cm Flow
Set time	ASTM D3910 (same as above)	12-hours maximum
Cure time	ASTM D3910 (same as above)	24-hours maximum
Wet stripping test	ISSA TB114	80%-coating minimum
Wet track abrasion test	ASTM D3910 (same as above)	75-g/ft ² maximum

Table 404.3.2.6.(b) Micro-Surface Mixture Requirements

Characteristic	Test Method	Value
Set time	ASTM D6372 Standard Practice for Design, Testing, and Construction of Micro-Surfacing	12-hours maximum
Cure time	ASTM D6372 (same as above)	24-hours maximum
Wet stripping test	ISSA TB114	80%-coating minimum
Wet track abrasion test	ASTM D6372 (same as above)	75-g/ft ² maximum
Marshall stability Flow units	ASTM D5581 Standard Test Method for Resistance to Plastic Flow of Bituminous Mixtures Using Marshall Apparatus (6 inch-Diameter Specimen)	1800-lbs. minimum 6- to 16-units
Hveem stability, exceeding a height twice the maximum aggregate size	ASTM D1560 Resistance to Deformation and Cohesion of Bituminous Mixtures by Means of Hveem Apparatus	35 minimum
Set Time 30-minute Blotter test Displacement test Water resistance test @ 30-Minutes	ISSA TB102	No Brown Stain No Displacement No Discoloration

404.3.3. Equipment. All methods and equipment employed in performing the work shall be subject to the approval of the OWNER before work is started and whenever found unsatisfactory they shall be changed and improved as required. All equipment must be maintained in a satisfactory condition.

The CONTRACTOR will provide suitable crack and pavement cleaning equipment, hand tools and any support equipment as necessary to perform the work.

404.3.3.1. Calibration. Each piece of equipment to be used shall be calibrated in the presence of the OWNER prior to construction. Previous calibration documentation covering the exact materials to be used may be accepted provided they were made during the calendar year. No machine will be allowed to work on the project until the calibration has been completed and/or accepted.

404.3.3.2. Verification. Test strips shall be laid (location to be determined by the OWNER) before construction begins. The OWNER will observe the test strip for verification or rejection according to the specifications. Upon failure of any test, additional test strips will be laid at no cost to the OWNER. The square-yards of the first test strip will be measured and paid for at the contract unit price.

A field test shall be made to check consistency of the surface treatment. If a line made through the surface treatment fills up, the mixture is too wet, which the CONTRACTOR shall correct. If the line stays, the slurry has a proper consistency.

404.3.3.3. Mixing Equipment.

404.3.3.3.1. Slurry Seal. The slurry seal mixing equipment shall be continuous flow mixing unit as to give a uniform and complete circulation of the batch in the mixer, so as not to segregate the aggregates, but will provide a thorough and uniform free flowing mix with the asphalt and water. The units shall be equipped with a water pressure system and nozzle type spray bar adequate for completely fogging the surface with 0.05- to 0.15-gallons-per-square-yard immediately ahead of the spreader box.

Application rate of aggregate, based on dry weight of aggregate, shall be 15- to 21-lbs-per-square-yard complete in place.

The residual asphalt content, based on % weight of dry aggregate, shall be 8% to 12%.

404.3.3.3.2. Micro-Surface Mixing Equipment. The material shall be mixed by a self-propelled micro-surfacing mixing machine which shall be a continuous flow mixing unit able to accurately deliver and proportion the aggregate, emulsified asphalt, mineral filler and water to a revolving multi-blade mixer and discharge the mixed product on a continuous flow basis. The machine shall have sufficient storage capacity for aggregate, emulsified asphalt, mineral filler and water to maintain an adequate supply to the proportioning controls. The machine shall be equipped with self-loading devices which provide for the loading of all materials while continuing to lay micro-surfacing, thereby minimizing construction joints.

Individual volume or weight controls for proportioning each material to be added to the mix shall be provided. Each material control device shall be calibrated and properly marked.

The mixing machine shall be equipped with a water pressure system and nozzle type spray bar to provide a water spray immediately ahead of and outside the spreader box with 0.05- to 0.15-gallons-per-square-yard.

The aggregate feed to the mixer shall be equipped with a revolution counter or similar device so the amount of aggregate used may be determined at any time. The mixing machine shall be equipped with an approved fines feeder that shall provide a uniform accurately metered, predetermined amount of the specified mineral filler. Application rate of aggregate, based on dry weight of aggregate, shall be 22- to 28-lbs-per-square-yard complete in place.

The emulsion pump shall be a positive displacement type and shall be equipped with a revolution counter or similar device so that the amount of emulsion used may be determined at any time. The residual asphalt content, based on % weight of dry aggregate, shall be 6% to 11.5%.

404.3.3.4. Spreading Equipment.

404.3.3.4.1. Slurry Seal. The spreader box shall be equipped to prevent loss of slurry seal from all sides and with a flexible rear strike-off capable of being adjusted. It shall have suitable means for side tracking to compensate for deviations in pavement geometry. The box shall be kept free of built-up asphalt and aggregate. The strike-off drag shall be kept completely flexible at all times.

404.3.3.4.2. Micro-Surface. The surface mixture shall be spread uniformly by means of a mechanical type spreader box attached to the mixer, equipped with paddles to agitate and spread the materials throughout the box. A front seal shall be provided to insure no loss of the mixture at the road contact point. The rear seal shall act as final strike off and shall be adjustable. The mixture shall be spread to fill cracks and minor surface irregularities and leave a uniform skid resistant application of material on the pavement. The longitudinal joint where two passes join shall be neat appearing, uniform and lapped. All excess material shall be removed from the job site prior to opening the road. The spreader box shall have suitable means provided to side shift the box to compensate for variations in pavement geometry.

404.3.4. Preparation. Any breakdowns, base failures, or other defects shall be properly repaired by the OWNER before application of the surface treatment. No work shall commence on any location until approval by the OWNER.

Immediately prior to applying the surface treatment, CONTRACTOR shall thoroughly clean the pavement of all loose materials, vegetation, soil and objectionable material. The CONTRACTOR shall cover manholes, valve boxes, raised pavement markers and other designated objects to insure their integrity. All pavement cleaning and covering of appurtenances shall be subject to the final approval and acceptance of the OWNER.

If required, the CONTRACTOR shall apply a tack coat or a second coverage of treatment on brick, concrete, or other highly absorbent or polished pavements. If a tack coat is required, a 1-part emulsion, 3-part water tack coat of the same asphalt emulsion type and grade as specified for the surface treatment is required. Rate of application of tack coat material shall be 0.05- to 0.10-gallons-per-square-yard. All debris and unused material shall be removed.

404.3.5. Surface Treatment Application. Surface treatments shall be placed on the location and within the time limit as specified by the OWNER.

404.3.5.1. Fogging. If conditions require, the pavement shall be pre-wetted by fogging ahead of the slurry/spreader box. Water used in fogging the surface shall be applied so that the entire surface is damp with no flowing water in front of the box. Rate of spray shall be 0.05- to 0.15-gallons-per-square-yard or as directed by the OWNER. No streaks, lumps, balls or unmixed aggregated shall be permitted.

404.3.5.2. Mix Stability. The mix shall be sufficiently stable during the spreading period so that the emulsion does not break, there is no segregation of the fines from the coarser aggregate and the liquid of the mix does not float to the surface.

404.3.5.3. Lines and Joints. Straight lines along curb gutters and shoulder will be required. No runoff on these areas will be permitted. Lines at intersections must be kept straight to provide a good appearance. Surface treatment shall be placed at the lip of the gutter or at a distance from the face of the curb as directed by the OWNER.

No excessive buildup or unsightly appearance shall be permitted on longitudinal or transverse joint. An excessive overlap will not be permitted on longitudinal joints. The CONTRACTOR shall provide suitable width spreading equipment to produce a minimum number of longitudinal joints throughout the project. Longitudinal joints shall be placed on lane lines when possible. If half passes are used, they shall not be the last passes on any paved area.

404.3.5.4. Rolling. If required, specified areas shall be rolled by a self-propelled 10-ton pneumatic roller with tire pressure of 50-psi and equipped with a water spray system. The slurried pavement shall be subjected to a minimum of 5 full coverages by the roller. Rolling should not commence until the slurry has cured enough so that it will not pick up on the tires. In areas of high traffic volume and subject to slow turning, e.g. major intersections, rolling may be feasible.

404.3.5.5. Hand Work. In areas where the spreader box cannot be used, hand squeegees to provide complete and uniform coverage shall apply the surface treatment. Any joint cracks not filled by the mix shall be corrected by use of hand squeegees. Handwork shall be completed during the machine applying process. Due to the difficulty in hand working micro-surfacing material because of the quick-set nature of the emulsion, hand work for micro-surface treatment shall be kept to a minimum.

404.3.5.6. Curing and Finishing. All traffic shall be kept off the treated area until it has cured to a firm condition that will prevent damage to the surface treatment. Any uncured areas damaged will be repaired satisfactory to the OWNER at the CONTRACTOR'S expense.

After completion of surface treatment placement, the CONTRACTOR shall remove covered objects (manhole covers, valve covers, raised traffic markers, etc.) so the object protected will remain fully functional. All objects not to have been covered shall be restored to original integrity. Any objects damaged by the CONTRACTOR'S work activities shall be repaired or replaced at no cost to the OWNER.

Any work directed by the OWNER to correct any appearance defect shall be subject to the final approval of the OWNER.

The CONTRACTOR shall remove all unused material and debris from the site prior to final acceptance.

404.3.6. Measurement and Payment. The treated area on each street shall be field measured and calculated in square-yards. Payment shall be approved if the amount of emulsion and aggregate fall within the specified application range per square-yard. Payment per square-yard shall be full compensation for grass removal, cleaning the existing pavement, all material (including mineral filler, water, modifiers and additives) labor, tools, equipment, maintenance of traffic and notification of adjacent property owners and incidentals necessary to complete the work.

404.4. BITUMINOUS SURFACE TREATMENT (CHIP SEAL)

404.4.1. Description. This item shall consist of a wearing surface composed of one, two or three applications of asphaltic materials, each covered with aggregate, constructed on the prepared base course or surface in accordance with the requirements as shown on the plans and these specifications.

404.4.2. Materials.

404.4.2.1. Asphaltic Materials. The asphaltic materials used shall be of the type and grade as specified by the owner and shall meet the requirements of [Item 302.3](#). Bituminous Materials.

WARNING TO CONTRACTOR: Attention is called to the fact that asphaltic materials are highly flammable. The utmost care shall be taken to prevent open flames from coming in contact with the asphaltic materials or the gases of same. The CONTRACTOR shall be responsible for any fires or accidents that may result from heating the asphaltic materials.

404.4.2.2. Aggregate. Aggregate shall be composed of dry, sound, durable particles of processed stone or steel slag having a percent of wear of not more than 35 when tested in accordance with ASTM C131 Method for Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine. Crushed gravel shall not be allowed. The aggregate shall be free from organic matter, clay, loam, or coated pebbles and shall contain no more than five-percent of slate, shale, schist, or soft particles.

The aggregate used shall be of the type and grade or types and grades selected from those prescribed in [Item 301.5](#). Flexible Subbase or Base (Crushed Stone/Concrete). The particular type and grade or types and grades shall be as provided on the plans or as required by the OWNER.

Aggregate when tested by standard laboratory methods shall meet the grading requirements in Table 404.4.2.2.(a) Chip Seal Aggregate Gradations. Prior to shipping aggregate to the project, the CONTRACTOR shall furnish the OWNER with samples of the proposed aggregate.

Table 404.4.2.2.(a) Chip Seal Aggregate Gradations

Sieve Size	% Retained, by weight	Sieve Size	% Retained, by weight
FIRST APPLICATION			
Small Aggregate "SB"		Large Aggregate "LB"	
5/8-in.	0%	1-in.	0%
1/2-in.	0 - 10%	3/4-in.	15 - 45%
1/4-in.	70 - 100%	1/2-in.	85 - 100%
No. 10	95 - 100%	1/4-in.	98 - 100%
SECOND APPLICATION			
Small Aggregate "ST"		Large Aggregate "LT"	
3/8-in.	0%	3/4-in.	0%
1/4-in.	2 - 20%	1/2-in.	0 - 10%
No. 10	70 - 100%	1/4-in.	65 - 85%
No. 20	95 - 100%	No. 10	90 - 100%
		No. 20	98 - 100%

404.4.2.2.1. Precoated Aggregate. The grade of aggregate specified shall meet all other requirements of [Item 404.4.2.2](#). Aggregate prior to the application of precoat or fluxing material. Materials that are not uniformly and/or properly coated, in the opinion of the OWNER, shall not be accepted for use.

Precoated aggregate shall be aggregate of the type and grade specified, coated with 0.5- to 1.5-percent (by weight) of residual bitumen from a precoating material. When limestone rock asphalt is used, it shall be fluxed with 0.5- to 1.5-percent (by weight) of fluxing material. The materials may be mixed on the job or at a central mixing plant and shipped ready for use. Mixes that do not maintain flow qualities such that the precoated aggregate may be satisfactorily spread by approved mechanical spreading devices will not be acceptable.

Precoated aggregate will show no stripping when tested in accordance with TxDOT test method Tex-530-C Effect of Water on Bituminous Paving Mixtures. If antistripping additives are required to meet this requirement, they shall meet the requirements of TxDOT Item 301 Asphalt Antistripping Agents.

404.4.3. Construction Methods.

404.4.3.1. Equipment and Preparation. All storage tanks, piping, retorts, booster tanks, and distributors used in storing or handling asphalt shall be kept clean and in good operating condition at all times. They shall be operated in such a manner that there shall be no contamination of the asphalt with foreign material.

The area to be treated shall be cleaned of dirt, dust or other deleterious matter by sweeping or other approved methods. If it is found necessary by the OWNER, the surface shall be lightly sprinkled just prior to the application of the asphaltic material.

404.4.3.2. Application of Asphalt. The OWNER shall select the temperature of application based on the temperature-viscosity relationship that shall permit application of the asphalt with the limits recommended in [Item 302.5](#). Storage, Heating and Application Temperature of Bituminous Materials. The CONTRACTOR shall apply the asphalt at a temperature within 15°F of the temperature selected. It shall be the responsibility of the CONTRACTOR to provide and maintain in good working order a recording thermometer at the storage heating unit at all times.

Asphaltic material may be placed by preheating aggregate to 280°F when the air temperature is 70°F and falling or when the air temperature is 50°F and rising.

Asphaltic material of the type and grade shown on the plans shall be applied on the clean surface by an approved type of self-propelled pressure distributor so operated as to distribute the material in the quantity specified, evenly and smoothly, under a pressure necessary for proper distribution. The CONTRACTOR shall provide all necessary facilities for determining the temperature of the asphaltic materials in all of the heating equipment and in the distributor, for determining the rate at which they are

applied, and for securing uniformity at the junction of two distributor loads. The distributor shall have been recently calibrated and the OWNER shall be furnished an accurate and satisfactory record of such calibration. After beginning the work, should the yield on the asphaltic materials appear to be in error, the distributor shall be recalibrated in a manner satisfactory to the OWNER before proceeding with the work.

Asphaltic materials for each course may be applied for the full width of the surface treatment in one application, unless the width exceeds 26-ft. No traffic or hauling shall be permitted over the freshly applied asphaltic materials. Asphaltic materials shall not be applied until immediate covering with aggregate is assured.

404.4.3.3. Application of Aggregate. Aggregate, of the type and grade shown on the plans for the first course, shall be immediately and uniformly applied and spread by approved calibrated mechanical spreaders, operated on the rear of the aggregate trucks or as a separate power-driving unit. These spreader units shall be approved by the OWNER prior to the start of the work. The aggregate shall be applied at the approximate rates indicated on the plans, within the limits shown in Table 404.4.3.4.(a) Chip Seal Rates of Application, and as directed by the OWNER. The entire surface shall then be broomed, bladed or raked as required by the OWNER and shall be thoroughly rolled with both pneumatic tire and steel wheel (3- to 6-tons) rollers to insure proper embedding into the bitumen. The rolling shall be continued until no more aggregate can be worked into the surface. Rolling shall meet the governing specifications for [Item 301.1.2](#), Rolling of Embankment, Subgrade or Flexible Base.

404.4.3.4. Rates of Application. The asphalt and aggregates shall be applied at the approximate rates indicated on the plans within the following limits, as directed by the OWNER. The rates of application and the estimated quantities of aggregate are based on the usual or average gradation of known materials. Prior to shipping aggregate to the project, the CONTRACTOR shall furnish the OWNER with samples of the proposed aggregate so that the gradation may be determined and rate of application changed if necessary.

Table 404.4.3.4.(a) Chip Seal Rates of Application

Application	Asphalt gal/yd ²		Aggregate yd ³ per yd ²	
	Minimum	Maximum	Minimum	Maximum
SMALLER AGGREGATE				
First, Aggregate "SB"	0.20	0.30	1:100	1:75
Second, Aggregate "ST"	0.30	0.40	1:200	1:150
LARGER AGGREGATE				
First, Aggregate "LB"	0.25	0.35	1:75	1:50
Second, Aggregate "LT"	0.35	0.45	1:150	1:100

404.4.3.5. Multiple Courses. Where double or triple surface courses are specified on the plans, each succeeding course shall be constructed by the procedures as prescribed for the first course. The rates of asphaltic material and aggregate for multiple-course construction shall be as shown on the plans within the limits shown in Table 404.4.3.4.(a) Chip Seal Rates of Application or as directed by the OWNER.

404.4.3.6. Maintenance and Completion. The CONTRACTOR shall be responsible for the maintenance of the surface and distribution of the excess aggregate until final completion and acceptance of the entire project by the OWNER. All holes or failures in the surface shall be repaired per each course by use of additional asphalt and aggregate. All fat or bleeding surfaces shall be covered with approved cover material per each course in such a manner that the asphaltic material will not adhere to or be picked up by the wheels of vehicles.

404.4.4. Measurement and Payment. Bituminous surface treatments shall be measured by the square-yard of surface area of completed and accepted per bid item “One-, “Two-, or “Three-Course Surface Treatment.”

Rolling shall not be measured for payment but shall be considered as subsidiary to the Items of “Asphalt” and/or “Aggregate.” Work performed and materials furnished as prescribed by this item and measured as provided in this item shall be paid for at the unit price bid for “One-, “Two-, or “Three-Course Surface Treatment,” which price shall be full compensation for cleaning and sprinkling the surface to be treated; for furnishing, preparing, hauling and placing all materials; for all blading, brooming, rolling; and for all manipulations, labor, tools, equipment and incidentals necessary to complete the work.

ITEM 405. ULTRA THIN CONCRETE PAVING (WHITETOPPING)

405.1. DESCRIPTION

This Item shall govern for a 2-inch thick to 4-inch thick bonded concrete overlay placed on an asphaltic surface in accordance with the details shown on the plans and the requirements of this Item.

405.2. MATERIALS

Unless otherwise shown on the plans or required herein, all materials shall conform to the requirements of [Item 303](#). Portland Cement Concrete Pavement, except for the following:

- (1) The concrete shall be designed to include seven (7) sacks of Type III cement per cubic yard.
- (2) The maximum water cement ratio shall not exceed 5.5-gallons per sack.
- (3) The fineness modulus of aggregate shall be 2.6 to 2.8 unless otherwise shown on the plans.
- (4) An ASTM Type A water-reducing admixture and an ASTM Type C non-chloride set-accelerating admixture shall be used to achieve the earliest possible concrete-setting times.
- (5) The use of a set-retarding admixture will not be permitted.
- (6) The concrete will be designed to achieve a minimum flexural strength of 425 psi.

Aggregate size shall conform to size number 467 as shown in Table 303.2.1.3.2.(a) Grading Requirements for Coarse Aggregates.

The entrained air content of the fresh concrete shall be 4% with a tolerance of +/-1% when tested in accordance with TxDOT Test Method Tex-416-A.

Reinforcing fibers in accordance with [Item 303.2.6](#). Fibrous Reinforcement shall be of the type and amount shown on the plans, and shall be added to the mix in accordance with the manufacturer's recommendations.

Curing materials shall conform to [Item 303.2.13](#). Curing Materials or as specified on the plans.

Equipment and forms shall comply with requirements as stated in [Item 303](#). Portland Cement Concrete Pavement.

405.3. CONSTRUCTION METHODS

405.3.1. General. Loads on the milled area shall be kept to a minimum so not to cause failure to the underlying material. This may require using small loads of concrete or other than normal concrete delivery methods. Once the milled area has been cleaned, no traffic other than construction equipment for the overlay shall be permitted on any portion of the milled area. The thickness of the concrete overlay shall be as specified on the plans. The screed shall be adjusted to provide an approved grade line and sufficient thickness. To identify insufficient depth areas prior to concrete placement, the following procedures shall be used, unless other methods are approved by the OWNER. To identify areas of insufficient depth, a filler block having a thickness ¼-inch less than the overlay thickness shall be attached to the bottom of the screed and the screed shall be passed over the area to be overlaid. Areas which have insufficient depths shall be corrected by adjustments of the screed and/or rail system, or by chipping or scarifying of the milled asphalt prior to the overlay as approved by the OWNER.

405.3.2. Preparation of Surface. Oil or other foreign material spilled or dripped onto the milled surface shall be removed by cleaning. Immediately before the concrete is placed, the asphalt surface shall be cleaned with a filtered air blast to remove windblown dust, dirt, debris, and standing water and then brought to a moist, approximately saturated surface dry condition. It is important that the milled surface be thoroughly clean so as to facilitate the bond between the asphaltic surface and the concrete.

405.3.3. Spreading and Finishing Concrete. The spreading and finishing of the concrete overlay shall be in accordance with [Item 303](#). Portland Cement Concrete Pavement, including environmental constraints.

405.3.4. Transverse Construction Joints. When the placing of concrete is stopped, CONTRACTOR shall provide a bulkhead of sufficient cross sectional area to prevent deflection that is shaped accurately to the cross section of the pavement. The bulkhead shall be at right angles to the centerline of the pavement, perpendicular to the surface and at the required elevation. Intentional stoppage of the placing of the concrete shall be at either a construction joint or at a weakened plane joint. This joint shall be sawed and sealed using a joint sealant in accordance with [Item 303](#). Portland Cement Concrete Pavement, type as indicated on the plans.

When an unintended stoppage occurs, the CONTRACTOR shall immediately install the above described bulkhead at a weakened plane joint. The available concrete should completely fill against the bulkhead and any concrete remaining on the subgrade ahead of the bulkhead shall be removed and disposed of as directed by the OWNER. This joint shall be sawed and sealed using a joint sealant in accordance with [Item 303](#), Portland Cement Concrete Pavement, type as indicated on the plans.

All construction joints adjacent to existing concrete paving, curb, or curb and gutter shall be sawed and sealed using a joint sealant in accordance with [Item 303](#), Portland Cement Concrete Pavement, type as indicated on the plans.

405.3.5. Initial Curing. Immediately after any section of pavement has been tined and the surface moisture has disappeared, the concrete surface shall be sprayed uniformly with a curing compound as specified in [Item 303.5.7](#), Curing. Immediately after this curing compound has dried, the concrete surface shall be sprayed uniformly with a second application of curing compound in accordance with [Item 303.5.7](#), Curing. Should the membrane be damaged from any cause, except for the sawing cutting, before the water cure is started, the damaged portions shall be repaired immediately with additional compound.

405.3.6. Saw Cutting Weakened Plane Joints. Unless otherwise shown on the plans, sawed joints shall be sawed to a minimum depth of one-third the thickness of the concrete overlay. The minimum saw cut depth for a dry, early saw cut shall be $\frac{3}{4}$ -inch.

Saw cuts shall be perpendicular to the surface of the overlay. Unless otherwise shown on the plans, the saw cuts shall be in lines that are perpendicular and parallel to the centerline of the travel lanes and spaced at a maximum distance apart of 1-foot for every inch of design overlay depth. Saw joints for radii shall be as detailed in the plans. Chalk line, offset string line, sawing template or other approved methods shall be used to provide a true joint alignment. The saw cuts are not to be sealed, but shall be cleaned of all deleterious material after sawing.

Since the starting and ending times for sawing is the function of many variables within the mix, the weather, and the type and number of saws used, the CONTRACTOR is wholly responsible for the timing and order of the saw cutting. If excess spalling or raveling occurs at the top of the saw cuts or the intersection of saw cuts, or if uncontrolled full depth cracking occurs before traffic is allowed on that portion of the concrete, that portion of concrete which is bordered by existing saw cuts shall be entirely removed and replaced at the CONTRACTOR's expense.

405.3.7. Deficient Thickness. The pavement shall be tested for depth by direct measurement in accordance with TxDOT Test Method Tex-423-A at locations selected by the OWNER. If the thickness of the pavement indicated by the direct measurement depth test is deficient by more than $\frac{1}{4}$ -inch from the plan thickness, the CONTRACTOR may verify the thickness by cores taken in accordance with TxDOT Test Method Tex-424-A at the locations selected by the OWNER.

Any area of pavement deficient in thickness by more than $\frac{1}{4}$ -inch of plan thickness shall be removed and replaced. The deficient area along with the concrete within the same border of the existing saw cuts shall be entirely removed, the asphalt surface chipped or scarified as described above, and the concrete replaced, all at the CONTRACTOR's expense.

405.3.8. Opening to Traffic. Opening of the completed overlay to normal construction traffic and to the traveling public shall be after the concrete has obtained a flexural strength of 255-psi or a compressive strength of 1800-psi.

405.4. MEASUREMENT

Ultra-Thin Concrete Paving will be measured by the square-yard of surface area of completed and accepted work including the area of the thickened edges as shown on the plans. When the placed concrete depth is greater than $\frac{1}{4}$ -inch of plan depth, due to conditions out of the control of the CONTRACTOR, the additional concrete volume in excess of the plan depth shall be measured by the cubic-yard. The planned thickened edges shall not be included in this volume.

405.5. PAYMENT

The work performed and materials furnished in accordance with this Item and measured as provided under "Measurement" shall be paid for at the unit price bid for "Ultra-Thin Concrete Paving" of the depth specified. Such price shall be full compensation for furnishing, loading, unloading, storing, hauling and handling of all concrete ingredients, including all freight and royalty involved; for placing and adjusting forms, including supporting material or preparing track grade; for mixing, placing, finishing and curing concrete; for sawing, cleaning and sealing concrete joints; and for all manipulations, labor, tools, equipment and incidentals necessary to complete the work.

When the placed concrete depth is greater than 1/4-inch of plan depth, due to conditions out of the control of the CONTRACTOR, the additional concrete volume in excess of the plan depth will be paid for by the cubic-yard at the Contract unit price. When the placed concrete depth exceeds the plan thickness due to CONTRACTOR's error or convenience, no adjustment to the Contract unit price will be made for this additional volume of concrete.

A close-up photograph of several large-diameter pipes stacked horizontally. The pipes in the foreground are dark, weathered metal, showing signs of rust and wear. The pipes in the background are a bright red color. The perspective is from a low angle, looking down the length of the pipes, creating a sense of depth.

Division 500

Underground
Construction
and Appurtenances

DIVISION 500 UNDERGROUND CONSTRUCTION & APPURTENANCES

TABLE OF CONTENTS

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
501.	UNDERGROUND CONDUIT MATERIALS	501-1 to 501-23
501.1.	<u>General</u>	
501.2.	<u>Clay Wastewater Pipe</u>	
501.3.	<u>Vitrified Clay Pipe Used in Trenchless Applications</u>	
501.4.	<u>Concrete Pressure Pipe and Fittings</u>	
501.5.	<u>Reinforced Concrete Wastewater Pipe With Rubber Gasket Joints</u>	
501.6.	<u>Reinforced Concrete Culvert, Storm Drain, Pipe and Box Section</u>	
501.7.	<u>Ductile-Iron Pressure Pipe and Fittings</u>	
501.8.	<u>Section Held for Future Use</u>	
501.9.	<u>Steel Pipe and Fittings</u>	
501.10.	<u>Seamless Copper Tubing</u>	
501.11.	<u>Corrugated Metal Pipe or Pipe Arch Shapes</u>	
501.12.	<u>Structural Plate Structures</u>	
501.13.	<u>Tunnel Liner Plates</u>	
501.14.	<u>Polyvinyl Chloride (PVC) Water Pipe</u>	
501.15.	<u>Polyvinyl Chloride (PVC) Pressure-Rated Pipe (SDR Series)</u>	
501.16.	<u>Molecularly Oriented Polyvinyl Chloride (PVCO) Water Pipe</u>	
501.17.	<u>Polyvinyl Chloride (PVC) Wastewater Pipe & Fittings with Dimension Control</u>	
501.18.	<u>Polyvinyl Chloride (PVC) Profile Gravity Wastewater Pipe and Fittings – For Direct Bury and Sliplining Applications</u>	
501.19.	<u>PVC Composite Pipe for Wastewater Conduits</u>	
501.20.	<u>Section Held for Future Use</u>	
501.21.	<u>Solid Wall Polyethylene Plastic Pipe for Water, Wastewater, and Pipe Rehabilitation</u>	
501.22.	<u>Polyethylene (PE) Large Diameter Wastewater Pipe with Modified Wall Profiles and Performance Standards</u>	
501.23.	<u>Thermoplastic Corrugated Drainage Tubing and Corrugated Smooth Lined Storm Water Pipe and Fittings</u>	
501.24.	<u>Fiberglass (Glass-Fiber-Reinforced Thermosetting-Resin) Wastewater Pipe</u>	
501.25.	<u>Fiberglass (Glass-Fiber-Reinforced Thermosetting-Resin) for Water Pipe</u>	
502.	APPURTENANCES	502-1 to 502-30
502.1.	<u>Manholes</u>	
502.2.	<u>Wastewater Main Cleanouts and Access Chambers</u>	
502.3.	<u>Fire Hydrants</u>	
502.4.	<u>Thrust Restraint</u>	
502.5.	<u>Fittings</u>	
502.6.	<u>Valves</u>	
502.7.	<u>Performed Flexible Conduit Joint Sealant</u>	
502.8.	<u>Polyethylene Wrap for Metal Pipe and Fittings</u>	
502.9.	<u>Corrosion-Resistant Coatings and Liners for Wastewater Conduit and Appurtenances</u>	
502.10.	<u>Connections to Conduit for Service</u>	
502.11.	<u>Miscellaneous Conduit Connections</u>	
502.12.	<u>Structures</u>	

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
503.	TRENCHLESS INSTALLATION	503-1 to 503-5
503.1.	Conduit Materials	
503.2.	Tunnel/Casing Pipe Spacers	
503.3.	Methods of Jacking, Boring or Tunneling	
503.4.	Measurement and Payment	
504.	OPEN CUT – BACKFILL	504-1 to 504-12
504.1.	General	
504.2.	Materials	
504.3.	Excavation and Foundation	
504.4.	Backfill-General Requirements	
504.5.	Embedment	
504.6.	Final Backfill	
504.7.	Measurement and Payment of Backfill	
505.	OPEN CUT – GENERAL CONDUIT INSTALLATION	505-1 to 505-3
505.1.	General	
505.2.	General Installation Requirements for Pipe Types	
506.	OPEN CUT – WATER CONDUIT INSTALLATION	506-1 to 506-8
506.1.	Description	
506.2.	Materials	
506.3.	Laying Water Conduit	
506.4.	Pipe Joints	
506.5.	Hydrostatic Test	
506.6.	Connections to Existing Water Conduits	
506.7.	Purging and Disinfection of Water Conduits	
506.8.	Plugs	
506.9.	Measurements and Payment	
507.	OPEN CUT – WASTEWATER CONDUIT INSTALLATION	507-1 to 507-8
507.1.	Description	
507.2.	Materials	
507.3.	Laying Wastewater Conduit	
507.4.	Wastewater Conduit Joints	
507.5.	Tests and Inspections	
507.6.	Measurement and Payment for Wastewater Conduit Installation	
508.	OPEN CUT – STORMWATER CONDUIT INSTALLATION	508-1 to 508-12
508.1.	Description	
508.2.	General	
508.3.	Reinforced Concrete Pipe and Box for Stormwater	
508.4.	Corrugated Metal Pipe	
508.5.	Structural Plate Conduit	
508.6.	Corrugated Thermoplastic Pipe	
508.7.	Measurement and Payment for Stormwater Conduit Installation	

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
509.	CROSSINGS	509-1
<u>509.1.</u>	<u>General</u>	
<u>509.2.</u>	<u>State Highway Crossings</u>	
<u>509.3.</u>	<u>Street and Alley Crossings</u>	
<u>509.4.</u>	<u>Railroad Crossings</u>	
<u>509.5.</u>	<u>Creek and River Crossings</u>	
<u>509.6.</u>	<u>Measurement and Payment of Crossings</u>	

ITEM 501. UNDERGROUND CONDUIT MATERIALS

501.1. GENERAL

All pipe and fittings shall be new.

The OWNER shall at all times have free access to the manufacturer's plant while production is in progress, and may at any time refuse to accept pipe made when the plant is failing to follow the stipulations of the specifications in regard to workmanship, or failing in provisions to insure a uniform product coming within the permissible variations of the specifications. The OWNER may reject pipe if adequate means and methods are not provided so as to insure the manufacture of a product of uniform high quality.

Pipe shall be color coded according to the American Public Works Association Uniform Color Code (i.e. blue for water, green for wastewater or storm drain lines, violet for reclaimed water, etc.) or labeled with labeling tape identifying its specific use. Where feasible, permanent identification of the piping service shall be provided by co-extruding color stripes into the pipe outside surface. The striping shall be of the same material except for the color. For co-extruded markings, IPS sized pipe shall have four equally spaced, longitudinal color stripes and DIPS sized pipe shall have three equally spaced pairs of longitudinal color stripes. The color or marking shall be visible on top of buried pipe when pipe is excavated.

Pipe shall be acceptable by the Underwriters' Laboratories, Inc. or Factory Mutual Research when specifically requested and shall be acceptable by the State Fire Insurance Commission for use in water distribution systems when used for fire protection without penalty. Potable water pipe shall also bear the seal of approval (or "NSF" mark) of the National Sanitation Foundation Testing Laboratory for potable water pipe.

Installation shall be performed in accordance with relevant portions of Division 500 Underground Conduit Construction and Appurtenances.

501.1.1. Rejection. Pipe, joints, fittings, or coatings may be rejected for failure to meet any of the requirements of this specification or for any manufacturing, transportation and/or handling defects that may cause pipe, joints, fittings or coatings to be unsuitable for intended use(s). When approved by the OWNER, materials may be re-tested to establish conformity. All rejected materials shall be plainly marked by the Engineer and shall be replaced by the CONTRACTOR with materials which meets the requirements of these specifications. Such rejected materials shall be removed immediately from the site of the work.

501.1.2. Damaged Pipe. Pipe that is damaged during installation will be repaired only by a method approved by the OWNER. If, in the opinion of the OWNER, a satisfactory repair cannot be made by the method(s) suggested by the CONTRACTOR or pipe manufacturer, the damaged pipe shall be removed and replaced with sound pipe that meets the specifications of the contract. Repairs or replacement will be at no cost to the OWNER including costs associated with removing and replacing non-damaged pipe for the purpose of removing damaged pipe.

501.2. CLAY WASTEWATER PIPE.

501.2.1. General. Clay wastewater pipe shall conform to ASTM C700 Vitrified Clay Pipe, Extra Strength, Standard Strength, and Perforated, having compression joints and bell and spigot ends or compression couplings for plain-end pipe.

501.2.2. Class. Extra strength vitrified clay wastewater pipe shall be used unless otherwise designated.

501.2.3. Fittings. Fittings shall be of the same test strength as the pipe as ordered or shown on plans.

501.2.4. Joints. Factory-fabricated compression joints and joints for fittings shall meet the requirements of ASTM C425 Compression Joints for Vitrified Clay Pipe and Fittings.

501.2.5. Pipe Tests. Tests of the pipe shall be made in accordance with ASTM C301 Test Methods for Vitrified Clay Pipe.

501.3. VITRIFIED CLAY PIPE USED IN TRENCHLESS APPLICATIONS

501.3.1. General. Clay pipe used for microtunneling, sliplining, pipe bursting, and tunnels shall conform to ASTM C1208 (C1208M) Vitrified Clay Pipe and Joints for Use in Microtunneling, Sliplining, Pipe Bursting, and Tunnels. The pipe shall have a minimum compressive strength of 7000-psi.

501.3.2. Pipe Joints. The pipe joint collar shall be manufactured of Series 316 stainless steel or better and compression discs are required to distribute the jacking forces.

501.3.3. Pipe Tests. Tests of the pipe shall be made in accordance with ASTM C1208 (C1208M).

501.4. CONCRETE PRESSURE PIPE AND FITTINGS

501.4.1. General. These specifications cover the manufacture of concrete pressure pipe designed for internal pressures from a minimum of 20-psi to a maximum of 350-psi. Products shall conform to relevant standards as noted in Table 501.4.1.(a) Standards for Concrete Pressure Pipe and Fittings.

Table 501.4.1.(a) Standards for Concrete Pressure Pipe and Fittings

Item Reference No.	AWWA Standard	Description
501.4.5	C301	Prestressed Concrete Pressure Pipe, Steel-Cylinder Type
	C304	Design of Prestressed Concrete Cylinder Pipe
501.4.6	C303	Bar-Wrapped Concrete Cylinder Pipe

Items 501.4.2. through 501.4.4., inclusive, shall apply to each type of pipe in [Item 501.4](#) Concrete Pressure Pipe and Fittings. Concrete Pressure Pipe and Fittings shall be provided in accordance with ANSI/AWWA C301. In accordance with C301, Section III.A – Purchaser Options and Alternatives, the purchasers are advised that, while the standard presents information on materials and procedures for manufacture of the pipe, it may not contain all of the engineering information needed to prepare a complete specification for a particular pipeline installation. A specific pipeline installation may require provisions more restrictive than those in the standard and will likely require additional design and installation details.

Reference to AWWA Manual M9 - Concrete Pressure Pipe, should be considered as a supplement to the use of the C301 standard, and information in the manual should not be regarded as superseding any portion of the C301 standard. Purchaser options and alternatives shall be provided by the specifier, including working pressure, surge pressure, field-test pressure, external loading conditions, method of bedding and backfilling, manner of storage and delivery (if required by the manufacturer), tabulated layout schedules, and detailed shop drawings and schedules submitted to the OWNER for review. Purchaser options and alternatives shall be specified in the supplemental conditions, plans, or technical specifications.

The type of pipe to be supplied shall be as shown on the plan and/or in the special provisions for each project.

The manufacturer shall submit a successful experience record in the design and construction of the type of concrete pressure pipe involved. Each type of pipe shall have the complete approval of the Underwriters' Laboratories, Inc., for the manufacture of the pipe specified and diameters required. Pipe shall have NSF61 standard approval for potable water applications.

Upon award of the Contract, the CONTRACTOR shall furnish OWNER with shop drawings showing the pipe and fittings to be furnished and shall include a tabulated layout schedule with reference to the stationing of the contract drawings with plan and profile drawings. Such drawings shall be subject to the approval of the OWNER and fabrication of pipe and fittings shall not be commenced until such drawings have been approved by the OWNER. Such approval by the OWNER shall not relieve the CONTRACTOR of any responsibility of providing pipe and/or fittings in accordance with the OWNER's plans and specifications.

No cracks will be permitted in the mortar lining of the pipe, except for minor hairline cracks. Pipe with cracks through the mortar wall or damaged bells, spigots or joint grooves shall not be accepted without manufacturer-approved repair. Cracks in the vicinity of the spigot of the pipe and those cracks in the vicinity of the circumferential wrappers and outlets shall not be allowed. Cracks up to 0.010-in in the lining of the pipe are acceptable if they are not excessive in length (should be less than 2 ft.).

All cracks to the mortar coating shall be repaired according to the manufacturer's specification prior to installation.

501.4.2. Fittings and Specials. The manufacturer shall furnish all fittings and special pieces required for closures, bends, branches, manholes, air valves, blow offs and connections to mainline valves and other fittings shown on the contract drawings or as set out in the specifications conforming with AWWA C301,

AWWA C303, or AWWA C304 as applicable. All openings in the pipe for fittings, manholes, taps, blow offs, etc. shall have the interior and exterior surfaces of the steel lined and coated with mortar. The lining thickness shall be a minimum of 0.5-inches for sizes 16-in. and smaller, and 0.75-in. minimum lining thickness for sizes larger than 16-in. The minimum coating thickness shall be 1-in. The type of fittings and details covering the design of fittings and specials shall be furnished by the manufacturer and subject to the approval of the OWNER. The fittings and specials shall comply in all respects with the requirements of AWWA with modifications as herein set forth.

501.4.3. Flanged Outlets. Flanged outlets shall be insulated at all points where external valves, pipe, fittings, etc., are connected to the line. The CONTRACTOR shall furnish an insulating flange kit, flange gaskets, insulating sleeves, and two plastic washers for each bolt approved by the OWNER. Bolts, nuts, and washers for flanged outlet connections shall be carbon steel.

501.4.4. Tests. All pipe shall be tested in accordance with applicable specifications and AWWA Standards. In addition to certification of all applicable tests required by governing AWWA Standards, the following tests or certifications of tests may be required.

501.4.4.1. Steel Cylinder Pipe. The manufacturer shall submit for approval the specified details of materials and methods of welding it proposes to use before any welding is done.

The manufacturer shall furnish one specimen for tensile tests of welds from each 3,000-ft. of pipe. If tests indicate the welding is unsatisfactory, additional samples as required shall be furnished. Two test cylinders out of each day's pour of the concrete used, or as required by the OWNER, shall be furnished for testing by an independent laboratory. The cost of such a test shall be borne by the OWNER. Certified test reports made by the manufacturer shall be acceptable in lieu of the test cylinders, provided such test certificates show that they cover pours from which the purchased pipe is made.

Mill test reports on each heat from which steel cylinders and reinforcing are rolled shall be furnished by the OWNER, if required.

Test certificates showing the physical properties of the compound used in the gaskets shall be furnished by the OWNER, if required.

501.4.4.2. Three-Edge Bearing Test. The manufacturer of concrete cylinder pipe supplied in accordance with the provisions of [Item 501.4](#). Concrete Pressure Pipe and Fittings shall have demonstrated, or shall demonstrate as may be required, that the pipe when tested in a three-edge bearing test as described in ASTM C497 (C497M) Concrete Pipe, Sections or Tile under a load equivalent to the design ditch load shall not deflect more than 0.1-percent. At the above specified load, there shall be no continuous cracks wider than 0.002-in. for a length of 12-in.

501.4.5. Prestressed Concrete Cylinder Pipe, AWWA C301.

501.4.5.1. General. The pipe shall comply in all respects with the requirements of AWWA C301 Prestressed Concrete Pressure Pipe, Steel Cylinder Type, for Water and Other Liquids. The pipe may be of two types of prestressed concrete steel cylinder pipe as specified on the plans and/or specifications or special conditions:

- (1) the lined cylinder type with a core composed of a steel cylinder lined with concrete and subsequently wire-wrapped directly on the steel cylinder and coated with the mortar.
- (2) the embedded cylinder type with a core composed of a steel cylinder encased in concrete and subsequently wire-wrapped on the exterior concrete surface and coated with concrete or mortar.

501.4.5.2. Design Pressures and Stresses. Design pressure shall be that shown on plans and/or specifications. The size of the high-tensile wire and the spacing and tension under which it is wound shall be such that the conditions required by AWWA C304 Design of Prestressed Concrete Cylinder Pipe are met.

501.4.6. Bar-Wrapped Concrete Cylinder Pipe, AWWA C303.

501.4.6.1. General. The pipe shall consist of a welded sheet-steel or plate-steel cylinder, manufactured by the spiral or straight seam method with joint rings attached, inside of which a cement mortar lining is centrifugally spun; a mild steel bar spirally wrapped under measured tension on the steel cylinder and protective cement mortar coating applied to the outside of the cylinder and spirally-wrapped rod.

The manufacturer shall furnish pipe in uniform lengths except lengths ordered as specials.

The pipe shall comply in all respects with the requirements of AWWA C303, with the following addition.

501.4.6.2. Design Pressures and Stresses. Design pressure shall be that shown on the plans and/or specifications. Steel cylinder and bar reinforcement shall be designed in accordance with AWWA Manual M9, Concrete Pressure Pipe.

501.5. REINFORCED CONCRETE WASTEWATER PIPE WITH RUBBER GASKET JOINTS

501.5.1. General. Except as applicable to [Item 501.5.2](#), Alternate Concrete Pipe D-Load Design, reinforced concrete pipe manufactured under these specifications shall conform to ASTM C76 (C76M) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe; or ASTM C655 (C655M) Reinforced Concrete D-Load Culvert, Storm Drain, and Sewer Pipe, and by a plant certified by the American Concrete Pipe Association, Texas Department of Transportation, or other recognized authority, with the following additions:

- (1) All pipe shall be machine made by a process which shall provide for uniform placement of zero slump concrete in the form and compaction by mechanical devices which shall assure a dense concrete in the finished product.
- (2) Aggregates for the concrete shall comply with requirements ASTM C33 Concrete Aggregates, with the additional requirement that the aggregate shall have a minimum of 50-percent of calcium carbonate equivalent.
- (3) Pipe furnished under this specification shall be steam cured in accordance with methods prescribed in ASTM C76 (C76M) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe except that the steam curing time shall be not less than eight-continuous-hours.
- (4) The pipe and connecting joints shall be subject to the hydrostatic tests set forth in ASTM C443 (C443M) Joints for Concrete Pipe and Manholes, Using Rubber Gaskets, both for pipes in straight alignment and for pipes in maximum deflected position without leakage either in the pipe or in the joints.

501.5.2. Alternate Concrete Pipe D-Load Design. When bedding is specified in accordance with [Item 504.5.2.16](#), Alternate Embedment for Concrete Pipe, reinforced concrete pipe shall conform to ASTM C1417 (C1417M) Manufacture of Reinforced Concrete Sewer, Storm Drain, and Culvert Pipe for Direct Design. This specification covers the manufacture and acceptance of precast concrete pipe designed to conform to the OWNER's design requirements and to ASCE 15-93, ASTM C655 (C655M) Specification for Reinforced Concrete D-Load Culvert, Storm Drain, and Sewer Pipe, or an equivalent design specification. Conditions 501.5.1. (1) through (4) apply to pipe provided under this specification and appropriate corrosion protection shall be furnished for pipe used in wastewater applications.

501.5.3. Steel Reinforcement. All steel reinforcement shall be in accordance with ASTM C76 (C76M) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe and shall be circular in shape. No elliptical reinforcement shall be permitted. Where Class III pipe of sizes larger than 30-in. in diameter are specified, the manufacturer may, at its option, furnish pipe manufactured with either Wall "B" or Wall "C" minimum thicknesses, and the applicable minimum steel area as listed for circular cages in Table II of ASTM C76 may be substituted, at the manufacturer's option, for those listed in Table III of ASTM C76, provided test strength requirements for Class III pipe are satisfactorily met.

Where Class IV or V pipe is specified, the steel as called for in the wall as designated shall be furnished. Quadrant reinforcement shall be acceptable. As an alternate the pipe may be designed as detailed in ASTM C655 (C655M) Reinforced Concrete D-Load Culvert, Storm Drain, and Sewer Pipe. Proof of design must be submitted.

501.5.4. Joints. Connecting joints shall be made using a flexible watertight rubber-type compression gasket. The rubber gasket shall be the sole element of the joint depended upon to provide water tightness.

501.5.4.1. Rubber Gaskets. All rubber-type gaskets shall be of the round profile design. The rubber gasket shall be required to meet and be tested in accordance with ASTM C443 (C443M) Joints for Circular Concrete Sewer and Culvert Pipe, Using Rubber Gaskets.

501.5.4.2. Deflection. The joint design shall provide for the deflection of a pipe unit by opening one side of the outside perimeter of the joint ½-inch wider than the full "home" position without reducing its

water tightness. Where greater deflections are required that provided by the joint design, beveled joints or elbows shall be provided.

501.5.4.3. Joint Approval. A detailed design of the joint or joints, including design and durometer hardness of the rubber gasket proposed to be furnished under this specification, shall be approved by the OWNER prior to installation. The design shall also include minimum and maximum interior joint opening in the assembled position in straight alignment and the maximum interior joint opening in the maximum deflected position. Joint dimensions (waste bell and spigot) should be addressed in shop drawings.

501.5.5. Fittings and Specials. Component parts for all specials such as bends, wyes, tees, etc. shall be manufactured on machines and in the same manner as straight joint concrete wastewater pipe under these specifications, except that joint lengths may be shorter than minimum listed.

501.5.6. Coatings and Linings. Coatings and liners called for in the specifications or as indicated on the plans shall meet the requirements of [Item 502.9](#), Corrosion-Resistant Coatings and Liners for Wastewater Conduit and Appurtenances and shall be installed or applied by the pipe manufacturer.

501.5.7. Repairs. Repairs shall be permitted as set out in ASTM C76 and/or ASTM C655 except field repairs shall be permitted only with prior approval of the OWNER. Repairs to pipe and shall be done in strict conformity with all applicable specifications, instructions and recommendations of the manufacturer to ensure material warranty. If, in the opinion of the OWNER, repairs should not be made, the section of pipe shall be rejected and removed from the construction site and not repaired or returned to any of the OWNER'S projects. Rejected pipe shall be marked in a manner mutually agreed upon by the OWNER and the pipe manufacturer.

Field repairs on damage to the gasket bearing area shall not be allowed without prior approval of the OWNER.

501.5.8. Markings. Each length of pipe shall bear the initials or name of the person, company or corporation by whom it was manufactured; date of manufacture; and the class of pipe. The markings shall be indented or stenciled on the exterior or interior of the barrel near the bell and shall be plainly legible for purpose of identification.

501.5.9. Tests. The pipe shall be required to meet and be tested in accordance with ASTM C76 (C76M) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe, or ASTM C655 (C655M) Reinforced Concrete D-Load Culvert, Storm Drain, and Sewer Pipe, as applicable.

The connecting joints shall be subject to the hydrostatic tests set forth in ASTM C443 (C443M) Joints for Circular Concrete Sewer and Culvert Pipe, Using Rubber Gaskets.

The rubber gasket shall be required to meet and be tested in accordance with ASTM C443 (C443M).

501.5.10. Rejection. The pipe may be rejected for having defects or failure to meet the requirements as follows:

- (1) variations in any dimension exceeding the permissible variations prescribed,
- (2) a piece broken out of the bell or spigot or tongue or groove end of such size that the water tightness of the joint should be impaired,
- (3) a shattering or flaking of concrete or other conditions indicating an improper concrete mix,
- (4) lack of uniformity in placement of steel which might preclude all joints being typical of those tested,
- (5) cracks sufficient to impair the strength, durability or serviceability of the pipe,
- (6) failure to conform with any of the specifications herein set forth or referenced,
- (7) the complete absence of distinct web-like markings, which may be indicative of a deficiency of water in the concrete mix, from the external surface of the pipe made by any process in which the forms are removed immediately after the concrete has been placed, unless specimens submitted for test that do not have such web-like markings shall have passed the physical tests required by these specifications,
- (8) failure of pipe to go completely "home" due to binding of spigot against bell or tongue against groove,
- (9) failure to pass any of the tests in [Item 501.5.9](#), Tests,
- (10) joint sections with spalls, cracks, fractures, or other imperfections that could adversely affect the performance of the joint,
- (11) failure to meet the requirements for coatings and linings.

501.6. REINFORCED CONCRETE CULVERT, STORM DRAIN, PIPE AND BOX SECTION

This item shall govern reinforced concrete culvert, storm drain, pipe and precast reinforced concrete box sections. Pipe shall be cured in accordance with the applicable ASTM Designations for each type of pipe as referred to below.

501.6.1. Reinforced Concrete Culvert, Storm Drain, and Pipe.

501.6.1.1. General. Except as applicable to [Item 501.6.1.1.1](#), Alternate Concrete Pipe D-Load Design, circular reinforced concrete pipe shall conform to ASTM C76 (C76M) Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe; arch pipe shall conform to ASTM C506 Reinforced Concrete Arch Culvert, Storm Drain, and Sewer Pipe; elliptical pipe shall conform to ASTM C507 Reinforced Concrete Elliptical Culvert, Storm Drain, and Sewer Pipe, of the class as designed on the plans subject to the following modifications:

- (1) All pipe shall be machine-made by a process which shall provide for uniform placement of zero slump concrete in the form and compaction by mechanical devices which shall assure a dense concrete in the finished product.
- (2) Sizes larger than 60-in. diameter shall be manufactured using two lines of circular reinforcement.
- (3) Where Class III pipe of sizes larger than 60-in. diameter are specified, the manufacturer may at its option furnish pipe manufactured with either Wall "B" or Wall "C" minimum thicknesses and the applicable minimum steel area as listed for circular cages in Table II of ASTM C76 (C76M), provided tests strength requirements for Class III pipe are satisfactorily met.

501.6.1.1.1. Alternate Concrete Pipe D-Load Design. When bedding is specified in accordance with [Item 504.5.2.16](#), Alternate Embedment for Concrete Pipe, reinforced concrete pipe shall conform to ASTM C1417 (C1417M) Manufacture of Reinforced Concrete Sewer, Storm Drain, and Culvert Pipe for Direct Design. This specification covers the manufacture and acceptance of precast concrete pipe designed to conform to the OWNER's design requirements and to ASCE 15-93, ASTM C655 (C655M) Specification for Reinforced Concrete D-Load Culvert, Storm Drain, and Sewer Pipe, or an equivalent design specification. Conditions of [501.6.1.1](#), modifications (1) and (2) apply to pipe provided under this specification.

501.6.1.2. Sizes and Permissible Variations. Variations in diameter, size, shape, wall thickness, reinforcement, placement of reinforcement, laying length and the permissible underrun of length shall be in accordance with the applicable ASTM specification for each type of pipe as referred to previously.

Where rubber gasket pipe joints are to be used, the design of joints and permissible variations in dimensions shall be in accordance with ASTM C443 Joints for Circular Concrete Sewer and Culvert Pipe, Using Rubber Gaskets, Sections 5 and 6.

501.6.1.3. Joints. Pipe to be placed along curves shall consist of whatever pipe joint lengths or beveled end joints of pipe or combination thereof that are required to place the pipe on the designated centerline curve with no more than one-half of the tongue length of the pipe exposed from its normal fully closed joint position.

501.6.1.3.1. Flexible Joint Sealant. Unless otherwise specified on the plans or in the special provisions, pipe joints shall be sealed with one of the following types of gaskets; Flexible Joint Sealant manufactured in accordance with ASTM C990, Expanded Cellular Rubber Gaskets in accordance with ASTM D1056 Flexible Cellular Materials – Sponge or Expanded Rubber, Class 2C1, or Elastomeric Seals. Each joint shall require one continuous gasket conforming to the joint shape. Gasket cross-sectional diameters shall be in accordance with the manufacturer's recommendations.

Cold-Applied Preformed Plastic Gaskets. Plastic gasket shall be produced from blends of refined hydrocarbon resins and plasticizing compounds reinforced with inert mineral filler and shall contain no solvents, irritating fumes, or obnoxious odors.

Expanded Cellular Rubber Gaskets. Expanded Cellular Rubber Gaskets shall be produced from tubular cross sections of a blend of nitrile and vinyl polymers meeting the physical requirement of ASTM D1056, Flexible Cellular Materials – Sponge or Expanded Rubber, Class 2C1.

Elastomeric Seals for Joining Concrete Structures. Elastomeric seals shall be produced from natural or synthetic rubber meeting the requirements of ASTM C1619 Standard Specification for Elastomeric Seals for Joining Concrete Structures.

501.6.1.4. Workmanship and Finish. Pipe shall be substantially free from fractures, large or deep cracks and surface roughness. The ends of the pipe shall be normal to the walls and centerline of the pipe within the limits of variations allowed as stated previously.

501.6.1.5. Pipe Marking. Markings shall be indented on the pipe section or painted thereon with waterproof paint. The following information shall be clearly marked on each section of pipe:

- (1) the class of pipe,
- (2) the date of manufacture,
- (3) the name or trademark of the manufacturer,
- (4) where elliptical reinforcement is used, one end of each section or joint of pipe shall be clearly marked during the process of manufacture or immediately thereafter on the inside and the outside of opposite walls to show the location of the “top” or “bottom” of the pipe as it should be installed.

501.6.1.6. Tests. The acceptability of the pipe in all diameters, strengths and classes shall be determined by such material tests performed as required in ASTM C76 (C76M), C506 or C507; by the results of the three-edge bearing test for the load to produce a 0.01-in. crack and ultimate load and by absorption tests on selected samples from the wall of the pipe in accordance with ASTM C497 (C497M) Concrete Pipe, Manhole Sections, or Tile; and by inspection of the finished pipe to determine its conformance with the design prescribed in these specifications and its freedom from defects.

Testing rates shall be as follows, except that in no case fewer than two specimens shall be furnished:

- (1) If subjected to three-edge-bearing tests for the 0.01-in. crack only, testing shall be performed on 0.8-percent of the number of pipe sections of each size included in the order. Pipes that have been tested only to the formation of a 0.01-in. crack and that meet the 0.01-in. test load requirements shall be accepted for use.
- (2) If subjected to three-edge-bearing tests for both the 0.01-in. crack and the ultimate load, testing shall be performed on 0.2-percent of the number of pipe sections of each size included in the order.

As an alternate to the three-edge-bearing test, concrete pipe 60-in. in diameter and over may be accepted, at the option of the manufacturer, on the basis of material tests and inspection of the completed product. Acceptability of pipe on this basis shall be determined by the results of material tests as required in ASTM C76, C506 or C507; by crushing tests on cores taken from the barrel of the completed and cured pipe; by absorption tests on samples from the wall of the pipe; and by inspection of the finished pipe, including amount and placement of reinforcement, to determine its conformance with the design prescribed in these specifications and its freedom from defects.

The manufacturer shall furnish facilities and personnel for taking the cores from the pipe barrel and for determining the compressive strength of the samples. When the cores cut from a section of pipe successfully meet the strength requirement, the core-holes shall be plugged and sealed by the manufacturer in a manner such that the pipe section shall meet all of the test requirements of ASTM C76, C506 or C507. Pipe sections, so sealed, shall be accepted for use.

Tested pipe accepted for use shall be marked “TEST” or otherwise appropriately identified. Should any of the test specimens fail to meet the test requirements, two consecutive joints in the same mix series shall be tested and results shall be a basis of accepting or rejecting the pipe of the series.

501.6.1.7. Rejection of Pipe. All rejected pipe shall be plainly marked by the OWNER and shall be replaced by the CONTRACTOR with pipe that meets the requirements of these specifications. Such rejected pipe shall be removed immediately from the site of the work.

501.6.2. Precast Reinforcement Concrete Box.

501.6.2.1. General. Precast reinforced concrete box sections shall conform to ASTM C1433 (C1433M) Standard Specifications for Precast Reinforced Concrete Monolithic Box Sections for Culverts, Storm Drains and Sewers and ASTM C1577 Standard Specification for Precast Reinforced Concrete Monolithic Box Sections for Culverts, Storm Drains, and Sewers Designed According to AASHTO

LRFD. More information may be found in ASTM C877 Standard Specification for External Sealing Bands for Concrete Pipe, Manholes, and Precast Box Sections.

501.6.2.2. Concrete. Boxes shall be machine-made or cast by process which will provide for uniform placement of concrete in forms and compaction by mechanical devices to produce dense, structurally sound concrete. Use concrete mixed in central batch plant or other batching facility from which quality and uniformity of concrete can be assured. Transit-mixed concrete is not acceptable. Representatives of the Engineer will inspect manufacturer's plant and casting operations as deemed necessary.

501.6.2.3. Joints. Joints shall conform to ASTM C990 Standard Specification for Joints for Concrete Pipe, Manholes, and Precast Box Sections Using Preformed Flexible Joint Sealants, Expanded Cellular Rubber Gaskets meeting the physical requirement of ASTM D1056, Flexible Cellular Materials - Sponge or Expanded Rubber, Class 2C1, ASTM C1677 Standard Specification for Joints for Concrete Box, Using Rubber Gaskets. For joints conforming to C1677, the elastomeric (gasket) material shall conform to ASTM C1619 Standard Specification for Elastomeric Seals for Joining Concrete Structures, Class C requirements. Gaskets which require oil resistant properties (e.g. Nitrile) shall meet Class D requirements. Gasket material for sealing tongue & groove joints shall be performed flexible butyl rubber meeting the requirements of ASTM C990 Section 6.2 Butyl Rubber Sealant, or Expanded Cellular Rubber Gaskets. Gasket width shall be in accordance with the joint material manufacturer's recommendations, and large enough to properly seal the entire perimeter of the tongue and groove joint.

501.6.2.4. Lifting Holes. For precast boxes, no more than 4 lifting holes shall be in each section. Lifting holes may be cast, cut into fresh concrete after form removal, or drilled. Lifting holes of sufficient size shall be used for adequate lifting based on the size and weight of the box section. Lifting holes larger than 3 inches in diameter are not acceptable. More than 1 longitudinal wire or 2 circumferential wires per layer of reinforcing steel may not be cut when locating lifting holes. Spalled areas around lifting holes shall be repaired when discovered.

501.6.2.5. Quality. Fine cracks on the surface of the member that do not extend to the plane of the nearest reinforcement are acceptable unless the crack are numerous and extensive.

501.6.2.6. Repairs. Cracks that extend into the plane of the reinforcement steel shall be repaired in an approved manor. Excessive damage, honeycombing, or cracking will be subject to structural review. The OWNER MAY accept box repairs that are sound, properly finished and cured in conformance with pertinent specifications.

501.7. DUCTILE-IRON PRESSURE PIPE AND FITTINGS

501.7.1. General. Ductile-iron pressure pipe 4-in. through 64-in. shall conform to the American National Standard for Ductile-Iron Pipe Centrifugally Cast for Water or Other Liquids, AWWA C151. In accordance with C151, Section III.A, purchaser options and alternatives shall be provided by the specifier, including pipe size, joint type, special joints, thickness or class, and laying length. Purchaser options and alternatives shall be specified in the supplemental conditions, plans, or technical specifications. Polyethylene encasement for ductile iron pipe systems shall conform to [Item 502.8](#). Polyethylene Wrap for Metal Pipe and Fittings. The CONTRACTOR shall protect the polyethylene wrap and prevent damage during embedment and backfill installation.

The ductile iron shall conform in all respects to the specifications set forth in ASTM Standard A377, Standard Index of Specifications for Ductile Iron Pressure Pipe. The specific grade of ductile iron used shall be Grade 60-42-10, with a Minimum Tensile Strength of 60,000 psi, a Minimum Yield Strength of 42,000 psi, and a Minimum Elongation in 2" of 10%.

501.7.2. Joints. All ductile-iron pressure pipe shall be furnished with one of the types of joints indicated in Table 501.7.2.(a) Ductile Iron Pressure Pipe Joint Types and as described in the proposal or bid request.

Bolts and nuts for mechanical joints or flanged ends (if used underground) shall be of a high-strength low-alloy corrosion-resistant steel and shall conform to ASTM F3125 (F3125M) High Strength Structural Bolts.

All threaded flanges shall be ductile iron.

Table 501.7.2.(a) Ductile Iron Pressure Pipe Joint Types

Type Joint	AWWA Standard
Push-on	AWWA C111 Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
Mechanical Joint	AWWA C111 (same as above)
Flanged Ends	AWWA C110 Ductile-Iron and Gray-Iron Fittings, 3 in.-48 in., for Water, or AWWA C115 Flanged Ductile-Iron Pipe with Ductile-Iron or Gray-Iron Threaded Flanges
Grooved Ends	AWWA C606 Grooved and Shouldered Joints

501.7.3. Coating and Lining. All ductile-iron pipe shall be bituminous coated outside and cement mortar lined inside. The cement mortar lining shall be seal coated in accordance with the latest revision of ANSI / AWWA C104 / A21.4 American National Standard for Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water. All ductile iron pipe shall require an exterior polywrap corrosion protection system as defined in the latest version of ANSI / AWWA C105 / A21.5 American National Standard for Polyethylene Encasement for Ductile-Iron Pipe Systems. In the event of tears, pinches, breaches, or other damage to the initial external polywrap protection layer, the use of dual layer external polywrap protection meeting the above standards shall be required. If this specification conflicts with manufacturer's installation recommendations, follow manufacturer's recommendations for ductile iron pipe installation.

501.7.4. Fittings. Fittings shall be of ductile-iron and shall conform to AWWA C110 ANSI Standard for Ductile-Iron and Gray-Iron Fittings, 3-in. through 48-in. for Water, or conform to AWWA C153 ANSI Standard for Ductile-Iron Compact Fittings for Water Service, 3-in. through 64-in., unless otherwise specified in the proposal, special specification or in the plans.

Welded-on outlets may be used in lieu of the tees shown on the plans. Outlet pipe shall be special thickness class 53. All weldments must be 55% nickel iron and each outlet pipe shall be air tested to 15-psi to insure weld integrity. The outlet branches must be made from ductile iron pipe.

All fittings shall be rated for a minimum of 250-psi working pressure unless otherwise specified.

Special fittings using end condition combinations of bells, spigots, mechanical, integrally restrained or push-on joints, flanges, or special internally locked joints shall be dimensioned in accordance with AWWA C110 or C153.

Bolts and nuts for mechanical joints or flanged ends shall be of a high-strength, corrosion-resistant low-alloy steel and shall conform to ASTM A325 (Type 3) or shall be stainless steel in accordance with ASTM A304 Carbon and Alloy Steel Bars Subject to End-Quench Hardenability Requirements.

The OWNER shall determine whether fittings shall be bituminous coated outside and cement-mortar lined inside with seal coat in accordance with AWWA C104 Standard for Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water or whether the interior and exterior surfaces shall be protected consistent with AWWA C116 Standard for Protective Fusion-Bonded Epoxy Coatings for the Interior and Exterior Surfaces of Ductile-Iron and Gray-Iron Fittings for Water Supply Service.

501.7.5. Tests. All ductile-iron pipe and fittings shall be tested in accordance with the applicable provisions of the specifications relating thereto.

501.7.6. Markings. Class, weight, and casting period shall be shown on each pipe.

501.8. SECTION HELD FOR FUTURE USE

501.9. STEEL PIPE AND FITTINGS

501.9.1. General. Steel pipe, fittings and specials shall conform to the details as shown on the plans or included in the specifications and as specified below. Steel Pipe and Fittings shall be provided in accordance with AWWA C200. In accordance with C200, Section III.A, purchaser options and alternatives shall be provided by the specifier, including pipe size, joint type, special joints, thickness or class, and laying length. Purchaser options and alternatives shall be specified in the supplemental conditions, plans, or technical specifications.

501.9.2. Applicable Standard Specifications. Except as modified or supplemented herein, all steel pipe, fittings and specials shall conform to the applicable requirements of the standard specifications indicated in Table 501.9.2.(a) Standards for Steel Pipe and Fittings.

Table 501.9.2.(a) Standards for Steel Pipe and Fittings

Standard	Designation
AWWA C200	Steel Water Pipe—6 in. and Larger
AWWA C203	Coal Tar Protective Coatings and Linings for Steel Water Pipeline — Enamel and Tape — Hot Applied
AWWA C205	Cement-Mortar Protective Lining and Coating for Steel Water Pipe — 4 in. and Larger — Shop Applied
AWWA C206	Field Welding of Steel Water Pipe
AWWA C207	Steel Pipe Flanges for Waterworks Service—Sizes 4 In. Through 144 in.
AWWA C208	Dimensions for Fabricated Steel Water Pipe Fittings
AWWA C209	Cold-Applied Tape Coatings for the Exterior of Special Sections, Connections, and Fittings for Steel Water Pipe
AWWA C210	Liquid-Epoxy Coating Systems for the Interior and Exterior of Steel Water Pipelines
AWWA C214	Tape Coating Systems for the Exterior of Steel Water Pipelines
AWWA C222	Polyurethane Coatings for the Interior and Exterior of Steel Water Pipelines and Fittings
AWWA C602	Cement-Mortar Lining of Water Pipelines in Place—4 in. and Larger
AWWA C606	Grooved and Shouldered Joints
ASTM A283	Low and Intermediate Tensile Strength Carbon Steel Plates
ASTM A139	Electric-Fusion (Arc)-Welded Steel Pipe (NPS 4 and Over)
NSF/ANSI 61	Drinking Water System Components

CONTRACTOR shall submit a written certification that the pipe has been manufactured and tested in accordance with the applicable standards. The pipe shall be manufactured, fabricated, coated and lined by a single manufacturer being a certified member in good standing of the Steel Plate Fabricators Association (SPFA).

501.9.3. Pipe and Fittings Requirements. Fabricated pipe and fittings shall be made of steel plate conforming to ASTM A283, Grade D, or ASTM A139, Grade B, C, or D in accordance with AWWA C200. Mill-type pipe and fittings shall be Grade B conforming to AWWA C200.

Nominal pipe diameter shall be as specified in the plans. Nominal diameters for steel pipe sizes under 24-in. are outside diameters and for sizes 24-in. and over are inside diameters per AWWA M11 Steel Pipe—A Guide for Design and Installation.

The pipe wall thickness shall be as specified in the plans.

Pipe sections shall be furnished in not less than 20 ft. lengths except for specials and closures sections as may be required.

501.9.4. Joints. Steel pipe and fittings shall be joined with any of the end types as specified below, unless a particular end type is specified. Flange ends shall be used only where specifically noted on drawings.

Welded joints shall conform to and be tested in accordance with AWWA C206.

Rubber gasketed joints may be used up to 72-in. in diameter and shall conform to, and be tested in accordance with AWWA C200.

Grooved and shouldered joints shall conform to, and be tested in accordance with AWWA C606.

Mechanically coupled joints shall consist of Dresser Couplings Style 38 or equal or as specified on the drawings.

Flanged joints shall conform to the AWWA C207, Class D. The thickness of flanges shall be as specified in Table 1 or 2 of AWWA C207, or as specified on the drawings.

501.9.5. Lining and Coating. Steel pipe and fittings shall be lined in accordance with any of the standards indicated in Table 501.9.5.(a) Lining and Coating for Steel Pipe and Fittings, unless a particular specification is shown on the plans.

The exterior surface of steel pipe and fittings to be installed underground shall be coated in accordance with AWWA C214. If coated in accordance with AWWA C214, then the fittings will be coated in accordance with AWWA C209. The exterior surface of steel pipe and fittings to be installed above ground shall be cleaned, primed and coated, all in accordance with either AWWA C222 or C210.

Table 501.9.5.(a) Lining and Coating for Steel Pipe and Fittings

Standard	Topic
AWWA C205	Cement-Mortar Protective Lining and Coating for Steel Water Pipe — 4 In. and Larger — Shop Applied
AWWA C210	Liquid-Epoxy Coating Systems for Interior and Exterior of Steel Water Pipelines
AWWA C222	Polyurethane Coatings for the Interior and Exterior of Steel Water Pipelines and Fittings
AWWA C602	Cement-Mortar Lining of Water Pipeline — 4 In. and Larger — in Place

501.9.6. Testing. All steel pipe shall be hydrostatically tested to a pressure that will induce a stress of 75% of the minimum yield strength of the steel in accordance with AWWA C200. Fittings fabricated from hydrostatically tested pipe shall not require shop hydrostatic testing. Welds for fittings that were not previously hydrostatically tested shall require hydrostatic testing, air testing, or other ASTM nondestructive testing.

501.10. SEAMLESS COPPER TUBING

501.10.1. General. These specifications pertain only to Type K, annealed (soft) copper water tubing for use with solder, flared, or compression-type fittings. The copper tubing shall conform to ASTM B88 Seamless Copper Water Tube.

501.10.2. Quality. The vendor shall be responsible for submission of a laboratory analysis of the products supplied. The manufacturer's own laboratory analysis is acceptable. The certificate of analysis shall state size and type of analysis and results obtained. A statement shall be made and validated that tests confirm compliance with the requirements of this specification.

The OWNER reserves the right to conduct or cause to have conducted independent laboratory tests. Where the results of such tests prove the quality requirements have not been met: (1) the costs of tests shall be charged to the vendor's account, and (2) the entire shipment may be rejected on the basis of such tests.

501.11. CORRUGATED METAL PIPE OR PIPE ARCH SHAPES

501.11.1. General. This item shall govern the furnishing of corrugated metal pipe for culverts and storm water conduit for the locations and designations as shown on the plans and contract specifications as herein outlined.

Pipe having a design hydraulic head exceeding 5-ft. of water will have helical corrugations and the lock seam shall be either continuously welded or caulked with a neoprene or mastic seal during fabrication. Caulked helical pipe shall be fabricated by applying a uniform bead of neoprene or mastic compound to the lock seam in such a manner that the inner surfaces of the lock seam are free of voids.

Shell Data shall specify diameter, classification (Type), material, gage and corrugation. This information shall be designated on the plans and/or contract specifications.

501.11.2. Pipe Manufacture. Corrugated metal pipe or pipe arch shapes shall meet the requirements of ASTM A760 (A760M) Corrugated Steel Pipe, Metallic-Coated for Sewers and Drains, ASTM B745 (B745M) Corrugated Aluminum Pipe for Sewers and Drains, or ASTM A742 (A742M) Steel Sheet, Metallic Coated and Polymer Precoated for Corrugated Steel Pipe. All pipe shall be manufactured with a minimum of two re-rolled ends

501.11.2.1. Steel Pipe. Galvanized or aluminized steel pipe shall be full circle or arch pipe conforming to AASHTO Designation M36, Type I, Type II or Type III as specified in the plans.

501.11.2.2. Aluminum Pipe. Aluminum pipe shall conform to the requirements of AASHTO Designation M196, Type I, Type II or Type III pipe arch as specified on the plans.

Aluminum pipe may be placed bare of any precoating, but any portions of aluminum pipe that are to be in contact with a metal other than aluminum or in contact with concrete containing chlorides, shall be insulated from this other metal or concrete by a coating of bituminous material or a plastic coating, such as asphalt mastic or polymeric coating. The coating applied to the aluminum pipe or pipe arch to provide an insulation between the aluminum and other metal shall extend a minimum distance of 1 ft. beyond the area of contact.

501.11.2.3. Precoated Galvanized or Aluminized Steel Pipe. Pipe shall be full circle or arch pipe conforming to AASHTO Designation M245, Type I, Type II or Type III as specified in the plans.

501.11.3. Classification (Type). Corrugated metal pipe shall be classified on the plans and/or specifications with the notations as set forth in ASTM A760 (A760M), ASTM B745 (B745M) and ASTM A742 (A742M) and indicated in Table 501.11.3.(a) Corrugated Metal Pipe Type.

Table 501.11.3.(a) Corrugated Metal Pipe Type

Type	Description
Type I	Pipe with a full circular cross section with a singular thickness of corrugated sheet, fabricated with annular or helical corrugations.
Type IA	Pipe with a full circular cross section, with an outer shell of corrugated sheet fabricated with helical corrugations and an inner liner of smooth (uncorrugated) sheet attached to the shell at helical lock seams. Unless otherwise shown on the plans or contract specifications, the inner liner of smooth (uncorrugated) sheets shall be 18-gage, polymer coated per ASTM A762 (A762M) Grade 10/10 or 20-gage, polymer coated per ASTM A762 (A762M) Grade 10/10.
Type IR	Pipe with a full circular cross section, with a single thickness of smooth sheet, fabricated with helical ribs projecting outward.
Type II	Type I pipe which has been reformed into a pipe-arch, having an approximately flat bottom.
Type IIA	Type IA pipe which has been reformed into a pipe-arch, having an approximately flat bottom.
Type IIR	Type IR pipe which has been reformed into a pipe-arch, having an approximately flat bottom.
Type III	Type I pipe which has been perforated to permit the inflow and outflow of water, intended for use as underdrains.
Type IIIA	Pipe shall consist of semi-circular cross section having a smooth bottom with a corrugated top shield which has been perforated, intended for use as deck drains.

501.11.4. Material. Corrugated metal pipe or pipe arch shapes shall be fabricated from corrugated sheets conforming to one of the styles indicated in Table 501.11.4.(a) Corrugated Sheets for Pipe or Pipe Arch Shapes.

Table 501.11.4.(a) Corrugated Sheets for Pipe or Pipe Arch Shapes

Metal		Standards
GALV	Galvanized Steel	ASTM A760 (A760M) Corrugated Steel Pipe, Metallic-Coated for Sewers and Drains
ALT2	Aluminized Type 2 Steel	ASTM A760 (A760M) (same as above)
POLY	Polymeric Steel	ASTM A762 (A762M) Corrugated Steel Pipe, Polymer Precoated for Sewers and Drains (Grade 10/10)
ALUM	Aluminum Alloy	ASTM B744 (B744M) Aluminum Alloy Sheet for Corrugated Aluminum Pipe

501.11.5. Gage. Where reference is made to gage of metal, the reference is to U.S. Standard Gage for uncoated sheets in ASTM A929 (A929M) Steel Sheet, Metallic-Coated by the Hot-Dip Process for

Corrugated Steel Pipe. Unless otherwise shown on the plans or contract specifications, minimum gages shall be as required by TxDOT *Standard Specifications for Construction of Highways, Streets and Bridges*, Item 460.4. Selection of Gages.

501.11.6. Corrugation. Corrugated configurations shall be governed by dimensional tolerances set forth in ASTM A760 (A760M). The corrugations as shown in Table 501.11.6.(a) Corrugation Configurations shall only be valid with their respective classifications (type).

Table 501.11.6.(a) Corrugation Configurations

Type	Configuration
Type 1	2 $\frac{2}{3}$ -in. x $\frac{1}{2}$ -in.; 3-in. x 1-in.; 5-in. x 1-in.
Type IA	2 $\frac{2}{3}$ -in. x $\frac{1}{2}$ -in.; 3-in. x 1-in.
Type IR	$\frac{3}{4}$ -in. x $\frac{3}{4}$ -in. x 7 $\frac{1}{2}$ -in.; $\frac{3}{4}$ -in. x 1-in. x 11 $\frac{1}{2}$ -in.
Type II	2 $\frac{2}{3}$ -in. x $\frac{1}{2}$ -in.; 3-in. x 1-in.; 5-in. x 1-in.
Type IIA	2 $\frac{2}{3}$ -in. x $\frac{1}{2}$ -in.; 3-in. x 1-in.
Type IIR	$\frac{3}{4}$ -in. x $\frac{3}{4}$ -in. x 7 $\frac{1}{2}$ -in.; $\frac{3}{4}$ -in. x 1-in. x 11 $\frac{1}{2}$ -in.
Type III	2 $\frac{2}{3}$ -in. x $\frac{1}{2}$ -in.; 3-in. x 1-in.

501.11.7. Repairs. All damage incurred in fabrication will be repaired at the fabrication location. Damage incurred during handling and placement will be repaired, inspected and approved by the OWNER prior to backfilling the pipe.

501.11.7.1. Galvanized Steel Pipe. Damaged spelter coating shall be repaired by thoroughly wire brushing the damaged area and removing all loose, cracked or weld burned spelter coating. The cleaned area shall be painted with a zinc dust-zinc oxide paint conforming to Federal Specifications TT-P-641.

501.11.7.2. Aluminized Steel Pipe. Damaged areas of aluminized coating, including saw cut ends and welds, shall be cleaned and repaired by brush coating of aluminized paint to the damaged, cut or welded area to a minimum thickness of 0.005-in.

501.11.7.3. Precoated Pipe. Damaged or cut areas of polymeric coatings shall be repainted by the application of a polymeric coating similar and compatible with the polymeric coating on the pipe and to a minimum 10-mil thickness.

Damaged areas of bituminous coated galvanized steel shall be repaired by repair of any damaged areas of spelter coatings in accordance with [Item 501.11.7.1](#). Galvanized Steel Pipe before repairing the bituminous coating by applying asphalt mastic to the same thickness as the original coating.

501.11.8. Pipe Marking. The following information shall be clearly marked on each section of pipe:

- (1) Date of manufacture of the pipe.
- (2) The name or trademark of the manufacturer of the pipe.
- (3) Gage or thickness of metal.
- (4) Alloy number (aluminum pipe only).

501.11.9. Couplings.

501.11.9.1. Coupling Bands. Except as may be otherwise required, coupling bands shall be of the same base material(s) as the pipe. Coupling bands shall lap evenly on each of the pipes being connected and shall fit securely into a least one full circumferential corrugation to form a tightly closed joint. Pipe end circumferential corrugations shall be the corrugation width and depth as shown on the plans or as specified by the Engineer.

All pipe shall be field jointed with corrugated locking bands. Coupling bands shall not be more than three nominal sheet thicknesses lighter than the pipe to be connected and in no case thinner than 0.052-in. The minimum width of the corrugated locking bands shall be as shown in Table 501.11.9.1.(a) Corrugated Locking Band Width for the corrugation which corresponds to the end circumferential corrugations on the pipe being joined.

Table 501.11.9.1.(a) Corrugated Locking Band Width

Corrugation	Minimum Band Width
2 $\frac{2}{3}$ -in. x $\frac{1}{2}$ -in.	10 $\frac{1}{2}$ -in.
3-in. x 1-in.	12-in.
6-in. x 1-in.	18-in.

When it is necessary to join a new pipe of helical corrugations to an existing pipe which was installed with no circumferential end corrugations, the two pipes shall be field jointed with helically corrugated bands. The width of helically corrugated bands shall conform to the minimum widths in Table 501.11.9.1.(b) Helically Corrugated Band Width.

Table 501.11.9.1.(b) Helically Corrugated Band Width

Helical End Corrugation	Minimum Band Width
$\frac{1}{2}$ -in. deep	12-in.
1-in. deep	14-in.

All coupling bands 12-in. wide or less shall be drawn together by means of a minimum of two $\frac{1}{2}$ -in. diameter bolts through angles or bar and strap device suitably welded; coupling bands greater than 12-in. wide shall have a minimum of three $\frac{1}{2}$ -in. diameter bolts.

501.11.9.2. Bell-and-Spigot Coupling. Except as may otherwise be required, bell-and-spigot couplings shall be of the same base material as the pipe, and in no case thinner than 0.052-in.

Couplings shall be bell and spigot type. The bell shall have a corrugation to engage the rerolled annular corrugation in the pipe, with a flare to receive the spigot end of the next section of pipe. The bell shall have factory-welded lap(s) applied after snugging the bell corrugation into the pipe rerolled annular corrugation.

Gaskets, if required, shall be polyisoprene (or similar) with a durometer of 45 ± 5 . The gasket on the spigot end shall be fluted with two flutes to prevent rolling when assembled in the field and to resist pull out from the bell.

501.12. STRUCTURAL PLATE STRUCTURES

501.12.1. General. Structural plate conduit, pipe arch, box culverts and special shapes shall meet the requirements of TxDOT *Standard Specifications for Construction of Highways, Streets and Bridges* Item 461 Structural Plate Structures and be in accordance with ASTM A761 Corrugated Steel Structural Plate, Zinc-Coated, for Field-Bolted Pipe, Pipe-Arches, and Arches for galvanized steel structures or ASTM B221 Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes, for aluminum alloy structures.

501.12.2. Plates. Steel plates shall consist of structural units of corrugated galvanized metal. Single plates shall be furnished in standard sizes to permit structure length increments of 2-ft. Aluminum plate shall consist of structural units of corrugated aluminum alloy. For aluminum alloy structures, cut plates shall be furnished on structure ends to permit structure length increments of 1-ft.

Plates shall be formed to provide bolted lap joints. The bolt holes shall be so punched that all plates having like dimensions, curvature, and the same number of bolts per foot of seam shall be interchangeable. Each plate shall be curved to the proper radius so that the cross-sectional dimensions of the finished structure will be as indicated on the plans. Joints shall be staggered so that not more than 3 plates are joined at any one point. Unless otherwise specified, bolt holes along those edges of the plates that will form longitudinal seams in the finished structure shall be:

- (1) staggered in rows 2-inches apart, with one row in the valley and one in the crest of the corrugations and not less than 4-bolts-per-foot for galvanized steel structures, or
- (2) in rows 1 $\frac{3}{4}$ -in. apart with 2 bolts in each valley and on each crest and not less than 16-bolts-per-3-feet for aluminum alloy structures.

Bolt holes along those edges of the plates that will form circumferential seams in the finished structure shall provide for a bolt spacing of not more than 12-in. The minimum distance from center of hole to edge of the plate shall be not less than $1\frac{3}{4}$ -times the diameter of the bolt. The diameter of the bolt holes in the longitudinal seams shall not exceed the diameter of the bolt by more than $\frac{1}{4}$ -in. Plates for forming skewed or sloped ends shall be cut so as to give the angle of skew or slope specified. Burned edges shall be free from oxide and burrs and shall present a workmanlike finish and legible identification numerals shall be placed on each plate to designate its proper position in the finished structure.

501.12.3. Corrugations. Permissible corrugations of metal plates to be furnished for each structure shall be shown on the plans. Corrugations for steel structures shall have a pitch of 6-in. with a tolerance of $\frac{1}{4}$ -in. and a depth of 2-in. with a tolerance of $\frac{1}{8}$ -in. The radius on the inside of the corrugations shall be at least $1\frac{1}{16}$ -in. for steel structures. Corrugations for aluminum alloy structures shall have a pitch of 9-in. with a tolerance of $\frac{3}{8}$ -in. and a depth of $2\frac{1}{2}$ -in. with a tolerance of $\frac{1}{8}$ -in. The radius of the inside of the corrugation shall be at least 2-in. for aluminum alloy structures.

501.12.4. Gauge Determination and Tolerances. The gage or minimum thickness of metal plates to be furnished for each structure shall be shown on the plans. The gauge and tolerances of aluminum plates shall conform to those in ASTM B221 Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes. The thickness of galvanized steel plates shall conform to those in ASTM A929/A929M Steel Sheet, Metallic-Coated by the Hot-Dip Process for Corrugated Steel Pipe.

501.12.5. Metal Headwalls. The material for metal headwalls shall comply with requirements shown on plans. When required, aluminum alloy inverts, toewalls footings and closure plates shall conform to the material requirements herein. Extruded aluminum transverse stiffeners shall conform to ASTM B221 Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes, Alloy 6061-T6.

501.12.6. Fasteners. Fasteners for steel structural plate shapes shall be high strength bolts $\frac{3}{4}$ -in. diameter, hot-dip galvanized, meeting ASTM A449 Quenched and Tempered Steel Bolts and Studs. Nuts shall conform to ASTM A563 Carbon and Alloy Steel Nuts, Grade C. Fasteners for aluminum structural plate shapes shall be $\frac{3}{4}$ -in. diameter, hot-dip galvanized steel, meeting ASTM A307 Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength with the zinc coating in accordance with ASTM A153 Zinc Coating (Hot-Dip) on Iron and Steel Hardware. Nuts shall conform to ASTM A563, Grade A.

Bolt lengths shall be such as to result in at least "full nuts" when tightened in place.

501.12.7. Anchor Bolts. Anchor bolts for anchoring the ends of structural plate conduits into concrete headwall, footings or toewalls, as shown on the plans, shall be $\frac{3}{4}$ -in. diameter conforming to ASTM A307 Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength with the zinc coating in accordance with ASTM A153 Zinc Coating (Hot-Dip) on Iron and Steel Hardware. The length, shape and placement of these anchor bolts shall be as shown on the plans or approved by the Engineer.

501.12.8. Identification. No plates shall be accepted unless the metal is identified by a stamp on each plate in accordance with AASHTO M167 for Steel Structural Plate or AASHTO M219 for Aluminum Alloy Structural Plates.

501.12.9. Inspections. If the Engineer so elects, it may have the material inspected and sampled in the rolling mill or in the shop where fabricated. Engineer may require from the mill the chemical analysis of any plate. The inspection, either in the mill or in the shop, shall be under the directions of the Engineer. The Engineer or its representative shall have free access to the mill or shop for inspection and every facility shall be extended to the Engineer or representative for this purpose. Any material that has been previously rejected at the mill or shop and included in a later lot will be cause for rejection unless it has been satisfactorily repaired.

The CONTRACTOR shall furnish an itemized statement of the number and size of plates in each shipment. From this list a visual inspection shall include an examination of the plates for deficiency in size, radius of curvature specified, and any evidence of poor workmanship as outlined herein. The inspection may include the taking of samples for chemical analysis and determination of weight of spelter coating on steel plates. The plates making up the shipment shall fully meet the requirements of these specifications. Any plates failing to do so will be rejected.

501.12.10. Rejection. In addition to the provisions of [Item 501.1.1](#), Rejection, structures shall be rejected on which the spelter coating has been bruised or broken either in the shop or in shipping, or which shows defective workmanship. The requirement applies not only to the individual plates but also to the shipment on any contract as a whole. Among others, the following defects are specified as constituting poor workmanship, and the presence of any or all of them in any individual culvert plate or in general in any shipment shall constitute sufficient cause for rejection:

- (1) elliptical shaping,
- (2) variation from a straight centerline,
- (3) ragged edges,
- (4) unevenly lined or spaced bolt holes,
- (5) illegible brands,
- (6) bruised, scaled or broken spelter coating,
- (7) dents or bends in the metal itself, or
- (8) uneven laps.

501.13. TUNNEL LINER PLATES

501.13.1. General. This specification covers the material, galvanizing, coating, shapes and gauge requirements of tunnel liner plates for use in tunneling under railroads, highways and streets.

501.13.2. Plates. The plates shall be fabricated from steel sheets conforming to the requirements of ASTM A1011 Steel, Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy and High-Strength Low-Alloy with Improved Formability. In addition, the flat plates before cold forming shall have mechanical properties indicated in Table 501.13.2.1.(a) Tunnel Liner Plate Requirements.

501.13.2.1.(a) Tunnel Liner Plate Requirements

Property	Minimum Value
Tensile Strength	42,000-psi
Yield Strength	28,000-psi
Elongation, 2-in.	30-percent

501.13.3. Bolts and Nuts. Bolts used with lapped seam type (2 flange) liner plates shall be not less than $\frac{5}{8}$ -in. diameter. Bolts shall conform to ASTM A449 Quenched and Tempered Steel Bolts and Studs for plate thickness equal to or greater than 0.209-in. and to ASTM A307 Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength for plate thickness less than 0.209-in. Nuts shall conform to ASTM A307.

Bolts and nuts used with the four-flanged type shall be not less than $\frac{1}{2}$ -in. for 7-gauge plates and lighter and not less than $\frac{5}{8}$ -in. diameter for plates heavier than 7-gauge. The bolts and nuts shall be quick acting coarse thread and shall conform to ASTM A307, Grade A.

501.13.4. Fabrication. The plates shall be new and unused prior to fabrication. All plates shall be punched for bolting on both longitudinal and circumferential seams or joints and shall be so fabricated as to permit complete erection from the inside of the tunnel. All plates shall be of uniform fabrication and those intended for one size tunnel shall be interchangeable.

501.13.5. Grout Holes. One-half of the total number of the top plates shall be equipped with 2-in. diameter grout holes to facilitate grouting above and around the tunnel liner conduit. All grout holes shall be equipped with screw type galvanized plugs for final watertight closure of the grout holes.

501.13.6. Galvanizing. After the plates are formed to shape and after all holes are punched, the plates shall be galvanized on all surfaces by the hot-dip process. A coating of prime western spelter or equal shall be applied in accordance with ASTM A123 Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products. Spelter coating shall be of first-class commercial quality free from injurious defects such as blisters, flux and uncoated spots. All nuts shall be galvanized to conform to ASTM A153 Zinc Coating (Hot-Dip) on Iron and Steel Hardware.

501.13.7. Bituminous Coating. The plates shall be given a bituminous coating meeting the current American Railway Engineering & Maintenance of Way Association specification or ASTM A849 Post-Applied

Coatings, Pavings, and Linings for Corrugated Steel Sewer and Drainage Pipe. Bituminous protected corrugated metal pipe or plates may be spray-coated in the field with a minimum dry film thickness of 0.05-in. prior to installation.

501.13.8. Section Properties. Section properties shall conform to those specified in AASHTO Standard Design Specifications for Highway Bridges, Section 16, Steel Tunnel Liner Plates.

501.13.9. Rejection. Structures on which the spelter coating has been bruised or broken either in the shop or in shipping or which shows defective workmanship shall be rejected. The requirement applies not only to the individual plates but also to the shipment on any contract as a whole. Among others, the following defects are specified as constituting poor workmanship, and the presence of any or all of them in any individual liner plate or in general in any shipment shall constitute sufficient cause for rejection:

- (1) uneven laps,
- (2) elliptical shaping,
- (3) variation from a straight centerline,
- (4) ragged edges,
- (5) unevenly lined or spaced bolt holes,
- (6) illegible brands,
- (7) bruised, scaled or broken spelter coating, or
- (8) dents or bends in the metal itself.

501.14. POLYVINYL CHLORIDE (PVC) WATER PIPE

501.14.1. General. Unplasticized polyvinyl chloride (PVC) water pipe shall meet the requirements of AWWA C900, sizes 4-in. to 60-in. diameter. In accordance with C900, Section III.A, purchaser options and alternatives shall be provided by the specifier, including working, occasional, and recurring surge pressures, pressure class, or dimension ratio (DR). Purchaser options and alternatives shall be specified in the supplemental conditions, plans, or technical specifications. Laying lengths shall be 20-ft ±1-in.

501.14.2. Approvals. PVC water pipe shall be approved by the Underwriters' Laboratories and shall be accepted by the State Fire Insurance Commission for use in water distribution systems in cities and towns of Texas. PVC water pipe shall also bear the seal of approval (or "NSF" mark) of the National Sanitation Foundation Testing Laboratory for potable water pipe.

501.14.3. Dimension Ratio. PVC water pipe shall meet the dimension ratios (DR's) and physical dimensions as shown in AWWA C900. The pressure classification refers to the maximum hydrostatic pressure to which the pipe shall be subjected in normal operations.

501.14.4. Joints. PVC water pipe shall be furnished with gasketed joints. Lubricant used for pipe and fittings assembly shall be nontoxic and in conformance to NSF61. The lubricant shall have no detrimental effect to either gasket or pipe.

501.14.5. Fittings. Fittings for PVC water pipe shall conform to one of the standards Table 501.14.5.(a) PVC Water Pipe Fittings unless otherwise specified. Fittings joints shall be push-on, integrally restrained, or mechanical. Bolts and nuts for mechanical and integrally restrained fittings joints shall be of a high-strength, corrosion-resistant, low-alloy steel and shall conform to ASTM A325 High Strength Bolts for Standard Steel Joints (Type 3) or shall be stainless steel in accordance with ASTM A304.

Table 501.14.5.(a) PVC Water Pipe Fittings Standards

Standard	Topic
AWWA C110 (ANSI A21.10)	Ductile-Iron and Gray-Iron Fittings, 3 in. Through 48 in. for Water
AWWA C153	ANSI Standard for Ductile-Iron Compact Fittings for Water Service
AWWA C907	Polyvinyl Chloride (PVC) Pressure Fittings for Water—4 in. Through 8 in.
AWWA C900	Polyvinyl Chloride (PVC) Pressure Pipe, and Fabricated Fittings, 4 in. Through 12 in. or Water Distribution

501.15. POLYVINYL CHLORIDE (PVC) PRESSURE-RATED PIPE (SDR SERIES)

501.15.1. General. PVC pressure-rated pipe shall conform to the current ASTM D2241, Poly (Vinyl Chloride) (PVC) Pressure-Rated Pipe (SDR Series).

501.15.2. Material. The pipe shall be made of PVC plastic having cell classifications of 12454 or 13343 in accordance with ASTM D1784.

501.15.3. Joints. Joint tightness shall be tested in accordance with ASTM D3139, Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals.

501.15.4. Testing. All pipe shall meet ASTM requirements for sustained pressure test, accelerated regression test, burst pressure, flattening and impact resistance.

501.16. MOLECULARLY ORIENTED POLYVINYL CHLORIDE (PVCO) WATER PIPE

501.16.1. General. Unplasticized (PVCO) Water pipe shall meet the requirements of AWWA Standard C909 Molecularly Oriented Polyvinyl Chloride (PVCO) Pressure Pipe, 4 In. – 24 In., for Water Distribution. Laying length shall be 20ft ± 1 inch.

501.16.2. Material. PVCO water pipe starting stock shall be made from ASTM D1784 cell class 12454 material, having an Hydrostatic Design Basis (HDB) of 4000-psi. When orientation is achieved, PVCO pipe will have an HDB of 7100-psi. The pressure classifications refer to the maximum hydrostatic pressure to which the pipe shall be subject in normal operations.

501.16.3. Dimensions. Dimensions shall conform to the requirements in AWWA C909.

501.16.4. Joints. PVCO water pipe shall be furnished with gasketed joints, meeting ASTM D3139 Joints for Plastic Pressure Pipes using Elastomeric Seals. Lubricant used for pipe and fittings assembly shall be nontoxic and shall have no detrimental effect to either gasket or pipe. Solvent cement shall not be used with PVCO pipe.

501.16.5. Fittings. Fittings for PVCO water pipe shall conform to American National Standard for Gray-Iron and Ductile-Iron Fittings, 3 In. through 48 In., For Water and Other Liquids, AWWA Standard C110 (ANSI A21.10) or AWWA C907 for Polyvinyl Chloride (PVC) Pressure Fittings for Water, 4 In. through 12 In., or AWWA C153 ANSI Standard for Ductile-Iron Compact Fittings for Water Service unless otherwise specified. Fittings joints shall be push-on or mechanical joints. Bolts and nuts for mechanical joints shall be of a high-strength, corrosion-resistant, low-alloy steel and shall conform to High Strength Bolts for Standard Steel Joints, ASTM A325 (Type 3) or stainless steel in accordance with ASTM A304.

501.17. POLYVINYL CHLORIDE (PVC) WASTEWATER PIPE & FITTINGS WITH DIMENSION CONTROL

501.17.1. General. PVC Wastewater Pipe and Fittings shall conform to ASTM D3034 Type PSM Poly(Vinyl Chloride) (PVC) Sewer Pipe and Fittings for 4 in. through 15 in. diameter and ASTM F679 Poly(Vinyl Chloride) (PVC) Large-Diameter Plastic Gravity Sewer Pipe and Fittings for greater than 15 in. diameter.

501.17.2. Material. The pipe shall be made of PVC plastic having cell classification of 12454, or 12364, and fittings shall be made of PVC plastic having cell classifications of 12454, or 13343 as defined in ASTM D1784 Rigid Poly(Vinyl Chloride) (PVC) Compounds and Chlorinated Poly(Vinyl Chloride) (CPVC) Compounds. Pipe type shall be determined by size as shown in Table 501.17.2.(a) PVC Wastewater Pipe Type.

501.17.2.(a) PVC Wastewater Pipe Type

Pipe Size (diameter)	Type	Standard
4-in. through 15-in., inclusive	Pipe stiffness of 46, 115 and 153	ASTM D3034
greater than 15-in.	Pipe stiffness of 46, 75 and 115	ASTM F679

501.17.3. Dimensions. Dimensions shall conform to requirements of ASTM D3034 or F679.

501.17.4. Testing. All pipe shall meet ASTM requirements for flattening, impact resistance, stiffness, joint tightness and extrusion quality as specified in ASTM D3034 or F679.

501.18. POLYVINYL CHLORIDE (PVC) PROFILE GRAVITY WASTEWATER PIPE AND FITTINGS – FOR DIRECT BURY AND SLIPLINING APPLICATIONS

501.18.1. General. This specification designates requirements for PVC plastic gravity wastewater pipe for the conveyance of domestic wastewater with various modified wall profiles and performance requirements.

501.18.2. Stiffness. Minimum pipe stiffness at five percent deflection shall be 46-psi for wastewater conduit as specified for all sizes when calculated in accordance with ASTM D2412 Determination of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading.

501.18.3. Pipe Classification. Pipe as indicated on the plans shall conform to one of the standards in Table 501.18.3. PVC Profile Gravity Pipe Standards.

501.19. PVC COMPOSITE PIPE FOR WASTEWATER CONDUITS

501.19.1. General. PVC composite pipe shall conform to ASTM D2680 Acrylonitrile-Butadiene-Styrene (ABS) and Poly (Vinyl Chloride) (PVC) Composite Sewer Piping for 8 in. through 15 in diameter. Acrylonitrile-Butadiene-Styrene (ABS) shall not be allowed.

501.19.2. Joints, Couplings and Fittings. Wyes or tees with saddle shall be provided as indicated on the plans. Adapters to other types of pipe shall be supplied as indicated on the plans.

501.19.2.1. Chemically Welded Joints. If the pipe is plane ended with couplings, the pipe shall be delivered prebelled. Sufficient primer and solvent cement shall be provided. The solvent cement shall conform to ASTM D2564 Solvent Cements for Poly (Vinyl Chloride) (PVC) Plastic Piping Systems.

501.19.2.2. O-Ring Joints. If the pipe is prebelled with an enlarged coupling, an O-Ring shall be provided for each joint. The physical properties of the gasket shall be at least equal to the requirements of ASTM C443 Joints for Circular Concrete Sewer and Culvert Pipe, Using Rubber Gaskets.

501.19.3. Tests. The pipe stiffness at five-percent vertical deflection shall be at best equal to or exceed 200-lb./in. of deflection for each diameter as determined by ASTM D2412 Test Method for Determination of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading. The physical test may be the 3-Edge Bearing Method under applicable ASTM Designation if preferred.

501.20. SECTION HELD FOR FUTURE USE.**501.21. SOLID WALL POLYETHYLENE PLASTIC PIPE FOR WATER, WASTEWATER, AND PIPE REHABILITATION**

501.21.1. General. Pipe and fittings shall conform to the material and physical properties as described in ASTM F714 Polyethylene (PE) Plastic Pipe (SDR-PR) Based on Outside Diameter, unless otherwise specified herein or in the special specifications. Standard Lengths shall be 40-ft or 50-ft for straight pipe. Coiled pipe may be obtained in reels of 500-ft, 1000-ft or 1500-ft depending on outside diameter and Dimension Ratio (DR) requested.

Solid wall high density polyethylene pipe (HDPE) for pressure water pipe shall meet the requirements of AWWA C901 Polyethylene (PE) Pressure Pipe and Tubing, ½ in. Through 3 In., for Water Service or AWWA C906 Polyethylene (PE) Pressure Pipe and Fittings, 4 In. Through 63 In., for Water Distribution.

501.21.2. Material. Pipe and fittings shall be made of high density, high molecular weight polyethylene pipe PE3408 material, polyethylene resin which conforms to Polyethylene Plastics Molding and Extrusion Materials, meeting the requirements of Type III, Grade P33, as defined in ASTM D3350 Polyethylene Plastics Pipe and Fittings Materials. The polyethylene plastic shall meet the Cell Classification requirements of 345464C or 345464E as defined in ASTM D3350. Pipe for non-pressure applications shall have a light colored interior for video inspection, unless otherwise specified in the plans, contract documents or purchase request.

501.21.3. Dimensions. The polyethylene (PE) pipe shall meet the dimension ratios and outside diameter, wall thickness and tolerances as provided in the reference specifications of manufacture as listed in Table 501.21.3.(a) Solid Wall PE Pipe Dimension Standards. Diameters and wall thickness other than those shown in the standards may be used if specifically called for in the plans, contract documents or purchase request, and if they are mutually agreed upon by the manufacturer and OWNER.

Table 501.21.3.(a) Solid Wall PE Pipe Dimension Standards.

Standard	Topic
AWWA C901	Polyethylene (PE) Pressure Pipe and Tubing, ½ in Through 3 in for Water Service
AWWA C906	Polyethylene (PE) Pressure Pipe and Fittings, 4in through 63in for Water Distribution and Transmission
ASTM D2239	Polyethylene (PE) Plastic Pipe (SIDR-PR) Based on Controlled Inside Diameter
ASTM D2737	Polyethylene (PE) Plastic Tubing
ASTM D3035	Polyethylene (PE) Plastic Pipe Based on Controlled Outside Diameter
ASTM F714	Polyethylene (PE) Plastic Pipe (SDR-PR) Based on Outside Diameter

501.21.4. Joints. Dependent upon installation requirements, site location, weather conditions, and the presence of water, joining shall be performed within or outside the excavation.

Sections of polyethylene pipe and fittings shall be joined by the butt fusion process, unless an alternate method is approved by the OWNER. The butt (heat) fusion method shall be performed in accordance with the pipe manufacturer's recommendations. Electrofusion fittings shall be used. Extrusion welding or hot gas welding of PE shall not be used for pressure pipe application or fabrications where shear or structural strength is important.

501.21.5. Tests and Requirements. Tests for compliance with this specification shall be made as specified herein and according to the applicable ASTM or AWWA Standard(s). All polyethylene pipe shall be tested for brittleness, joint separation, quality, and ring stiffness as specified in the applicable ASTM or AWWA Standard(s). A certification of compliance with this specification shall be furnished by the manufacturer for all material furnished under this specification. In addition, the OWNER may, at its own expense, witness inspection and test of the materials.

501.21.5.1. Tensile Properties. The tensile strength, yield strength, elongation and elastic modulus of the material shall be determined in accordance with Tensile Properties for Plastics, ASTM D638 (D 638M).

501.21.5.2. Hydrostatic Properties. The long term hydrostatic strength rating shall be listed in the name of the pipe and fittings manufacturer in PPI (Plastic Pipe Institute) TR-4, Recommended Hydrostatic Strengths and Design Stresses for Thermoplastic Pipe and Fittings compounds, with a standard grade HDB rating of 1600-psi at 73°F.

501.21.5.3. Melt Index. The melt index of the polyethylene plastic, as determined in accordance with ASTM D1238 Flow Rates of Thermoplastics by Extrusion Plastometer, shall meet the requirements as specified in ASTM D3350 Cell Classification of 4.

501.21.5.4. Density. The density of the polyethylene plastic, as determined in accordance with ASTM D1505 Density of Plastics by the Density - Gradient Technique shall have specific base resin densities meeting the requirements as specified in ASTM D3350 Cell Classification 3.

501.21.5.5. Environmental Stress Cracking Resistance. The environmental stress cracking resistance (ESCR) of the material shall meet the requirements as specified in ASTM D3350 Cell Classification of 6 using ASTM F1473 (PENT) or meet a Cell Classification of 4 according to ASTM D1693.

501.21.5.6. Wastewater Pipe Stiffness. Minimum pipe stiffness at five-percent deflection shall be 46-psi for all sizes of gravity and pressure wastewater conduits as specified in Section XI "Deflection Control In Unpressurized Polyethylene Piping Systems," Table X1.1 "Pipe Stiffness Ranges for Specified Materials" and DR's of ASTM F714.

501.22. POLYETHYLENE (PE) LARGE DIAMETER WASTEWATER PIPE WITH MODIFIED WALL PROFILES AND PERFORMANCE STANDARDS

501.22.1. General. High Density Polyethylene gravity wastewater pipe and fittings in nominal sizes 18-in. through 120-in. with integral bell joints shall conform to current ASTM F894 Polyethylene (PE) Large Diameter Profile Wall Sewer and Drain Pipe.

501.22.2. Materials. The pipe and fittings shall be made of high density, high molecular weight polyethylene pipe material meeting the requirements of Type III, Class C, Category 5, Grade P34, as defined in ASTM D3350 Polyethylene Plastics Pipe and Fittings Materials with a minimum cell classification of 345444C.

501.22.3. Stiffness. Minimum pipe stiffness at five-percent deflection shall be 10-psi for wastewater as specified for all sizes when calculated according to Appendix XI, "Relation of RSC To Pipe Properties and Pipe Stiffness" of ASTM F894.

501.22.4. Joints. Joint tightness shall be tested in accordance with ASTM D3212 Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals.

501.22.5. Testing. Pipe shall be tested for flattening, quality and ring stiffness as specified in the applicable ASTM Designations.

501.23. THERMOPLASTIC CORRUGATED DRAINAGE TUBING AND CORRUGATED SMOOTH LINED STORM WATER PIPE AND FITTINGS

501.23.1. General. High Density Corrugated and Corrugated Smooth Lined Thermoplastic storm water tube/pipe and fittings shall conform to Table 501.23.1.(a) Thermoplastic Storm Water Pipe and Fittings.

Table 501.23.1.(a) Thermoplastic Storm Water Pipe and Fittings.

Pipe Material	Topic	Standard
Polyvinyl Chloride (PVC)	PVC Corrugated Storm Water Pipe With A Smooth Interior	ASTM F949 (4"-36")
Polyethylene (PE)	PE Corrugated Pipe With A Smooth Interior	AASHTO M294 (12"-60") AASHTO M252 (3"-10")
Polypropylene (PP)	PP Corrugated Pipe With A Smooth Interior	ASTM F2736 (6"-30")

501.23.2. Materials.

501.23.2.1. PVC. The storm water conduit/drainpipe shall be of PVC compound having a minimum cell classification of 12454 in accordance with ASTM D1784 Rigid Poly (Vinyl Chloride) (PVC) Compounds and Chlorinated Poly (Vinyl Chloride) (CPVC) Compounds. The fittings shall be made of PVC compound having a cell classification of 12454 or 13343 as defined in ASTM D1784.

501.23.2.2. PE. The tube/pipe and fittings shall be made of virgin polyethylene which conforms with the requirements of cell class 335400C as defined and described in ASTM D3350 Polyethylene Plastics Pipe and Fittings Materials.

501.23.2.3. PP. Polypropylene compound for pipe and fitting production shall be impact modified copolymer meeting the material requirements of ASTM F2736, Section 4 for the respective diameters. Minimum pipe stiffnesses at 5% deflection shall meet or exceed ASTM F2736, Section 6.2.6 Pipe Stiffness.

501.23.3. Stiffness.

501.23.3.1. PVC. Constant minimum pipe stiffness at five-percent deflection shall be 46-psi for storm conduit as specified for all sizes when calculated in accordance with ASTM D2412 Determination of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading.

501.23.3.2. PE. Minimum tube/pipe stiffness at 5-percent deflection shall be 50-psi for 3-in. through 10-in. diameters and as outlined in Section 7.4 of AASHTO M-294 for other diameters.

501.23.3.3. PP. Minimum pipe stiffnesses at 5% deflection shall meet or exceed ASTM F2736, Section 6.2.6 Pipe Stiffness.

501.23.4. Joints.

501.23.4.1. PVC. Joints shall be an integral bell-gasketed joint. When the joint is assembled, it shall prevent misalignment of adjacent pipes and form either a soil tight joint (2-psi hydrostatic test per AASHTO Standard Specification for Highway Bridges, Section 26.4.2.4) or a watertight joint (10.8-psi

test per ASTM D3212 Standard Specification for Joints for Drain and Sewer Plastic Pipes using Flexible Elastomeric Seals) as required.

501.23.4.2. PE. Joint integrity shall be tested in accordance with ASTM F667 Large Diameter Corrugated Polyethylene Pipe and Fittings, Section 9.6 for PE corrugated pipe up to 24" or AASHTO M-294 and M-252 for smooth-lined corrugated pipe. Profile wall HDPE pipe joints shall be made and tested in accordance with ASTM D3212 Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals.

501.23.4.3. PP. Pipe shall be joined with a gasketed integral bell & spigot joint meeting the requirements of ASTM F2736 for the respected diameters (12"-30"), and shall be watertight according to the requirements of ASTM D3212. Gasket shall be installed by the pipe manufacturer and covered with a removable, protective wrap to ensure the gasket is free from debris. 12"-30" diameters shall have a reinforced bell with a polymer composite band installed by the manufacturer.

501.23.5. Testing.

501.23.5.1. PVC. Pipe shall be tested for flattening, impact resistance and extrusion quality as specified in the applicable ASTM Designations.

501.23.5.2. PE. All polyethylene tubing/piping shall be tested for elongation, brittleness, joint separation, quality and ring stiffness as specified in the applicable AASHTO M-294, AASHTO M-252 or ASTM F2648, as applicable.

501.23.5.3. PP. All polypropylene piping shall be tested as per ASTM F2736, Section 8 as applicable.

501.24. FIBERGLASS (GLASS-FIBER-REINFORCED THERMOSETTING-RESIN) WASTEWATER PIPE

501.24.1. General. This specification designates requirements for fiberglass glass-fiber reinforced thermosetting-resin pipe (RTRP) sizes from 8-in. to 144-in. for the conveyance of wastewater. Pipe for gravity application shall conform to ASTM D3262 for "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Sewer Pipe. Pipe for force main applications shall conform to or ASTM D3754 for "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Sewer and Industrial Pressure Pipe. If ASTM D3754 pipe is selected, its actual outside diameter shall be in accordance with AWWA C950 Fiberglass Pressure Pipe.

501.24.2. Stiffness. Minimum pipe stiffness at 5-percent deflection shall be 46-psi for gravity and pressure wastewater conduit and 36-psi for gravity sliplining applications as specified for all sizes when calculated in accordance with ASTM D2412 Test Method for Determination of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading.

501.24.3. Joints. Joint tightness shall be tested in accordance with ASTM D4161 for "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pipe Joints Using Flexible Elastomeric Seals.

501.24.4. Fittings. Fittings shall conform to ASTM D5685 Fiberglass (Glass-Fiber-Reinforced Thermosetting-Resin) Pressure Pipe Fittings or D3840 Standard Specification for "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pipe Fittings for Nonpressure Applications.

501.24.5. Testing. Pipe shall be tested for inside and outside diameter, wall thickness, squareness of pipe ends, chemical requirements, stiffness, beam strength as specified in the respective ASTM D3681 Test Method for Chemical Resistance of "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pipe in a Deflected Condition, ASTM D2412 Standard Test Method for Determination of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading, and ASTM D3262 Standard Specification for "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Sewer Pipe.

501.25. FIBERGLASS (GLASS-FIBER-REINFORCED THERMOSETTING-RESIN) FOR WATER PIPE

501.25.1. General. This specification designates requirements for glass-fiber reinforced thermosetting resin pipe in sizes 8-in. to 156-in. intended for water conveyance in pressurized systems of less than 450 psi. Pipe manufactured for these applications shall conform to ASTM D3517 Standard Specification for "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pressure Pipe.

501.25.2. Joints. Joints shall either be bell & spigot with elastomeric gasket, flanged, lay-up lamination or mechanical coupling. Gaskets shall comply with ASTM F477 Standard Specification for Elastomeric Seals (Gaskets) for Joining Plastic Pipe. Lay-up laminations shall be of manufacturer approved materials and

applied by, or under, the supervision of a pipe manufacturer's representative. Mechanical coupling shall be of a type approved for use on the pipe by the manufacturer.

501.25.3. Fittings. Fittings shall conform to ASTM D5685 Standard Specification for Fiberglass (Glass-Fiber-Reinforced Thermosetting-Resin) Pressure Pipe Fittings. Only fittings approved for use by the pipe manufacturer shall be permitted.

501.25.4. Markings. All pipe shall have be clearly marked by the manufacturer designating nominal size, pressure class, stiffness, manufacturer's name or trademark, and ASTM D3517 Standard Specification for "Fiberglass" (Glass-Fiber-Reinforced Thermosetting-Resin) Pressure Pipe.

501.25.5. Testing. All pipe and fittings, once in place complete with compacted backfilled shall be hydrostatically tested at 120-percent of design pressure in accordance with [Section 506.5](#). Hydrostatic Test.

ITEM 502. APPURTENANCES

502.1. MANHOLES

502.1.1. Manhole Materials. Manholes shall be fabricated in different configurations to meet the specific needs required in the water or wastewater or storm water system.

502.1.1.1. Precast Reinforced Concrete Manhole Sections. These specifications cover precast reinforced concrete manhole sections, which shall conform to ASTM C478 Precast Reinforced Concrete Manhole Sections, with the following additions:

- (1) Aggregates for the concrete shall comply with requirements of ASTM C33 Concrete Aggregates.
- (2) Resilient connectors between reinforced concrete manhole structures and pipes shall meet the requirements of ASTM C923 Resilient Connectors Between Reinforced Concrete Manhole Structures, Pipes and Laterals

502.1.1.1.1. Joints. Joints shall conform to the joint specification ASTM C443 Joints for Concrete Pipe & Manholes, Using Rubber Gaskets. All joints shall have rubber gaskets. Rubber gaskets shall meet the requirements of [Item 501.5.4.1. Rubber Gaskets](#).

502.1.1.1.2. Coatings and Linings. Coatings and linings called for in the specifications or shown on the plans shall meet the requirements as specified by the OWNER and shall be installed or applied by the manufacturer. Add mixtures may be required as per OWNER specification.

502.1.1.1.3. Lifting Devices. Manhole sections and cones may be furnished with lift lugs or lift holes. If lift lugs are provided, they shall be 180° apart. Cast-in-place nuts must have clean threads capable of inserting lug bolts. OWNER shall approve the lift lug design. If lift holes are provided, they shall be plugged with a nonmetallic nonshrink grout approved by the OWNER. Field repairs shall not be allowed without OWNER approval.

502.1.1.1.4. Rejection. Manhole sections shall be subject to rejection on account of failure to conform to any of the requirements specified herein or having defects as follows:

- (1) Variations in any dimensions exceeding the permissible variation prescribed.
- (2) A piece broken out of the bell, spigot, tongue or groove in such size that the watertightness of the joint could be impaired.
- (3) Any shattering or flaking of concrete or other conditions indicating an improper concrete mix.
- (4) Lack of uniformity in placement steel which might preclude all joints being typical of those tested.
- (5) Cracks sufficient to impair the strength, durability, or serviceability of the pipe.
- (6) Joint sections with spalls, cracks, fractures, or other imperfections that could adversely affect the performance of the joint.

502.1.1.2. Fiberglass Manholes. Fiberglass manholes shall conform to all ASTM standards governing plastic laminations and ASTM D3753, Glass-Fiber-Reinforced Polyester Manholes and Wetwells, with supplementary details or additions as set forth in these specifications. See Standard Drawing 5040.

502.1.1.2.1. Manufacturing. The barrel and cone shall each be produced in a continuous manufacturing process that insures continuous reinforcement and uniform strength and composition. The cone section, if produced separately, shall be affixed to the barrel section at the factory with a reinforced glass resin joint resulting in a one-piece unit. Field made joints shall not be acceptable.

502.1.1.2.2. Manhole Configuration. The manhole shall be a circular cylinder with a minimum internal diameter of 4-ft. The cone of the manhole shall have a bearing surface wide enough to facilitate the placement of adjustment rings. The ring and cover shall not be placed directly on the manhole. The manway reducer shall be concentric with respect to the manhole cylinder. Eccentric manway reducers shall not be permitted. Manhole gaskets shall be used to ensure a watertight assembly.

502.1.1.2.3. Testing. All tests included in Glass Fiber-Reinforced Polyester Manholes, ASTM D3753, shall be required. Manufacturer shall provide OWNER a product certification if requested. This certification shall confirm the fiberglass manhole provided is in compliance with the testing requirements outlined in the ASTM standard.

502.1.1.2.4. Rejection. Any fiberglass manhole shall be subject to rejection for failure to conform to any of the requirements of these specifications. Any manhole found to be defective or damaged resulting from improper handling or installation shall be removed and replaced at no additional expense to the OWNER. Patching shall not be acceptable.

502.1.2. Grade Adjustment Risers. Casting shall be raised to final grade adjustment of access covers and frame assemblies made using adjustment risers. Risers may be concrete, polyethylene, metal, or rubber meeting requirements below or other materials as approved by the OWNER. OWNER shall specify material. Adjustment risers shall be tested to assure compliance with impact and loading requirements of the AASHTO Standard Specification for Highway Bridges. To determine the suitability of a specific ring or frame and to insure a proper fit, the dimensions of the existing frames, grates and covers must be verified by the CONTRACTOR and provided to the supplier prior to fabrication of the adjustment rings and frames.

Installed grade adjustment risers and riser assemblies shall fit within the existing casting without interference, cause no binding to the manhole lid, be immobile and watertight. Manhole lids shall have bearing on all of the surface of inner ring(s).

502.1.2.1. Precast Concrete Adjustment Riser. Concrete adjustment risers shall be precast, reinforced concrete meeting requirements of ASTM C478 Precast Reinforced Concrete Manhole Sections. Preformed flexible gaskets shall be used below each riser.

502.1.2.2. HDPE Adjustment Riser. The HDPE adjustment risers shall be manufactured from high density polyethylene plastic as identified in ASTM D1248 Polyethylene Plastic Molding and Extrusion Materials. They may be molded from 100% recycled HDPE material or have other recycled HDPE material content. Material properties shall be tested and qualified for usage according to the test methods in ASTM D1248. HDPE risers shall be manufactured using the injection molding process as defined by the Society of Plastic Engineers.

502.1.2.3. Metal Adjustment Riser.

502.1.2.3.1. Steel. Inner riser rings shall consist of 3/4" thick domestic steel meeting the requirements of ASTM A36 Carbon Structural Steel. Intermediate and outer rings shall be one of the combinations indicated in Table 502.1.2.3.1.(a) Steel Adjustment Risers, as specified by the OWNER.

Table 502.1.2.3.1.(a) Steel Adjustment Risers

Intermediate ring	Outer ring	Type
none	ASTM A36 steel 1/2" thick	solid
ASTM A36 12-gauge steel	1/2" x 1/2" surrounding intermediate ring at finished elevation	solid
none	ASTM A36 steel 1/2" thick	Adjustable ¹
ASTM A36 steel 1/8" thick	1/2" x 1/2" surrounding intermediate ring at finished elevation	Adjustable ¹

1. Adjustment devices for adjustable steel risers shall be fabricated from stainless steel, have a positive lock, and be in line with the lower bearing bar. It shall be capable of adjustment $\pm 3/8$ " from nominal.

Rings shall be fabricated to $\pm 1/16$ " concentricity. The outer riser ring shall have an inside diameter no greater than $3/16$ " larger than the outside diameter of the manhole lid. All materials shall be coated as specified by OWNER.

Certified welders shall securely weld rings in accordance with American Welding Society D1.5 Bridge Code to prevent differential movement between rings under traffic loads.

502.1.2.3.2. Iron. Gray iron adjustment risers shall be manufactured from iron conforming to ASTM A48 Gray Iron Castings, Class 35B, in accordance with AASHTO M306. Ductile iron adjustment risers shall be manufactured from iron conforming to ASTM A536 Ductile Iron Castings, Grade 70-50-05.

502.1.2.4. Rubber Adjustment Riser. The adjustment risers shall be manufactured from a mixture of rubber and appropriate additives to create a flexible product that will not rot, chip or break, and is resistant to moisture, oil and other common automotive chemicals. Product shall be stable under a wide range of temperatures and resistant to temperature fluctuations. Rubber adjustment risers may be

produced with recycled rubber content. Results of the tests listed in Table 502.1.2.4.(a) Rubber Adjustment Riser Tests shall be provided to the OWNER.

Table 502.1.2.4.(a) Rubber Adjustment Riser Tests

Property	ASTM Test Method	Topic
Density	C642	Test Method for Density, Absorption, and Voids in Hardened Concrete
Durometer hardness, molded and interior surfaces	D2240	Rubber Property-Durometer Hardness
Tensile strength	D412	Vulcanized Rubber and Thermoplastic Rubbers and Thermoplastic Elastomers-Tension
Compression deformation, initial and final	D575	Rubber Properties in Compression
Compression set	D395	Rubber Property-Compression Set
Freeze and thaw when exposed to deicing chemicals	C672	Scaling Resistance of Concrete Surfaces Exposed to Deicing Chemicals
Coefficient of thermal expansion	C531	Linear Shrinkage and Coefficient of Thermal Expansion of Chemical-Resistant Mortars, Grouts, Monolithic Surfacing, and Polymer Concretes
Weathering (70 hours at 70 C)	D573	Rubber-Deterioration in an Air Oven

502.1.3. Frame and Cover. Frame (Ring) and cover shall meet the requirements of [Item 806.4.1.2](#). Iron Castings.

502.1.4. Manhole Construction. TCEQ regulations shall take precedence in the case of conflict between these specifications and TCEQ regulations.

Manholes shall be of sufficient inside diameters to allow personnel to work within them and to allow proper joining of the pipes in the manhole wall. Unless otherwise specified, manholes shall have an inside diameter of at least 48-inches.

Manholes constructed in advance of paving projects shall be constructed with the top of the concrete portion of the manhole 23-inches below the final finished grade. The ring and cover shall be placed on a built-up section of approved grade rings and approved sealers between rings and between rings and other materials. Manholes shall be watertight. The type and size, if greater than 4-feet inside diameter, shall be shown on the plans for each location. The CONTRACTOR shall furnish all appropriate equipment and access required for inspection.

Backfilling of manholes shall comply with [Section 504.4](#).

502.1.4.1. Manhole Types and Requirements. Manholes in water lines shall be Cast-In-Place or Precast as described below and as shown in Division 5000 Standard Drawings. Manholes in wastewater service lines may be any of those described below, also shown in Division 5000 Standard Drawings. Manholes in storm sewers shall be Cast-In-Place, Precast, or constructed according to Standard Drawing 6010A-B. Storm sewer junction boxes shall be constructed according to Standard Drawing 6010A-B or constructed according to engineered plans. Manholes may be standard or shallow, as specified by the OWNER.

502.1.4.1.1. Cast-In-Place. The base, wall and cone shall be Class F or Class PF concrete as specified by the OWNER, in conformance with [Item 702](#). Concrete Structures, poured and vibrated to assure a monolithic structure free from infiltration. Typical requirements are shown in Standard Drawing 5030. Manufacturer shall submit shop drawings for OWNER approval. Construction joints with waterstops must be approved by the OWNER.

502.1.4.1.2. Precast. Precast manholes shall conform to the requirements of [Item 502.1.1.1](#). Precast Reinforced Concrete Manhole Sections. Typical requirements are shown in Standard Drawing 5020. The base shall be Class F or Class PF concrete as specified by the OWNER, in

conformance with [Item 702](#), Concrete Structures. The precast sections shall be of the bell-and-spigot design incorporating trapped O-ring gaskets in conjunction with premolded joint sealing compound, or tongue-and-groove with a premolded joint sealing compound (water or storm water). Wastewater precast sections shall be sealed using trapped O-rings gaskets in conjunction with premolded joint sealing compound. Premolded joint sealing compound may be used for water line manholes only when approved by the OWNER. Prior to placing each section of manhole riser or cone, the bells and spigots to be joined shall be thoroughly cleaned, the gasket properly placed, lubricated and the joint pushed home. Combination of joints shall be selected to minimize the number of individual segments. Long joints shall be used in the bottom and shorter segments utilized for top adjustments. Lift holes may be used but must be filled with a nonshrink grout after the section is in place. Precast manholes used in floodplains shall require sealed anchor design.

502.1.4.1.3. Fiberglass. Fiberglass manholes shall conform to the requirements of [Item 502.1.1.2](#), Fiberglass Manholes. The fiberglass portion of the manhole shall be delivered in one piece. Field jointing shall not be permitted. Fiberglass manholes shall be installed in accordance with the manufacturer's recommendation and with supplementary details, additions or exceptions as directed by the OWNER and/or as shown on the plans. Typical requirements are shown in Standard Drawing 5040. The base shall be Class F or Class PF reinforced concrete as required per [Item 702](#), Concrete Structures as specified by the OWNER. A minimum of 8 holes $\frac{5}{8}$ -in. in diameter shall be drilled equidistantly around the periphery of the manholes at a distance 4-in. from the bottom for use in inserting #4 reinforcing bars to be keyed into the concrete base to prevent the manhole from floating. All holes shall be sealed around the reinforcing steel to prevent leakage.

502.1.4.1.4. Drop. Drop manholes shall be constructed in accordance with details on the plans. Typical requirements are shown in Standard Drawings 5070 and 5080. The basic construction for drop manholes shall be identical to that described for standard manholes preceding with special provisions incorporated to provide drop piping and appurtenances as detailed.

502.1.4.1.5. Pressure Type. Pressure type manholes (sealed manholes) shall be constructed in accordance with Standard Drawing 5050 unless otherwise shown on the plans.

502.1.4.1.6. Standard Manhole. Standard manholes shall be constructed to the proper elevation as required and to a depth of at least 6-ft. above the invert of the main(s) or lateral(s) in the system.

502.1.4.1.7. Shallow Manhole. Shallow manholes shall be constructed for specific locations in a storm sewer system for depth less than 6-ft. when specifically designated on the project plans, or when so directed by the OWNER.

502.1.4.2. Vents. When specified, vents shall be constructed as shown in Standard Drawing 5060 unless the OWNER provides details for vent construction.

502.1.4.3. Invert. The invert of manholes shall be formed in a typical pattern regardless of the wall construction.

502.1.4.3.1. Flow Channel. When specified in the special provisions or in the plans, the pipe shall be laid through the manhole stations where possible, prior to concreting, so that the full depth of the pipe is embedded in concrete to form the flow channel.

502.1.4.3.2. Flow Channel Alternate. Where pipe cannot be used through the manhole due to intersecting flow channels, flow channels equivalent to the top of pipe shall be formed with concrete, then troweled to a smooth, even finish with a steel trowel.

502.1.4.3.3. Manhole Bench. The manhole bench from wall line to flow channels shall be sloped and troweled smooth on a grade of 1-in.-per-foot with a liberal radius applied at flow channel intercepts.

502.1.4.4. First Full Joint. The first full joint of pipe extending from the manhole shall be cradled in concrete to the pipe joint in the same pour as that for the manhole base slab as shown on the plans.

502.1.4.5. Grade Adjustment Risers. Installation of risers shall be shown on the plans. Grade risers and sealers shall be approved by the OWNER. Risers may be of concrete, polyethylene, metal, rubber or other materials meeting the requirements of [Item 502.1.2](#), Grade Adjustment Risers. The minimum

number of risers required of the type approved shall be used. The manhole and grade adjustment shall form a watertight assembly. Tapered adjustment risers shall be used to match road grade. The annular space between risers and cone basin, between risers and cover frame, and between multiple risers shall be sealed using an approved sealant. Butyl sealant shall be used for HDPE.

502.1.4.6. Covers. Manhole covers shall be detailed on the plans. Manhole covers of nominal 30-inch or larger diameter are required for all manholes where personnel entry is anticipated. Manholes located within the floodplain shall have gasketed, pressure-type lids and bolted covers, or have another means of preventing inflow.

Installation of covers shall be shown on the plans. For all manhole installations, the manhole covers shall be provided with pick slots or bars in lieu of pick holes. (Pickholes are allowed for stormdrain manholes.) If the rim elevation above surrounding ground is prohibited by land use or other reasons, a cover with a pick slot or bar as described for use in street locations shall be used.

502.1.4.7. Concrete Pad. A 5-ft. by 5-ft. square concrete pad shall be constructed as shown on the plans for manhole installation outside of paved areas.

502.1.4.8. Wastewater Manhole Frame Seals. All newly constructed Wastewater Manholes shall include an Internal Frame Seal as approved by OWNER. All costs for furnishing and installing the seal and extensions shall be included in the applicable Unit Price bid for Wastewater Manholes.

502.1.5. Manhole Testing. Manholes shall be tested by hydrostatic exfiltration or vacuum testing, or other method as approved by TCEQ and determined by the OWNER. Manholes shall be tested after installation with all connections (existing and/or proposed) in place. Drop-connections and gas sealing connections shall be installed prior to testing.

502.1.5.1. Exfiltration Testing Manholes. The rate of exfiltration for manhole testing shall not exceed 0.025-gallons per foot diameter per foot of manhole depth per hour. Alternative test methods shall ensure compliance with the above allowable leakage. Hydrostatic exfiltration testing shall be performed as follows: All wastewater lines coming into the manhole shall be sealed with an internal pipe plug, then the manhole shall be filled with water, and maintained full for at least 1-hour. For concrete manholes a wetting period of 24-hours may be used prior to testing in order to allow saturation of the concrete. If the manhole fails the hydrostatic test, the manhole shall be repaired and retested until it passes the test.

502.1.5.2. Vacuum Testing Manholes. Vacuum testing of manholes shall be performed by the CONTRACTOR in compliance with these specifications. All lift holes and exterior joints shall be plugged with a non-shrink grout. No grout shall be placed in horizontal joints prior to testing. All pipes entering the manhole shall be plugged. Stubouts, manhole boots, and pipe plugs shall be secured to prevent movement while the vacuum is drawn. A minimum 60-in./lb. torque wrench shall be used to tighten the external clamps that secure the test cover to the top of the manhole. The test head shall be placed at the inside of the top of the cone section, and the seal inflated in accordance with the manufacturer's recommendations. A vacuum of 10-inches-of-mercury (34-kPa) shall be drawn, and the vacuum pump shut off. With all valves closed, the time for the vacuum to drop to 9-inches-of-mercury (30-kPa) shall not be less than the time indicated in Table 502.1.5.2.(a) Vacuum Drop Minimum Time.

Table 502.1.5.2.(a) Vacuum Drop Minimum Time

Depth of MH (feet)	Manhole Diameter		
	48"	60"	72"
	Minimum Time Required for a Vacuum Drop of 1" Hg (min:sec)		
0 – 20	0:40	0:50	1:00
22	0:44	0:55	1:06
24	0:48	1:00	1:12
26	0:52	1:05	1:18
28	0:56	1:10	1:24
30	1:00	1:15	1:30
See note 1.	0:04	0:05	0:06

1. Additional 2-ft. depths, add indicated time for each 2-ft.

Manholes shall be accepted with relation to vacuum test requirements if they meet the criteria above. Any manhole that fails the initial test must be repaired with a non-shrink grout or other suitable material based on the material from which the manhole is constructed. The manhole shall be retested as described above until a successful test is made. After a successful test, the temporary plugs shall be removed.

502.1.6. Measurement and Payment of Manholes. Measurement and payment for manholes shall be on a per each basis and shall cover all costs for the structure complete in place as designed. Included shall be all excavation, castings, reinforcing steel, concrete, backfill, and other materials, and all appurtenances for a complete and functional unit.

Payment for grade adjustment for existing manholes shall be measured and paid per each manhole.

The payment for extra depth in excess of the basic manhole depth shall be made under a separate item of bid as defined herein. If a separate bid item is not established in the contract, there shall not be any payment for extra depth, and the manhole shall be paid for as per each regardless of the depth. Unless specified otherwise, only one bid item shall provide payment for extra depth of manhole structures in excess of the basic depth for all types of manholes under consideration. Such extra depth shall be allocated on the total depth of all manholes, excluding shallow manholes, specified for the project. Payment for extra depth of the various types of manholes shall be at a unit price bid per linear foot of additional depth, measured to the nearest $\frac{1}{10}$ ft. over the basic depth stipulated for the type manholes under bid. A standard manhole is 6-ft. deep measured from the top of the manhole cover to the flow line of the invert. A shallow manhole is less than 6-ft. deep as measured above.

The contract price shall be the total compensation for the furnishing of all labor, materials, tools, equipment and incidentals necessary to complete the work, including earth excavation, disposal of surplus materials and backfill, all in accordance with the plans and these specifications.

502.2. WASTEWATER MAIN CLEANOUTS AND ACCESS CHAMBERS

Cleanouts shall be constructed in accordance with the plans and these specifications for materials and construction.

502.2.1. Typical Cleanout. Typical cleanout requirements are shown in Standard Drawing 5110.

502.2.2. Access (Sampling) Chambers. An access chamber may be specified in a wastewater or storm drainage situation that requires access for maintenance and inspection equipment without human entry. Chamber may be used in lieu of cleanouts, dead-end manholes or sampling ports.

The chamber body shall be a one-piece, rotational molded polyethylene unit that is corrosion resistant, lightweight, and designed for use in traffic and non-traffic locations where sewer pipe is 6", 8", 10" or 12" in diameter. The chamber shall be adaptable to clay, cast iron, ductile iron, PVC, and/or concrete pipe through use of an eccentric coupling. Such coupling shall be provided with the chamber or recommended by the chamber manufacturer and readily obtainable.

502.2.2.1. Composition and Characteristics. The wastewater access chamber shall be rotational molded of 100% virgin, hexane-based, Linear Low Density Polyethylene meeting the minimum standards in Table 502.2.2.1.(a) Access Chamber Requirements.

Table 502.2.2.1.(a) Access Chamber Requirements

Characteristic	Test Method	Value
Density	ASTM D1505	0.936-grams/cm ³
Tensile Strength @ Yield	ASTM D638	2490-psi
Flexural Modulus	ASTM D790	87,000-psi
Heat Distortion @ 66psi Load	ASTM D648	151°F
Low Temp. Impact @ 125 mils Thick	ARM Std. (B)	45-ft.-lbs.
Environmental Stress Corrosion Cracking (ESCR), 100% Igepal	ASTM D1693	> 1000-Hours
Wall thickness	-	minimum 0.375"

Additionally, at minimum, size and dimensions shall be sufficient to accommodate insertion of 36" long, standard tractor type closed-circuit TV cameras and manufactured within a 0.50-inch tolerance of required dimensions. Chamber shall be manufactured with no seams or welds. Chamber interior shall be white or cream color for visibility. Bottom of chamber shall form a channel (invert) with minimal flow disruption. Top of chamber shall have capability of accepting 18" sewer pipe and gasket. Outlets and inlets shall be male (spigot) type extensions connecting to existing or new piping systems with eccentric reducing couplings. Spigot sizes of chamber shall be in accordance with ASTM D3034 Type PSM Poly(Vinyl Chloride) (PVC) Sewer Pipe and Fittings, SDR 35 Sewer Pipe sizing.

502.2.2.2. Access Chamber Installation. Installation shall conform to manufacturer recommendations, with supplemental requirements contained herein. Chamber assembly including lid shall be watertight. Appropriate flexible couplings shall be used between chamber coupling and pipe. Couplings shall be attached and sized prior to lowering chamber into trench. All gaskets including those included with lid shall be properly seated, and CONTRACTOR shall insure that gaskets are not rolled or twisted. Embedment (bedding and backfill) material as provided for surrounding pipe shall be provided for chamber compacted to a minimum 80% Proctor Density, unless the OWNER specifies otherwise. Embedment material shall be prevented from entering chamber.

Two 3" minimum thickness grade rings shall be included in the access chamber assembly. If standard manhole ring and cover is to be used, it shall be set on grade rings according to normal specified standards to meet local codes. If chamber is to be installed in backyard or easement location where it may be undesirable to have a manhole cover visible, the polyethylene, sealed lid of the chamber may be fitted with a non-ferrous metal disk. Once the disk is epoxy bonded to lid and covered with earth or other ground cover, the metal will allow the chamber to be located with a typical metal locator if access is required.

502.2.2.2.1. Installation on Existing Pipe. The OWNER may specify special conditions in addition to those listed above.

502.2.2.2.2. Installation in New Construction. In addition, installation in new construction shall also meet these provisions. Excavation shall be performed in accordance with [Item 201](#), Site Protection or [Item 701.2](#), Structural Removal, Excavation, and Backfill, as determined by the OWNER. The excavation shall provide a minimum of 6 in. outside the widest dimension of the chamber allowing enough space for installation workers to function. Normally, the trench width for the chamber will be no wider than the trench excavated for the pipe being laid. The chamber shall be lowered into trench and connected to pipe as the pipe is laid. Enough crushed stone shall be placed around the lower portion of the chamber to support it and prevent it from leaning.

502.2.3. Measurement and Payment of Cleanouts. Measurement and payment for cleanout structures shall be on a per each basis and shall cover all costs for the structure complete in place as designed.

Included shall be all excavation, castings, reinforcing steel, concrete, backfill, and other materials, and all appurtenances for a complete and functional unit.

Cleanouts shall not be measured and paid for according to depth.

The contract price shall be the total compensation for the furnishing of all labor, materials, tools, equipment and incidentals necessary to complete the work, including earth excavation, disposal of surplus materials and backfill, all in accordance with the plans and these specifications.

502.3. FIRE HYDRANTS

502.3.1. Materials. Fire hydrants which are to be installed as shown on the plans or to be furnished for general installation shall be dry-barrel traffic model that conform to AWWA C502 Standard for Dry-Barrel Fire Hydrants, except for changes and/or additions specified as follows or as shown on the plans or in the contract specifications. All hydrant components covered by NSF-61 must comply with NSF-61 requirements.

502.3.1.1. Supplementary Details Specified. The type of shut-off may be either of the following:

- (1) Compression type with the flow.
- (2) Compression type against the flow.

The valve action shall provide positive shut-off at minimum closing torque. Wedge action closing gates shall not be permitted, and the scissors type main valves shall not be permitted unless approved by the OWNER.

Inlet connection shall be mechanical joint unless otherwise specified and shall be for a 6-in. cast iron pipe with minimum net valve opening of 5¼-in. unless otherwise specified.

Delivery classification: number and size of pumper and hose nozzles shall be as shown on the plans and contract specifications.

Bury length: ground to bottom of connecting pipe shall be 4-feet or as specified by the OWNER.

Diameter outlet connections: hose and pumper nozzle threads shall be of the size and type shown on the plans.

Gaskets shall be furnished on all nozzle caps and shall be long life, black rubber meeting ASTM D2000, Classification System for Rubber Products in Automotive Applications, or equal.

Unless otherwise specified in the special provisions or in the plans, the operating and nozzle cap nuts shall be tapered pentagon nuts with faces not less than 1-in. high.

Drain valve and outlet: hydrants shall be equipped with a minimum of two drainholes and provided with an automatic and positively operating noncorrodible drain or dip valve so as to drain the hydrant completely when the main valve is shut.

Direction to open is to be specified in the contract specifications. Number of turns to open shall be in accordance with AWWA Standard C502.

The outside of the hydrant shall be thoroughly cleaned and thereafter painted in the shop with one coat of primer. After shop priming, a finish coat of colored paint as specified by OWNER shall be applied to the exterior above ground surfaces.

502.3.1.2. Breakable Type Hydrants. Breakable or Sleeve Type Couplings. The barrel of the hydrant between the base and the nozzle section must be made in two parts connected by a swivel flange or breakable flange which shall permit facing of the nozzles in any desired direction in increments of 45° or less. The complete hydrant shall be of such design that when the hydrant barrel is broken through traffic collision or otherwise, it may be replaced without disturbing the base of the hydrant.

The materials used for gaskets between the upper and lower barrels and the base and nozzle section shall be compounded to conform to ASTM D2000 or an equal material that shall have OWNER approval prior to substitution unless otherwise specified in the plans.

Provision shall be made in the design of the stem to disconnect the stem from the hydrant parts above the standpipe break point in the event of traffic accidents. Design of the coupling shall be such that when the coupling is broken, no parts shall come loose and fall into the hydrant barrel, and the break shall not occur through the pins or bolts holding the coupling to the stem.

502.3.1.3. Main Valve Seats. Main valve seats shall be of such design that incorrect positioning is impossible.

502.3.1.4. Nozzle Cap Chains. When required by the OWNER, the nozzle cap chains shall be in accordance with AWWA C502 Dry-Barrel Fire Hydrants.

502.3.1.5. Flanges. All flanges other than barrel flanges shall be equipped with mechanical joints. Gland bolts shall be high-strength, low-alloy, corrosion-resistant steel conforming to ASTM A325 Structural Bolts, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength, Type 3.

502.3.1.6. Operating Stems. The spindle of the operating stem and the stem nuts for hydrants having the operating threads located in the barrel or waterway shall be manganese bronze, Everdur or other high-quality noncorrodible metal. Barrel bolts and nuts shall meet the requirements of ASTM A307 Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.

All working parts in the waterway, except for sliding stem support mechanisms, shall be bronze-to-bronze or bronze-to-iron unless otherwise specified in the special provisions or in the plans.

502.3.1.7. O-Ring. Hydrant stem packing boxes, where needed, shall be provided with O-ring grooves and sealed with O-rings. O-rings shall be furnished in lieu of stem packing. They shall be of the double O-ring type designed so that the rubber rings shall move against a bronze, stainless steel or other noncorrodible metal surface. O-ring shall be in accordance with ASTM D2000, Classification System for Rubber Products in Automotive Applications.

502.3.1.8. Extensions. Fire hydrants shall be designed to accept a 6 in., 12 in. or 18 in. extension and no more than one extension and maximum of 18 in.

502.3.1.9. Hydrant Heads. The hydrant shall be constructed so that the nozzles may be faced in any desired direction.

502.3.1.10. Drawings. Proposals shall be accompanied by catalogue cuts, photographs or drawings in duplicate showing complete detailed dimensions of the hydrants when requested by the OWNER.

502.3.1.11. Upperstem Thread Lubrication. Upperstem thread lubrication may be accomplished with oil or grease. When oil is used, it shall be in conjunction with a functional oil reservoir and an oil filler port. The hydrant shall be factory filled with a USP white mineral oil such as Lubriplate No. 3-V (SAE 20), Mobile Whiterex 425 or equal. Means for field check of oil lubrication level shall be provided. When grease is used, the hydrant shall be factory lubricated with a food grade grease such as Lubriplate No. 630-AA (medium soft), or equal. Means for field lubrication without disassembly shall be provided.

502.3.1.12. Tests and Affidavit of Compliance. Manufacturers shall be required to furnish the OWNER certificate of compliance with AWWA C502 and this specification.

Technical manufacturing drawings or certificate of tests relating to fire hydrants for contract installation must be supplied by the CONTRACTOR to OWNER not later than two weeks after beginning construction when identical hydrants have previously been approved by the OWNER, or prior to installation when identical hydrants have not previously been approved by the OWNER. Technical manufacturing drawings or certificate of tests must be supplied for all hydrants purchased by the OWNER. Technical drawings or certificates shall have the OWNER'S approval before final payment shall be made.

502.3.1.13. Sample Hydrant. The OWNER may purchase one sample hydrant for verification of compliance with these and manufacturer's specifications. The OWNER may test this sample; and, if it fails to meet any of the specifications, the hydrant shall be returned to CONTRACTOR at CONTRACTOR'S expense. CONTRACTOR shall refund to the OWNER the full purchase price of the hydrant.

502.3.1.14. Rejection. Fire hydrants or materials specified in this section may be rejected for failure to meet any of the provisions of this specification or for any defects causing them to be unsuitable for their intended use.

502.3.2. Installation. Fire hydrants shall be installed as shown in Standard Drawing 4120, on the appurtenance sheets or as directed by the OWNER.

Set fire hydrant on the lot line extended when possible. The horizontal center of the hydrant shall be placed not less than 3-feet and not more than 8-feet from the back of the nearest curb or edge of pavement no closer than 18-inches to existing or proposed sidewalks, and located at least 1-foot outside of the area

between the Points of Curvature of the corner turning radii at intersections unless otherwise indicated on the plans.

The hydrant shall set truly vertical and be securely braced and blocked on well-compacted or undisturbed soil surrounded by a minimum of 7-CF clean gravel or stone to permit free draining of the hydrant, with the large pumper nozzle facing the nearest curb.

Fire hydrants shall be braced and blocked on a Class B or Class PB concrete per [Item 702](#). Concrete Structures, or as specified by the OWNER. Concrete slab shall not be less than 4-in thick and not less than 3-ft. by 3-ft. square buried to a depth between 6- and 12-inches below finished grade. A splash pad that extends to the sidewalk, or to curb in the absence of a sidewalk, shall be installed if directed by the OWNER. Hydrant shall be set perpendicular with the pumper nozzle facing the nearest curb, and to a depth such that the center of the nozzle is between 18- and 28-inches from the top of finished grade.

Any adjustment needed after installation shall be made by the CONTRACTOR without extra compensation.

502.3.3. Measurement and Payment. Fire hydrants shall be paid for at the contract unit price per each, complete in place, as provided in the proposal and contract. The contract price shall be the total compensation for the furnishing of all labor, material, tools, equipment, hydrant extensions, concrete, gravel drains, paint or protective coating and incidentals necessary to complete the work.

The hydrant lead shall be paid for at the unit price bid for installing pipe. The gate valve and box installed in leads shall be paid for at the unit price bid for installing gate valves and boxes, or as specified by OWNER.

Fire hydrant extensions shall be paid for at the unit price bid per foot if a separate pay item is established in the contract.

Refer to Standard Drawing 4120.

502.4. THRUST RESTRAINT

Each change in direction of a pressure conduit, fittings, and plugs in pressure conduits shall be restrained in such a manner as shall substantially brace the same against undisturbed trench walls. Type of thrust restraint shall be as specified on the plans.

502.4.1. Concrete Blocking. Standard thrust blocking shall conform to appropriate details and tables of Standard Drawings 4010A through 4040. Special blocking shall be accomplished with Class B or Class PB concrete per [Item 702](#). Concrete Structures, or as specified by the OWNER and as detailed on the appurtenance sheet or as detailed on the plans.

502.4.2. Mechanical Joint Restraint. Mechanical joint restraint may be used on ductile iron or PVC pipe. Installation shall follow manufacturer's recommendations.

Restraining mechanisms for PVC pipe and fittings shall be tested and pressure rated in accordance with ASTM F1674 Standard Test Method for Joint Restraint Products for Use with PVC Pipe.

502.4.2.1. Ring and Wedging. Ring and wedging mechanical joint restraint shall be incorporated into the design of the follower gland. The restraint shall be sized and selected for material compatibility according to manufacturer's instructions. The restraining mechanism shall consist of individually actuated wedges that increase their resistance to pull-out as pressure or external forces increase. The device shall be capable of full mechanical joint deflection during assembly and the flexibility of the joint shall be maintained after burial. The joint restraint ring and its wedging components shall be of grade 60-42-10 ductile iron conforming to ASTM A536 Ductile Iron Castings. The wedges shall be ductile iron heat treated to a minimum hardness of 370 BHN. Dimensions of the gland shall be such that it can be used with the standardized mechanical joint bell conforming to AWWA C111 Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings and AWWA C153 Ductile-Iron Compact Fittings for Water Service. Torque limiting twist-off nuts shall be used to insure proper actuation of the restraining wedges. Necessary spacers, gaskets and bolts shall be supplied by the manufacturer of ring and wedging restraint. Ring and wedging shall be coated as specified for pipe and fittings.

Restraint for nominal pipe sizes greater than 48-inches shall be engineered.

502.4.2.2. Integrally Restrained Mechanical Joints. In addition to specifications for Ductile Iron fittings in [Item 501.7](#). Ductile-Iron Pressure Pipe and Fittings or [Item 501.14](#). Polyvinyl Chloride (PVC)

Water Pipe, integrally restrained mechanical joints shall conform to the applicable provisions of the standards listed in Table 502.4.2.2.(a) Integrally Restrained Mechanical Joint Standards.

Table 502.4.2.2.(a) Integrally Restrained Mechanical Joint Standards

Standard	Topic
AWWA C111	Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings
AWWA C116	Protective Fusion-Bonded Epoxy Coatings for the Interior and Exterior Surfaces of Ductile-Iron and Gray-Iron Fittings for Water Supply Service
ASTM D3139	Joints for Plastic Pressure Pipes Using Flexible Elastomeric Seals
ASTM F477	Elastomeric Seals (Gaskets) for Joining Plastic Pipe

502.4.3. Welding. Reinforced Concrete Cylinder Pipe (RCCP) may be internally or externally welded, as specified by the OWNER, according to manufacturer criteria in conformance with appropriate AWWA Standards.

502.4.4. Measurement and Payment. No separate payment shall be made for restraint, unless specified otherwise by the OWNER.

502.5. FITTINGS

502.5.1. Brass Stops, Cocks, and Fittings for Waterworks Service.

502.5.1.1. General. Stops, cocks, and other fittings furnished under these specifications shall be in accordance with AWWA C800 Standards for Underground Service Line Valves and Fittings of the size and type specified, except cast solder-joint fittings shall conform to alloy 83-4-6-7, ASTM B584 Practice for Copper Alloy Sand Castings for General Applications. All stops, cocks and fittings shall be full size throughout the size specified.

502.5.1.2. Physicals. Any pipe, fitting, solder or flux used in the installation or repair of any public water system shall be lead-free. For the purpose of these Specifications, the term 'lead free' means (1) Not containing more than 0.2 percent lead when used with respect to solder and flux; and (2) Not more than a weighted average of 0.25 percent lead when used with respect to the wetted surfaces of pipes, pipe fittings, plumbing fittings, and fixtures.

The weighted average lead content of a pipe, pipe fitting, plumbing fitting, or fixture shall be calculated by using the following formula: For each wetted component, the percentage of lead in the component shall be multiplied by the ratio of the wetted surface area of that component to the total wetted surface area of the entire product to arrive at the weighted percentage of lead of the component. The weighted percentage of lead of each wetted component shall be added together, and the sum of these weighted percentages shall constitute the weighted average lead content of the product. The lead content of the material used to produce wetted components shall be used to determine compliance. For lead content of materials that are provided as a range, the maximum content of the range shall be used.

Brass used shall have a tensile strength (as determined from test bars) of not less than 30,000-psi when tested as prescribed by ASTM B208 Practice for Preparing Tension Test Specimens for Copper-Base Alloys for Sand, Permanent Mold, Centrifugal, and Continuous Castings (Fig. 5).

Fittings shall be designed for 200-psi working pressure and, when subjected to hydrostatic test pressures $1\frac{1}{2}$ times working pressure or when subjected to a minimum of 85-psi air pressure while submerged in water, shall not leak or show signs of structural failure.

Stops and cocks containing brass parts shall be shipped prelubricated with a light fluid lubricant between key and body. Lubricant shall remain fluid indefinitely, either in storage or in service.

502.5.1.3. Design Features of Stops and Cocks. Seating surfaces of the ground key type shall be tapered and shall be accurately fitted together by turning the key and reaming the body. Seating surfaces shall be lapped together using suitable abrasives to insure accurate fit. The large end to the tapered surface of the key shall be reduced in diameter for a distance that shall bring the largest end of the seating surface of the key into the largest diameter of the seating surface of the body, and the taper

seat in the body shall be relieved on the small end, so that the small end of the key may extend through to prevent wearing of a shoulder and to facilitate proper seating of the key. The stem end of the key, key nut and washer shall be so designed that if the key nut is tightened to failure point, the stem of the key shall not fracture. The nut and the stem shall withstand a torque on the nut of at least three-times the necessary effort to properly seat the key without failure in any manner.

The ball stop shall have a full-size round-way opening with straight-through flow, teflon coated bronze ball with a minimum of 0.5-mil thickness coating. The stop must be so constructed that it may be disassembled and the ball removed without special tools.

Plug type stop shall have full size round way opening with straight-through flow. Seating surfaces shall be brass (or teflon coated brass) to rubber O-rings, providing positive pressure seal without mechanical means. The stop must be so constructed that the plug may be removed without special tools. Rubber O-rings should conform to requirements of ASTM D2000 Classification System for Rubber Products in Automotive Applications and test method shall conform to ASTM D1414 for Test Methods for Rubber O-Rings.

Inlet and outlet threads, of the types specified, shall conform to the applicable tables of AWWA Standard C300 Reinforced Concrete Pressure Pipe, Steel-Cylinder Type, and inlet threads shall be protected in shipment by a plastic coating or other equally satisfactory means. If used, coupling nuts shall have a bearing skirt machined to fit the outside diameter of the pipe for a length at least equal to the outside of the pipe.

Corporation stops shall be so designed as to rotate about the axis of the flow passageway within a circle of rotation small enough to properly clear the inside of any standard tapping machine of appropriate size.

The outlet side of ¾-in. brass curb stops shall be female iron pipe with flared copper pipe, compression or female iron pipe thread on the inlet, as specified. The outlet side of 1-in., 1½-in. and 2-in. brass curb stops shall be female iron pipe with compression, streamline or female iron pipe thread on the inlet, as specified.

The outlet side of ¾-in. and 1-in. corporation stops shall be flared copper pipe or compression with male AWWA “tapered” thread or male iron pipe thread on inlet side, as specified. The outlet side of 1½-in. and 2-in. corporation stops shall be compression or streamline with male AWWA “tapered” thread or male iron pipe thread on inlet side, as specified.

502.5.1.4. Design Features of Fittings. All castings shall be smooth, free from burrs, scales, sand holes and defects of every nature which would make them unfit for the use for which they are intended.

Nuts shall be smooth cast and shall have symmetrical hexagonal wrench flats.

Flare-joint fittings shall be smooth cast. Seating surfaces for metal-to-metal seal shall be machined to proper taper or curve, free from any pits or protrusions.

Solder-joint fittings shall be smooth cast. Inside surfaces of solder-joint ends shall be machined smooth to proper inside diameter.

All thread fittings, of all types, shall have N.P.T. threads, and male threaded ends shall be protected in shipment by a plastic coating or other equally satisfactory means.

Compression tube fittings shall have a Buna-N beveled gasket or equal. Compression nut shall have:

- (1) for plastic or copper pipe and tubing, an approved restraining device.
- (2) for iron pipe, a stainless steel set screw to bite in and lock on the pipe.

502.5.1.5. Tests. All brass stops, cocks and fittings included in this section shall be tested in accordance with the applicable provisions of the specifications relating thereto.

502.5.1.6. Rejection. Brass stops, cocks, and fittings may be rejected for failure to meet any of the requirements of this specification.

502.5.2. All Other Fittings. All other fittings shall conform to respective provisions of [Item 501](#), Underground Conduit Materials, listed according to conduit type. In water pipe, Ductile Iron or Ductile Iron Compact fittings shall consist of standard crosses, tees, bends, reducers, sleeves, plugs, blind flanges, etc. Fittings for reinforced concrete pressure pipe, steel cylinder type, shall consist of special crosses, tees, bends, reducers, dished plugs, closure sections, flanged outlets, blind flanges, bored flanges, etc.

502.5.3. Measurement and Payment. Payment for fittings shall be made only if a separate bid item is established in the Contract. If a separate bid item is not established, the fittings shall be included in the price of the pipe bid item.

Ductile Iron and Ductile Iron Compact Fittings shall be measured for payment per ton if a separate bid item is established in the Contract. Special fittings for reinforced concrete pressure pipe, steel cylinder type, shall be measured for payment per each, grouped as to size and kind. Fittings that are an integral part of a special item, such as a bored flange in an air valve installation, shall not be measured for payment per each, but shall be included in the contract unit price for that special item.

502.6. VALVES

502.6.1. Metal Seated Gate Valves for Ordinary Waterworks Service.

502.6.1.1. General Description. All gate valves 3-in. through 48-in. shall conform to AWWA Standards C500 Metal-Seated Gate Valves for Water Supply Service, except for changes or specified alternatives as detailed in this specification or as shown on the plans and contract documents. Materials must comply with NSF Standard 61 – Drinking Water System Components – Health Effects. Tests and design data may be as designated on the plans and contract specifications.

Valves over 16-in. in diameter shall be installed in a special vault, as indicated in appropriate Division 4000 Standard Drawings, or the gear box shall be enclosed in a manhole and supported on a concrete pad. Smaller valves shall be supported with concrete, all as detailed in appurtenance sheets attached to the plans.

Gate valves larger than 48-in. shall be a special consideration. The OWNER shall hydrostatically test all gate valves larger than 48-in. for a reasonable period after receipt of a specified test pressure.

All gate valves shall be iron body, bronze mounted, double disc, parallel seat, nonrising stem, internal wedging type. Valves must embody the best workmanship and finish. Valve design shall provide minimum torque designs effectively reducing friction and drag through thrust collar design and tracks for gates.

502.6.1.2. Bonnet Bolting. Body bolts, studs and nuts shall be 304 stainless steel.

502.6.1.3. Ends. Valves shall have flanged, push-on, or mechanical-joint ends, or any combination of these as may be specified.

Mechanical-joint ends shall conform to AWWA C111 (ANSI A21.11) American National Standard for Rubber-Gasket Joints for Ductile-Iron and Gray-Iron Pressure Pipe and Fittings. Push-on joint ends shall conform to AWWA C111 (ANSI A21.11). Flanged ends shall conform to AWWA C110 (ANSI A21.10) American National Standard for Gray-Iron and Ductile-Iron Fittings, 3 In. through 48 In. for Water and Other Liquids, Class 125-lb. Bolts and nuts for mechanical joints shall be of a high-strength, low-alloy corrosion-resistant steel conforming to ASTM A325 (A325M) High-Strength Bolts for Structural Steel Joints (Type 3). All mechanical-joint glands shall be ductile iron.

502.6.1.4. Gates and Rings. Gates and rings shall conform to AWWA Standards C500 except as follows: All gates above 4-in. shall be cast iron with bronze-gate rings, and 4-in. gates may be solid bronze. Gates 3-in. and smaller shall be solid bronze.

502.6.1.5. Wedging Device. Wedging devices shall conform to the requirements of AWWA C500, except as follows: Gate valves 4-in. and smaller shall have solid bronze wedges. Wedges for valves above 4-in. may be solid bronze or cast-iron with an integral bronze nut. Wedging surfaces may be bronze, monel, or stainless steel cast integral with the wedge. Stem nuts or wedging surfaces that are attached with fasteners are not acceptable. Wedging surfaces on valves up to 16-in. shall be bronze-, monel-, or stainless-steel-to-iron. Wedging surfaces on valves 16-in. and larger shall be bronze-to-bronze, monel-to-monel, or stainless-to-stainless. Other moving surfaces integral to the wedging action shall be bronze to iron.

502.6.1.6. Rollers and Tracks and Scrapers for Horizontal Valves. Rollers and tracks and scrapers for horizontal valves shall conform to AWWA Standards C500, with the following exception: Babbitt tracks shall not be acceptable.

502.6.1.7. Valve Stems and Nuts. Stem and nuts shall be in accordance with AWWA Standards C500, except as follows: Stem nuts shall be of a nongalling, high-grade brass or bronze and shall have threads of sufficient length to develop the full strength of the stem. Stems as received shall meet the minimum strengths as specified. Upset stems on valves larger than 16-in. shall not be permitted under these specifications. Upset stems shall conform to the requirements of AWWA C500.

502.6.1.8. Stuffing Boxes. Stuffing boxes shall conform to the requirements of AWWA Standards C500 with the following exceptions: All valves 2-in. through 16-in. shall be equipped with double O-rings, provided arrangement is made for replacement under pressure of the upper O-ring when the valve is fully open. All geared valves shall be equipped with double O-rings in the main stuffing box. All horizontal valves shall have attached stuffing boxes as per the above AWWA Standards. Stuffing box bolts and nuts shall be 304 stainless steel.

502.6.1.9. Follower Glands and Gland Bolts and Nuts. Glands, gland bolts and nuts shall conform to the requirements of AWWA Standards C500 with the following exceptions: Gland flanges or followers that are a separate part may be cast iron or bronze. Glands for valves over 12-in. in diameter shall be solid bronze or cast-iron bronze bushed. Gland bolts and nuts shall be either bronze or Type 302 stainless steel. For either choice both bolts and nuts shall be of the same material.

502.6.1.10. Hand Wheels and Operating Nuts. All valves 2-in. in diameter and above shall be nut operated unless otherwise ordered. All operating nuts shall be ductile iron or cast iron. Handwheels shall be furnished only when called for on plans or in the contract specifications. All valves shall open by turning counterclockwise or as specified by OWNER.

502.6.1.11. Gearing. Gearing shall be in accordance with AWWA C500. Spur or bevel gearing as called for on the plans or as applicable shall be provided on all valves 18-in. in diameter and larger.

502.6.1.12. Gear Cases. Gear cases shall be furnished on all geared valves. All geared valves shall be equipped with extended type gear cases, with cast iron side plates. Stuffing boxes shall be located on top of the bonnet and shall be outside the gear case. Gear cases shall be lubricated and enclosed with oil seal or O-ring at all shaft openings to prevent the entrance of water which may be in the manhole or vault. Valves equipped with ball or roller type thrust bearings inside the grease case shall have all shaft openings sealed with double O-rings. Gear cases shall be cast iron.

502.6.1.13. Bypass Valves. Bypass valves shall conform to the requirements of AWWA C500 with the following exceptions: Bypass valves are required on all 18-in. valves and larger AWWA C500 valves. Properties, construction and design requirements herein specified are applicable to bypass valves, except stems on bypass valves over 4-in. shall have the same physical qualities as for 30-in. and larger.

502.6.1.14. Cast Iron. All gray cast iron shall conform to the requirements of ASTM A126 Gray Iron Castings for Valves, Flanges, and Pipe Fittings, Class B or ductile iron shall conform to ASTM A536 Ductile Iron Castings.

502.6.1.15. Horizontal Valves. All valves over 16-in. in diameter shall be designated for horizontal installation in a horizontal pipeline unless shown otherwise on the plans. All other valves shall be vertical.

502.6.1.16. Valves for Installation in Vertical Pipeline. Valves 14-in. and larger AWWA C500 valves ordered for installation in vertical pipeline shall be equipped with disc face tracks and wedge springs to prevent pre-wedging. Valves 4-in. through 12-in. shall be double disc, square-bottom valves.

502.6.1.17. Tapping Valves. Tapping valves shall conform to the requirements of AWWA C500, and the other requirements of this section with the following exceptions: Tapping valves shall have oversize seat rings to permit entry of standard tapping machine cutters. In the open position, valve gates shall be clear of the ports so that the cutter shall pass through without making contact with the gates. Valves shall have an inlet flange conforming to AWWA C110 (ANSI A21.10) Class 125, with a machined projection to mate with tapping sleeve outlet flange recess to assure correct alignment. This alignment ring shall comply with MSS Standard SP-60 Connecting Flange Joint Between Tapping Sleeves and Tapping Valves. Valves shall have standard mechanical joint outlet and shall fit any standard tapping machine.

502.6.1.18. Tests and Inspection. All valves shall be tested by the manufacturer in accordance with AWWA C500. Any leaking at the test pressure through any casting or between the bronze ring and the cast iron body shall cause the said casting to be rejected. No plugging or patching to stop any leakage shall be allowed.

When requested at any time, notarized certificates of material and test compliance for these valves shall be provided. Such reports furnished shall be identified by purchase order or contract. The material shall also be identified as to location within the valve and specification or composition.

502.6.2. Resilient-Seated Gate Valves for Ordinary Waterworks Service.

502.6.2.1. General Description. All gate valves 3-in. through 36-in. shall conform to AWWA Standards C515 for Reduced-Wall, Resilient-Seated Gate Valves for Water Supply Service, or C509 for Resilient-Seated Gate Valves for Water-Supply Service, except for changes or specified alternatives as detailed in this specification or as shown on the plans and contract documents. Materials must comply with NSF Standard 61 – Drinking Water System Components – Health Effects. Tests and design data may be as designated on the plans and contract specifications.

Gate valves larger than 36-in. shall be a special consideration. The OWNER shall hydrostatically test all gate valves larger than 36-in. for a reasonable period after receipt.

All gate valves shall be iron body, resilient seated, nonrising bronze stem and bronze stem nut. Valves must have the resilient seat bonded and vulcanized to the wedge and employ the best workmanship and finish. Valve design shall provide minimum torque designs effectively reducing friction and drag through thrust collar design and guide tracks for the gate.

502.6.2.2. Bonnet Bolting. Bonnet Bolting shall conform to [Item 502.6.1.2](#). Bonnet Bolting.

502.6.2.3. Ends. Ends shall conform to [Item 502.6.1.3](#). Ends.

502.6.2.4. Gate. Gate shall be encapsulated with an elastomer that meets all requirements of AWWA C515 or C509. The bonding of the rubber to the gate shall meet the requirements of ASTM D429, Test Method A or Method B. Gates 3-in. and smaller shall be rubber encapsulated bronze.

502.6.2.5. Valve Stems and Nuts. Stem and nuts shall be in accordance with AWWA Standards C515 or C509 except as follows: Stem nuts shall be of a nongalling, high-grade brass or bronze and shall have threads of sufficient length to develop the full strength of the stem. Stems as received shall meet the minimum strengths as specified. Upset stems on valves larger than 16-in. shall not be permitted under these specifications.

502.6.2.6. Stuffing Boxes. Stuffing boxes shall conform to the requirements of AWWA Standards C515 or C509 with the following exceptions: Arrangement is made for replacement under pressure of the upper O-ring when the valve is fully open. All geared valves shall be equipped with double o-rings in the main stuffing box. All horizontal valves shall have attached stuffing boxes as per the above AWWA Standards.

502.6.2.7. Follower Glands and Gland Bolts and Nuts. Glands, gland bolts and nuts shall conform to the requirements of AWWA Standards C515 or C509 with the following exceptions: Gland flanges or followers, if used, that are a separate part may be cast iron or bronze. Glands for valves over 12-in. in diameter shall be solid bronze or cast-iron bronze bushed. Gland bolts and nuts shall be either bronze or Type 302 stainless steel. For either choice both bolts and nuts shall be of the same material.

502.6.2.8. Hand Wheels and Operating Nuts. Hand wheels and operating nuts shall conform to [Item 502.6.1.10](#).

502.6.2.9. Gearing. Gearing shall be in accordance with AWWA Standards C515 or C509. Spur or bevel gearing as called for on the plans or as applicable shall be provided on all valves 18-in. in diameter and larger.

502.6.2.10. Gear Cases. Gear cases shall be furnished on all geared valves. Gear cases shall be lubricated and enclosed with oil seal or O-ring at all shaft openings to prevent the entrance of water which may be in the manhole or vault. Valves equipped with ball or roller type thrust bearings inside the grease case shall have all shaft openings sealed with double O-rings. Gear cases shall be gray iron or ductile iron.

502.6.2.11. Bypass Valves. Bypass valves are not required on resilient seated gate valves.

502.6.2.12. Cast Iron. Cast iron shall conform to [Item 502.6.1.14.](#)

502.6.2.13. Horizontal Valves. Valves for horizontal installation shall be equipped with wedge guide caps or inserts to guide and support the wedge during travel. All valves over 16-in. in diameter shall be designated for horizontal installation in a horizontal pipeline unless shown otherwise on the plans. All other valves shall be vertical.

502.6.2.14. Valves for Installation in Vertical Pipeline. All resilient seated gate valves shall be suitable for horizontal mounting in a vertical pipeline without special modifications.

502.6.2.15. Tapping Valves. Tapping valves shall conform to the requirements of AWWA Standards C515 or C509 and the other requirements of this section with the following exceptions: Tapping valves shall have a port opening to permit entry of standard tapping machine cutters. In the open position, valve gates shall be clear of the ports so that the cutter shall pass through without making contact with the gate. Valves shall have an inlet flange conforming to AWWA C110 (ANSI A21.10) Class 125, with a machined projection to mate with tapping sleeve outlet flange to assure correct alignment. This alignment ring shall comply with MSS Standard SP-60 Connecting Flange Joint Between Tapping Sleeves and Tapping Valves. Valves shall have standard mechanical joint outlet and shall fit any standard tapping machine.

502.6.2.16. Tests and Inspection. All valves shall be tested by the manufacturer in accordance with AWWA Standards C515 or C509. Any leaking at the test pressure through any casting shall cause the said casting to be rejected. No plugging or patching to stop any leakage shall be allowed.

When requested at any time, notarized certificates of material and test compliance for these valves shall be provided. Such reports furnished shall be identified by purchase order or contract. The material shall also be identified as to location within the valve and specification or composition.

502.6.3. Air Valves.

502.6.3.1. General. Unless otherwise indicated in the plans or contract specifications, air valves shall meet the requirements of AWWA C512 Air Release, Air/Vacuum and Combination Air Valves for Water Works Service with exceptions specified herein. Only wastewater air valves shall be used for wastewater applications.

502.6.3.2. Description. Air valves shall be of two types as follows:

- (1) An air valve called for on the plans shall mean an air and vacuum valve of the ball type designed to permit the escape of air from a pipeline when the line is being filled and to permit air to enter the pipeline when the line is being emptied.
- (2) A combination air valve called for on the plans shall mean a combination air and vacuum and air release valve designed to fulfill the functions of air and vacuum valve and also designed to permit the escape of air accumulated in the line at the high point when the line is under pressure while in operation. Air valves 3-in. and smaller shall be self-contained in one unit. Air valves larger than 3-in. may be a combination of two valves.

502.6.3.3. Material. The valves shall be stainless steel or iron body, stainless steel, brass or bronze fulcrum levers and links, stainless steel ball floats and pins, steel flange bolts and nuts, Buna-N synthetic rubber seats or equal against bronze or stainless steel, and brass for other parts.

502.6.3.4. Inlets and Outlets. Inlets shall be threaded for 2-in. and smaller and flanged for 3-in. and larger. Outlets shall be threaded through 4-in.

502.6.3.5. Operating Pressure and Testing. The valves shall be designed to operate under an operating pressure of 200-psi and shall be tested to 1½ times that pressure.

502.6.4. Brass Wheel Valves.

502.6.4.1. General. Valves furnished under this specification shall be wedge disc, non-rising stem gate valves with threaded ends. They shall be equipped with bronze hand wheels and nuts and shall have bronze packing gland followers. They shall be of all brass and/or bronze construction.

502.6.4.2. Pressure Rating. Valves shall be rated for 125-psi saturated steam working pressure and 200-psi for liquids and gases up to 150°F.

502.6.4.3. Tests. Each valve furnished under these specifications shall be tested at a hydrostatic pressure of 250-psi with the valve open. Under this test the valve shall not show any indication of leakage at the packing or anywhere on the body. Each valve shall also be tested at hydrostatic pressure of 250-psi applied to one end only with the valve closed. There shall be no indication of leakage by the gate or through the packing under this test.

502.6.4.4. Direction to Open. Valve shall open by turning the handwheel counterclockwise.

502.6.4.5. Material Specifications. The materials used in the manufacture of these valves shall equal or exceed the specifications shown in Table 502.6.4.5.(a) Brass Wheel Valve Materials.

Table 502.6.4.5.(a) Brass Wheel Valve Materials

Part	Material	Designation/Specification
Packing	Teflon impregnated asbestos or approved equal	
Body	Bronze	ASTM B62 Standard Specification for Composition Bronze or Ounce Metal Castings
Bonnet	Bronze	ASTM B62
Gates	Bronze	ASTM B62
Handwheel	Bronze	ASTM B62
Handwheel Nut	Bronze	ASTM B62
Gland & Packing Nut	Lead-free Brass	ASTM B16/B16M Standard Specification for Free-Cutting Brass Rod, Bar and Shapes for Use in Screw Machines
Stem	Bronze	ASTM B62, 50,000-psi minimum tensile strength

502.6.4.6. Stem. Stem shall be completely free of visible flaw, and matching shall be smooth and free of defect. A back seating surface shall be provided on the wedge or on the lifting nut to seat tightly against the bonnet when the valve is open to seal the packing gland against line pressure so that the valve may be repacked against line pressure.

502.6.4.7. Threaded Ends. Valve ends shall be threaded internally with American National Taper pipe threads. Thread shall be clean, smooth, true to form and concentric with the axis of the valve. Variations in alignment of thread shall not exceed $\frac{1}{16}$ -in.-per-foot. Thread shall be chamfered approximately to the major diameter of the thread at the face of the valve at an angle approximately 45° with the axis of the thread for the purpose of easy entrance in making a joint and for protection of the thread.

502.6.4.8. Valve Body. The body of the valve shall offer sufficient support to the gate while it is moving to keep the gate wedge in place and to accurately align the gate on the body seat. The waterway opening shall be equal to or greater than the nominal pipe size.

502.6.4.9. Gate. The gate shall be of wedge design and may be furnished either solid or two-piece. Two-piece or "split" disc gates shall be equipped with lifting nut. Gate faces shall be accurately machined and fitted into the valve body in such a manner that the center of the gate circle is very slightly above the center of the seat circle when the valve is tightly closed.

502.6.4.10. Workmanship. All valve parts shall be true to form, free from injurious defects and shall be seated and finished in a workmanlike manner. Casting shall be free from blow holes, porosity, hard spots, excessive shrinkage, cracks or other injurious defects. They shall be smooth and well cleaned both inside and outside, and all fins and similar roughness shall be removed. Castings shall not be repaired, plugged, brazed or burned in.

502.6.4.11. Packaging. Valve shall be closed for shipment and wrapped or packaged in accordance with best commercial practice as necessary for mechanical protection and ease in handling.

502.6.5. Butterfly Valves.

502.6.5.1. General. Butterfly valves and actuators shall conform to AWWA C504 Rubber-Seated Butterfly Valves and to these specifications:

- (1) Type of body shall be short body, flanged.
- (2) Body material shall be cast iron or ductile iron.
- (3) Class shall be as specified on the plans or contract specifications.
- (4) Shafts shall be Type 304 or 316 stainless steel.
- (5) Flange holes shall be drilled full size.
- (6) Valve seats shall be natural rubber or Buna-N and polished stainless steel, Type 304 or 316, 90° seating angle only, with a 360° uninterrupted seating surface.
- (7) Shaft seals shall be standard split-V packing or double O-ring seal cartridges.
- (8) Discs shall be ductile iron, cast iron, or fabricated steel.
- (9) Operating nuts shall be ductile iron.

502.6.5.2. Submittals. The following shall be furnished to the OWNER. Incomplete data shall be cause for rejection of bid.

- (1) Weights and drawings in accordance with AWWA C504.
- (2) Guaranteed delivery time after receipt of purchase order.
- (3) Number of turns of handwheel required to close valve.
- (4) The required actuator torque (To) in foot-pounds for each butterfly valve based on the specified operating conditions of pressure and flows.
- (5) Seating-unseating torque (To) in foot-pounds required for each butterfly valve.
- (6) Rated torque capability of each butterfly valve actuator.

The following data shall be furnished if not previously available to the OWNER:

- (7) Experience: evidence of at least five years satisfactory experience building butterfly valves to AWWA Standards.
- (8) Torque tests in accordance with rubber seated butterfly valves AWWA C504.
- (9) Proof of design tests in accordance with AWWA C504.

502.6.5.3. Ends. Valves shall have flanged ends. Flanged ends shall conform to AWWA C110 (ANSI A 21.10), Class 250-lb.

502.6.5.4. Actuators.**502.6.5.4.1. Manual Actuators.**

Location. All actuators shall be located at the right end of a horizontal shaft with the input shaft vertical and upward looking in the direction of flow, unless otherwise noted.

Closure. The valve shall close by turning the input shaft clockwise. All handwheels shall turn clockwise to close the valve. All operators shall be equipped with a disc position indicator with each valve. The indicator shall be highly visible, clearly showing the legends "Open" and "Closed" at the ends of a 90° arc, with a pointer to show the disc position (Closed — 0° and Open — 90°). The arc shall be graduated in degrees.

Type. All manual actuators shall be totally enclosed worm gear type and traveling-nut type. All manual worm gear type actuators shall be Limitorque, Type HBC or approved equal.

Sizing. Each valve actuator shall be sized for the maximum valve torque requirements based on the operating pressures and flow rates as specified.

502.6.5.4.2. Electric Motor Actuator. Each electric actuator shall conform to AWWA C504 and shall be of sufficient size to open and close the valve against maximum differential pressure and maximum required torque conditions when voltage at motor terminals is 90-percent of nominal voltage and shall have totally enclosed worm gear reducer with spur gear attached. Limit switches shall be of the four train gear with switches adjustable to operate at any point in the opening or closing cycle of the valve.

Limit switches and torque switches shall be located in a special compartment that is an integral part of the actuator and shall be readily accessible. Each limit switch shall have two normal closed contacts. Limit switch gearing shall be in step at all times whether in power or manual operation.

Limit switch gearing shall be stainless steel or high-grade bronze. Two torque switches shall be furnished, one for opening direction and one for closing direction. The torque switches shall be connected in series so that they will operate regardless of the phasing of the power.

Torque and thrust loads in both closing and opening directions shall be limited by torque switches. Each torque switch shall be provided with a micrometer adjustment and reference setting indicator. The adjustment shall permit a variation of approximately 40-percent in torque setting. Switches shall have a rating of not less than 6-amperes at 120-volts-a.c. and 2.2-amperes at 115-d.c. The torque switches shall be in series with the opening and closing coils of the starter.

The torque switches shall be factory adjusted by the manufacture for this application.

A handwheel for manual operation shall be provided. Motor shall not rotate when handwheel is in use. A fused motor shall not interfere with manual operation. For valve control, furnish for each valve a reversing starter in watertight enclosure that is integral with the actuator housing. Furnish a push-button station NEMA-4 with red and green indicating lights separate from the valve actuator. Space heaters shall be provided to protect the motor, reversing starter and limit switch compartments from moisture condensation. Valve control wiring diagrams shall be furnished with submittal data.

Valve actuators shall conform to latest revision of AWWA C504 and shall be designed to hold the valve in any intermediate position between fully opened and fully closed without creeping and fluttering.

502.6.5.4.3. Other Actuators. Other types of actuators shall conform to AWWA C504.

502.6.5.5. Shipment and Storage Requirements. Electric motor actuated valves shall be shipped to bonded covered warehouse storage to be designated by the OWNER. Valves shall be stored indoors and shall have space heaters energized. Full face flange protectors of waterproof plywood shall be at least one-inch thick.

502.6.5.6. Tests. All butterfly valves shall be tested by the manufacturer in accordance with AWWA C504. Test results shall be furnished to the OWNER.

502.6.6. Line Valve Installation. At locations shown on the plans, CONTRACTOR shall furnish and install valves of the type and size indicated. Valve vaults shall be furnished as provided in the special contract documents and constructed in accordance with [Item 702.5.8.8](#). Vaults and applicable Division 4000 Standard Drawings.

502.6.6.1. Gate Valves. Valves shall be carefully handled and lowered into position in such a manner as to prevent damage to any part of the valve. The valve shall be placed in the proper position and held securely until all connections have been made. Where valves are to be placed in a concrete structure, the floor shall be completed before installing the valve. The valve shall be securely blocked so that its weight is carried by the floor rather than being supported by connected piping. See also Standard Drawing 4050.

502.6.6.2. Air Release Valves. The term "air release valve" as used in this section shall apply to the installation of both air release valve and combination air and vacuum release valves. Vaults shall be furnished as an integral part of either air release valve or combination air and vacuum release valve installation.

Air valves shall be installed in the manner shown in Standard Drawings 4090 – 4100B and on the appurtenance sheet unless otherwise indicated on the plans. The proper valve and fitting sizes shall be installed on mains in accordance with the schedule in Table 502.6.6.2.(a) Minimum Air Release Valve Sizing unless otherwise specified by the OWNER.

Table 502.6.6.2.(a) Minimum Air Release Valve Sizing¹

I.D. of Main (in.)	Size of Valve and Fitting (in.)
16 and smaller	1
18 through 36	2
42 and larger	3

1. This table is for use if no sizing is indicated on the plans.

Matching taps shall be provided for and made in accordance with [Item 502.10](#). Connections to Conduit for Service. Fittings required for mounting air valves shall be as specified in [Item 502.5](#). Fittings. All fittings shall be tight, leak free and plumbed true to the required position.

502.6.7. Rejection. Any valve may be rejected for failure to meet its respective requirements of this specification or referenced specifications.

502.6.8. Measurement and Payment. Where valves are furnished by the OWNER, the valves shall be measured for payment for handling, placing, installing, jointing, testing and all incidentals per each, grouped by size. Where the valves are to be furnished by the CONTRACTOR, the valves shall be measured for payment for furnishing, hauling, handling, placing, installing, jointing, testing and all incidentals per each, grouped by size. The price bid for valves shall include vault, roadway box, cover, extension pipe and pad supports since separate pay items shall not be set up for these items. Manholes or vaults for valve gear boxes shall be paid for at the contract unit price per each, grouped by sizes, complete in place, if provided in the proposal and contract. The contract unit price shall be the total compensation for labor, materials, tools, equipment and incidentals necessary to install valves complete in place in strict accordance with drawings, specifications, and/or instructions of the OWNER.

502.7. PREFORMED FLEXIBLE CONDUIT JOINT SEALANT

502.7.1. General. This specification covers a cold-applied preformed flexible butyl rubber or plastic sealing compound for sealing interior and/or exterior space on concrete sewer pipe and manhole sections, where infiltration or exfiltration is a factor in the design.

502.7.2. Applicable Standards. Except as modified or supplemented herein, all preformed flexible joint sealants shall conform to the applicable requirements of the standard specifications listed in Table 502.7.2.(a) Conduit Joint Sealant Standards.

Table 502.7.2.(a) Conduit Joint Sealant Standards

Publisher	Standard
Federal Specification	SS - S - 210A(1) Sealing Compound, Preformed Plastic, For Expansion Joints
American Association for State Highway and Transportation Officials (AASHTO)	M198

502.7.3. Basis of Acceptance. The acceptability of the preformed flexible joint sealant shall be determined by the results of physical tests, by inspection and by approval of its experience record.

502.7.4. Material. The joint sealer shall be supplied in either extruded rope form of suitable cross-sectional area or flat tape form and shall be sized as recommended by the manufacturer and approved by the Engineer. The joint sealer shall be protected by a suitable removable wrapper. The joint sealer shall not in any way depend on oxidation, evaporation, or any other chemical action for either its adhesive properties or cohesive strength. The joint sealer shall remain totally flexible without shrinking, hardening, or oxidizing regardless of the length of time it is exposed to the elements.

The manufacturer shall furnish an affidavit attesting to the successful use of the product as a preformed flexible joint sealant on concrete pipe and manhole sections for a period of at least 5-years.

If requested by the OWNER, the CONTRACTOR shall provide results of above specified tests to insure product compliance with these specifications or shall supply an affidavit of compliance from the manufacturer insuring compliance with these specifications.

502.7.5. Installation of Joint Sealant. All surfaces to be in contact with the joint sealant shall be thoroughly cleaned of dirt, sand, mud or other foreign matter. A primer shall be applied to all surfaces prior to installing the joint sealant in accordance with recommendations by the manufacturer. The protective paper wrapper shall remain on the joint sealant until immediately prior to placement of the pipe in the trench. After removal of the protective paper wrapper, the joint sealant shall be kept clean.

Backfilling of pipe laid with this joint sealer may proceed after the joint has been inspected by the OWNER.

502.7.6. Rejection. The preformed flexible joint sealant may be rejected for failure to meet any of the requirements of this specification.

502.7.7. Measurement and Payment. Joint sealant shall not be paid for separately, but shall be considered subsidiary to furnishing and installing conduit.

502.8. POLYETHYLENE WRAP FOR METAL PIPE AND FITTINGS

These specifications cover polyethylene film used as a wrap to protect cast iron and other metals in a corrosive soil environment.

502.8.1. Material. Unless otherwise specified, encasement material, sizing, and marking shall conform to AWWA C105 Polyethylene Encasement for Ductile-Iron Pipe Systems.

502.8.2. Installation. Unless otherwise specified, encasement installation shall conform to AWWA C105. Polyethylene wrapping of pipe, fittings or hydrants shall precede blocking or restraint.

Fittings such as bends and reducers shall be wrapped similarly to pipe. Specials such as but not limited to valves, hydrants, and crosses shall be wrapped by splitting, tucking and overlapping the polyethylene tube, then closing the field-made splices with the required tape. All seams shall be folded twice prior to taping in accordance with AWWA C105.

Material to cover valves may be acquired from the overlapping excess polyethylene tub on the adjacent pipe lengths. The tubing shall be drawn over the bell of pipe on either side and insulated with field-made seams as described above.

Hydrants shall be encased with the polyethylene tubing slipped over the hydrant and extended to a point 2-in. to 3-in. above the ground line. The wrap shall be excluded from the drain region to allow normal drain function of the hydrant.

502.8.3. Rejection. Failure to meet any of the specifications contained in this section shall be cause for rejection of the materials.

502.8.4. Measurement and Payment. No separate payment shall be made for polyethylene wrap. It shall be considered subsidiary to the bid items on which the polyethylene wrapping is required.

502.9. CORROSION-RESISTANT COATINGS AND LINERS FOR WASTEWATER CONDUIT AND APPURTENANCES

502.9.1. General. Coatings and liners are used as a protective barrier attached to the interior walls of concrete, ductile iron, or steel pipe or manhole sections, special concrete appurtenances for protection against the corrosive chemical elements which may occur in certain domestic wastewater environments and for protection against certain corrosive wastes from industry.

All work for and in connection with the installation of the coatings and linings, including interlocking liner plates and epoxy lining in concrete pipe and the field sealing and welding of joints, shall be done in strict conformity with all applicable specifications, instructions and recommendations of the manufacturer.

502.9.2. Basis of Acceptance. The acceptability of the protective material and its attachment to the pipe or appurtenance shall be determined by the results of tests, by inspection and by approval of its experience record. The tests are designed to prove, demonstrate and insure:

- (1) whether or not the protective material is the same as used in the tests,
- (2) surface continuity and lack of holidays and voids,
- (3) adhesion,
- (4) resistance to temperature changes,
- (5) resistance to abrasion,
- (6) resistance to fire, and
- (7) chemical resistance.

The inspection at the manufacturing plant or in the field is to determine:

- (1) whether or not the protective material is the same as used in the tests,
- (2) that it is attached in the same manner, and as uniformly, as it is attached to the concrete in the tests,
- (3) that the joint areas are adequately protected.

The experience record of the protective material attached to the pipe or appurtenances must be acceptable.

To qualify the material and the attachment of the material to the pipe or appurtenances for acceptance, all tests must be met or certified for the specific protection intended, all conditions to be evaluated by inspection must be met, and the experience record must be submitted and approved.

502.9.3. Testing Requirements. Unless otherwise specified, the manufacturer of the protective material is responsible for meeting the testing, inspection standards and experience records as described herein, except in the case of a pipe manufacture electing to procure the protective material and applying the material as the pipe is manufactured. In such a case the pipe manufacturer would be responsible.

The test results shall be certified by a recognized testing laboratory acceptable to the OWNER and do not necessarily have to be made on each project.

The inspection results shall be attested to in writing by a licensed Professional Engineer or witnessed by the Engineer representing the OWNER. The experience record shall be documented with dates, locations, actual number of feet of protected conduit in the ground, length of time in the ground, the nature of the environment against which the conduit is being protected and the names and addresses of responsible references who shall verify the facts in the experience record.

502.9.4. Physical Requirements.

502.9.4.1. Chemical Resistance. The OWNER may designate which of the solutions mentioned may be used or may designate others.

The chemical resistance test shall be made as follows:

- (1) The specimens, approximately 5-in. long, 2¼-in. wide and 1-in. thick, shall be cut from the pipe. The protective material shall be attached to these test specimens in the same manner as it would be attached to the pipe. The protective material shall be to manufacturer's specified minimum thickness. If curing is required, the protective material shall be cured to the manufacturer's recommendations.

- (2) The protective material on the prepared test specimens shall be tested for indentation hardness in accordance with the requirements of ASTM D2240 Test Method for Rubber Property—Durometer Hardness and the hardness recorded.

- (3) The prepared test specimens shall then be placed in wide mouth glass containers half submerged in the following solutions:

5%	sulphuric acid
5%	hydrochloric acid
3%	salt (NaCl) water
1%	phenol
5%	alum
5%	phosphoric acid
10%	biodegradable detergent
100%	motor oil

- (4) The containers shall be closed and held at 100°F for six-months.

- (5) After six months the specimens shall be taken from the containers and tested again for indentation hardness in accordance with the requirements of ASTM D2240. The test durometer hardness shall be made in both the area exposed to the liquid and in the area exposed to the vapor above the liquid. There shall be no loss of indentation hardness either in the area below the liquid or in the area above the liquid.

502.9.4.2. Surface Continuity, Holidays, and Voids. Voids and holidays shall be cause for rejection. The surface continuity and holiday test shall be made as follows:

- (1) An electrical holiday detector, capable of producing and maintaining a voltage equal to 800 times the square root of the specified minimum protective thickness expressed in mils, shall be used to determine the complete continuity of the protective surface.
- (2) The electrical holiday detector shall be used on a full size piece the protective material taken from a production run.

502.9.4.3. Adhesion to the Pipe or Appurtenances.

502.9.4.3.1. Adhesion to Concrete. Where the protective material adheres directly to the concrete, adhesion test shall be made as follows:

- (1) Make a test specimen by drilling a core hole through the protective material and the pile to produce a core sample 1-in. in diameter by $\frac{3}{4}$ -in. or more in depth. (This hole may be repaired and the pipe from which the sample was taken may be used.)
- (2) Check the protective material for thickness.
- (3) Cement the test specimens onto a solid wooden block at least 2-in. x 2-in. x 1-in. in thickness so that the protective material is cemented onto the wooden block.
- (4) Allow sufficient time for the cement to set.
- (5) Support the wooden block so that the test specimen is on its underside and hang a 40-pound weight on the test specimen. This can be done using an ordinary wooden clamp.
- (6) This test should be made at an ambient temperature of between 60°F and 90°F.
- (7) The protective material shall adhere to the material for a minimum of two-hours.

502.9.4.3.2. Anchored to Concrete. Where the protective material is anchored to the concrete by fins embedded or dovetailed into the concrete adhesion test shall be made as follows:

- (1) Using a large enough square footage of the protective material to be a representative sample, the fins shall not be capable of being pulled out of the material, usually concrete, nor the protective material torn away from the embedded fins using less than a pull equal to 50-psi.
- (2) For the adhesion test, either [Item 502.9.4.3.](#) Adhesion to the Pipe or Appurtenances or paragraph (1) above shall be used, but not both.

502.9.4.4. Resistance to Temperature Changes. The test for resistance to temperature changes for those materials that adhere directly to the concrete shall be made in accordance with the latest ASTM Method when required by the OWNER.

502.9.4.5. Resistance to Abrasion. The test for resistance to abrasion shall be made as follows:

- (1) A 1-foot length of pipe which has been lined with the protective material shall be suitably capped and arranged on rollers so that it can be revolved at high speeds. A door shall be left in one end so that access can be had to the interiors of the test section.
- (2) A slurry shall be made composed of six-pounds of gravel and three-pounds of water, and it shall be placed inside the test section and the test section shall be rotated so that the protective material has peripheral speed of four-feet-per-second. After 1,500,000 revolutions, the protective material shall not show visible signs of wear or abrasion.

502.9.4.6. Resistance to Fire. The protective material, if plastic, shall be tested for resistance to fire by meeting the requirements of ASTM D635 Test Method for Rate of Burning and/or Extent and Time of Burning of Self-Supporting Plastics in a Horizontal Position. The material shall be self-extinguishing or nonburning according to ASTM D635.

502.9.5. Appurtenance Protection. Adequate protection shall be provided at the ends of joints.

All special shapes such as tees and wyes, branches, slants and curves shall be protected with the protective material, and they shall be given the same degree of protection provided to the production run of pipe. Lift holes, if called for on the plans or in the specifications, shall be sealed with epoxy or sealant recommended by the coating or liner manufacturer that shall pass the tests as set out in this [Item 502.9.](#) Corrosion-Resistant Coatings and Liners for Wastewater Conduit and Appurtenances.

502.9.6. Inspection. The tests required under the physical test requirements section of this specification need only be made once on any one project. Each length of pipe or special may be subject to visual

inspection during manufacture, transportation or laying by the OWNER in order to cull and reject pipe as specified in [Item 502.9.8](#). Rejection.

502.9.7. Repair of Coatings and Liners. Where the protective material is damaged or where the adhesion of the protective material to the concrete is damaged, repairs may be made at the discretion of the OWNER.

502.9.8. Rejection. The protective material shall be rejected if:

- (1) any the tests described under physical test requirements are not met,
- (2) the manufacturing method of applying, adhering and curing the protective material differs from that used on the test samples,
- (3) the protective material thickness as used on the test samples exceeds the minimum specified in the manufacturer's specification by more than five-percent, or
- (4) it cannot be adequately repaired in the field.

502.9.9. Measurement and Payment. No separate payment shall be made for coating or lining unless otherwise specified by the OWNER. It shall be considered subsidiary to the bid items on which the coating or lining is required.

502.10. CONNECTIONS TO CONDUIT FOR SERVICE

502.10.1. Definitions. "Service" shall be defined as a service line to an individual customer. "Bullheads" shall be defined as an individual service line with branches at the end to serve two or more customers.

502.10.2. Materials.

502.10.2.1. Service Clamps. Service clamps shall be designed for tapping water pipe under normal service pressure. The clamp shall consist of a contoured saddle fastened to the pipe by one U-bolt for the single strap clamp for pipes less than 4-in. I.D., and by two U-bolts for double strapped clamps or shall consist of two sections or halves that shall be fastened together with a minimum of two bolts and nuts for pipes 4-in. I.D. and larger. The saddle shall be sealed against the pipe with a rubber gasket and shall have a heavy hub tapped with a corporation stop thread. The clamp shall be designed for 150-psi water working pressure.

502.10.2.1.1. Service Saddles. The service saddles shall be shaped so as to provide approximately 180° coverage around the pipe. Service saddle shall be material conforming to ASTM B62 Composition Bronze or Ounce Metal Castings or as otherwise specified by OWNER. Casting shall conform to AWWA C800.

Service Saddle Hubs. The service saddle hub for single and double strap clamps shall have a wall thickness of not less than ½-in. including threads. The hub shall be tapped with a corporation stop thread of the size specified.

The thread shall have a taper and pitch in accordance with AWWA Standard C800 for Threads for Underground Service Line Fittings. The hub shall be reinforced so that threads shall not be distorted by bending movements.

Open slots for bolts shall not be allowed.

Clamps. Double strapped clamps 4-in. through 12-in. shall have not less than the thickness from the point of the built-up hub segment to the segment immediately adjoining the holes for the service saddle straps specified in Table 502.10.2.1.1.(a) Clamp Minimum Thickness.

Table 502.10.2.1.1.(a) Clamp Minimum Thickness

Clamp Size (in.)	Minimum Thickness (in.)
4	0.190
6	0.195
8	0.195
10	0.195
12	0.215

Markings. Service saddles shall be distinctly marked with cast letters showing manufacturer's name, type pipe saddle as designed for (cast iron, ductile, etc.) and minimum/maximum o.d. ranges.

502.10.2.1.2. Straps. Straps shall be of materials conforming to ASTM B124 Copper and Copper Alloy Forging Rod, Bar, and Shapes, or ASTM B98 Copper-Silicon Alloy Rod, Bar, and Shapes, or A276 Stainless Steel Bars and Shapes. Straps shall be formed flat on one side to fit uniformly against the wall of the pipe. Rod diameter shall be not less than $\frac{5}{8}$ -in. flattened to $\frac{3}{4}$ -in. on one side.

Straps shall be threaded $\frac{5}{8}$ -in. 11-NC-2A for a distance such that $\frac{1}{2}$ -in. remains after clamp is fully tightened on pipe.

502.10.2.1.3. Gaskets. Gaskets shall be of neoprene rubber. Shore hardness shall be 65 ± 5 . Gasket shall be of O-ring type, $\frac{3}{16}$ in. thick and securely fastened to the service saddle to facilitate installation.

502.10.2.1.4. Nuts. Nuts shall be of the same material as service saddles or straps. Nuts are to be semi-finished heavy hexagon tapped $\frac{5}{8}$ -in. 11-NC-2B.

502.10.2.1.5. Hydrostatic Test. All products not previously approved for use shall be subject to hydrostatic test. Service clamps shall not leak or show any structural deformation under a hydrostatic test pressure of 300-psi for 30-days.

502.10.2.1.6. Rejection. All service clamps furnished under these specifications shall be subject to inspection by the OWNER. If any products are found not to conform to the specifications, the lot or any portion thereof may be rejected.

502.10.2.1.7. Water Tubing. See [Item 501.10.](#) for conduit requirements.

502.10.2.2. Tapping Valves. Tapping valves shall conform to the requirements of [Item 502.6.1.17.](#) Tapping Valves.

502.10.2.3. Tapping Sleeves. The material for tapping sleeve bodies shall be cast iron or ductile iron in accordance with AWWA C110 (ANSI 21.10) or ASTM A285 Pressure Vessel Plates, Carbon Steel, Low-and Intermediate-Tensile Strength, Grade C carbon steel, in two sections or halves to be bolted together with high-strength, corrosion-resistant, low-alloy steel bolts conforming to AWWA C111 (ANSI A21.11). Branch outlet of tapping sleeves shall be flanged with a machined projection or recess to mate with tapping valve inlet flange to assure correct alignment.

Cast-iron and ductile-iron tapping sleeves shall be mechanical joint, or as specified, with dimensions to secure proper fit on the type and class of pipe on which they are to be used. Bolts, nuts and glands for mechanical-joint ends shall conform to the requirements of [Item 502.6.1.3.](#) Ends.

Steel sleeves shall be restricted to use on pipe sizes 12-in. and larger and subject to the following additional specifications:

- (1) Flange shall conform to AWWA Standard C207 for Steel Pipe Flanges for Waterworks Service — Sizes 4 In. through 144 in. Class D, ANSI 150 lb. (68.0 kg) drilling. Gasket shall be affixed around the recess of the tap opening in such a manner as to preclude rolling or binding during installation.
- (2) All steel sleeves shall be fusion bonded epoxy coated to an average of 12-mil thickness. Finished epoxy coat shall be free of laminations and blisters, shall not peel and shall remain pliable and resistant to impact.
- (3) Steel sleeves shall be provided with a $\frac{3}{4}$ -in. NPT test opening so that test can be made prior to tapping. Opening shall be provided with a $\frac{3}{4}$ -in. bronze plug.

502.10.2.4. Meter Boxes. The meter box shall be constructed for impact strength and corrosion resistance. The meter box may not be constructed of a material known to degrade in wet, acidic or alkaline soil. Materials specified by the OWNER may include, but are not limited to, cast or ductile iron, precast polymer concrete, corrugated galvanized sheet metal, and plastics such as HDPE, LDPE and LMDPE.

Cast iron shall meet ASTM A48 Gray Iron Castings, Class 30B. Ductile iron shall meet ASTM A536 Ductile Iron Castings. Corrugated galvanized sheet metal (minimum thickness of .036 inches) made with G-90 galvanized coating shall be minimum 20 gauge and galvanized according to requirements of [Item 804.3.](#) Galvanizing. Plastics may be black or white and shall be UV stabilized.

All meter box rings and covers shall be solid, made of gray cast iron conforming to ASTM A48 Class 30B or ductile iron conforming to ASTM A536 and shall bear the MFG ID, casting product number, and Country of Origin.

Where traffic is anticipated, the meter box, with cover installed, shall be able to bear a minimum of 16,000-lb load in a wheel load (H-20) style test.

Box dimensions shall be specified by OWNER. The OWNER may specify boxes compatible with remote meter reading. Meter boxes shall be clearly marked with manufacturers ID and model number.

502.10.3. Water Conduit Connections. This section and [Item 506.6](#). Connections to Existing Water Conduits shall govern for the construction of connections to water conduits.

502.10.3.1. Taps and Tap Assemblies in Water Conduit. Taps and/or tap assemblies of the specified size shall be installed in locations as detailed and indicated on the plans or as specified.

502.10.3.1.1. Taps. Taps for transmission of water or air from the main into system service accessories can be either of two types as follows:

- (1) Standard internal pipe threaded holes in wall of water mains. These taps may be either manufactured into the pipe or installed in the field.
- (2) Tap installations that are made by clamping a service saddle equipped with a sealed threaded port on the periphery of the main and then drilling through the pipe wall to complete each service port. Taps may be made either on an uncharged system or into a main under pressure.

502.10.3.1.2. Tap Assemblies. The tap assembly shall consist of a corporation stop and an iron to copper connection attached to a hard copper (Type K) tubing terminating approximately 1-ft. below ground surface with a brass gate valve as shown and detailed on the plans to serve as additional air release.

When tap assemblies are an integral part of an air valve installation, measurement and payment shall be in accordance with [Item 502.6](#). Valves.

Tap assemblies may be required by the project plans and specifications adjacent to gate valve installations. Tap assemblies so required shall be installed in the water main on either side of the valve. Payment for the tap assemblies shall be included in the unit price bid for furnishing and installing the gate valve complete in place.

When taps are required for flushing, chlorination and/or testing, the CONTRACTOR shall locate the taps in accordance with Standard Drawing 4110 or other detail drawings, plans or in locations directed by the OWNER. No separate payment shall be made for taps required for testing, flushing, and/or chlorination.

Upon completion of the testing and purification, the CONTRACTOR shall return to the job site, remove the blow-off down to the corporation stop, backfill leaving the corporation stop in place, and replace all pavement. The CONTRACTOR'S removal of the blow-off shall include all labor, materials, tools, equipment and incidentals necessary to complete the work, including excavation, backfill and disposal of surplus materials without additional compensation.

502.10.3.1.3. Tapping Sleeves. Steel sleeves shall not be used for taps greater than 75-percent of the pipe diameter. Use of steel sleeves for "size-on-size" taps is prohibited unless sleeve is full-bodied stainless steel, as approved by OWNER.

All steel sleeves shall be crated in wooden crates that shall provide protection from damage to epoxy coating during transport and storage.

502.10.3.1.4. Tapping Ductile Iron Pipe. Service taps, unless otherwise specified, shall be made in cast iron pipe by direct tapping of the pipe wall (without use of tap saddles) for tap sizes relative to pipe diameters as shown in Table 502.10.3.1.4.(a) Tapping Ductile Iron Pipe.

Table 502.10.3.1.4.(a) Tapping Ductile Iron Pipe

Tap Diameter	Pipe Diameter
¾-in. and 1-in.	4-in. through less than 12-in.
1½-in. and 2-in.	12-in. and larger

When direct tapping of cast iron pipe cannot be made within the limits as provided above, taps shall be made as set forth in this specification, utilizing service saddles.

502.10.3.1.5. Tapping Concrete Pipe. Tap location shall be provided to the pipe manufacturer, when available, and taps shall be made by the manufacturer during the fabrication phase of the pipe when locations are so furnished. Taps fabricated during manufacture with a diameter less than or equal to 2-in. shall be provided with brass or bronze insert bushings. Taps greater than 2-in. shall be provided as flanged outlets with flange to thread insulator adapter kits. When taps are required to be made in the field, the taps shall be made in accordance with the pipe manufacturer's recommended procedures and to the satisfaction of the OWNER.

502.10.3.1.6. Tapping Asbestos Cement (AC) Pipe.

If a tap to existing asbestos cement pipe is necessary, use **EXTREME CAUTION** to avoid the airborne release of asbestos fibers.

Taps to asbestos cement pipe can be made with bronze double strap tapping saddles, tapping tees, or pre-tapped couplings with brass insert bushings. A tapping tee shall be paid for as a fitting. If pre-tapped couplings are called for in the contract and proposal, a separate pay item shall be provided for each, classified as to size.

502.10.3.1.7. Tapping PVC Pipe. Service taps in AWWA C900 PVC pressure pipe shall be made with a shell cutter assembly and the coupon removed for tap sizes relative to pipe class and diameter as shown in Table 502.10.3.1.7.(a) Tapping PVC Pipe.

Table 502.10.3.1.7.(a) Tapping PVC Pipe

Tap Diameter	Pipe Diameter	Pressure Class
¾-in. and 1-in.	6-in. to 12-in.	150 and 200

When direct tapping of PVC pipe cannot be made within the limits as hereinbefore provided, taps shall be made as set forth in this specification, utilizing service saddles.

502.10.3.1.8. Measurement and Payment. Measurement shall be for individual taps made by size, and payment shall be absorbed under [Item 506](#). Water Conduit Installation or [Item 502.6](#). Valves unless otherwise specified.

502.10.3.2. Services and Bullheads. The details on installation and materials required are shown in applicable Division 4000 Standard Drawings or on the appurtenance sheets attached to the plans.

The end of each water service connection shall be marked with heavy gauge polyethylene tape, 6-inches in width with a thickness of 0.004-inches. The tape should be blue in color on which has been printed "Caution Buried Water Line Below" in continuous print. The tape should have a minimum tensile strength of 1700-psi lengthwise and 1200-psi crosswise.

Meter boxes shall be buried to protect the meter from unauthorized access, damage and freezing.

502.10.3.2.1. Procedures for Transferring Service. The CONTRACTOR will inform the customer that the service is being transferred. Splices in service lines shall conform to Standard Details 4130 and 4140, unless otherwise approved by OWNER.

Short Service. A water service shall be classified as a "Short Service" if the existing service line to the water meter is on the same side of the street as the new main and requires the existing service line to be replaced to complete the installation as indicated on the plans and specified herein. A curb stop will be installed on the end of the service line.

Long Service. A water service shall be classified as a "Long Service" if the existing service line to the meter is on the opposite side of the street as the new main and requires a new service line to be installed under the street to complete the installation as indicated on the plans and specified herein.

All new services will be flushed according to [Item 506.7](#). Purging and Disinfection of Water Conduits. The main will then be hydrostatically tested and disinfected. After a good sample is received, the CONTRACTOR will then begin transferring the services.

The water serving the customer through the existing water service will be stopped by closing a corp or curb stop on the existing water service. The existing customer line and new service line will then be cut at the property line and connected. Galvanized customer lines will not be threaded for connection, but will be cut and connected with a coupling.

Any meter box located within a driveway or sidewalk shall be relocated and placed in the parkway or behind the sidewalk as directed by the OWNER. Reuse of the existing water meter box shall be as determined by the OWNER. The connection of the new service water lines to the meter shall be considered subsidiary to the service installation.

502.10.3.2.2. Measurement and Payment. Where water services have to be transferred from a line to be replaced, killed or salvaged to a line being constructed, they shall be paid for per each, as set out in the proposal and contract.

Bullheads or water services shall be measured and paid for at the contract price per each, in accordance with size and location, complete in place, as provided in the proposal and contract. The tapping saddle shall be measured and paid for as part of the service. There shall be no extra pay for extra depth in the installation of service leads (deadheads).

Meter boxes shall be paid for per meter box.

The contract price shall be the total compensation for the furnishing of all labor, materials, tools, equipment and incidentals necessary to complete the work.

502.10.4. Wastewater Conduit Connections. This section shall govern for the construction of connections to wastewater conduits. Connections of wastewater pipe to existing wastewater conduits or wastewater appurtenances shall be as shown on the plans or as directed by the Engineer. Details of construction shall be shown on the plans.

The end of each wastewater service connection shall be marked with heavy gauge polyethylene tape, 6-inches in width with a thickness of 0.004-inches unless a cleanout is present. The tape should be green in color on which has been printed "Caution Buried Wastewater Line Below" in continuous print. The tape should have a minimum tensile strength of 1700-psi lengthwise and 1200-psi crosswise.

502.10.4.1. Service Connection. Service pipe shall be of the same pipe material as the main wastewater conduit unless otherwise specified on the plans or in the contract or approved by the OWNER. Connections shall be made to prevent the occurrence of bi-metallic corrosion or any other corrosion that can result by joining incompatible materials.

Wastewater service connections shall be defined as a service line connecting the customer's wastewater system at the property line or utility easement to the main wastewater conduit and shall consist of the service combination tee wye, the necessary Class B or Class PB (as specified by the OWNER) concrete cradle or crushed stone for the tee wye, the service pipe necessary to extend the line from the main wastewater conduit to the customer's property line and a plug placed in the end of the service line.

Services for single-family residence shall normally be 4-inches in diameter. Standard 4-inch laterals shall consist of a standard wye and bend and the necessary pipe and cleanout as shown on the plans or directed by the OWNER. Larger laterals in non-residential uses shall consist of a manhole and the necessary minimum 6-inch pipe as shown on the plans or directed by the OWNER. If the CONTRACTOR is required to connect or reconnect the service line to the customer's wastewater system, the connection shall be as shown on the plans. If the CONTRACTOR is not required to connect to the customer's wastewater system, the service line shall be plugged and sealed.

Extra depth service connections shall be installed when the wastewater main is at a depth greater than that necessary to serve the abutting property. The service is identical to a standard connection except that pipe risers will be installed at a maximum 45-degree angle into the trench walls to connect the combination tee wye and 45-degree bend to the service pipe. Where possible, a minimum slope of 1/4-in.-per-foot (equivalent to a 2% slope) will be maintained. Where the wastewater main is located in the street and the abutting property slopes to the street, the wastewater service shall normally have a minimum depth of 5-feet below the top of the curb at the point where it passes beneath the curb. Where

abutting property slopes away from the wastewater main, service connections shall be placed at a depth adequate to serve the normally expected use of the property.

Where water and wastewater service connections cross, they shall be treated in accordance with TCEQ regulations.

502.10.4.2. Cleanouts. Service line cleanouts shall conform to Standard Drawing 5120. If service line cleanouts are required, double cleanouts shall be installed at the property line, or as specified by OWNER. When specified in the special provisions or in the plans, a test tee shall be installed at the end of the service line (located in the parkway), with the branch in a vertical position.

502.10.4.3. Measurement and Payment. Wastewater conduit connections shall be measured at the contract unit price per each, complete in place. The contract unit price shall be total compensation for the furnishing of all labor, materials, tools, equipment and incidentals necessary to complete the work, including excavation, concrete encasement, if required, disposal of excess material, backfill, embedment, concrete blocking, paving and sod, all in accordance with the plans and specifications.

502.11. MISCELLANEOUS CONDUIT CONNECTIONS

502.11.1. Pitot Outlets. Pitot outlets shall be of the type indicated on the plans or appurtenance sheet. Pitot outlets shall be measured for payment for each. Pitot outlets shall be paid for at the contract unit price per each.

502.11.2. Facilities for Dewatering of Water Lines. There shall be constructed, at the location shown and detailed in the plans, permanent standard blow-offs and drains and special dewatering facilities to permit the blowing off and/or the dewatering of lines or sections of line.

Permanent blow-offs and drains shall be measured as complete units. Payment shall be made for permanent blow-off and drain at the unit price bid which shall be full compensation for the complete installation. Payment for permanent blow-offs with dewatering sump manhole shall be made on a lump sum basis at the unit price bid, which shall be full compensation for complete installation, including excavation and backfill from blow-off fitting to manhole, furnishing and installing sump manhole and other items needed for complete installation exclusive of items for which there are bid items in the proposal.

502.11.3. Wastewater Connections. Connection of wastewater mains to existing manholes and to other wastewater mains where constructing a manhole is not feasible or not required shall be watertight. The use of pipe hammers or jackhammers is prohibited.

502.12. STRUCTURES.

502.12.1. Description. This section shall govern for the construction of all miscellaneous structures such as junctions, transitions, and utility supports, and for the construction of appurtenances such as deep-cut connections, wyes, stoppers and bulkheads, and such other miscellaneous structures or appurtenances which may be shown on the plans. Construction shall conform with any applicable provisions of Division 700. Structures.

Unless otherwise specified on the plans, all storm sewer structures such as junctions, transitions, manholes, cleanouts, wyes, elbows, tees, stoppers and such other miscellaneous structures or appurtenances which may be shown on the plans shall be made of the same base metal and coating (metallic or otherwise) as the pipe on which it is connected. All such structures or appurtenances field fabricated or otherwise will be repaired in accordance with [Item 502.9.7. Repair of Coatings and Liners](#) or [Item 804.3.5. Repair of Damaged Zinc Coating](#), as applicable.

In general there shall not be a pay item for pipe support when a temporary part of conduit installation, but the contract prices for the new or re-laid pipe, shall be the total compensation for the furnishing of all labor, tools, materials, equipment and incidentals necessary to complete the work including excavation, installation and removal of the temporary piping, construction of piers, stripping of forms, disposal of surplus materials, in accordance with the plans and specifications. Where a pay item is included, the contract price shall be the additional compensation for all excavation, labor, tools, and materials over and above the bid price for furnishing and installing the conduit.

502.12.2. Permanent Concrete Structures. The construction of reinforced concrete structures, including junctions, transitions, vaults, piers and beam supports, and such other similar structures as may be covered

by this specification, shall be performed in accordance with the requirements of [Item 702](#). Concrete Structures, applicable Division 1000-5000 Standard Drawings, and the following additional requirements. Unless otherwise specified, all concrete shall have an average compressive strength at 28-days equal or greater than 3000-psi. Excavation shall be made to the required depth and of sufficient width to construct the work to grade, form and dimensions. All soft and yielding materials shall be removed and replaced with acceptable materials. The subgrade shall be moistened to a minimum depth of 2-in. before placing concrete. All formed surfaces of the concrete exposed to public view shall be given a textured finish as shown on the plans. All other formed surfaces shall be given the "Type 1 Finish," as described in [Item 702.5.13](#). Finishing Exposed Surfaces. Corrosion protection shall be applied as may be called for on the plans or the proposal and shall be measured for payment and paid for at the contract price as detailed in [Item 502.9](#). Corrosion-Resistant Coatings and Liners for Wastewater Conduit and Appurtenances.

Permanent concrete structures shall be measured and paid for in accordance with [Item 702](#). Concrete Structures, as provided for in the contract documents. No measurement or payment shall be made for reinforcing steel.

502.12.3. Miscellaneous Pipe Structures. Riprap and miscellaneous pipe structures that may be necessary shall be designed in detail on the plans.

The structures shall be measured for payment per each or in linear feet between the limits set out on the plans as provided for in the proposal and contract. Miscellaneous concrete shall be measured for payment paid for at the contract unit price as provided in the proposal and contract, typically in cubic yards. The contract price shall be the total compensation for the furnishing of all labor, materials, tools, equipment and incidentals necessary to complete the work, including all excavation, disposal of surplus materials and backfill, in accordance with the plans and these specifications.

502.12.4. Connections to Existing Structures. The bottom of the existing structure shall be mortared or concreted, if necessary, to eliminate any drainage pockets by the new connection in general accord with details for the new structure as shown on the plans. Where conduit is connected into old structures that are to remain in service, any damage to the structure resulting from the work of making the connection shall be restored by the CONTRACTOR to the satisfaction of the Engineer.

502.12.5. Waterstops. Waterstops shall be of the type and kind and of materials designated on the plans. Care shall be taken that the waterstop is properly located and held in position during placement of concrete. For particular material, the following shall apply:

- (1) PVC Material. Splices of waterstop shall be performed by fusing the material, using a heat device thermostatically controlled in accordance with the manufacturer's recommendations.
- (2) Copper Material. Any copper sheets which are damaged under construction operations shall be repaired or replaced. Splices shall be made by lapping and soldering or other approved method.

No separate payment shall be made for waterstop material or for installation of this item. The costs shall be included in the price bid for the completed structure into which the materials are incorporated.

502.12.6. Water Migration Barrier. Water migration barrier prevents water flow along an embedded conduit. A 3-ft. $\pm$ 1-ft. long clay barrier (30< P.I. <40) shall be placed at 200-ft. intervals or as directed by OWNER along all water and wastewater mains. This clay barrier shall be for the full width and depth of the trench, replacing all bedding, embedment and backfill materials, and shall be placed at the mid-point of a length of pipe being placed, but not at a location where a lateral or service connects with the water and wastewater main.

ITEM 503. TRENCHLESS INSTALLATION

503.1. CONDUIT MATERIALS

Conduit materials shall be indicated on the plans and shall conform to the specifications of [Item 501](#). Underground Conduit Materials.

503.2. TUNNEL/CASING PIPE SPACERS

503.2.1. General. This specification covers the materials and requirements for pipe restraining system for pipe installation in tunnels or casing pipe under railroads, highways, streets or other trenchless situations. Restraining systems shall prevent pipe joint separation during and after installation and shall provide dielectric insulation between the carrier pipe and the tunnel liner/casing pipe and shall be resistant to corrosion.

503.2.2. Types.

503.2.2.1. Steel Rib and Wood Lagging System. Steel ribs shall conform to ASTM A36 Carbon Structural Steel. The ribs shall be of the size shown on the plans, special provisions or approved from a design load submittal. The ribs shall be bent by cold pressing in dies.

Wood lagging shall have a minimum thickness of 2.75-in. and a minimum average ultimate stress capacity of 5,000-psi. The ultimate stress capacity to be determined according to ASTM D198 Static Tests of Lumber in Structural Sizes, flexure test on five randomly selected timbers from each shipment of lagging. The maximum load carried by each timber disregarding the highest and lowest one of the five timbers tested shall be averaged to determine the ultimate stress capacity of that shipment.

Nuts shall conform to ASTM A307 Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength. The bolts shall conform to ASTM A449 Quenched and Tempered Steel Bolts and Studs for rib thickness equal to or greater than 0.209-in. and to ASTM A307 Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength for rib thickness less than 0.209-in.

503.2.2.2. PVC Restrained Casing Spacer System. PVC Restrained Casing Spacers shall be provided at all pipe bell joints and not more than 10-feet apart to support pipe and its contents.

Casing spacer runners shall be an ultra-high molecular weight polymer with a minimum tensile impact of 600-ft-lbs/sq.in. Restrainer body and runner supports shall conform to ASTM A536 High Strength Ductile Iron Grade 65-45-12. Connecting rods and nuts shall conform to high strength, low alloy steel as designated in ANSI/AWWA Standard C-111/A21.11

503.2.2.3. HDPE Casing Spacers. Spacers shall provide full circumferential support in case the carrier pipe twists as it is pushed through the casing. Casing spacers shall have a minimum projection height necessary to clear the bell of the carrier pipe or as otherwise indicated on the plans. Casing spacers shall fasten tightly onto the carrier pipe to prevent spacer movement during installation. The span between spacers should result in conservative long-term load safety factors with carrier pipe full of fluid. Manufacturer shall provide the load carrying capacity of the spacer assembly and maximum spacing shall conform to manufacturer's recommendations.

503.2.2.4. Alternate Casing Spacers. When approved by the OWNER, Nylon, Stainless Steel, Ductile Iron, or Carbon Steel Casing Spacers may be used. Such alternate systems shall conform to all requirements as stated in the plans.

503.2.3. Tests. Tests for compliance with this specification shall be as specified herein. A certification of compliance with this specification along with a report of each test shall be furnished to the OWNER.

503.2.4. Rejection. Tunnel/casing spacers and related materials may be rejected for failure to meet any of the requirements of this specification.

503.3. METHODS OF JACKING, BORING OR TUNNELING

503.3.1. Description. This specification shall govern for the provision of the required opening for the installation of conduits by the methods of jacking, boring or tunneling as shown on the plans and in conformity with this specification.

503.3.2. Materials. The encasement and carrier pipe shall be of the type and strength as indicated on the plans. All necessary materials shall conform to the applicable sections of these specifications or as specified by the OWNER(S) or Engineer.

503.3.3. Construction Methods.

503.3.3.1. General. The CONTRACTOR may request to perform the work by jacking, boring, or tunneling in lieu of open cut.

Where encasement with carrier pipe is required to be installed under railroad embankments or under highways, streets or other facilities by jacking, boring or tunneling methods, construction shall be made in a manner that shall not interfere with the operation of the railroad, highway or other facility and shall not weaken or damage any embankment or structure. The CONTRACTOR shall notify all railroad companies or TxDOT at least 48-hours prior to construction. The CONTRACTOR shall provide insurance as required by the governing authority.

During construction operations, barricades and lights to safeguard traffic and pedestrians shall be furnished and maintained around the excavation, equipment, and materials as required in [Item 107.20](#), Protection of Work and of Persons and Property, until such time as the backfill has been completed and then shall be removed from the site. All excavations shall be safely secured at all times to prevent unauthorized access to the excavation site.

The CONTRACTOR shall take the proper precautions to avoid excavating earth or rock or shattering rock beyond the limits of excavation needed to install the conduit. All damages caused by excavating or blasting, either to surface or subsurface structures, shall be repaired or replaced by the CONTRACTOR at the CONTRACTOR'S own cost and expense. The CONTRACTOR shall dispose of all surplus materials at its own expense.

The drilling of pilot holes for the alignment of pipe prior to its installation by jacking, boring, or tunneling shall not be a requirement but may be necessary to maintain grade.

503.3.3.2. Construction by Jacking. If the grade of the pipe at the jacking end is below the ground surface, suitable pits or trenches shall be excavated for the purpose of conducting the jacking operations and for placing end joints of the pipe. This excavation shall not be carried to a greater depth than is required for placing of the guide and jacking timbers and a horizontal distance no nearer the roadbed than the minimum distance shown on the plans.

At the other end of the pipe, an approach trench shall be excavated accurately to grade. All open trenches and pits shall be braced and shored or their walls sloped in such a manner as shall adequately prevent caving or sliding of the walls into the open trench or pit and be in accordance with the requirements of [Item 107.20](#), Protection of Work and of Persons and Property.

Heavy-duty jacks suitable for forcing the pipe through the embankment shall be provided by the CONTRACTOR. In operating jacks, even pressure shall be applied to all jacks used. Suitable bracing between jacks and the jacking head shall be provided so that pressure shall be applied to the pipe uniformly around the ring of the pipe. The jacking head shall be of such weight and dimensions that it shall not bend or deflect when full pressure is applied at the jack. The jacking head shall be provided with an opening for the removal of excavated material as the jacking proceeds. A suitable jacking frame or backstop shall be provided. The pipe to be jacked shall be set on guides which are straight and securely braced together in such manner as to support the section of pipe and to direct it in the proper line and grade. All timber and other materials used in the construction of the jacking assembly shall be of such quality and dimensions that they shall withstand all stresses to which they are subjected in such a manner as to insure even pressures on the pipe during jacking operations. The whole jacking assembly shall be placed so as to line up with the direction and grade of the pipe.

As the jacking proceeds, the embankment material shall be excavated slightly in advance of the pipe in such a manner as to avoid making the excavation larger than the outside diameter of the pipe, with the excavated material being removed through the pipe. The excavation for the underside of the pipe, for at least $\frac{1}{3}$ of the circumference of the pipe, shall conform to the contour and grade of the pipe. The excavation for the top half of the pipe shall conform closely to the outside diameter of the pipe and a clearance greater than 2-in. shall not be permitted. All voids between the pipe and the earth shall be

filled with grout per ASTM C476 Grout for Masonry. Grout holes may be provided in the pipe, or grouting may be made through drill holes from the ground surface if practicable. The grouting shall follow immediately upon completion of the jacking operation. Grout shall have a maximum compressive strength of 100-psi at 28-days.

All carrier pipe installed by jacking shall be supported by a quarter point cradle of Class B or Class PB concrete as specified by the OWNER across the jacking pit and to the first joint in the ditch section on each end.

The distance that the excavation shall extend beyond the end of the pipe depends on the character of the material, but it shall generally not exceed 2-ft. The pipe preferably shall be jacked from the low or downstream end. Lateral or vertical variation in the final position of the pipe from the line and grade established by the OWNER shall be permitted only to the extent of 1-in. per 10-ft., provided that such variation shall be regular and only in one direction and that the final grade of the flow line shall be in the direction indicated on the plans.

Once jacking of pipe is begun, the operation shall be carried on without interruption, insofar as practicable to prevent the pipe from becoming firmly set in the embankment.

Any pipe damaged in jacking operations shall be repaired if approved by the OWNER or removed and replaced by the CONTRACTOR at the CONTRACTOR'S entire expense.

The pits or trenches excavated to facilitate jacking operations shall be filled as soon as practicable or as directed by the OWNER. The pits or trenches shall then be backfilled in accordance with the location and conditions as are covered elsewhere in these specifications.

If a carrier pipe is laid through an encasement pipe, the bedding of crushed rock, concrete, grout or granular material, if any, shall be considered a part of the unit price of the jacking operation.

503.3.3.3. Construction by Boring. The hole shall be bored mechanically with a suitable boring assembly designed to produce a smooth, straight shaft and so operated that the completed shaft shall be at the established line and grade. The size of the bored hole shall be of such diameter to provide ample clearance for bells or other joints. The holes are to be bored mechanically. The boring shall be done by using either a pilot hole or a dry bore method.

A pilot hole boring shall be constructed by the following method: An approximate 2-in. pilot hole shall be bored the entire length of the crossing and shall be checked for line and grade on the opposite end of the bore from the work pit. The pilot hole shall serve as the centerline of the larger diameter hole to be bored.

The dry bore shall be constructed as follows: The casing pipe shall be advanced as the soil is removed by augers. Bentonite may only be used as a lubricant. Casing shall be new or used steel conduit approved by the OWNER, with a minimum inside diameter sufficiently larger than the outside diameter of the carrier pipe or ducts to accommodate placement or removal.

All carrier pipe installed by boring shall be supported by a quarter point cradle of Class B or Class PB concrete as specified by the OWNER across the boring pit and to the first joint in the ditch section on each end. All pits should have crushed rock and sump areas to remove water. Where groundwater is found, pits shall be lined with filter fabric.

All voids shall be grouted per ASTM C476 Grout for Masonry and shall be considered a part of the unit price of the boring operation.

In addition to the requirements stated above, the applicable provisions of [Item 503.3.3.2. Construction by Jacking](#) in regard to the construction of trench, tolerance in line and cradle, method of operations, backfilling, etc. shall govern for construction by boring.

503.3.3.4. Construction by Guided Boring or Directional Drilling. Guided boring or directional drilling shall be accomplished according to the standards in *Trenchless Technology Guidelines* published by the International Society for Trenchless Technology.

503.3.3.5. Construction by Tunneling. The tunnel shall be excavated in such a manner and to such dimensions so as to permit placing of the proper supports necessary to protect the excavation. The CONTRACTOR shall take the proper precautions to avoid excavating earth or rock or shattering rock beyond the limits of excavation shown on the plans. All damages caused by excavating and blasting,

either to surface or subsurface structures, shall be repaired or replaced by the CONTRACTOR at its own cost and expense. Adequate provisions shall be made for safety and health of the workers. All equipment operated in the tunnel shall be powered by either air or electricity. No equipment shall be permitted in the tunnel that uses a petroleum product such as fuel.

Electric lights shall be used for illumination of completed portions of the tunnel used for passage and wherever lighting is needed for inspection of the work. A sufficient number of lamps shall be used to properly illuminate the work, and all wiring for electric power and lights shall be installed and maintained in a safe and secure manner in accordance with the current applicable electrical specifications of the OWNER. CONTRACTOR shall maintain the tunnel air in a condition suitable for the health of the workers and sufficiently clear for surveying operations. A sufficient supply of fresh air shall be provided and maintained at all times in all underground places. Provisions shall be made for the quick and complete removal of gases and dust resulting from blasting or other tunnel operations. Except when unnecessary due to natural ventilation, artificial ventilation shall be maintained in the tunnel by ventilating plants of ample capacity operated when needed to meet the preceding requirements.

If required by the plans or if required for safety, suitable steel or timber sheeting, shoring and bracing in accordance with [Item 107.20.3](#), Trench Safety shall be used to support the sides and roof of the excavation. When the installation is completed, and if approved by the OWNER, supports may be left in place, provided that they clear the encasement or carrier pipe. No separate payment shall be made for supports left in place. Nothing contained herein shall prevent the CONTRACTOR from placing such temporary or permanent supports as it shall deem necessary, nor shall anything contained herein be construed as relieving the CONTRACTOR from its full responsibility for the safety of workers and for all damages to personal property caused by its operations.

If the tunnel is to be lined with concrete as a monolithic structure, then the overbreak, if any, or voids shall be poured with Class A or Class PA concrete as specified by the OWNER. The CONTRACTOR shall not be compensated for overbreaks.

No pipe shall be placed until the foundation is in a condition satisfactory to the OWNER. Tunnel dimensions shown on the plans are minimum dimensions. Any excess excavation and subsequent backfill, concrete or grout fill shall be at the expense of the CONTRACTOR. The pipe shall be laid in the tunnel true to line and grade. Tolerance in line and grade shall be as specified in [Item 503.3.3.2](#), Construction by Jacking.

If indicated or specified, the entire void between the outside of the pipe and the tunnel walls or the inside face of the tunnel lining shall be grouted per ASTM C476 Grout for Masonry unless the permanent sheeting, bottom, sides and roof of the tunnel are in a condition satisfactory to the OWNER. The minimum thickness of grout backfill where specified shall be maintained throughout. Grout required for backfill in excess of the minimum dimensions shown on the plans shall be at the entire expense of the CONTRACTOR.

All pipe damaged during construction operations shall be repaired, if approved by the OWNER, or removed and replaced by the CONTRACTOR at the CONTRACTOR'S entire expense.

503.3.3.6. Joints. If corrugated galvanized metal pipe is used, joints may be made by field bolting or by connecting bands, whichever is feasible. When reinforced concrete pipe 24-in. and larger in diameter with tongue-and-groove joints is used for the encasement pipe, the interior joints for the full circumference shall be sealed, packed with mortar and finished smooth and even with the adjacent section of pipe.

503.4. MEASUREMENT AND PAYMENT.

Jacking, boring or tunneling shall be measured for payment in linear feet along the centerline of the pipe measured from face to face of the trench ends or pit walls between which the jacking, boring or tunneling traverses and shall not be classified for payment according to depth. The carrier pipe, when required, shall be measured for payment as provided in the contract documents. Jacking, boring or tunneling shall be paid for at the contract unit price per linear foot (m) complete in place, as provided in the proposal and contract. Open pits required for jacking, boring or tunneling shall be considered incidental and shall not be paid for separately. The contract unit price shall be the total compensation for furnishing and placing all materials including encasement

pipe, if required, and grout backfill; for all jacking, boring, tunneling, excavation and backfill; for all sheeting, shoring, bracing and drainage; for disposal of all surplus materials; and for all labor, tools, equipment and incidentals necessary to complete the work, all in accordance with the plans and these specifications. The carrier pipe, when required, shall be paid for as provided in the contract documents.

No additional compensation will be provided for jacking, boring, or tunneling in lieu of open cut approved by the OWNER. The removal of any obstruction that conflicts with the placing of the pipe will not be measured for payment or paid for as a separate contract pay item. The removal of any such obstruction will be included in such contract pay items as are provided in the proposal and contract. The drilling of pilot holes will be considered as incidental work and the cost thereof shall be included in such contract pay items as are provided in the proposal and contract. The CONTRACTOR shall only be paid for the limits as shown on the plans. Any overrun, except as approved by the OWNER, shall be at the CONTRACTOR'S expense.

ITEM 504. OPEN CUT – BACKFILL

504.1. GENERAL

This section addresses the process of open cut and backfill. Backfill shall mean embedment and final backfill. Embedment shall mean bedding and initial backfill. Bedding shall mean the material upon which a pipe rests. Initial backfill shall mean material that covers the storm sewer, wastewater collection system, and water lines. Final backfill shall mean the material required to fill the trench from the top of the initial backfill to ground elevation or subgrade of a street.

Work shall include:

- (1) Pollution Prevention shall be performed in accordance with [Item 202](#). Temporary Erosion, Sedimentation, and Water Pollution Prevention and Control;
- (2) Site preparation as part of open cut installation shall be performed in accordance with [Item 203](#). Site Preparation, except shall be considered as incidental work and the cost thereof shall be included in such contract pay item as provided in the proposal and contract;
- (3) Excavation shall be performed in accordance with [Item 203.2](#). Unclassified Channel Excavation.
- (4) Landscaping shall be performed in accordance with [Item 204](#). Landscaping;
- (5) Trench safety shall be performed in accordance with [Item 107.20](#). Protection of Work and of Persons and Property;
- (6) Restoration of disturbed areas shall be performed in accordance with [Item 107.27](#). Restoration of Property.

504.2. MATERIALS

504.2.1. Pipe Embedment Material for Special Applications. The pipe shall be embedded in accordance with details shown on the plans for the type of embedment indicated or specified. In general, if no particular type of embedment is shown on the plans nor specified, CONTRACTOR shall use material according to pipe manufacturer recommendation.

504.2.2. Pipe Embedment Material for Storm, Water and Wastewater Mains.

504.2.2.1. Crushed Stone Embedment. The aggregates shall consist of durable particles of crushed stone, free from frozen material or injurious amounts of salt, alkali, organic matter or other material either free or as adherent coating, and its quality shall be reasonably uniform throughout. It shall have a wear of not more than 40-percent when tested in accordance with TxDOT Test Method Tex-410-A Abrasion of Coarse Aggregate Using the Los Angeles Machine.

When tested by standard laboratory methods, crushed stone embedment for each gradation shall meet the requirements of Table 504.2.2.1.(a) Crushed Stone Embedment Gradations.

Table 504.2.2.1.(a) Crushed Stone Embedment Gradations

Passing or Retained on Sieve	Percent by Weight
Standard Crushed Stone — Aggregate Grade 4	
Retained on 1½-in. sieve	0%
Retained on 1-in. sieve	0 to 5%
Retained on ½-in. sieve	40 to 75%
Retained on No. 4 sieve	90 to 100%
Retained on No. 8 sieve	95 to 100%
Blended Crushed Stone — Aggregate Grade 48	
Retained on 1½-in. sieve	0%
Retained on 1-in. sieve	0 to 5%
Retained on ½-in. sieve	40 to 75%
Retained on No. 4 sieve	75 to 100%
Retained on No. 8 sieve	90 to 100%
Fine Crushed Stone — Aggregate Grade 8	
Retained on ½-in. sieve	0%
Retained on ¾-in. sieve	0 to 5%
Retained on No. 4 sieve	35 to 60%
Retained on No. 8 sieve	90 to 100%
Coarse Crushed Stone	
Passing 1½-in. sieve	100%
Retained on ¾-in. sieve	100%

504.2.2.2. Granular Material. Granular material shall be free flowing, such as sand or hydraulically graded crushed stone fines, or mixed sand and gravel, or sandy loam. The material shall be free from lumps, stones over two inches in diameter, clay and organic matter.

504.2.2.3. Select Material. Select material shall be gravel, fine stone cuttings, sand, sandy loam or loam free from excessive clay. Stone cuttings shall have no dimension greater than two-inches.

504.2.2.4. Crushed Stone for Foundation. Crushed stone for foundation shall meet the requirements for [Item 504.2.2.1](#). Crushed Stone Embedment except the gradation shall be according to Table 504.2.2.4.(a) Crushed Stone for Foundation Gradation.

Table 504.2.2.4.(a) Crushed Stone for Foundation Gradation

Passing or Retained on Sieve	Percent by Weight
Passing 5-in. sieve	100%
Retained on 2-in. sieve	100%

504.2.2.5. Natural Gravel. Natural gravel shall consist of uncrushed stones meeting the requirements for wear as outlined in [Item 504.2.2.1](#). Crushed Stone Embedment. The material shall be washed and screened and not have by weight more than one-percent organic matter, clays or loam and not more than five-percent by weight of any one of or combination of slate, shale, schist or soft particles of sandstone. The gradation shall be according to Table 504.2.2.5. (a) Natural Gravel Gradation.

504.2.2.6. Sand. Sand shall consist of clean, hard, durable, uncoated grains, free from lumps and organic material. All particles must pass a No. 8 sieve.

504.2.3. Final Backfill. The trench shall be backfilled in accordance with details shown on the plans for the type of backfill indicated or specified.

If filter fabric is required by OWNER, place filter fabric conforming to TxDOT Specification DMS-6200 between the native soil and the backfill.

504.2.3.1. Type “A” Backfill. Type “A” backfill shall meet the following requirements:

504.2.3.1.1. Tests. The liquid limit shall not exceed 35 when tested in accordance with ASTM D4318 Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils. The plasticity index shall not exceed 10 when calculated in accordance with ASTM D4318. The linear shrinkage shall not exceed six-percent when Type “A” backfill is used for pavement base material.

504.2.3.1.2. Gradation. The material when tested by standard laboratory methods shall meet the gradation in Table 504.2.3.1.2.(a) Type “A” Gradation.

Table 504.2.3.1.2.(a) Final Backfill Type “A” Gradation

Passing or Retained on Sieve	Percent by Weight
Passing 2-in. sieve (50 mm)	100%
Passing ½-in. sieve (12.5 mm)	50 to 85%
Passing No. 4 sieve (4.75 mm)	20 to 65%
Passing No. 100 sieve (150 µm)	0 to 5%

504.2.3.2. Alternate Allowable Type “A”. Field sand having the following requirements may be used in lieu of Type “A” backfill for filling trenches. The field sand material shall be obtained from approved sources; shall consist of durable particles; and shall be free of thin or elongated pieces, lumps of clay, soil, loam or vegetable matter. The material shall be required to meet the gradation in Table 504.2.3.2.(a) Alternate Allowable Type “A” Gradation when tested from source of supply test samples.

Table 504.2.3.2.(a) Alternate Allowable Type “A” Gradation

Passing or Retained on Sieve	Percent by Weight
Passing No. 4 sieve (4.75 mm)	100%
Passing No. 16 sieve (1.18 mm)	80 to 100%
Passing No. 50 sieve (300 µm)	20 to 60%
Passing No. 100 sieve (150 µm)	10 to 40%
Passing No. 200 sieve (75 µm)	0 to 10%

504.2.3.3. Type “B” Backfill. Type “B” backfill is native or imported material. Type “B” backfill shall at minimum meet the following quality requirements.

504.2.3.3.1. Tests. The liquid limit shall not exceed 35 when tested in accordance with ASTM D4318. The plasticity index shall not exceed 12 when tested in accordance with ASTM D4318.

504.2.3.3.2. Gradation. Type “B” backfill shall meet the requirements in Table 504.2.3.3.2.(a) Final Backfill Type “B” Requirements.

Table 504.2.3.3.2.(a) Final Backfill Type “B” Requirements

Description	Limits
Stone. All stone must be reasonably uniform in distribution throughout the backfill material in order to be considered acceptable for use, regardless of the width of trench in which the material is to be used.	
Maximum amount of stone permitted, regardless of trench width, as a percent of final backfill volume	50%
Largest dimension of stone allowed in trenches 4-ft. or less in width	3-in.
Largest dimension stone to total final backfill volume, regardless of trench width	3%
Largest dimension of stone allowed in trenches greater than 4 ft. in width	6-in. Total volume not to exceed 1% of backfill
Lumps. All lumps must be reasonably uniform in distribution throughout the backfill material in order to be considered acceptable for use, regardless of the width of trench in which the material is to be used	
Maximum amount of clay or gumbo lumps permitted, regardless of trench width, as a percent of final backfill volume	25%
Largest dimension of clay or gumbo lumps in trenches 4-ft. or less in width	6-in.
Largest dimension of clay or gumbo lumps permitted in trench greater than 4-ft. in width.	10-in. Total volume not to exceed 1% of backfill

504.2.3.3.3. Additional Requirements. Additional requirements for Type “B” backfill when used in streets:

- (1) 35 percent or less shall pass the No. 200 sieve.
- (2) Material otherwise meeting specifications requirements and having a PI greater than 15 shall be considered as suitable for use only when compaction procedure includes mechanical compaction.
- (3) Material shall be of such characteristics that it shall stabilize without the use of lime or other similar additive and form an acceptable street subbase material.

504.2.3.4. Flowable or Stabilized Backfill. Flowable or stabilized backfill shall consist of a mixture of native soils or manufactured materials, cement and/or fly ash, and water which produces a material with unconfined compressive strength of between 250-psi and 450-psi after 28-days. Any materials used shall be primarily granular, with a plasticity index <12 and with 100% passing a ¾-in. sieve. The flowable mixture shall be mixed in a pug mill, concrete mixer, or transit mixer and shall have a minimum slump of 5-in. The flowable mixture must be allowed to set prior to the placement of any overlying material. Stabilized backfill as defined in [Item 504.6.2](#). Stabilized Backfill requires manual compaction.

504.2.3.5. Modified Flowable Backfill. Modified flowable backfill in areas of possible future excavation such as utility installations shall consist of a mixture of native soils or manufactured materials, cement and/or fly ash, air-entraining material, and water which produces a material with unconfined compressive strength of between 50-psi and 150-psi after 28-days. Modified flowable backfill in permanent areas such as abandoned pipe closures, abutments and embankments shall contain similar materials and shall have an unconfined compressive strength of greater than 150-psi after 28 days. Any materials used shall be primarily granular, with a plasticity index <12 and with 100% passing a ¾-in. sieve. The flowable mixture shall be mixed in a pug mill, concrete mixer, or transit mixer and shall have a minimum slump of 5-in. The flowable mixture must be allowed to set prior to the placement of any overlying material.

504.2.3.6. Fast Set Flowable Backfill. Fast Set Flowable Backfill shall be brought to site via volumetric concrete mixer and consist of an appropriate amount of cement (with other additives as necessary) mixed with mortar sand to flow and fill all voids in the excavation. This fill shall develop a compressive strength of 1120 pounds per square foot one hour after placement, and a 28-day compressive strength with the range of 25 to 100 psi. The material must be such that it can be capped in one and one-half to two hours.

504.2.4. Rejection. Materials that fail to meet the requirements of these specifications may be rejected by the OWNER. Such rejection shall incur no cost to the OWNER. Material sources, from which materials with properties not meeting these specifications are delivered, may be rejected as further supply sources to the project by the OWNER. Such rejection shall incur no cost to the OWNER.

504.3. EXCAVATION AND FOUNDATION

504.3.1. Excavation. Excavation shall be performed in accordance with [Item 203](#). Site Preparation.

504.3.2. Foundation. During the progress of the work, should the foundation for the conduits be in material unsuitable for the subgrade of the conduit, which is not the result of the CONTRACTOR'S negligence to make proper provisions for adequate drainage of the excavation, the CONTRACTOR shall remove such unsuitable subgrade material to the depth directed by the OWNER. The space thus created shall be filled with stone as described in [Item 504.2.2.4](#). Crushed Stone for Foundation, coarse crushed stone as described in [Item 504.2.2.1](#). Crushed Stone Embedment, or Class B or Class PB concrete (as specified by the OWNER) as described in [Item 702.3](#). Mix Design and Mixing Concrete for Structures. The type of material to be used for the foundation shall be determined by the OWNER. In lieu of removing the subgrade material or in conjunction with placement of the foundation material, the OWNER may require a geotextile material as described in the contract documents to be placed between the bedding and the subgrade or between the foundation material and the subgrade.

The entire foundation area in the bottom of all excavation shall be firm, stable and at uniform density as nearly as practicable. Unless necessary, materials shall not be disturbed. The final cleaning off and preparing of the foundation area shall be done immediately prior to the placing of the embedment materials or structures.

504.3.2.1. Foundation Measurement. Foundation material shall be measured for payment complete in place to the dimensions prescribed by the OWNER. Geotextile material, if used, shall be measured for payment complete in place to the dimensions prescribed by the OWNER.

504.3.2.2. Foundation Payment. Foundation material shall be paid for at the contract unit bid price in cubic yards as provided for in the contract. Geotextile material shall be paid for at the contract unit bid price per square yard as provided for in the contract. If a bid item is not established in the contract for foundation material and/or geotextile material, it shall be considered subsidiary to the contract (non-pay item).

In case of failure to make adequate pumping, draining and bailing provisions, resulting in unstable subgrade conditions, and which shall require any of the hereinbefore described foundations, such foundations shall be placed at the entire cost of the CONTRACTOR and shall not be measured or paid for as separate contract pay items.

The contract unit price shall be total compensation for furnishing all labor, tools, materials, equipment and incidentals necessary to complete the work, including all excavation and disposal of surplus material.

504.4. BACKFILL – GENERAL REQUIREMENTS

504.4.1. Description. This specification shall govern construction of all types of storm drain, wastewater collection systems, and water structures except where the requirements are revised by another governing specification. All structures shall be constructed in accordance with the design requirements, with the details shown on the plans, and with the requirements herein provided. Other applicable sections or parts of these specifications shall govern for such miscellaneous and incidental construction necessary to complete the work in accordance with the plans and specifications.

For specific applications, pipe materials, etc. refer to [Section 504.5.2](#). Embedment Classes.

504.4.2. Materials and Equipment. All materials used in the construction of work specified in this division shall conform to the applicable sections of these specifications and approved by the OWNER. Any materials placed before approval of the OWNER shall be removed, if directed by the OWNER, and replaced with approved materials.

All machinery and equipment necessary for the construction of the work specified herein shall be on the project and shall be maintained in good condition to insure the completion of the work without excessive delays for repairs and replacements. Equipment used for disposal of surplus materials beyond the limits of the work shall be such as to avoid spilling or wasting of materials along the line of haul. The CONTRACTOR shall immediately clean up all materials spilled or wasted along the line of haul. The OWNER reserves the right to approve the location and methods of disposal for surplus material.

504.4.2.1. Water for Construction. Unless otherwise specified in the contract, water required for construction and furnished from the OWNER'S distribution system shall be paid and accounted for as prescribed by the OWNER. The CONTRACTOR shall make and bear the cost of all necessary arrangements and means for hauling the water. Water shall be furnished free of charge from the OWNER'S main, if available, for filling newly constructed water mains for flushing, sterilizing and hydrostatic testing. Construction water, if delivered through a fire hydrant meter, shall be protected by a reduced pressure zone assembly provided at the CONTRACTOR'S expense.

504.4.2.1.1. Use of Fire Hydrant and Valves. The CONTRACTOR shall not operate any fire hydrant or valve in the existing water system without the permission of the OWNER. If permission is granted, the CONTRACTOR shall use only approved fire hydrant and valve wrenches. The OWNER shall inspect all fire hydrants and/or valves operated by the CONTRACTOR prior to final acceptance of the project. All repairs or replacements required to restore satisfactory operation of fire hydrants and/or valves shall be at the expense of the CONTRACTOR.

504.4.2.2. Material and Equipment Storage. The CONTRACTOR shall confine equipment, storage of materials, and construction operations to the area shown on the Contract Drawings or as directed by OWNER. Storage shall not unreasonably encumber the site or public right-of-way with construction equipment or materials. Materials shall be stored in a manner to best protect and preserve the material to the satisfaction of the OWNER. Materials shall be sorted and stored neatly and accessibly. Materials not properly stored shall not be eligible for inclusion in partial pay estimates. Storage shall also comply with all requirements of [Item 106](#), Control of Material.

504.4.3. Sequence. The sequence of operations to be followed shall be prepared by the CONTRACTOR for approval by the OWNER. The sequence shall meet the job requirements for completion time, avoid interference with plant operations and conform to plan and specification requirements. The construction of all storm drain and wastewater collection systems shall begin at the outlet or lower end, unless otherwise directed by the OWNER. Tributary lines for storm drain and wastewater collection systems shall not be started until the main line has been built to their junction points.

504.4.4. Connections. The connections of conduits or appurtenances to conduits shall be made in accordance with the plans and as directed by the OWNER. This work shall be done in such a manner so as not to damage any of the structures involved. Any damage to the structures due to the connection shall be repaired at the CONTRACTOR'S expense. No connecting conduit shall project beyond the inside surface of other conduits or appurtenances, except in case of pipe laid through a manhole.

504.5. EMBEDMENT

Embedment is the bedding and initial backfill. The type of embedment to be used for storm water collection systems, wastewater collection systems or water mains shall be specified in the contract documents or on the plans.

504.5.1. General**504.5.1.1. Terms.**

D — Inside diameter of the pipe.

OD — Outside diameter of the pipe.

B_c — Outside diameter of the pipe.

B_d — Trench width.

Stone cuttings are rock trench excavated material. The maximum allowable dimension of the stone to be used for embedment is 1-in.

Densities shall be shown as a percent of the maximum dry density at not less than 2% below optimum moisture of samples of the material as determined by the ASTM D698 Maximum Density Optimum Moisture Test.

504.5.1.2. Flexible Pipe. 16-in. or greater diameter flexible pipe may be strutted horizontally and vertically prior to backfilling. After backfilling, the struts shall be removed and the deflection checked to verify that excessive deflection as specified has not occurred. If excessive deflection has occurred, the pipe shall be removed and reinstalled.

504.5.1.3. Trench Dimensions. Trench dimensions shall be determined according to Table 504.5.1.3.(a) Trench Dimensions unless otherwise specified as greater.

Table 504.5.1.3.(a) Trench Dimensions

Pipe size	Trench Dimensions
Minimum Depth of Trench Below the Pipe	
27-in. and smaller	3-in.
30-in. to 60-in.	4-in.
66-in and larger	6-in.
Limiting Trench Width	
24-in. pipe and smaller	24-in. or O.D. of the pipe plus 16-in., whichever is greater
Greater than 24-in., to and including 72-in.	O.D. of the pipe installed plus 24-in.
Larger than 72-in.	O.D. times 1.25 plus 1-ft.

504.5.2. Embedment Classes.

504.5.2.1. Class “A” Embedment. See Standard Drawing 3010. The embedment consists of concrete bedding and initial backfill of granular material.

After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{4}B_c$, minimum of 6 in. measured from the outside of the pipe bell, the pipe shall be laid to grade on supporting brick or concrete block and jointed as specified. A compressible strip shall be placed between the pipe and the support. The pipe shall be restrained, if required, to prevent flotation. Class B or Class PB concrete as specified by the OWNER shall be poured on either side of the pipe to form the bedding under the pipe and up the sides of the pipe $\frac{1}{4}B_c$. The concrete placed under the pipe shall have a sufficient fluidity so it can flow under the haunches and be puddled to insure even support.

The initial backfill layer shall be granular material and shall be brought to a point 12-in. above the top of the pipe.

504.5.2.2. Class “A-1” Embedment. See Standard Drawing 3010. The embedment consists of crushed stone bedding and a cap of concrete as initial backfill.

After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{4}B_c$, minimum of 6 in. measured from the outside of the pipe bell, the bedding layer shall be brought to a point slightly above grade with compacted standard gradation crushed stone. Bell holes shall be formed, if required, a trough scooped out to grade, and the pipe laid and jointed as specified. The stone shall then be brought up in uniform layers on either side of the pipe $\frac{1}{2}B_c$.

Class B or Class PB concrete as specified by the OWNER, plain or reinforced as specified in the plans, shall be poured over the top of the pipe and bells to cover the pipe with a thickness of $\frac{1}{4}B_c$, 4-in. minimum to form the initial backfill layer.

504.5.2.3. Class “B” Embedment. See Standard Drawing 3020. The embedment consists of crushed stone bedding and initial backfill of select material or granular material.

After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{8}B_c$, minimum of 6 in. measured from the outside of the pipe bell, the bedding shall be brought up to a point slightly above the grade with stone cuttings or crushed stone, standard gradation. Bell holes shall be formed, a trough scooped out to grade and the pipe laid and joined as specified. The crushed stone or stone cuttings shall then be brought up the sides of the pipe in uniform layers $\frac{1}{2}B_c$.

The initial backfill shall consist of granular material. The material shall be placed on top of the crushed stone in uniform layers on either side of the pipe to a point 12 in. above the top of the pipe and compacted to at least 90-percent of maximum density as determined by ASTM D698.

504.5.2.4. Class “B+” Embedment. See Standard Drawing 3020. The embedment consists of fine crushed stone bedding and initial backfill of granular material.

After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{8}B_c$, minimum of 6 in. measured from the outside of the pipe bell, the bedding shall be brought up to a point slightly above grade with fine crushed stone. Bell holes shall be formed, a trough scooped out to grade and the pipe laid and jointed as specified. The stone shall then be brought up in uniform layers on either side of the pipe $\frac{1}{2}B_c$.

The initial backfill shall consist of granular material. The material shall be placed on top of the stone and shall be brought up in uniform layers on either side of the pipe to a point 12-in. above the top of the pipe. Density shall be at least 90-percent of maximum density as determined by ASTM D698.

504.5.2.5. Class “B-1” Embedment. See Standard Drawing 3020. The embedment consists of fine crushed stone bedding and initial backfill of select material or granular material.

After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{8}B_c$, minimum 6 in. for measured from the outside of the pipe bell, the bedding shall be brought up to a point slightly above grade with fine crushed stone. Bell holes shall be formed and the pipe laid and jointed as specified.

The stone shall then be brought up in uniform layers on either side of the pipe $\frac{3}{4}B_c$.

The initial backfill shall consist of compacted granular material brought up to a point 6 in. above the top of the pipe. Density shall be at least 90-percent of maximum density as determined by ASTM D698.

504.5.2.6. Class “B-2” Embedment. See Standard Drawing 3030. The embedment consists of fine crushed stone bedding and initial backfill of select material or granular material.

After the trench has been cut to a depth below the barrel of the pipe 6 in. measured from the outside of the pipe bell, the bedding layer shall be brought to a point slightly above grade with compacted fine crushed stone. Bell holes shall be formed, if required, a trough scooped out to grade, and the pipe laid and jointed as specified. The stone bedding layer shall then be brought up in uniform layers on either side of the pipe $\frac{3}{4}B_c$.

The initial backfill shall consist of compacted granular material and shall be brought to a point 12 in. above the top of the pipe. Density shall be at least 90-percent of maximum density as determined by ASTM D698.

504.5.2.7. Class “B-3” Embedment. See Standard Drawing 3030. The embedment consists of granular material.

After the trench has been cut to a depth below the barrel of the pipe a distance of minimum of 6 in. measured from the outside of the pipe bell, the bedding shall be brought to a point slightly above grade with compacted fine sand. Bell holes shall be formed, if required, a trough scooped out to grade, and the pipe laid and jointed as specified. The granular material shall then be brought up in uniform layers on either side of the pipe and over the pipe to a point 12 in. above the top of the pipe.

504.5.2.8. Class “B-4” Embedment. See Standard Drawing 3030. The embedment consists of cement-treated backfill.

After the trench has been cut to a depth below the barrel of the pipe a distance of minimum of 6 in. measured from the outside of the pipe bell, the bedding shall be brought to a point slightly above grade with cement-treated backfill. Bell holes shall be formed, if required, a trough scooped out to grade and the pipe laid and jointed as specified. The cement-treated backfill shall then be brought up to uniform layers on either side of the pipe and over the pipe to a point 6 in. above the top of the pipe.

504.5.2.9. Class “C” Embedment. See Standard Drawing 3040. The embedment is a bedding of crushed stone or stone cuttings and initial backfill of select material or granular material.

After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{8}B_c$, minimum of 6 in. measured from the outside of the pipe bell, the bedding shall be brought up to a point slightly above grade with stone cuttings or standard crushed stone. Bell holes shall be formed, a trough scooped out to grade, and the pipe laid and jointed as specified. The stone shall then be brought up in uniform compacted layers on either side of the pipe $\frac{1}{6}B_c$.

The initial backfill shall be granular material and shall be brought up in uniform compacted layers to a point 6 in. above the top of the pipe. Density shall be at least 90-percent of maximum density as determined by ASTM D698.

504.5.2.10. Class “C+” Embedment. See Standard Drawing 3040. The embedment consists of fine crushed stone bedding and initial backfill of granular material.

After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{8}B_c$, minimum of 6 in. measured from the outside of the pipe bell, the bedding layer shall be brought up to a point slightly above grade with fine crushed stone. Bell holes shall be formed, a trough scooped out to grade, and the pipe laid and jointed as specified. The stone shall then be brought up in uniform, compacted layers on either side of the pipe $\frac{1}{6}B_c$.

The initial backfill shall be granular material and shall be brought up in uniform, compacted layers to a point 6 in. above the top of the pipe. Density shall be at least 90-percent of maximum density as determined by ASTM D698.

504.5.2.11. Class “C-1” Embedment. See Standard Drawing 3040. The embedment shall consist of fine sand bedding and initial backfill of granular material.

After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{8}B_c$, minimum of 6 in. measured from the outside of the pipe bell, the bedding layer shall be brought up to a point slightly above grade with fine sand. Bell holes shall be formed, a trough scooped out to grade and the pipe laid and jointed as specified. The sand shall then be brought up in uniform compacted layers on either side of the pipe $\frac{1}{6}B_c$.

The embedment backfill shall be granular material and shall be brought up in uniform, compacted layers to a point 6-in. above the top of the pipe. Density shall be at least 90-percent of maximum density as determined by ASTM D698.

504.5.2.12. Class “D+” Embedment. See Standard Drawing 3050. The embedment consists of select material.

After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{8}B_c$, minimum of 6 in. measured from the outside of the pipe bell, the embedment shall be brought up to a point slightly above grade with select material. Bell holes shall be formed, a trough scooped out to grade and the pipe laid and jointed as specified. The material shall then be brought up in uniform compacted layers to a point 6 in. over the top of the pipe. Density shall be at least 90-percent of maximum density as determined by ASTM D698.

504.5.2.13. Class “G” Embedment. See Standard Drawing 3050. The embedment consists of Class B or Class PB concrete as specified by the OWNER.

After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{4}B_c$, 6 in. minimum measured from the outside of the pipe bell, the pipe shall be laid and jointed as specified. The pipe shall be supported by brick or concrete block. A compressible strip shall be placed between the pipe and support. The pipe shall be restrained, if required, to prevent flotation. Class B or Class PB

concrete as specified by the OWNER shall be poured on either side of the pipe to form the embedment under the pipe, up the sides and over the top of the pipe and bells with a minimum thickness of 6 in. The concrete placed under the bell shall have a sufficient fluidity so it can flow under the haunches and be puddled to insure even support.

504.5.2.14. Class “G-1” Embedment. See Standard Drawing 3060. The embedment consists of Class “G” embedment as specified above and a trench backfill of Class B or Class PB concrete as specified by the OWNER or stabilized backfill, whichever is specified in the plans, and a 6 in. thick Class B or Class PB (as specified by the OWNER) concrete cap as initial backfill.

504.5.2.15. Class “H” Embedment. See Standard Drawing 3060. The embedment consists of a completely encased pipe with standard Crushed Stone, Grade 4. After the trench has been cut to a depth below the barrel of the pipe a distance of $\frac{1}{2}B_c$, 6 in. minimum, the bedding layer shall be brought to a point slightly above grade with compacted crushed stone. Bell holes shall be formed, a trough scooped out to grade and the pipe laid and jointed as specified. The material shall then be brought up in uniform compacted layers of 6 in. to a point 6 in. over the top of the pipe.

504.5.2.16. Alternate Embedment for Concrete Pipe. The Engineer may design alternate embedment for concrete pipe. Such embedment shall be designed according to Design Data 40, Standard Installations and Bedding Factors for the Indirect Design Method written by the American Concrete Pipe Association. Such embedment shall be constructed as shown on the plans.

504.5.3. Initial Backfill.

504.5.3.1. General. Initial backfill is the material that covers the storm drain system, wastewater collection system, and water lines. Backfill procedure is that procedure required to return trenches or excavated areas to a condition satisfactory to the OWNER. Such backfilling occurs in two general areas. They are: (1) areas not subject to vehicular traffic; and (2) areas subjected directly to, or influenced by, vehicular traffic.

The methods of backfilling to be used shall vary with the width of trench, the character of the materials excavated, the method of excavation, the type of conduit and the degree of compaction required. The placing of backfill shall not begin until the pipe structure has been properly bedded and jointed and until approval has been given by the OWNER. The excavation shall be backfilled only with approved material.

504.5.3.2. Compaction. Compaction of all backfill material shall be performed in a manner that shall not crack, crush and/or cause the installed pipe to be moved from the established grade and/or alignment, as shown on the plans. Satisfactory density shall be obtained at various depths on all backfill material as indicated from random selected test points prior to the required exfiltration or pressure tests that are to be performed on lines being constructed. The required moisture content shall be at not less than 2% below nor more than 4% above the optimum moisture of the material or as specified by the OWNER. In-place density/moisture content shall be tested and verified as specified by the OWNER, or at a minimum frequency of once per 300-linear-feet per 1-foot of compacted depth.

504.5.3.2.1. Densities — Areas Subjected To or Influenced by Vehicular Traffic. The trench backfill shall be mechanically compacted to the top of the subgrade in 6-in. loose lifts to at least 95-percent of maximum density as determined by ASTM D698 Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lb/ft³). The embedment shall be compacted by a method approved by the OWNER to a density as specified under the description of the embedment as outlined in [Item 504.5. Embedment](#).

504.5.3.2.2. Densities — Areas Not Subjected To or Influenced by Vehicular Traffic. The trench backfill shall be placed in layers not more than 10-in. loose depth and shall be compacted by mechanical means, subject to the restrictions outlined in [Item 504.5.3.2.5. Compaction Methods](#) to at least 90-percent of maximum density as determined by ASTM D698. The embedment shall be compacted by a method approved by the OWNER to a density as specified under the description of the embedment required as outlined in [Item 504.5. Embedment](#).

504.5.3.2.3. Special Situations. In areas specifically designated in the plans and specifications, the entire backfill shall be backfilled and compacted to the density specified.

504.5.3.2.4. Limitations. Densities as specified shall be obtained as the project progresses. No more than 75-percent of the pipe installation on the project is to be completed until specified compaction and density requirements have been ascertained on backfill material for at least 25-percent of the pipe laid, or until an approval to proceed with pipe installation has been given by the OWNER.

504.5.3.2.5. Compaction Methods. The method of compaction shall be left to the discretion of the CONTRACTOR with the following exception, unless otherwise specified, provided the degree of compaction is obtained and provided that the pipe is not damaged in the process. If any potential damage to the pipe due to a method of compaction exists, in the opinion of the OWNER, that method of compaction shall not be allowed.

Compaction of any backfill material by flooding or jetting shall not be permitted.

Hand-operated mechanical tampers may be used with approval of the OWNER for compacting backfill.

504.5.3.3. Rejection. If the backfill does not meet the specified density and optimum moisture requirements throughout its depth, the OWNER shall require its removal and replacement to meet the above requirements at the CONTRACTOR'S expense.

504.6. FINAL BACKFILL

Final backfill material is the material required to fill the trench from the top of the initial backfill to ground elevation or subgrade of a street.

504.6.1. Excavated Material. Excavated material may be used in the trench backfill, provided (1) it meets the requirements of [Item 504.2.3.3](#), Type "B" backfill, and (2) the material is approved for backfill by the OWNER.

504.6.2. Stabilized Backfill. Stabilized backfill shall consist of a mixture of native soils including the trench excavation, approved for use by the OWNER, and two sacks of cement per cubic-yard. All material shall be mixed in a concrete mixer or transit mix unless approved otherwise by the OWNER. The stabilized backfill shall be compacted in a moist condition or water added to provide a free flowing mixture. If a free flowing mixture is used, the initial set must be permitted prior to placement of any material on the surface of the stabilized backfill.

504.6.3. Concrete Backfill. Concrete backfill shall consist of selected stone material or granular material mixed with a minimum of two sacks of cement per cubic-yard. All material shall be mixed in a concrete mixer or transit mixed unless approved otherwise by the OWNER.

504.6.4. Granular Material Backfill. Granular material backfill shall meet the requirements of [Item 504.2.2.2](#), Granular Material.

504.6.5. Sand Backfill. Sand backfill shall meet the requirements of [Item 504.2.2.6](#), Sand.

504.6.6. Flowable Backfill. Flowable backfill shall meet the requirements of [Item 504.2.3.4](#), Flowable Backfill.

504.6.7. Modified Flowable Backfill. Modified flowable backfill shall meet the requirements of [Item 504.2.3.5](#), Modified Flowable Backfill.

504.6.8. Fast Set Flowable Backfill. Fast Set Flowable Backfill shall meet the requirements of [Item 504.2.3.6](#), Fast Set Flowable Backfill.

504.7. MEASUREMENT AND PAYMENT OF BACKFILL

504.7.1. Measurement of Backfill Material. Measurement of backfill, which includes embedment and final backfill, shall be made per linear-foot of pipe only if a separate bid item is established in the Contract.

504.7.2. Payment of Backfill Material. Payment for backfill shall be made at the contract unit price per linear-foot of pipe only if a separate bid item is established in the Contract. This shall include furnishing and placing all materials and for all labor, tools, equipment and incidentals necessary to complete the work, all in accordance with the plans and specifications. No allowance for waste shall be made.

504.7.2.1. Special Embedment. If the OWNER orders an embedment material other than that specified in the Contract, it shall be paid for as an extra in price per linear foot of pipe, as compacted in place, except if another class embedment is ordered by the OWNER because the CONTRACTOR has over-excavated the trench width.

If the CONTRACTOR over-excavates the trench width and the OWNER orders another class of embedment to be used, the embedment shall be paid per linear-foot of pipe, compacted in place for the embedment originally specified if the original embedment was specified to be paid as a separate bid item. In lieu of another class of embedment, the CONTRACTOR may elect to use another class pipe if approved by the OWNER. The pipe shall be paid for as specified in relevant Items of Division 500 Underground Conduit Construction and Appurtenances at the unit price per linear-foot for the pipe originally specified if the original pipe was specified to be paid as a separate bid item.

If the CONTRACTOR elects to use another class embedment and the use of the embedment is approved by the OWNER, but not directed by the OWNER, the embedment shall be paid per linear-foot of pipe, compacted in place for the embedment originally specified if the original embedment was specified to be paid as a separate bid item.

504.7.2.2. Final Trench Backfill. If the CONTRACTOR elects to use a material other than the excavated material as trench backfill and the use of the material is approved by the OWNER, but not directed by the OWNER, the material shall be furnished and placed at no cost to the OWNER. The excavated material shall be disposed of at no cost to the OWNER.

If the OWNER orders the excavated material to be removed and disposed of and replaced with another material and a separate bid item is not established, the material shall be paid as an extra. The disposal of the rejected excavated material shall be at no cost to the OWNER.

If the OWNER orders the excavated material to be removed and disposed of and replaced with another material because of neglect of the CONTRACTOR to properly remove or store the material, or if the CONTRACTOR fails to compact the excavated material in the trench to the density requirements and the OWNER orders the material removed, the excavated material shall be replaced with a material approved by the OWNER at no cost to the OWNER. The disposal of the rejected material shall be at no cost to the OWNER.

504.7.2.3. Trench Safety. Payment for trench safety shall be according to the provisions of [Item 107.20](#). Protection of Work and of Persons and Property.

ITEM 505. OPEN CUT – GENERAL CONDUIT INSTALLATION

505.1. GENERAL

505.1.1. Conduit Location. The location of conduit to be installed will be determined by the Engineer using generally accepted design criteria, which includes the current guidelines of the TCEQ.

505.1.2. Location and Protection of Existing Utilities. Location and protection of existing utilities shall be carried out in accordance with [Item 107.24](#), Existing Structures, Facilities and Appurtenances.

505.1.3. Street Cut Permit. If required by the OWNER, the CONTRACTOR shall obtain a street cut permit prior to beginning the work. The CONTRACTOR shall have the executed permit available on the job site during the duration of the work.

505.1.4. Handling and Protection of Materials. All pipe, fittings and specials shall be handled in such a manner as not to damage the material. All dirt and trash shall be removed from the pipe prior to installation. All pipe and fittings handled with clamps or slings must meet with the approval of the OWNER; no hooks shall be permitted.

When it becomes necessary to deflect the pipe to avoid obstructions, the deflection of each joint must be within the limits provided by the manufacturer and be approved by the OWNER.

The pipe is to be kept clean during the laying operation and free of all dirt and trash. At the close of each operating day, the open end of the pipe is to be effectively sealed against the entrance of all objects and especially water.

505.1.5. Stringing of Pipe. Unless prior approval from the OWNER is granted to do otherwise, stringing of pipe in advance of the laying operation shall be restricted to one week's laying and shall be done in such a manner as to create no hazard to not interfere with traffic. Ready access shall be provided to all streets, alleys and driveways. The pipe shall be protected with barricades and warning signs at all times. Any damage to the pipe shall be corrected at the expense of the CONTRACTOR.

505.1.6. Laying Underground Conduit. Prior to being lowered into the trench, each pipe shall be carefully inspected; those not meeting specifications shall be rejected and either destroyed or removed from the job. All lumps or excrescences on the ends of conduit shall be removed before it is lowered into the trench. No pipe shall be laid except in the presence of the OWNER, unless otherwise specified, and the OWNER may order the removal of and re-laying of any pipe not so laid. The pipe and specials shall be so laid in the trench that after the project is completed the interior surface shall conform accurately to the grade and alignment indicated on the plans. Bell holes shall be excavated and all pipe shall be carefully adjusted to fit snugly in cradling or bedding so that the entire length bears on cradling or bedding material with no wedging or blocking to hold up the bell. All pipe shall be laid in the dry, regardless of the type of joint used.

Pipes shall be laid with the bell or groove end up grade unless otherwise approved by the OWNER and, in any event, shall be laid with the bell or collar away from the last section placed. Pipe must be swabbed clean before placement in the ditch.

Before laying the pipe, the interior of the joints shall be carefully bored smooth and clean and the annular space shall be kept free from dirt, stones or water. Pipe shall be installed and joints made up in complete conformance with the instructions and recommendations regarding proper installation and assembly furnished by the manufacturer. Proper facilities shall be provided for hoisting and lowering the section of the pipe into the trench without disturbing the prepared foundation and the sides of the trench. All pipe shall be so laid that the contact in the joint between two lengths of pipe shall be uniform throughout the circumference of the joint. Where curves in the alignment are indicated on the drawings, standard pipe (short sections of pipe or bevels) shall be used with the outside edge of the joint pulled away from the seat to make a smooth curve.

When work is suspended on the line for any reason, the end of the line shall be properly closed with an effective watertight seal or plug manufactured for this purpose.

505.1.7. Grades. The grade line shown on the profile is the elevation of the invert or flow line of the conduit. The OWNER shall establish benchmarks, base lines and other principal control points for use in construction. It shall be at the CONTRACTOR'S expense to establish all working or construction lines and grades as required and determined from the base measurements and control points set by the OWNER and shall be solely

responsible for the accuracy thereof. Wherever an offset needs to be over 10-ft., the CONTRACTOR shall be required to furnish a survey type tripod level or its equivalent in order to accurately transfer the grade to the trench or excavation. Where construction operations require the removal of the OWNER'S stakes, the CONTRACTOR shall reference such points in an approved manner. If they cannot be referenced, the CONTRACTOR must obtain authorization for their removal. In the case of their destruction or unauthorized removal, they shall be replaced by the OWNER at the CONTRACTOR'S expense.

The full responsibility for holding to alignment and grade shall rest upon the CONTRACTOR.

If a profile is not furnished for a water main, the main shall be constructed with a minimum cover as shown in Table 505.1.7.(a) Water Main Minimum Cover, unless directed otherwise by the OWNER.

Table 505.1.7.(a) Water Main Minimum Cover

Main Size	Minimum Cover (ft.) ¹	
	Unimproved Streets or Open Areas	Improved Streets (Curb, Gutter, and Subsurface Storm Drain)
Less than 12-in.	5-ft.	4-ft.
12-in. through 18-in.	6-ft.	5-ft.
20-in. and larger ²	7-ft.	6-ft.

1. The minimum cover requirement shall be measured from a point as designated on the plans.

2. May be greater if Air Relief and Vacuum Control Valves are on the main.

3. Unimproved streets are streets without curb and gutter and minimal surfacing.

505.2. GENERAL INSTALLATION REQUIREMENTS FOR PIPE TYPES

505.2.1. Section Held for Future Use

505.2.2. Concrete Pressure Pipe. When required in the project specifications, the pipe manufacturer shall furnish a factory-trained, job-experienced field representative who shall visit the project periodically during the course of installation. The project visiting schedule shall be approved by the OWNER. The field representative shall also be subject to call by the CONTRACTOR and/or OWNER to advise and assist with the solution of field problems. During visits, the representative shall observe all phases of the project including location and condition of pipe, stockpiled and installed pipe, trench width, if applicable, bedding and backfill, assembly of pipe joints and protection of steel. If, in the opinion of the representative, any phase of the installation is unsatisfactory to the extent of jeopardizing the performance of the pipe, representative shall so advise the CONTRACTOR'S superintendent and the OWNER.

After installation, flanged outlets shall be encased with mortar in a pipe diaper.

Test stations shall be provided at the appropriate locations as indicated on the plans to insure proper bonding and effectiveness of cathodic protection measures for concrete pressure pipe.

505.2.3. Concrete Gravity Pipe. Pipe shall be installed in accordance with ASTM C1479 Installation of Precast Concrete Sewer, Storm Drain, and Culvert Pipe Using Standard Installations.

505.2.4. Ductile Iron Pipe. Unless otherwise specified by the OWNER, ductile iron pipe shall be protected with a polyethylene encasement that conforms to [Item 502.8](#). Polyethylene Wrap for Metal Pipe and Fittings.

505.2.5. PVC Water Pipe. Pipe produced to the specifications of [Item 501.14](#). Polyvinyl Chloride (PVC) Water Pipe shall be installed in accordance with AWWA C605 Underground Installation of Polyvinyl Chloride (PVC) Pressure Pipe and Fittings for Water.

505.2.6. PVC Pressure-Rated Pipe Installation. Pipe produced to the specifications of [Item 501.15](#). Polyvinyl Chloride (PVC) Pressure-Rated Pipe (SDR Series) shall be installed in accordance with ASTM D2774 Practice for Underground Installation of Thermoplastic Pressure Piping. An engineering evaluation of specific installation requirements is recommended.

505.2.7. Molecularly Oriented Polyvinyl Chloride Installation and Special Conditions. Installation of pipe meeting specifications of [Item 501.16](#). Molecularly Oriented Polyvinyl Chloride (PVCO) Water Pipe shall be accomplished according to AWWA C605 Underground Installation of Polyvinyl Chloride (PVC) Pressure Pipe and Fittings for Water with the following conditions/exceptions:

- (1) Solvent cement shall not be used with PVCO pipe.
- (2) PVCO pipe must be tapped through a saddle. Direct tapping the wall is not permitted.
- (3) The maximum recommended operating temperature is 130°F

505.2.8. PVC Wastewater Pipe Installation. Pipe produced to the specifications of [Item 501.17](#). Polyvinyl Chloride (PVC) Wastewater Pipe & Fittings With Dimension Control shall be installed in accordance with ASTM D2321 Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications. Engineering evaluations of specific installation requirements is recommended.

505.2.9. PVC Profile Gravity Pipe Installation. Pipe produced to the specifications of [Item 501.18](#). Polyvinyl Chloride (PVC) Profile Gravity Pipe and Fittings – for Direct Bury and Sliplining Applications shall be installed in accordance with ASTM D2321 Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications. Engineering evaluations of specific installation requirements is recommended.

505.2.10. Section Held for Future Use

505.2.11. PVC Corrugated Pipe. Pipe produced to the plans and specifications shall be installed in accordance with ASTM D2321 Standard Practice for Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications or AASHTO Section 30 for any drainage application. Engineering evaluations of specific installation requirements is recommended.

505.2.12. Solid Wall Polyethylene Pipe Installation. Engineering evaluations of specific installation requirements are recommended.

Water pipe produced to the specifications of [Item 501.21](#). Solid Wall Polyethylene Plastic Pipe for Water, Wastewater, and Pipe Rehabilitation shall be installed according to the standard practice of ASTM D2774 Underground Installation of Thermoplastic Pressure Piping, ASTM F1962 Use of Maxi-Horizontal Directional Drilling for Placement of Polyethylene Pipe or Conduit Under Obstacles, Including River Crossings, and/or to appropriate engineered pipe bursting techniques.

Wastewater pipe produced to the specifications of [Item 501.21](#). Solid Wall Polyethylene Plastic Pipe for Water, Wastewater, and Pipe Rehabilitation shall be installed according to the standard practice of ASTM D2321 Underground Installation of Thermoplastic Pipe for Sewers and Other Gravity-Flow Applications, ASTM D2774, ASTM F1962, and/or to appropriate engineered pipe bursting techniques.

505.2.13. Thermoplastic Corrugated Drainage Tubing and Corrugated Smooth Lined Storm Water Pipe and Fittings. Engineering evaluations of specific installation requirements and pipe type selection are recommended. Installed per ASTM D2321, or AASHTO Section 30 except where installations are under proposed or existing paving; then, follow [Item 508.6.5.2](#). Backfilling to 1 ft. above the top of the pipe.

The internal diameter of the installed barrel of the tube/pipe must not be reduced by more than 5-percent of the actual inside diameter when measured not less than 30-days following completion of installment.

505.2.14. Fiberglass Pipe Installation. Installed pipe produced to the specifications of [Item 501.24](#). Fiberglass (Glass-Fiber-Reinforced Thermosetting-Resin) Wastewater Pipe shall be installed utilizing an envelope of standard crushed rock bedding materials, [Item 504.2.2](#). Pipe Embedment Material for Water And Wastewater Mains to a minimum of 6-in. above the crown of the pipe. Engineering evaluations of specific installation requirements are recommended. The internal diameter of the installed barrel of the pipe must not be reduced by more than 3-percent of its base inside diameter when measured not less than 30-days following completion of installation. Long term deflection shall not exceed 5-percent.

ITEM 506. OPEN CUT – WATER CONDUIT INSTALLATION

506.1. DESCRIPTION

This work shall include the installation and construction, complete in place, of water conduit and appurtenances as specified herein and in conformity with the lines, grades, dimensions, materials and designs shown on the plans.

506.2. MATERIALS

The pipe shall be of the kind and strength shown on the plans and provided in the proposal and contract. Unless otherwise specified, materials shall meet the requirements of [Item 501](#), Underground Conduit Materials and [Item 502](#), Appurtenances. Materials for corrosion protection of water conduits and appurtenances shall be of the type as may be called for on the plans or in the special specifications.

Any pipe, fitting, solder or flux which is used in the installation or repair of any public water system must be lead-free. For the purpose of these Specifications, the term 'lead free' means:

- (1) Not containing more than 0.2 percent lead when used with respect to solder and flux; and
- (2) Not more than a weighted average of 0.25 percent lead when used with respect to the wetted surfaces of pipes, pipe fittings, plumbing fittings, and fixtures.

506.3. LAYING WATER CONDUIT

Laying pipe shall not begin until after the initial embedment has been placed in the trench and after the condition of trench, line and grade have been approved by the OWNER.

The pipe, after being visually inspected and approved for laying by the OWNER, shall be laid, beginning at an existing opening, unless otherwise approved by the OWNER and, in any event, shall be laid with the bell or collar away from the last section placed.

All pipe shall be so laid that the contact in the joint between 2 lengths of pipe shall be uniform throughout the circumference of the joint. Where curves in the alignment are indicated on the drawings and the curves are flat, standard pipe shall be used with the outside edge of the joint pulled away from the seat to make a smooth curve. Deflection of the joint to form curves shall not exceed the limits of Table 2, AWWA C600 Installation of Ductile-Iron Water Mains and Their Appurtenances. Where curves are sharp, short sections of pipe, bevels or bends shall be used and blocked.

When pipe is cut by the CONTRACTOR to insert a valve or fitting, the bell and remaining section may be laid beyond the valve or fitting.

All pipe, fittings, valves, and hydrants shall be carefully delivered to the site and lowered into the trench, piece by piece, by means of a derrick, ropes, or other suitable tools or equipment, in such a manner as to prevent damage to water conduit materials, protective coatings, and linings. Under no circumstance shall water conduit materials be dropped or dumped into the trench.

The pipe and fittings shall be inspected for defects. All lumps, blisters, and excess coating material shall be removed from the bell and spigot ends of each pipe. Additionally, the inside of the bell or coupling and the outside of the spigot shall be wire brushed and wiped clean, dry, and free of all foreign and objectionable material before the pipe is laid. Every precaution shall be taken to prevent foreign material from entering the pipe while it is being placed in line.

506.4. PIPE JOINTS

All joints in pipe shall be thoroughly cleaned at the time the joint is made.

506.4.1. Rubber Gasket Joints. Rubber gaskets shall conform to the applicable specifications under which the pipe is supplied. Loose gaskets shall be protected from sunlight, contamination and contact with gasoline or fuels.

Rubber gasket joints for water conduits consist of 4 general types:

- (1) Push-on type used for ductile iron, steel and plastic pipe.
- (2) Mechanical type used for ductile iron and fittings.
- (3) Rubber and steel joint ring type used for steel cylinder type, reinforced concrete pipe.
- (4) Double rubber gasket couplings used for pressure pipe.

Each type, except mechanical, requires the use of a lubricant to facilitate assembly. The lubricant shall be nontoxic, shall not support the growth of bacteria and shall have no deteriorating effect on the gasket. The lubricant shall not impart taste or odor in a pipe that has been flushed in accordance with [Item 506.7](#). Purging and Disinfection of Water Conduits. Care should be taken not to over-use the lubricant since it would then require excess effort to disinfect.

506.5. HYDROSTATIC TEST

Before being accepted, all ductile iron and plastic pipelines constructed shall be tested with a hydraulic test pressure of not less than 150-psi, maintained over a period of not less than 4-hours unless otherwise specified by the OWNER, except that polyethylene pipe shall be tested as described below in [Item 506.5.1](#). Hydrostatic Testing Polyethylene Pipe, unless otherwise specified by the OWNER. Alternately, a 2-hour test may be conducted on PVC in accordance with AWWA C605 Underground Installation of Polyvinyl Chloride (PVC) Pressure Pipe and Fittings for Water and a 2-hour test may be conducted on ductile iron in accordance with AWWA C600 Installation of Ductile-Iron Water Mains and Their Appurtenances. Concrete pressure pipe shall be tested with a hydraulic test pressure of 120-percent of the design pressure. Steel pressure pipe shall be tested with a hydraulic test pressure not to exceed 150-percent and not less than 120-percent of the design working pressure. The rate of leakage of all pipe tested shall not exceed 11.65-gallons-per-inch of nominal diameter of pipe per mile over a 24-hour period. Water lines of materials in combination shall be tested for the type of pipe (material) with the least stringent hydraulic test pressure maintained over a period of not less than 4-hours. Acceptable test values are provided in Table 506.5.(a) Allowable Leakage for 4-Hours at Test Pressure of 150-psi.

All newly laid pipe, or any valve section thereof, shall be subjected to the test with the gauge located at the lowest point in the system to be tested. If the line cannot be tested at its lowest point, a correction factor of minus 0.43 lb./vert. ft. shall be made.

Table 506.5.(a) Allowable Leakage for 4-Hours at Test Pressure of 150-psi (gallons)

Length (Ft.)	Pipe Diameter (Inches)															
	6	8	10	12	14	16	18	20	24	30	36	42	48	54	60	66
5	0.01	0.01	0.02	0.02	0.03	0.03	0.03	0.04	0.04	0.06	0.07	0.08	0.09	0.10	0.11	0.12
10	0.02	0.03	0.04	0.04	0.05	0.06	0.07	0.07	0.09	0.11	0.13	0.15	0.18	0.20	0.22	0.24
15	0.03	0.04	0.06	0.07	0.08	0.09	0.10	0.11	0.13	0.17	0.20	0.23	0.26	0.30	0.33	0.36
20	0.04	0.06	0.07	0.09	0.10	0.12	0.13	0.15	0.18	0.22	0.26	0.31	0.35	0.40	0.44	0.49
25	0.06	0.07	0.09	0.11	0.13	0.15	0.17	0.18	0.22	0.28	0.33	0.39	0.44	0.50	0.55	0.61
50	0.11	0.15	0.18	0.22	0.26	0.29	0.33	0.37	0.44	0.55	0.66	0.77	0.88	0.99	1.10	1.21
75	0.17	0.22	0.28	0.33	0.39	0.44	0.50	0.55	0.66	0.83	0.99	1.16	1.32	1.49	1.66	1.82
100	0.22	0.29	0.37	0.44	0.51	0.59	0.66	0.74	0.88	1.10	1.32	1.54	1.77	1.99	2.21	2.43
200	0.44	0.59	0.74	0.88	1.03	1.18	1.32	1.47	1.77	2.21	2.65	3.09	3.53	3.97	4.41	4.85
300	0.66	0.88	1.10	1.32	1.54	1.77	1.99	2.21	2.65	3.31	3.97	4.63	5.30	5.96	6.62	7.28
400	0.88	1.18	1.47	1.77	2.06	2.35	2.65	2.94	3.53	4.41	5.30	6.18	7.06	7.94	8.83	9.71
500	1.10	1.47	1.84	2.21	2.57	2.94	3.31	3.68	4.41	5.52	6.62	7.72	8.83	9.93	11.03	12.14
600	1.32	1.77	2.21	2.65	3.09	3.53	3.97	4.41	5.30	6.62	7.94	9.27	10.59	11.92	13.24	14.56
700	1.54	2.06	2.57	3.09	3.60	4.12	4.63	5.15	6.18	7.72	9.27	10.81	12.36	13.90	15.45	16.99
800	1.77	2.35	2.94	3.53	4.12	4.71	5.30	5.88	7.06	8.83	10.59	12.36	14.12	15.89	17.65	19.42
900	1.99	2.65	3.31	3.97	4.63	5.30	5.96	6.62	7.94	9.93	11.92	13.90	15.89	17.87	19.86	21.85
1000	2.21	2.94	3.68	4.41	5.15	5.88	6.62	7.36	8.83	11.03	13.24	15.45	17.65	19.86	22.07	24.27
Valve	0.19	0.25	0.31	0.37	0.44	0.50	0.56	0.62	0.75	0.94	1.12	1.31	1.50	1.68	1.87	2.06

Allowable Leakage (gal.) for 4 hours = $4 \times (S \times D \sqrt{P}) \div 133,200$

S = Length of Pipe, Ft.

D = Diameter of Pipe, In.

P = 150 psi

Height Correction = 0.43 psi/Ft.

Valve Leakage Allowable = 0.0078 Gal./Hour/In. of nominal valve size

Test — Ductile Iron, Plastic, and at 150 psi

— Concrete 120% of Design Pressure

— Steel 120% Min. to 150% Max. Design Working Pressure

If the tests indicate a leakage in excess of the above rate, then the CONTRACTOR shall be required to find and repair the leak. Even if the test requirements are met, all apparent leaks shall be stopped. Allowance for valve

leakage to the atmosphere may be determined as no more than 0.0078-gal. /hr. /in. of nominal valve size. The OWNER cannot guarantee that an old existing system valve shall hold the required pressure. The CONTRACTOR has the option of plugging the new conduit prior to tying onto the existing system and testing against the old valve. If the old valve does not hold against the test pressure, then the CONTRACTOR must cut and plug the new conduit, hydrostatic test the new conduit, and then complete the tie-in. Internal test plugs may be used in larger reinforced concrete conduits in lieu of plugging prior to making a tie-in.

The cost of testing and repairing the leaks, including all uncovering, repairing, backfilling and incidental work, shall be at the expense of the CONTRACTOR.

506.5.1. Hydrostatic Testing Polyethylene Pipe. Pipe shall be tested after installation is complete and in accordance with ASTM F2164 Standard Practice for Field Testing of Polyethylene (PE) and Cross linked Polyethylene (PLEX) Pressure Piping Systems using Hydrostatic Pressure.

Testing may be conducted on the full system or in sections. Test section length shall be determined by the capacity of the testing equipment. Lower capacity pressurizing or filling equipment may not be capable of completing the test within permissible time limits. If so, higher capacity test equipment or a shorter test section may be required by the OWNER.

Before applying test pressure, CONTRACTOR shall allow time for the test fluid and the test section to equalize to a common temperature. For pressure piping systems that include polyethylene pipe or fittings:

- (1) The maximum permissible test pressure is measured at the lowest elevation in the test section.
- (2) The maximum permissible test pressure is 150% of the system design operating pressure when the test section is all polyethylene pressure piping.
- (3) The maximum permissible test pressure is the pressure rating of the lowest pressure rated, non-polyethylene part in the system when the system contains non-polyethylene parts.

CONTRACTOR shall not subject lower pressure rated, non-polyethylene parts or devices to pressures above their pressure ratings. Lower pressure rated parts may be removed or isolated from the test section to avoid damage or failure. CONTRACTOR shall vent isolated parts or equipment to atmosphere.

All thermoplastic pipes have reduced strength at elevated temperature. Test pressure must be reduced when the test section is at elevated temperature from service conditions or from environmental conditions such as being warmed by the sun. To determine the allowable elevated temperature test pressure, CONTRACTOR shall multiply the test pressure by the appropriate multiplier in Table 506.5.1.(a) Polyethylene Pipe Elevated Temperature Test Pressure Multipliers.

Table 506.5.1.(a) Polyethylene Pipe Elevated Temperature Test Pressure Multipliers

Test Section Temperature, T							
°F	$T \leq 80^1$	$80 < T \leq 90$	$90 < T \leq 100$	$100 < T \leq 110$	$110 < T \leq 120$	$120 < T \leq 130$	$130 < T \leq 140^2$
°C	$T \leq 27^1$	$27 < T \leq 32$	$32 < T \leq 38$	$38 < T \leq 43$	$43 < T \leq 49$	$49 < T \leq 54$	$54 < T \leq 60^2$
Multiplier	1.00	0.90	0.80	0.75	0.65	0.60	0.50

1. Use the 80°F multiplier for 80°F and lower temperatures.

2. The maximum service temperature for polyethylene pressure piping is 140°F.

When testing at pressures above system design pressure or up to 150% of the system design pressure, the maximum test duration is 8-hours including time to pressurize, time for initial expansion, time at test pressure, and time to depressurize the test section. If the test is not completed due to leakage, equipment failure, or for any other reason, CONTRACTOR shall depressurize the test section completely, and allow it to relax for at least 8-hours before pressurizing the test section again.

Testing procedure shall be carried out as follows:

- (1) Filling. CONTRACTOR shall fill the restrained test section completely with test liquid.

WARNING – CONTRACTOR shall ensure that there is no air trapped in the test section. Failure with entrapped air can result in explosive release. CONTRACTOR shall use equipment vents at high points to remove air.

- (2) Initial Expansion Phase. CONTRACTOR shall gradually pressurize the test section to test pressure, and maintain test pressure for 3-hours. During the initial expansion phase, polyethylene pipe will expand slightly. Additional test liquid will be required to maintain pressure. It is not necessary to monitor the amount of water added during the initial expansion phase.
- (3) Test Phase. Immediately following the initial expansion phase, CONTRACTOR shall reduce test pressure by 10-psi, and stop adding test liquid. If test pressure remains steady (within 5% of the target value) for 1-hour, no leakage is indicated.
- (4) Depressurizing. At the conclusion of the test, CONTRACTOR shall carefully depressurize the test section by the controlled release of test liquid. The test liquid may need to be drained and its disposal shall be subject to applicable environmental regulations.

506.6. CONNECTIONS TO EXISTING WATER CONDUITS

Connection to an existing water conduit shall include not only branch connections but in-line connections for the purpose of making required pipe adjustments as well. Any connection or series of connections required to be performed on an existing water conduit shall meet with the OWNER'S specific approval as to the seasonal period when the work can be performed, the length of time required for the work to be completed, the work procedures proposed, and/or any other facet that could affect quality or quantity of water supply to the affected area. The work shall be performed with stringent built-in safeguards (such as adequate back-up equipment, labor and materials available) to insure that time schedules are met without failure and subsequent set-back. Every effort shall be made to accomplish as much of the work as possible before actual tie-in is made into the existing conduit. This is especially applicable where vertical and horizontal concrete thrust blocks are a necessity to impose proper restraint of the pipe when the conduit is returned to full service. See Standard Drawings 4010A – 4040 for vertical and horizontal thrust blocks.

The CONTRACTOR shall notify the OWNER at least 48-hours in advance of a required valve shutdown.

Where indicated on the plans and/or herein specified, the CONTRACTOR shall connect the new conduit to existing conduits. The CONTRACTOR shall furnish all labor, materials, equipment and services required for the locating and uncovering of the existing line; the making of cuts in the existing line; the removal, relocation, and/or lowering of existing lines as required (See Standard Drawing 4200); dewatering of the trench; connecting of the existing lines to the new conduit; and all appurtenant work required for complete connection. Appurtenant work shall follow the requirements stated herein and as specified in [Item 502](#), Appurtenances. Relocated conduits or lines shall be laid so that all valves shall be set vertically. The CONTRACTOR shall be required to plug and block lines, crosses, tees or other fittings installed in the new conduit to permit hydrostatic testing and chlorination prior to making connections. Such plugs and blocking shall be adequate to withstand an applicable test pressure.

Where cut-ins are made immediately adjacent to valves which are under pressure, the CONTRACTOR shall take all necessary precautions to brace such valves with temporary blocking. Bracing shall be of ample size and properly placed to prevent movement or blowing off of any pipe, valves or fittings due to water pressure on the conduit.

Connections to existing water conduits shall be made at the locations shown, as specified, and/or as directed by the OWNER. All such connections shall be made in a most expeditious and workmanlike manner to cause the least inconvenience to water customers and to traffic. The detailed schedule of operations for making each connection shall be approved by the OWNER before any work thereupon is commenced.

In the case where blow-off connections or fire hydrants are not provided for flushing, the CONTRACTOR shall be required to leave one end of the new conduit open for flushing and then plug and block the end for chlorination and testing.

There shall be no separate pay items for taps, blow-offs for hydrostatic testing, disinfection purposes, and connections to existing water mains unless otherwise approved by the OWNER. Taps and blow-offs for hydrostatic testing and disinfection purposes shall be installed by the CONTRACTOR, at locations specified by the OWNER. This may include placing a blow-off on an existing conduit at the tie-in, or addition of a blow-off(s) at an isolated existing valve, for facilitation of hydrostatic testing and/or chlorination. Compression type curb stops are not permitted for blow-offs

Upon completion of the hydrostatic testing and disinfection the CONTRACTOR shall return to the job site and remove the blow-off down to the corporation stop. CONTRACTOR shall leave the corporation stop and backfill,

replacing all pavement. Removal of the blow-off shall include all labor, materials, tools, equipment, and incidentals necessary to complete the work, including excavation, disposal of surplus materials, and backfill with no separate pay item.

506.6.1. Water Main Tie-In During Off Hours. Tie-in connections affecting curtailment of quality or quantity of water to an area, businesses, etc., must be performed during the weekend or off-hours. All work must be coordinated through the OWNER or its representatives. Delay costs due to shut down and connection issues are considered incidental work and shall be borne by the CONTRACTOR. Unless otherwise stated in the contract, this item is a No Separate Pay Item.

506.7. PURGING AND DISINFECTION OF WATER CONDUITS

506.7.1. General. Before any newly constructed water conduit shall be permitted to be placed into service, it shall be purged and tested or purged, disinfected and tested until the bacterial count within the conduit meets the standards of disinfection according to Federal and State regulations.

The CONTRACTOR shall perform the purging, disinfection and testing activities unless the OWNER specifies otherwise. Should the CONTRACTOR's carrier be required to transport potable water to the job site for conduit testing, tankage and all piping, including pumps used to transport or transfer potable water into the conduit, shall be disinfected and/or approved for that use by the OWNER.

When the entire pipeline or selected sections, as approved by the OWNER, have been completed, the line or section shall be disinfected according to the following procedures.

Table 506.7.1.(a) Required Flow and Openings to Flush Pipelines at 40 psi Pressure

Pipe Diameter (in)	Flow Required 2.5 ft/sec (gpm)	Size of Tap			Number of 2½ " Hydrant Outlets on Pipe
		1	1½	2	
4"	100	1	-	-	1
6"	200	-	1	-	1
8"	400	-	2	1	1
10"	600	-	3	2	1
12"	900	-	-	2	2

506.7.2. Pre-Disinfection. Before being chlorinated, the main(s) shall be filled to eliminate air pockets and shall be flushed to remove particulates. The flushing velocity in the main shall not be less than 2.5 ft/s unless the OWNER determines that conditions do not permit the required flow to be discharged to waste. Flushing is no substitute for disinfection measures during construction.

Certain contaminants, such as caked deposits, resist flushing at any feasible velocity. In mains of 24 inch diameter and larger, an acceptable alternative to flushing is to broom-sweep the main, carefully removing all sweepings prior to chlorinating the main.

For convenience in certain locations, it may be directed by the OWNER that hypochlorite be placed in the pipe as laid.

506.7.3. Purging. Purging may be accomplished by passing an appropriate sized "poly-pig(s)" through the pipe or by flushing, as determined by the OWNER.

- 506.7.3.1. Poly-Pig Method.** If the poly-pig method of purging is to be used, the CONTRACTOR shall be required to prepare the conduit for the installation and removal of "poly-pigs." The OWNER shall purge the system unless the CONTRACTOR is specified to do the work. This method shall include the following:
- (1) In general, this shall consist of furnishing all equipment, material, and labor to satisfactorily expose cleaning wye, remove cleaning wye covers, etc., as directed by the OWNER.
 - (2) Where expulsion of the "poly-pig" is required through a dead-ended conduit, the CONTRACTOR shall make every effort to prevent back flow of purged water into the conduit after passage of the pig. On small pipe, such as cast iron pipe through 12-in., backwater re-entry into the pipe can be prevented

by the temporary installation of mechanical joint shallow bends and pipe joints to provide a riser out of the trench. On larger pipe, additional excavation of the trench may serve the same purpose.

- (3) Where the pipe in the conduit forms a loop distribution system, every effort shall be made to sweep the entire system.
- (4) Short dead-end pipe sections not swabbed by the pig shall be flushed.
- (5) Backflow water which has inadvertently entered the pipe under conditions similar to those described in [Item 506.7.3.1](#), (2) preceding shall be flushed from the system.
- (6) After passage of the “poly-pig,” flushing of all backwater from the pipe, and satisfactory test results, at the direction of the OWNER, the CONTRACTOR shall: secure test location openings by plugging and blocking, installing cleaning wye blind flanges, etc.; then backfill; and complete all appurtenant work necessary to secure the system, or proceed with disinfection.

506.7.3.2. Flushing Method. If the “flushing” method of purging is used, the CONTRACTOR shall be required to prepare the conduit by installing blow-offs at locations and sized as directed by the OWNER. This method shall also include the following:

- (1) In general, this shall consist of furnishing all equipment, material and labor to satisfactorily install blow-offs of sizes shown in Table 506.7.3.2.(a) Flushing Method Blow-Off Requirements.

Table 506.7.3.2.(a) Flushing Method Blow-Off Requirements

Size Conduit	Size Blow-Off
2-in. thru 8-in.	¾-in.
10-in. thru 12-in.	1½-in.
16-in. and greater	2-in.

- (2) After flushing is complete and satisfactory test results are received at the direction of the OWNER, the CONTRACTOR shall secure the conduit, backfill, and complete all appurtenant work to secure the system, or proceed with disinfection. The CONTRACTOR shall, in the securing of the conduit, remove the blow-off down to the corporation stop.

506.7.4. Water Sample Analysis. After purging, an analysis may be made on the water sample drawn from a chlorination blow-off and sampling point at the OWNER’S request. (Samples drawn from fire hydrants have in the past proved unreliable and except in extreme cases shall not be used for the purpose of analysis.) Should the analysis indicate that the bacteria count is below the limits of the established standards for purity, no further disinfection is necessary unless specifically required by the OWNER.

506.7.5. Disinfection. Disinfection of the conduit shall be accomplished by the “continuous feed” method or the “slug” method as directed by the OWNER and described as follows. The free chlorine amounts shown are minimum. Higher rates may be required by the OWNER. Calcium hypochlorite granules shall be used as the source of chlorine.

506.7.5.1. CONTRACTOR Requirements. No matter who performs the disinfection activities described below, the CONTRACTOR shall be required, as a minimum, to prepare the conduit for disinfection and secure same after chlorination is complete. This shall include the following:

- (1) In general, this shall consist of furnishing all equipment, material and labor to satisfactorily prepare the conduit for the disinfection method selected by the OWNER. The CONTRACTOR shall also be required to provide adequate provisions for sampling.
- (2) Unless otherwise specified in the special contract documents, the CONTRACTOR shall make all necessary taps into the pipe to accomplish chlorination of a new line.
- (3) After satisfactory completion of the disinfection operation and at the direction of the OWNER, the CONTRACTOR shall remove surplus pipe at the chlorination and sampling points, plug the remaining pipe, backfill, and complete all appurtenant work necessary to secure the conduit.

506.7.5.2. Continuous Feed Method. If the “continuous feed” method of chlorination is used, the following steps shall be taken:

- (1) Water from the existing distribution system or other approved source of supply shall be made to flow at a constant rate in the newly laid conduit.

- (2) At a point not more than 10-ft. downstream from the beginning of the new conduit, water entering the new conduit shall receive a dose of chlorine such that the water shall have not less than 100-mg/L free chlorine, or as required by TCEQ, whichever is greater. Chlorine applications shall not cease until the entire conduit is filled with heavily chlorinated water.
- (3) The chlorinated water shall be retained in the conduit for at least 24-hours, during which time all valves and hydrants in the section treated shall be operated in order to disinfect the appurtenances. Every effort shall be made to prevent the flow of chlorinated water into conduits in active service. At the end of the 24-hour period, the treated water in all portions of the conduit shall have a residual of at least 10-mg/L free chlorine.
- (4) The heavily chlorinated water shall then be flushed from the conduit and disposed of in a manner and at a location specified by the OWNER.
- (5) The chlorine residual shall be tested prior to flushing operations. If the chlorine residual exceeds 4-mg/L, the water shall remain in the new water conduit until the chlorine residual is less than 4-mg/L. The CONTRACTOR may choose to evacuate the water into water trucks or other approved storage facility and treat the water with Sodium Bisulfite or another dechlorination chemical or method appropriate for potable water and approved by the OWNER until the chlorine residual is reduced to 4-mg/L or less. After the specified chlorine residual is obtained, the water may then be discharged into the drainage system or utilized by the CONTRACTOR.

506.7.5.3. Slug Method. If the “slug” method of chlorination is used, the following steps shall be taken:

- (1) Water from the existing distribution system or other approved source of supply shall be made to flow at a constant rate in the newly laid conduit.
- (2) At a point not more than 10-ft. downstream from the beginning of the new conduit, water entering the conduit shall receive a dose of chlorine such that the water shall have not less than 100-mg/L free chlorine. The chlorine shall be applied continuously and for a sufficient time to develop a solid column or “slug” of chlorinated water that shall expose all interior surfaces to the “slug” for at least 3-hours.
- (3) As the chlorinated water flows past the fittings and valves, they shall be operated so as to disinfect the appurtenances. Every effort shall be made to prevent the flow of chlorinated water into conduits in active service.
- (4) The heavily chlorinated water shall then be flushed from the conduit and disposed of in a manner and at a location specified by the OWNER.

506.7.5.4. Sampling. Unless otherwise specified, the OWNER’S personnel or representative shall inject the chlorine disinfectant into the conduit, monitor the solution and perform the water analysis.

An OWNER’S representative shall take water samples from a suitable tap (not through a fire hydrant) for analysis by the OWNER’S laboratory, unless otherwise specified in the special provisions or in the plans. No hose or fire hydrant shall be used in the collection of samples.

Microbiological sampling shall be done prior to connecting the new conduit into the existing distribution system in accordance with AWWA C651 Disinfecting Water Mains. Samples for bacteriological analysis shall be collected in sterile bottles treated with sodium thiosulfate. Two consecutive sets of acceptable samples, taken at least 24-hours apart, shall be collected from the new conduit. At least one set of samples shall be collected from every 1,000-linear-feet of the new water conduit, plus one set from the end of the line and at least one set from each branch. If trench water has entered the new conduit during construction or, if in the opinion of the Engineer, excessive quantities of dirt or debris have entered the new conduit, bacteriological samples shall be taken at intervals of approximately 200-linear-feet. Samples shall be taken of water that has stood in the new conduit for at least 16-hours.

Unsatisfactory test results shall require a repeat of the disinfection process and resampling as required above until a satisfactory sample is obtained.

506.8. PLUGS

Permanent plugs shall be placed at the ends of all pipe.

506.8.1. Cut and Plugs. Cut and plugs will only be paid when a CONTRACTOR is required to excavate at a separate location outside of the on-going pipeline installation. All other cut and plugs (those that require plugs only) associated with the same excavation when connecting the new pipeline to an existing pipeline is considered incidental work and is not a separate pay item. Actual cut & plugs shall be paid under appropriate bid item numbers.

506.9. MEASUREMENT AND PAYMENT

506.9.1. Measurement. Pipe, including corrosion protection if in place on the pipe, shall be measured for payment in linear feet along the center line of the pipe actually laid. No deductions shall be made for fittings and valves, measurements being from center to center of fittings. Where a change in the size of the pipe occurs in the line, the measurement shall be to the center of the fitting. Where a change in the size of the pipe occurs in line, the measurement shall be to the center of the reducer. Conduits shall not be classified for payment according to the depth of the cut.

A pay item shall be included for connections to existing conduits unless otherwise specified in the Contract.

506.9.2. Payment. Pipe, including corrosion protection in placed on the pipe, shall be paid for at the contract unit price per linear foot, and completed in place, as provided by the proposal and contract.

Connections to existing conduits shall include furnishing and placing of fittings, valves, pipe and concrete blocking in accordance with [Item 502](#). Appurtenances.

Where plugs are classified separately as contract pay items, payment shall be made in accordance with the contract unit price per each, complete in place, as provided in the contract. Such price shall be total compensation for furnishing all labor, materials, tools, equipment and incidentals necessary to complete the work, including all excavation, disposal of surplus material and backfill, all in accordance with the plans and specifications.

The contract price per linear foot of conduit shall be the total compensation for the furnishing of all labor, materials, tools, equipment and incidentals necessary to complete the work, including excavations, backfill, and disposal of surplus materials in accordance with the plans and these specifications.

Measurement and payment for hydrostatic testing and disinfection shall not be applicable under this construction specification unless specified otherwise. The CONTRACTOR shall provide materials, equipment and services in support of both purging and disinfection of the conduit. All costs for these services shall be included in the unit price bid in the proposal per foot of pipe complete in place, and no other compensation shall be allowed.

ITEM 507. OPEN CUT – WASTEWATER CONDUIT INSTALLATION

507.1. DESCRIPTION

This work shall include the installation and construction, complete in place, of wastewater conduits and appurtenances as specified herein and in conformity with the lines, grades, dimensions, materials and designs shown on the plans.

507.2. MATERIALS

The pipe shall be of the kind and strength shown on the plans and provided in the proposal and contract. Unless otherwise specified, materials shall meet the requirements of [Item 501](#). Underground Conduit Materials and [Item 502](#). Appurtenances.

507.3. LAYERING WASTEWATER CONDUIT

CONTRACTOR shall follow the same standard of care and general sequence as that described in [Item 506.3](#). Laying Water Conduit. Appurtenance installation shall meet the requirements of [Item 502](#). Appurtenances.

507.4. WASTEWATER CONDUIT JOINTS

507.4.1. Rubber Gasket Joints. Rubber gaskets shall conform to applicable specifications under which the pipe is supplied. Loose gaskets shall be protected from sunlight, contamination and contact with gasoline or fuels. On pipe for which the gasket is not fixed in place by the manufacturer, the bell-and-spigot or tongue-and-groove shall be thoroughly cleaned by wire brushing and wiping until clean and dry. On pipe which does not require the rubber gasket to be cemented in place, the rubber gasket shall be placed in position on the spigot ring just prior to laying the pipe. The lower edge of the gasket shall be placed under the spigot, in the seat and stretched evenly upward on each side to fit over the top of the spigot, and the rubber gasket shall fit snugly and not have uneven tensile stresses.

After checking to be sure that the bell-and-spigot are thoroughly clean, the inside surface of the bell shall be lubricated with a suitable solution (flax soap) to facilitate the telescoping of the joint. Petroleum lubrication shall not be permitted. The spigot end of the pipe shall be entered into the bell of the adjoining pipe until it contacts the gasket uniformly. The pipe shall then be pushed into the bell to the reference mark (a distinct circumferential line), which is placed on the pipe's spigot end by the manufacturer to indicate the correct depth of penetration. If undue resistance to insertion of the pipe end is encountered, or if the reference mark does not position properly, CONTRACTOR shall disassemble the joint and check the position of the gasket. If the gasket is twisted or pushed out of its seat, CONTRACTOR shall inspect components, repair or replace damaged items, clean the components, and repeat the assembly steps. Exceptional care shall be taken in making the field joint. Bumping of the pipe shall not be permitted. On small pipe, if the bottom of the trench is firm enough, a bar having a blade on the end may be pushed into the ground; then the bar may be used as a lever to push the pipe home. However, if trench conditions are too unstable or are in rock, it shall be necessary to use mechanical means to bring the pipe together positively. Each joint shall be partially backfilled or suitably blocked to prevent creeping.

Unless otherwise specified in the special provisions or in the plans, for all sizes of concrete pipe larger than 24-in. in diameter, the inside annular space provided for that purpose shall be completely filled with a plastic Portland cement mortar (composed of 1-part-cement to 2½-parts-sand), preformed flexible joint sealant in rope form, or toweling type.

Where the pipe has been corrosion protected and an annular space is open, only the bottom half of the inside annular space shall be filled with mortar, and a ready-mix cold-pour compound shall be used in the upper half, as hereinbefore described, that is resistant to acid alkalis and gases and is compatible with rubber. The joint shall be finished smoothly and all surface materials removed.

507.4.2. Chemically Welded Joints. The joint materials shall conform to the applicable specifications under which the pipe is supplied. The joint shall be installed per recommendations of the manufacturer. The ditch embedment should be to grade, with the advance bell hole scooped out prior to laying so that the pipe shall be to grade as the joint is made.

507.4.3. Compression Joints. The joint materials shall conform to the applicable specifications under which the pipe is supplied. The bells and spigots must be thoroughly clean. Extreme care must be

exercised to prevent damage to the joint. The spigot end shall be inserted into the bell and pushed home after a suitable lubricant, as recommended by the pipe manufacturer, is applied. Petroleum lubrication shall not be permitted. The ditch embedment should be to grade, with the advance bell hole scooped out prior to laying so that the pipe should be to grade as the joint is made.

507.4.4. Joints for Closure Sections. Spigot-to-spigot closures: clay pipe (4-, 6- and 8-in.) to clay pipe (4-, 6- and 8-in.), cast iron soil pipe (4-, 5- and 6-in.) to clay pipe (4- and 6-in.) and asbestos-cement pipe (4-, 6- and 8-in.) to clay pipe (4-, 6- and 8-in.) shall be made using a synthetic rubber or plastic compressible type coupling as detailed on the appurtenance sheet that shall conform to [Item 501.2.4. Joints](#). The two bands for patching the coupling shall be corrosion-resistant steel or stainless steel. The band shall be tensioned to provide a residual compression of at least 30-psi between coupling and the pipe.

Closures of 4-in. clay bell to 4-in. cast iron spigot (for lateral cleanouts) and of 6-in. clay spigot to 6-in. concrete bell (rubber gasket type joint) shall be made, using compression type, wedge shaped synthetic rubber or plastic adapter rings, as detailed on the appurtenance sheet that shall conform to [Item 501.2.4. Joints](#). The adapter shall be lubricated to facilitate making the joint after the ends and bells have been thoroughly cleaned. All closure section and sections jointed shall be sawed at right angles to the centerline of the section.

507.4.5. Other Joints. Other type joints should be installed as per instructions from the pipe or joint manufacturer, after approval of the joint by the OWNER.

507.5. TESTS AND INSPECTIONS

In order to ascertain that the main shall perform the function for which it was designed and constructed, performance tests shall be routinely executed. Inspection by closed circuit television shall be performed when so desired by the OWNER. Infiltration or exfiltration or air tests, as determined by the OWNER, may be made on sections of the contract work to assure that contract performance is satisfactory. All wastewater pipe shall be air tested upon completion of backfill. Wastewater force mains shall be hydrostatically tested.

507.5.1. Pipe Testing. Tunneler, bored or jacked sections of all pipe shall be tested by a method to be determined by the OWNER.

Testing shall be performed by the CONTRACTOR in the presence of the OWNER after all backfilling and compaction are complete. All sections between manholes or between a manhole and a dead end shall be tested separately. In the making of all tests, the CONTRACTOR shall furnish the required equipment and labor, under the direction of the OWNER. Tests may be repeated until each wastewater conduit individually meets the specifications as to quantity of allowable infiltration or exfiltration or air leakage as set out below. All testing work shall be included in the bid price.

If a gravity main is specified to be hydrostatically tested, the test shall be in accordance with [Item 506.5. Hydrostatic Test](#), except that the test pressure, duration of the test, and allowable leakage shall be specified. The CONTRACTOR shall remove the test water from the main after the test if required by the OWNER.

507.5.1.1. Infiltration Test (Not Commonly Used). The total seepage in infiltration of ground water as determined by test shall in no case exceed 50-gallons-per-inch of nominal diameter of pipe per mile over a 24-hour period, and shall be the same regardless of piping material used. The allowable leakage of each manhole, or other structure, shall be as specified on the plans. An infiltration test or tests shall be made on all sections of the project where air testing could not be adequately performed or if ordered by the OWNER and on each manhole individually before placing the system in service and before any connections are made to other wastewater conduits. If the quantity of the effluent into the conduit or conduits is in excess of the maximum quantity as hereinbefore specified, the joints shall be repaired or the wastewater conduit relayed, if necessary, or other remedial construction shall be performed by and at the expense of the CONTRACTOR, in order to reduce the quantity of ground water infiltration to an amount within limits as specified.

The test shall be made by utilizing ground water, if any, or flooding a section at a time. Observation from jetting is not acceptable.

It is the intent of the OWNER that no allowance shall be made for seepage of ground water at the time the test is performed (zero infiltration). The actual connection to the existing system will not be permitted without prior approval of the OWNER. It is the intent of the OWNER to complete the construction

of new wastewater mains and test the system prior to any connection to the existing system. Exceptions may be made by the OWNER in the event an existing main is to be connected to the new main upstream of the outfall of the new main. A stopper may be used until a tie-in is approved by the OWNER.

507.5.1.1.1. Using Existing High Ground Water. Where the natural ground water, after well points are removed, is above the top of the pipe for a section, the flowing of water in the pipe and the rate of seepage and infiltration for the section so submerged can be measured.

507.5.1.1.2. Flooding by Sections. Backfill shall be brought up to at least 1-ft. over the pipe on the section to be tested. More cover may be required on larger pipes to prevent the pipe from floating out of grade. Dams or dikes are placed tightly around pipe at either end and the ditch filled with water to an average depth of 4-ft. over the pipe. Flow at the lower end is measured for the section so submerged.

Dikes shall be placed around each manhole, and the area adjacent to the manhole shall be flooded to the top of the manhole and the flow into the manhole measured.

507.5.1.2. Exfiltration. A section of pipe below a manhole is bulk headed at either end with a 6-in. pipe inserted into lower bulkhead and by use of a 90-degree bend. The 6-in. pipe is set in a vertical position. A 2-in. vent pipe is inserted in lower end and extended upward 4-ft.. The 6-in. pipe is filled with water, filling the wastewater conduit until all air is forced out through the vent tube. When the water levels are level in the 2-in. and 6-in. pipes, the drop in the 6-in. pipe due to exfiltration over a specific time shall be measured and the loss of water due to exfiltration calculated. This amount shall be reduced by 25-percent to obtain equivalent infiltration over a specific time and the loss of water due to exfiltration calculated. Conditions encountered in construction may vary this procedure slightly, but essentially this method shall be used.

507.5.1.3. Low Pressure Air Testing. The CONTRACTOR shall furnish adequate personnel and equipment required to perform the tests. This test covers procedures for testing wastewater pipelines when using the low pressure air test method to demonstrate the integrity of the installed pipe line and the construction procedures. This test is used for testing 4-in. to 33-in. circular wastewater pipelines utilizing gasketed joints. Lines with a 27-in. and larger inside diameter may be tested by the individual joint method.

The low pressure air test was developed to enable detection of damaged pipe or improper jointing and is a test which determines the rate at which air under pressure escapes from an isolated section of wastewater conduit. The rate of air loss is intended to indicate the presence or absence of pipe damage and whether or not the joints have been properly constructed. The test is not intended to indicate water leakage limits and cannot be used as a measure of infiltration or exfiltration leakage under service conditions.

507.5.1.3.1. Preparation of the Wastewater Line to be Tested. The section of wastewater line to be tested shall be flushed and cleaned prior to conducting the low pressure air test. This serves to clean out the debris, wet the pipe and produces the most consistent results.

507.5.1.3.2. Low Pressure Air Line Test Procedures. The procedure for the low pressure air test shall conform to the procedures described in ASTM C828 Test Method for Low-Pressure Air Test of Vitrified Clay Pipe Lines, ASTM C924 Testing Concrete Pipe Sewer Lines by Low-Pressure Air Test Method, ASTM F1417 Test Method for Installation Acceptance of Plastic Gravity Sewer Lines Using Low-Pressure Air, or other appropriate procedures, except for testing times. Testing times shall be as outlined in this Item.

Isolate the section of wastewater line to be tested by means of inflatable stoppers or other suitable test plugs. The ends of all branches, laterals, tees, wyes and stubs to be included in the test should be plugged to prevent air leakage. All plugs should be securely braced to prevent possible blow out due to the internal air pressure. One of the plugs should have an inlet tap, or other provision for connecting a hose to a portable air control source.

Connect the air hose to the inlet tap and a portable air control source. The air equipment shall consist of necessary valves and pressure gauges to control the rate at which air flows into the test

section and to enable monitoring of the air pressure within the test section. The testing apparatus shall be equipped with a pressure relief device to prevent the possibility of loading the test section with the full capacity of the compressor.

Add air slowly to the test section until the pressure inside the pipe is raised to 3.5-psi greater than the pressure exerted by groundwater above the pipe.

After adequate pressure is obtained, regulate the air supply so that the pressure is maintained for a period of 2-minutes. This allows the air temperature to stabilize in equilibrium with the temperature of the pipe walls. The pressure will normally drop slightly until equilibrium is obtained. During this period all assessable plugs shall be checked with soap solution to detect any plug leakage.

Once the pressure is stabilized, the minimum time allowable for the pressure to drop from 3.5-psig to 2.5-psig shall be computed from the following equation:

$$T = (0.0850 \times D \times K) \div Q$$

where

T	=	time, seconds
K	=	0.000419 DL, but not less than 1.0
D	=	average inside pipe diameter, in.
L	=	length of line of same pipe size being tested, ft.
Q	=	rate of loss, 0.0015 cu. ft./min./sq. ft. internal surface shall be used

Minimum holding times required according to pipe diameter are shown in Table 507.5.1.3.2.(a) Duration Requirements for Air Testing. The test may be stopped if no pressure loss has occurred during the first 25% of the calculated testing time. If any pressure loss or leakage has occurred during the first 25% of the testing period, then the test shall continue for the entire test duration, as outlined in Table 507.5.1.3.2.(a), or until failure.

Upon completion of the test, the bleeder valve is opened and all air is allowed to escape. Plugs shall not be removed until all air pressure in the test section has been released. No one shall be allowed in the trench or manhole while the test is being conducted.

Table 507.5.1.3.2.(a) Duration Requirements for Air Testing
Time Required for Loss of Pressure from 3.5 psig to 2.5 psig
for Size and Length of Pipe Indicated for Q = 0.0015 and initial K = 1.0

Pipe Dia. (in.)	Minimum Time ¹ (sec.)	Length for Min. Time (ft.)	X for Longer Length ²	Test Time (sec.) for Length (L) (ft.) Shown							
				100 ft.	150 ft.	200 ft.	250 ft.	300 ft.	350 ft.	400 ft.	450 ft.
4	227	597	0.380	227	227	227	227	227	227	227	227
6	340	398	0.855	340	340	340	340	340	340	342	385
8	453	298	1.520	453	453	453	453	456	532	608	684
10	567	239	2.374	567	567	567	567	712	831	950	1068
12	680	199	3.419	680	680	684	855	1026	1197	1368	1539
15	850	159	5.342	850	850	1068	1336	1603	1870	2137	2404
18	1020	133	7.693	1020	1020	1539	1923	2308	2692	3077	3462
21	1190	114	10.471	1190	1571	2094	2618	3141	3665	4188	4712
24	1360	99	13.676	1368	2051	2735	3419	4103	4787	5470	6154
27	1530	88	17.309	1731	2596	3462	4327	5193	6058	6924	7789
30	1700	80	21.369	2137	3205	4274	5342	6411	7479	8548	9616
33	1870	72	25.856	2586	3878	5171	6464	7757	9050	10343	11635

1. The test may be stopped if no pressure loss has occurred during the first 25% of the calculated testing time. If any pressure loss or leakage has occurred during the first 25% of the testing period, then the test shall continue for the entire test duration, as outlined above, or until failure.

2. X is a factor used to find test duration time (t) for total length (L), where L must be greater than minimum length in the following equation: $t = X(L)$

507.5.1.3.3. Individual Joint Test Method. All wastewater conduit 36-in. and larger in diameter shall be 100% air tested at each joint connection only. A visual inspection of each joint shall be performed immediately after testing. The method of testing shall be described in [Item 507.5.1.3.2.](#)

Low Pressure Air Line Test Procedures except for test time. The time allowed for the pressure drop from 3.5 psig to 2.5 psig shall be 10-seconds. No joint shall be air tested until the pipe has been backfilled. Air testing shall be performed as pipe installation progresses. At no time shall pipe installation exceed 100-feet from the last joint tested. If the joint fails to pass the joint air test, necessary repairs as recommended by the pipe manufacturer may be made if approved by the OWNER and the joint retested. Failure to pass the air test after repairs have been made may be cause for rejection.

507.5.1.4. Flexible Pipe (Deflection) Testing. Upon completion of flexible wastewater pipe installation, the CONTRACTOR shall test pipe for vertical deflection. Deflection tests shall be performed no sooner than 30-days after complete pipe placement and densification of backfill. The pipe shall be cleaned and inspected for offsets and obstructions prior to testing.

Deflection testing shall be performed by the CONTRACTOR at no cost to the OWNER. No payment will be made for delays that result from the CONTRACTOR's performance of deflection testing.

Nominal inner diameter 27-in. or smaller shall be tested by mandrel. For all pipes 27-in. ID or smaller, the mandrel shall be pulled through the pipe by hand to ensure that maximum allowable deflections have not been exceeded. Pipe with nominal ID larger than 27-in. up to and including 36-in. nominal ID may be tested by an alternate method as approved by the OWNER. If a mandrel is selected to test pipe between 27-in. up to and including 36-in., the minimum diameter, length and other requirements shall conform to the dimensions and requirements as stated below. Deflection measurement for ID's nominally larger than 36-in. shall be determined using a 1-in. diameter rigid, nonadjustable metal bar approved by the OWNER; a minimum-radius rigid template; or by a method approved by the OWNER.

507.5.1.4.1. Mandrel. Prior to use, the mandrel shall be certified by the Engineer or by another entity approved by the Engineer. Use of an uncertified mandrel or a mandrel altered or modified after certification will invalidate the deflection test. Mandrel requirements are as follows:

- (1) odd-number of legs with 9 legs minimum
- (2) effective length not less than its nominal diameter
- (3) fabricated of rigid and nonadjustable steel
- (4) fitted with pulling rings at each end
- (5) stamped or engraved on some segment other than a runner indicating the pipe material specification, nominal size, and mandrel OD (e.g., PVC D3034-200nim-187.10mm; PVC D3034-8"-7.366")
- (6) furnished in a suitable carrying case labeled with the same data as stamped or engraved on the mandrel
- (7) minimum diameter at any point along the full length as indicated in Table 507.5.1.4.1.(a) Mandrel Sizing

Table 507.5.1.4.1.(a) Mandrel Sizing

Pipe Material	Nominal Size	ASTM Baseline Minimum Mandrel Diameter ¹
	Inches	Inches
PVC-ASTM D3034 (SDR 26)	6	5.33
	8	7.11
	10	8.87
	12	10.55
	15	12.90
PVC-ASTM D3034 (SDR 35)	6	5.46
	8	7.28
	10	9.08
	12	10.79
	15	13.20
PVC-ASTM F679	18	16.92
	21	19.95
	24	22.45
	27	25.30
	30	28.50

1. Metric mandrel diameters are rounded conversions of mandrel diameters in U.S. Standard Measures. If and when the types of pipe are available and specified by the appropriate ASTM in metric dimensions as the primary measure, the Engineer shall determine the appropriate mandrel diameter according to the requirements of this subsection.
2. Mandrels for Fiberglass Reinforced Polymer Mortar (FRPM) shall be per manufacturer's specification at maximum 3% deflection.
3. For pipe sizes and mandrels not specified on table, mandrels should be sized to pipe manufacturer's maximum recommended deflections.
4. For larger diameter mandrel sizes, consult with the manufacturer.

507.5.1.4.2. Maximum Allowable Deflections. The maximum average ID shall be equal to the average OD per applicable ASTM Standard minus two minimum wall thicknesses per applicable ASTM Standards. Manufacturing and other tolerances shall not be considered for determining maximum allowable deflections.

Maximum allowable deflections shall be governed by the mandrel requirements as stated above and shall nominally be as follows, except that deflections of up to 6.5% of the nominal inside diameter are acceptable for drainage applications:

- (1) Three (3) percent of the maximum average ID for PVC Composite Pipe.
- (2) For all plastic pipe other than PVC Composite Pipe, the percentage listed of maximum average ID shall be as in Table 507.5.1.4.2.(a) Maximum Percentage Deflection Allowed.

Table 507.5.1.4.2.(a) Maximum Percentage Deflection Allowed

Nominal Pipe Size (in.)	Percentage Deflection Allowed
Up to and including 12	5.0
Over 12, up to and including 30	4.0
Over 30, up to and including 60	3.0
Over 60, up to and including 90	2.5
Over 90, up to and including 120	2.0
Over 120	1.5

If the mandrel fails to pass, the pipe shall be considered to be overdeflected. Any overdeflected pipe shall be uncovered and, if not damaged, reinstalled. Damaged pipe shall not be reinstalled, but shall be removed and replaced. Any pipe subjected to any method or process other than removal,

which attempts, even successfully, to reduce or cure any overdeflection, shall be uncovered, removed and replaced with new pipe.

507.5.2. Television Inspection. If television inspection is not performed by the OWNER, it shall be performed by the CONTRACTOR in accordance with these specifications.

Experienced personnel shall perform the inspection by closed circuit color television. A digital file and suitable log shall be submitted to the OWNER after installation of the pipe. Digital file shall include voice description, as appropriate with stationing of services indicated. Data and stationing shall be included on video. The OWNER's representative must be present during the CONTRACTOR's television inspection, unless otherwise authorized by the OWNER. Generally, the representative will be present for at least a portion of the television inspection.

All videos and run sheets shall be given to the OWNER's representative for storage and inspection by the OWNER. All videos and run sheets will become the property of the OWNER. Should any portion of the inspection tapes be of inadequate quality or coverage, as determined by the OWNER, the CONTRACTOR will have the portion reinspected and recorded at no additional expense to the OWNER.

If repairs are required, another television inspection must be made after the repairs are complete at no cost to the OWNER.

The CONTRACTOR may employ a firm qualified in this type of work to make the television inspection. The video(s) and run sheets should be furnished directly to the OWNER not the CONTRACTOR. The firm must attach a decal to the video(s) that states the following and signed by the officer of the firm: "I certify this video represents all or a part of the television inspection performed on Contract No. XXXXX and has not been altered or changed in any manner."

507.5.2.1. Equipment, Video and Run Sheet Requirements. Video must be compatible with the OWNER's equipment. All information gathered must be legible, easily read or viewed, and of high definition color in accordance with National Association of Sewer Service Companies (NASSCO) or equal. By voice on the video the operator must:

- (1) Note the date and time the recording was made.
- (2) Note the CONTRACTOR's name, project name, and contract number.
- (3) Note the name of the company performing the television inspection and the name of the operator.
- (4) Note the location, designation, and size of the main and the direction in which the test was made.
- (5) Identify every 50-foot station.
- (6) Identify the station of each manhole.
- (7) Identify the location and station of deficiencies in accordance with Pipeline Assessment and Certification Program (PACP) (as defined by NASSCO).
- (8) Identify the location and direction of entry of laterals.

A run sheet, compatible with the video, must be made noting deficiencies.

507.5.2.2. Television Inspection Special Procedures. CONTRACTOR shall follow procedural recommendations of camera manufacturer, or as approved by OWNER.

All wastewater conduit must be filled with enough water to fill all low points. The television inspection must be done immediately following the filling of the conduit. The depths of standing water allowable for mains that are greater than 24-in. in diameter shall be evaluated by the OWNER and the OWNER will determine if corrective action is required. Allowable standing water depths at the end of construction for 6-in. through 24-in. conduits shall be no greater than indicated in Table 507.5.2.2.(a) Allowable Depth of Standing Water.

Table 507.5.2.2.(a) Allowable Depth of Standing Water

Grade	Maximum Depth of Standing Water
Less than 0.7%	½-in.
0.7% and greater	0

507.5.2.3. Criteria for Acceptance of TV-Inspected Pipe. The OWNER shall decide if repairs are required, which decision shall be final. Repairs shall be no additional cost to the OWNER. Acceptance criteria are as follows unless otherwise specified.

- (1) No pulled or slipped joints.
- (2) No water infiltration.
- (3) No cracked or damaged pipe.
- (4) No structural damage to the pipe.
- (5) Wastewater lines are clean.

507.6. MEASUREMENT AND PAYMENT FOR WASTEWATER CONDUIT INSTALLATION

507.6.1. Measurement. Pipe, including corrosion protection, if in place on the pipe, or unless otherwise covered by a special bid item, shall be measured for payment in linear feet along the centerline of the pipe measured from centerline of manhole to centerline of manhole or to the end of the line in a case where no manhole exists. Deductions shall be made for special structures. Pipe which extends only through the wall of the structure shall be measured to the actual end of the pipe. No deductions shall be made for fittings, measurements being from center to center of fitting. Conduits shall not be classified for payment according to depth unless a separate trenching item is not included.

507.6.2. Payment. Pipe, including corrosion protection in place on the pipe, or unless otherwise covered by a separate bid item, shall be paid for at the contract unit price per linear foot, complete in place, as provided by the contract. The contract price per linear foot shall be the total compensation for furnishing of all labor, materials, tools, equipment, and incidentals necessary to complete the work in accordance with the plans and these specifications.

ITEM 508. OPEN CUT – STORMWATER CONDUIT INSTALLATION

508.1. DESCRIPTION

This item shall govern and control the furnishing and placing of culvert pipe and/or conduits or drainage lines, including pipe fittings, connecting drain lines to curb inlets, all joints, all connections to new or existing pipe or headwalls, manholes, catch basins etc., to the lines and grades shown on the plans. All pipe and fittings shall be of the types, shapes, classes, sizes and dimensions as shown thereon; and as may be required to complete the work as shown on the plans.

508.2. GENERAL

508.2.1. Excavation, Embedment, and Backfill. All excavation, pipe embedment, and backfill shall conform to the relevant requirements of [Item 504](#), Open Cut – Backfill, with modifications specified herein.

508.2.2. Trenchless Installation. Where tunneling or jacking methods are shown on the plans or permitted by the OWNER, methods shall conform to the requirements of [Item 503](#), Trenchless Installation.

508.3. REINFORCED CONCRETE PIPE AND BOX FOR STORMWATER

This item shall govern and control the furnishing and placing of reinforced concrete storm water collection system.

508.3.1. Materials. Reinforced concrete pipe and jointing materials shall conform to the requirements of [Item 501.6](#), Reinforced Concrete Culvert, Storm Drain, Pipe and Box Section.

508.3.2. Installation.

508.3.2.1. Pipe. All activities shall be in compliance with ASTM C1479. Bedding and backfill shall be as described in [Item 504](#), Open Cut - Backfill. The CONTRACTOR shall furnish, at its own expense, and place in position as directed by the OWNER all necessary batter boards, string lines, plummets, graduated poles, lasers, etc., required in establishing and maintaining the lines and grades. The batter boards and all location stakes must be protected from possible damage or change of location.

All pipe and fittings shall be laid and jointed in a dry trench.

Unless otherwise authorized, start the laying of pipe on the bedding at the outlet end with the spigot or tongue end pointing downstream, and proceed toward the inlet end with the abutting sections properly matched, true to the established lines and grades. Fit, match, and lay the pipe to form a smooth, uniform conduit. Where bell-and-spigot pipe is used, cut cross trenches in the foundation to allow the barrel of the pipe to rest firmly upon the bedding. Do not cut cross trenches more than 2 in. larger than the bell ends of the pipe. Lower sections of pipe into the trench without damaging the bedding and the sides of the trench. Carefully clean the ends of the pipe before the pipe is jointed. Prevent the earth or bedding from entering the pipe when it is laid. Fill all lifting holes with plugs.

The bedding grade under the middle third of the pipe outside diameter shall be prepared before laying the pipe section. Making adjustments in grade by exerting force on the barrel of the pipe with excavating equipment, by lifting and dropping the pipe, or by lifting the pipe and packing bedding material under it shall be prohibited. If the installed pipe section is not on grade, the pipe section shall be completely unjoined, the grade corrected, and the pipe then rejoined.

When elliptical pipe with circular reinforcing or circular pipe with elliptical reinforcing is used, the pipe shall be laid in the trench in such a position that the markings "top" or "bottom" shall not be more than 5° from the vertical plane through the longitudinal axis of the pipe.

508.3.2.2. Box. All activities shall be in compliance with ASTM C1675. Bedding and backfill shall be as described in [Item 504](#), Open Cut - Backfill. When precast boxes are used to form multiple barrel structures, place the box sections in conformance with the plans or as directed. Place material to be used between barrels as shown on the plans or as directed. Unless otherwise authorized, start the laying of boxes on the bedding at the outlet end and proceed toward the inlet end with the abutting sections properly matched. Fit, match, and lay the boxes to form a smooth, uniform conduit true to the established lines and grades. For trench installations, lower the box sections into the trench without damaging the box or disturbing the bedding and the sides of the trench. Carefully clean the ends of the box before it is placed. Prevent the earth or bedding material from entering the box as it is laid. Proper facilities and equipment shall be provided for hoisting and lowering the box sections without disturbing

the leveling course and the sides of the excavation or damaging the box section. Proper equipment, such as a come-along or puller, should be utilized to join the sections together. Remove and re-lay, without extra compensation, boxes that are not in alignment or that show excessive settlement after laying. Unless otherwise approved by the OWNER, loads from construction equipment transferred to a box before, during, or after fill placement, either directly or through the fill, shall not be greater than the loads assumed in the design.

508.3.3. Jointing. Jointing shall be one of the following types: Cold applied preformed plastic gaskets, flexible joint sealant, expanded cellular gaskets, or rubber gaskets. Jointing materials shall conform to the requirements of [Item 501.6.1.3](#). Joints. Gasket installation practices shall be in accordance with the manufacturer's recommendations.

508.3.3.1. Cold Applied Preformed Plastic Gaskets or Flexible Joint Sealant (Mastic). If required by OWNER, a suitable primer of the type recommended by the manufacturer of the gasket joint sealer may be brush applied to the tongue-and-groove joint surfaces and the end surfaces and allowed to dry and harden. No primer shall be applied over mud, sand or dirt or sharp cement protrusions. The surface to be primed must be clean and dry when primer is applied. Primer that shows cracking or flaking at time of installation shall not be accepted.

Before laying the pipe in the trench, attach the plastic gasket sealer around the tapered tongue or tapered groove near the shoulder or hub of each pipe joint. Remove the paper wrapper from one side only of the two-piece wrapper on the gasket and press it firmly to the clean, dry pipe-joint surface. The outside wrapper is not to be removed until immediately before pushing the pipe into its final position.

When the tongue is correctly aligned with the flare of the groove, remove the outside wrapper on the basket and pull or push the pipe home with sufficient force and power (backhoe shovel, chain hoist, ratchet hoist or winch) to cause the evidence of squeeze-out of the gasket material on the inside or outside around the complete pipe joint circumference. Remove any joint material that pushed out onto the interior of the pipe that would tend to obstruct the flow. Pipe shall be pulled home in a straight line with all parts of the pipe on line and grade at all times. Pipe damaged by this operation shall be subject to review by the OWNER and, if necessary, a change in the jointing procedure may be required. Backfilling of pipe laid with plastic gasket joints may proceed as soon as the joint has been inspected and approved by the OWNER. Special precautions shall be taken in placing and compacting backfill to avoid damage to the joints.

When the atmospheric temperature is below 60°F, plastic joint seal gaskets shall either be stored in an area warmed to above 70°F, or artificially warmed to this temperature in a manner satisfactory to the OWNER. Gaskets shall then be applied to pipe joints immediately prior to placing the pipe in the trench, followed by connection to previously laid pipe.

Refer to ASTM C990 Standard Specification for Joints for Concrete Pipe, Manholes, and Precast Box Sections Using Preformed Flexible Joint Sealants.

508.3.3.2. Flexible Cellular Materials. Joints using flexible cellular gaskets do not need to be primed. If they are primed, be certain the primer is cured and non-tacky before installing gaskets.

The CONTRACTOR shall provide a copy of the manufacturer's installation instructions to the OWNER. Just before laying the pipe in the trench, stretch the gasket around the tapered tongue (or wedge it into the tapered groove) near the shoulder or hub of each pipe joint. Treat these low-tensile gaskets gently when handling. When the tongue is correctly aligned with the flare of the groove, pull or push home with sufficient force and power (winch, ratchet hoist, chain hoist or backhoe shovel) to compress the gasket to the extent that the joint gap falls within the recommended range around the entire pipe joint circumference.

CAUTION: Do not close the joint flush, or completely flatten the gasket.

Joint gap ranges for each gasket size are shown in Table 508.3.3.2.(a) Joint Gap Ranges.

Table 508.3.3.2.(a) Joint Gap Ranges

Gasket Sizes as Printed on Parts	Joint Gap Range	
	Minimum	Maximum
3/8" x 3/8"	3/8"	3/4"
1/2" x 3/8"	3/8"	7/8"
3/4" x 3/8"	3/8"	1"
1/2" x 1/2"	1/2"	1-1/8"
3/4" x 1/2"	1/2"	1-1/4"
7/8" x 1/2"	1/2"	1-1/4"
1-1/8" x 1/2"	1/2"	1-3/8"
1/2" x 3/4"	3/4"	1-1/2"
5/8" x 3/4"	3/4"	1-1/2"
3/4" x 3/4"	3/4"	1-5/8"
7/8" x 3/4"	3/4"	1-5/8"

508.3.3.3. Rubber Gaskets.

- (1) Ensure that bell and spigot are free from cracks, chips, and other defects.
- (2) Brush loose dirt and debris from the inside surface of the bell, the spigot, and the gasket.
- (3) Stretch the gasket around the spigot, with the nose against the step, and the tube lying flat against the spigot.
- (4) If not self-lubricating, apply manufacture recommended water-based lubricant on the gasket and bell.
- (5) Align the spigot with the bell, ensuring that the gasket is in contact with the bell around the complete periphery, then thrust pipe home using suitable manual or mechanical means.

508.3.4. Fittings.

508.3.4.1. Poured Concrete Pipe Collars. At all changes in pipe sizes in the conduit line, except at manholes, a pipe collar, as shown in detail on the plans, shall be provided. The locations at which such collars are to be provided are shown on the plan-profile sheets, and their costs are to be included in the price bid for furnishing and installing reinforced concrete pipe. No extra payment shall be made for the installation of concrete pipe collars as shown on the plan-profile sheets.

508.3.4.2. Shop and Field Fabricated Wyes, Tees, Crosses and Bends. Shop or field fabricated wyes, tees, crosses or bends shall be furnished and installed where indicated or required by the OWNER. Fittings for pipe, the largest size of which is less than 24-in. in diameter, shall be shop fabricated. Fittings for larger pipe, which is 24-in. in diameter and increasingly larger, may be field fabricated. Care shall be taken in the fabrication that the concrete walls of the pipe are broken back only enough to provide the required finishing opening. The reinforcing mesh or bars in each pipe shall be joined by bending, twisting or spot welding, which shall provide a rigid connection. Concrete or mortar meeting the requirements of [Item 303](#), Portland Cement Concrete Pavement or [Item 702](#), Concrete Structures shall be wiped over the reinforcing wires connecting the two-pipe joints, compacted by light blows, shaped to the contour of the pipe barrels, lightly brushed for finish and cured under wet burlap.

508.3.4.3. Poured Concrete Pipe Plugs. When conduit lines terminate at locations which do not include connection to drainage structures, the end of the pipe shall be plugged with a field-cast unit as shown on the plan-profile sheets, and the costs thereof are to be included in the price bid to furnish and install reinforced concrete pipe. No extra payment shall be made for the installation of concrete pipe plugs as shown on the plan-profile sheets.

508.4. CORRUGATED METAL PIPE

This item shall govern and control the furnishing and placing of corrugated metal storm water collection system.

508.4.1. Pipe Materials. Unless otherwise specified on the plans or required herein, corrugated metal pipe may be aluminum, galvanized steel, aluminized steel, or precoated galvanized or aluminized steel. Pipe

shall be full circle or pipe arch type as shown on the plans. Damage to materials incurred prior to backfilling shall be corrected according to [Item 501.11.7](#). Repairs.

508.4.2. Couplings. Materials shall conform to the requirements of [Item 501.11.9](#). Couplings. Joints shall prevent infiltration of side material during the life of the installation. Connecting bands shall be placed with the clamping angles and bolts at the tops of the pipe. When it is necessary to join a new pipe of helical corrugations to an existing pipe which was installed with no circumferential end corrugations, the two pipes shall be field jointed with helically corrugated bands.

508.4.3. Excavation of Backfilling. In addition to the requirements of [Item 508.2.1](#). Excavation, Embedment, and Backfill, the provisions contained herein apply.

When pipes are laid in a trench, the trench when completed and shaped to receive the pipe shall be of sufficient width to provide free working space for satisfactory bedding and jointing and thorough tamping of the backfill and bedding material under and around the pipe.

Backfilling for the metal pipe structures is a critical phase of the construction and strict adherence of [Item 504](#). Open Cut – Backfill is required. Unless otherwise shown on the plans or permitted in writing by the OWNER, no heavy earth moving equipment will be permitted to haul over the structure until a minimum of 4-ft. of permanent or temporary, compacted fill has been placed thereon. Until a minimum cover over pipe of 12-in. is obtained, only hand operated tamping equipment will be allowed within vertical planes 2-ft. beyond the horizontal projection of the outside surfaces of the structure. Prior to adding each new layer of loose backfill material, until a minimum of 12-in. of cover is obtained, an inspection will be made of the inside periphery of the structure for local or unequal deformation caused by improper construction methods. Evidence of such will be reason for such corrective measures as may be directed by the OWNER. OWNER may require CONTRACTOR to remove and replace pipe damaged by the CONTRACTOR'S backfilling operation at no additional cost to the OWNER.

508.4.4. Laying Corrugated Metal Pipe. Unless otherwise authorized by the OWNER, the laying of pipes on the prepared foundation shall be started at the outlet end, and separate sections firmly joined together, with outside laps of circumferential joints pointing upstream and with longitudinal laps on the sides. Any metal in joints which is not protected by galvanizing or aluminizing shall be coated as approved by the OWNER. Proper facilities shall be provided for hoisting and lowering the sections of pipe in to the trench without damaging the pipe or disturbing the prepared foundation and the sides of the trench. Any pipe which is not in alignment or which shows any undue settlement after laying, or is damaged, shall be taken up and re-laid without extra compensation.

Multiple installations of corrugated metal pipe and pipe arches shall be laid with the center lines of individual barrels parallel. Unless otherwise indicated on the plans, the clear distances between outer surfaces of adjacent pipes listed in Table 508.4.4.(a) Clear Distances shall be maintained.

Table 508.4.4.(a) Clear Distances

Diameter of Pipe	Clear Distance Between Pipes Full Circle and Pipe Arch	Pipe Arch
18-in.	1-ft. 2-in.	21-in. x 15-in.
24-in.	1-ft. 5-in.	28-in. x 20-in.
30-in.	1-ft. 8-in.	35-in. x 24-in.
36-in.	1-ft. 11-in.	42-in. x 29-in.
42-in.	2-ft. 2-in.	49-in. x 33-in.
48-in.	2-ft. 5-in.	57-in. x 38-in.
54-in.	2-ft. 10-in.	64-in. x 43-in.
60-in.	3-ft. 2-in.	71-in. x 47-in.
66-in.	3-ft. 2-in.	77-in x 52-in.
72-in. through 84-in.	3-ft. 2-in.	—
90-in. through 120-in.	3-ft. 5-in.	—

508.4.5. Connections. Where new structures are constructed as extensions to structures in place or are joined to existing structures, the construction shall include all work necessary to provide a proper connection between the new structure and the old as indicated on the plans, including coating of the connection when required.

508.4.6. Reuse of Existing Headwalls. When existing headwalls and aprons are specified on the plans for reuse, the portion to be reused shall be severed from the existing pipe and moved to the new position previously prepared, by approved methods.

Connections shall conform to the requirements for joining sections of pipes as indicated herein or as shown on the plans. Any headwalls, aprons or pipe attached to the headwall damaged during moving operations shall be restored to their original condition at the CONTRACTOR'S expense. The CONTRACTOR, if it so desires, may remove and dispose of the existing headwalls and aprons and construct new headwalls at its own expense, in accordance with the pertinent specifications and design indicated on the plans or as furnished by the OWNER.

508.5. STRUCTURAL PLATE CONDUIT

This work shall consist of furnishing and installing structural plate conduit of standard or special shapes conforming to these specifications of the sizes, out dimensions, the minimum gage or thickness of metal, footing design, if required, and material required by plans, at the places designated on the plans or by the OWNER, in conformity with established lines and grades.

508.5.1. Materials.

508.5.1.1. Structural Plates. The plates used for construction of structural plate conduits shall conform to the specifications in [Item 501.12](#) Structural Plate Structures.

508.5.1.2. Concrete. Concrete, curing and reinforcing steel shall conform to [Item 702](#), Concrete Structures. Unless otherwise shown on the plans, concrete for footings and headwalls shall be Class A or Class PA as specified by the OWNER. Concrete for longitudinal stiffeners (thrust beams), when specified for steel structures, shall be Class B or Class PB as specified by the OWNER and shall be reinforced in accordance with the plans. Concrete used in longitudinal stiffeners (thrust beams) on steel structures shall cure a minimum of 3-days before backfilling against or over the stiffener. Riprap for slope protection and for invert paving, when required, shall be Class B or Class PB concrete as specified by the OWNER, with reinforcement as specified on the plans and shall conform to the requirements of [Item 803.3](#), Riprap.

508.5.2. General Construction Methods. Structural plate conduits shall be constructed from the specified materials in accordance with the plans and this item.

Steel plates will have approximately a 2-in. lip beyond each end crest, which results in the actual length of a given structure being approximately 4-in. longer than the nominal length, except when skewed or beveled. Footings for arches shall be designed and constructed to accommodate this additional length.

The distance between multiple structures shall be shown on the plans with the minimum distance being that space required to permit adequate compaction of backfill material.

508.5.3. Excavation. Unless otherwise required, all structural excavation shall be in accordance with the requirements of [Item 701.2](#), Structural Removal, Excavation, and Backfill, and the additional requirements herein. The excavation will be of sufficient width to provide ample working space for erection and proper compaction of backfill and bedding material. The CONTRACTOR shall provide adequate drainage of the cut and bedding during the construction operation.

If the quality of the native soil is as good as or better than the proposed backfill material, excavation shall be to the limits set forth in the [Item 701.2](#), Structural Removal, Excavation, and Backfill. If the quality of the native soil is less than that of the proposed backfill material, the excavation shall extend, from each side of the barrel, a minimum horizontal distance of $\frac{1}{2}$ -span or $\frac{2}{3}$ -rise, whichever is greater.

508.5.4. Substructures for Structural Plate Arches. The substructure for structural plate arches shall be as detailed on the plans. Concrete footings, when required, shall be placed entirely on either rock or firm soil. When footing area is partially rock and partially soil, the rock shall be removed below grade and replaced with suitable materials so that a slightly yielding, compacted earth cushion is provided below the

footing for a minimum of 12-in. When a thin layer of soil is partially covering rock within the bearing area and when practical to do so, the soil may be removed and the footings placed directly on rock in accordance with details shown on the plans.

Footings shall be formed and finished to true lines and grades as established by the OWNER. Anchors or slots shall be set to true line and grade when placing concrete for each substructure unit. No plates for arch structures shall be placed until the substructure has cured for a minimum of 3-days.

Any portion of an aluminum structure that is in contact with a metal other than aluminum or in contact with concrete containing chlorides shall be insulated from this other metal or concrete containing chlorides by a coating of bituminous material or a plastic coating, such as asphalt, mastic or polymeric coating. The coating shall be applied to the aluminum structure to provide insulation between the aluminum and other metal or concrete containing chlorides and shall extend a minimum distance of 1-foot beyond the area of contact.

508.5.5. Foundations for Structural Plate Conduits with Metal Inverts. Horizontal ellipses, box culverts, or other structural plate shapes with metal inverts shall be placed on a shaped bed of granular material carefully and accurately shaped to fit the lower part of the structure for at least 10-percent of its overall height, except that the length of bedding arc need not exceed the width of the bottom plate. The granular material shall be at least 3-in. in thickness, so as to obtain uniform seating of the corrugations on the structure bed. For culverts, the bedding specified herein shall be the full width of the invert. Where rock, in either ledge or boulder formation, is encountered, it shall be removed below grade and replaced with a compacted earth cushion having a thickness of not less than ½-in.-per-foot height of fill over the top of the structure, with the minimum allowable thickness of 12-in. and a maximum of 24-in. under the structure. Where the soil encountered at the established grade is a quicksand, muck or similar unstable material, it shall be removed and replaced in accordance with the requirements of [Item 701.2](#), Structural Removal, Excavation, and Backfill.

508.5.6. Skewed Structures. The end skew shall not exceed 45°. When the skew of arches is more than 15°, the length of the structure shall be such that no portion of the live load will be carried by the cut portion of the arch end. Where right-of-way or other conditions do not permit the required length, the cut end shall be supported by a rigid headwall designed to meet the conditions. When the skew angle of pipes exceeds 20° and the structure has the ends cut to fit a slope, the ends shall be reinforced with concrete riprap or other suitable end treatment as indicated on the plans or as directed by the OWNER. If headwalls are required, the plates shall be anchored to the headwall with not less than ¾-in. diameter by 6-in. minimum length bolts, at not over 19-in. centers. If structures are to have skewed ends, bevels, step-bevels or other special end treatment, this information will be shown on the plans.

508.5.7. Erection and Shape Control. When all plates of a structure are in position, all bolts not already in place shall be inserted and all nuts tightened progressively and uniformly, beginning at one end of the structure. All nuts shall be tightened a second time to a torque of not less than 150-ft.-lbs. nor more than 300-ft.-lbs. for steel structures, and not less than 125-ft.-lbs. nor more than 150-ft.-lbs. for aluminum structures.

It is essential that bolts be well tightened. If an impact wrench is used, a sufficient number of bolts shall be checked with a long-handled, structural or socket wrench or torque wrench to insure that they are properly tightened. All service bolts used in drawing the plates together shall be replaced with standard high strength bolts.

Lateral ties, struts and/or false-work may be required on some structures to maintain proper shape and alignment during erection and backfill operations. Monitoring of the structure shape throughout erection and backfill requires careful observations of the symmetry and uniform curvature of the periphery of the structure. If there is any tendency toward loss of symmetry in shape or loss of curvature in the structure periphery, even though the structure is within the tolerances stated herein, construction involving the structure shall cease until a proper course of action is established.

CONTRACTOR shall furnish acceptable devices for monitoring the horizontal and vertical shape of the structure. For box culverts and structures not requiring longitudinal or transverse stiffeners, the shape shall be kept within 2-percent of design measurements (span or rise, whichever is greater) or 5-in., whichever is less, during erection and backfilling. For structures requiring either longitudinal stiffeners or transverse

stiffeners (except box culverts), a minimum of 5 monitoring devices shall be furnished at transverse sections, with one at each longitudinal stiffener, one at the top of the structure, and one at each mid span of the top arc. These shall be installed at each end and as a minimum on 24-ft. increments for the entire structure length.

For the shape factor furnished (shape factor = R_t/R_s , where R_t is the radius of the top arc and R_s is the radius of the side arc), unless otherwise shown on the plans, the allowable sag from design shape during erection, as a percentage of the rise shall not exceed tolerances shown in Table 508.5.7.(a) Allowable Sag.

Table 508.5.7.(a) Allowable Sag

Shape Factor	Allowable Sag (expressed as percentage of the rise)
up to 2.74	4%
2.75 through 3.24	2%
3.25 and greater	1%

Shape shall be checked at least after each two, 1-ft. compacted lifts of backfill, with the upward movement of the top of the structure during backfilling, not to exceed 2-percent of the rise, nor more than 50-percent loss of the mid-ordinate of the side plates, nor more than 25-percent deviation of any mid-ordinate of the top plates, all measured from the design shape. Selective top loading of the structure may sometimes be required to prevent distortion in excess of tolerances given herein.

508.5.8. Backfilling. Backfilling and/or construction of the embankment around and over the structure is a critical phase of the construction, and strict adherence to these construction methods is required. Backfilling and/or embankment construction around the structure shall be performed in accordance with [Item 203](#). Site Preparation and [Item 504](#). Open Cut – Backfill, except as modified herein.

Any damage to plates or structures caused by equipment and/or backfilling operations shall be corrected or removed and replaced to the OWNER'S satisfaction at the entire expense of the CONTRACTOR.

508.5.8.1. Structural Plate Conduits Without Longitudinal or Transverse Stiffeners and Box

Culverts. Unless otherwise shown on the plans or permitted in writing by the OWNER, no heavy earth moving equipment will be permitted to haul over the structure until a minimum of 4-ft. of permanent or temporary compacted fill has been placed thereon. Within vertical planes 2-ft. beyond the horizontal limits of the structure and until a minimum of 2-ft. of cover has been compacted over the structure, only hand operated, mechanical tamping equipment will be permitted.

During the backfilling operations, extreme care shall be taken to avoid unequal pressures and to obtain uniformly compacted backfill material of uniform density throughout the length of the structure and to insure proper backfill under the structure.

The structure shall be backfilled so that when backfill is complete, the inside dimensions shall be within tolerances set forth in [Item 508.5.7](#). Erection and Shape Control. Backfill material will be placed and compacted in maximum 8-in. lifts simultaneously along each side of the structure until the height of the backfill has reached the crown of the structure. Backfill shall continue to be placed in maximum 12-in. lifts over the crown in layers extending laterally from the crown and compacted using hand operated or light compaction equipment until the design height is obtained.

For multiple structures the same backfill phases will be performed for all structures more or less simultaneously. Backfilling between the barrels will usually require that the material be placed with a crane and bucket or other suitable equipment. Backfill material shall not be dropped from a height or concentrated in such an amount prior to distribution over the top arc that damage to the flexible structure will result. Compaction of this backfill shall be with hand operated tampers or other acceptable equipment.

508.5.8.2. Structural Plate Conduits Requiring Longitudinal or Transverse Stiffeners Except Box

Culverts. The plans will designate, when appropriate, the longitudinal stiffener designs for steel structures or a transverse stiffener design for aluminum structures. The backfill material to be used adjacent to and over the structure to the minimum required cover (as shown on the plans) shall be a

granular type material such as a well graded sand and gravel (preferably sharp, rough and angular if possible), or a uniform sand or gravel. Plastic soils will not be permitted. The structure backfill material shall conform to one of the following soil classifications as defined in Table 508.5.8.2.(a) Classification of Soils and Soil-Aggregate Mixtures.

- (1) For height of fill less than 12-ft.: A-1, A-3, A-2-4 and A-2-5 may be used.
- (2) For height of fill of 12-ft. or greater: A-1 and A-3 may be used.

Table 508.5.8.2.(a) Classification of Soils and Soil-Aggregate Mixtures

GENERAL CLASSIFICATIONS = GRANULAR MATERIALS (35-Percent or Less Passing No. 200)					
Characteristic	Group Classification				
	A-1		A-3	A-2	
	A-1-a	A-1-b		A-2-4	A-2-5
Sieve Analysis, Percent Passing: (No. 10) (No. 40) (No. 200)	50 max. 30 max. 15 max.	— 50 max. 25 max.	— 51 max. 10 max.	— — 35 max.	— — 35 max.
Characteristics of Fraction Passing 0.425 mm. (No. 40) Liquid limit Plasticity index	— 6 max.		— N. P.	40 max. 10 max.	41 min. 10 max.
Usual Types of Significant Constituent Materials	Stone Fragments, Gravel and Sand		Fine Sand	Silty or Clayey Gravel and Sand	

The backfill material shall be compacted to at least 95-percent of maximum density as determined by ASTM D698 Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³). Moisture content shall be within minus-2- to plus-4-of-optimum. It may not be possible to develop this compacted density in the first lift of material over the top arc (Phase 2 described below) due to the influence of the flexible structure; therefore, density in at least the first lift over the top arc (Phase 2) will be the highest density attainable using equipment authorized herein.

The backfill pattern and sequence, up to at least the depth of minimum required cover, shall be in three phases. Phase 1 of the backfill operation will be to backfill under the haunches and/or along the side-walls of the structure. Backfill material will be placed in maximum 8-in. lifts simultaneously along each side of the structure until the height of backfill has reached the top of the longitudinal stiffeners or that longitudinal seam (edge of structure crown where the top arc plates connect to the side arc plates).

Phase 2 will be to work simultaneously symmetrically from both sides of the structure with light track type equipment pushing material over the crown until three 12-in. lifts of backfill have been placed and compacted uniformly over the crown. The light track equipment shall not exceed 20,000-pounds gross weight with a track pressure less than 1700-pounds-per-square-foot.

After the crown has been uniformly covered, Phase 3 will be to continue to place maximum 12-in. lifts of backfill, compacted, which extend laterally from the crown and compact over the crown and at the sides of the structure using hand operated or light tractor drawn compaction equipment working at the same time on each side of the structure at the same longitudinal location, until at least the minimum required depth of cover is attained. Wheel type equipment will not be allowed over the crown of the structure until Phase 3 is complete.

For multiple structures the same backfill phases will be performed for all structures more or less simultaneously. Backfilling between the barrels will usually require that the material be placed with a crane and bucket or other suitable equipment. Backfill material shall not be dropped from a height or concentrated in such an amount prior to distribution over the top arc that damage to the flexible structure will result. Compaction of this backfill shall be with hand operated tampers or other acceptable equipment.

508.6. CORRUGATED THERMOPLASTIC PIPE

This item shall govern and control the furnishing and placing of corrugated thermoplastic pipe to be used in storm water collection systems.

508.6.1. Pipe Materials. Unless otherwise specified on the plans or as required herein, corrugated thermoplastic pipe shall meet the requirements of [Item 501.23](#), Thermoplastic Corrugated Drainage Tubing and Corrugated Smooth Lined Storm Water Pipe and Fittings. Pipe shall be full circle as shown on the plans. Damage to the materials incurred prior to backfilling shall be removed and replaced.

508.6.2. Couplings. Materials shall conform to the requirements of [Item 501.23.4](#). Joints shall prevent infiltration of side material during the life of the installation. Soil-tight Joints shall be bell and spigot or utilize couplings that engage at least two full corrugations on each pipe section in accordance with AASHTO M330.

508.6.3. Installation of Pipe. The CONTRACTOR shall furnish, at its own expense, and place in position as directed by the OWNER all necessary batter boards, string lines, plummets, graduated poles, lasers, etc., required in establishing and maintaining the lines and grades. The batter boards and all location stakes must be protected from possible damage or change of location. The cost of replacement of location stakes shall be at no additional cost to the OWNER.

All pipe and fittings shall be laid and jointed in a dry trench of a minimum width as shown in Table 508.6.3.(a) Minimum Trench Widths for the Installation of Corrugated Thermoplastic Pipe.

The minimum depth of cover and trench width should be established by the OWNER based on evaluation of specific project conditions or ASTM D2321.

Table 508.6.3.(a) Minimum Trench Widths for the Installation of Corrugated Thermoplastic Pipe

Nominal Inside Pipe Diameter (Inches)	Typical Outside Pipe Diameter (inches)			Minimum Trench Width ¹ (Inches)
	HDPE	PP	PVC	
4	4.9	NA	4.3	21
6	6.9	NA	6.4	23
8	9.1	NA	8.6	25
10	11.2	NA	10.8	27
12	14.3	14.5	12.8	30
15	17.5	17.6	15.7	33
18	21.5	21.2	19.2	38
24	28.0	28.0	25.6	46
30	35.5	35.4	32.2	55
36	42.0	41.1	38.7	63
42	47.5	47.2	NA	71
48	54.0	53.8	NA	79
54	61.0	NA	NA	88
60	67.0	66.5	NA	95

¹For pipe sizes larger than those shown above, use pipe manufacturer's recommendation or ASTM D2321.

Install foundation and bedding as required by the OWNER. Unless otherwise authorized by the OWNER, the laying of the pipe on the prepared foundation shall be started at the outlet or downstream end with the spigot or tongue end of the pipe joint pointing downstream. Place pipe and fittings in the trench with the invert conforming to the required elevations, slopes, and alignment. Place embedment materials by methods that will not disturb or damage the pipe. Work in and tamp the haunching material in the area between the bedding and the underside of the pipe before placing and compacting the remainder of the embedment in the pipe zone.

Laying shall proceed toward the inlet or upstream end with each abutting section of pipe properly matched, true to the established lines and grades. Approved facilities shall be provided for hoisting and lowering the sections of pipe or the sides of the trench. The ends of the pipe shall be carefully cleaned before the pipe is placed in the trench. As each length of the pipe is laid, the open end shall be protected to prevent

the entrance of earth or bedding material. The pipe shall be fitted and matched so that when laid in the prepared bedding, it shall form a smooth, uniform conduit.

508.6.4. Jointing. Jointing shall be one of the following types: Soil-tight joints shall meet the requirements of [Item 501.23.4](#). Joints; Water-tight Joints shall meet the requirements of [Item 501.23.4](#). Joints. The CONTRACTOR is to comply with manufacturer's recommendations for assembly of joint components, lubrication, and making of joints.

508.6.5. Excavation and Backfilling. In addition to the requirements of [Item 504](#). Open Cut – Backfill, the provisions contained herein apply.

When pipes are laid in a trench, the trench when completed and shaped to receive the pipe shall be of sufficient width to provide free working space for satisfactory bedding and jointing and thorough tamping of the backfill and bedding material under and around the pipe. Backfilling for thermoplastic pipe structures is a critical phase of the construction and strict adherence of [Item 504](#). Open Cut – Backfill is required. Unless otherwise shown on the plans or permitted in writing by the OWNER, no heavy earth moving equipment will be permitted to haul over the structure until a minimum of 2 feet of depth for 24 inch diameter and smaller pipes or a minimum of 3 feet on pipes larger than 24 inches in diameter of permanent or temporary, compacted fill has been placed thereon. Until a minimum cover over pipe of 12 inches is obtained, only hand operated tamping equipment will be allowed within vertical planes 2 feet beyond the horizontal projection of the outside surfaces of the structure. Prior to adding each new layer of loose backfill material, until a minimum of 12 inches of cover is obtained, an inspection will be made of the inside periphery of the structure for local or unequal deformation caused by improper construction methods. Evidence of such will be reason for such corrective measures as may be directed by the OWNER. OWNER may require CONTRACTOR to remove and replace pipe damaged by the CONTRACTOR'S backfilling operation at no additional cost to the OWNER.

508.6.5.1. Shaping and Bedding. Bed the pipe in a foundation of compacted cohesionless material, such as sand, crushed stone, or pea gravel, with a maximum allowable size of 1 in. Extend this material a minimum of 6 in. below the outermost corrugations or ribs, and carefully and accurately shape it to fit the lowest part of the pipe exterior for a minimum of 10% of the overall height. When requested by the OWNER, furnish a template for each size and shape of pipe to be placed for use in checking the shaping of the bedding. Provide a template consisting of a thin plate or board cut to match the lower half of the cross section of the pipe.

508.6.5.2. Backfilling. Backfill from the pipe bedding up to 1 ft. above the top of the pipe to provide necessary structural support to the pipe and control pipe deflection. Take special precautions when placing and compacting backfill material. Place special emphasis obtaining uniform compacted density throughout the length of the pipe, to avoid unequal pressure. Use extreme care to ensure proper backfill under the pipe, in the haunch zone.

Provide backfill material meeting the following specifications:

- (1) Type I- Provide backfill consisting of flowable fill in accordance with [Item 504.2.3.4](#) Flowable Backfill. Place the flowable backfill across the entire width of the trench and maintain a minimum depth of 12 in. above the pipe. Wait a minimum of 24 hours before backfilling the remaining portion of the trench with other backfill material in accordance with [Item 504.2.3](#). Final Backfill.
- (2) Type II- Provide backfill consisting of cement stabilized backfill in accordance with [Item 504.2.3.5](#). Modified Flowable Backfill. Place and compact cement stabilized backfill to completely fill any voids.
- (3) Type III- Provide backfill consisting of hard, durable, clean granular material that is free of organic matter, clay lumps, and other deleterious matter. Provide backfill meeting the gradation requirement shown in Table 508.6.5.2.(a). Place the backfill material along both sides of the completed structure to a depth of 12 in. above the pipe. Place the backfill in uniform layers a minimum of 6 in. deep (loose measurement), wet if required and thoroughly compacted between adjacent structures and between the structure and the sides of the trench. Until a minimum cover of 12 in. is obtained, only hand-operated tamping equipment will be allowed within vertical planes 2 ft. beyond the horizontal projection of the outside surfaces of the structure. If using Type III backfill,

place filter fabric between the native soil and the backfill as directed by OWNER. Filter fabric shall meet TxDOT Specification DMS-6200.

Table 508.6.5.2.(a) Gradation Requirements for Type III Backfill Material

Sieve Size	Percent Retained (Cumulative)
1 in.	0-5
7/8 in.	0-35
1/2 in.	0-75
3/8 in.	0-95
No. 4	35-100
No. 10	50-100
No. 200	90-100

508.6.6. Pipe Testing. Upon completion of pipe installation, the CONTRACTOR shall test thermoplastic and thermoset pipe for deflection. Deflection tests shall be performed no sooner than 30-days after densification of backfill.

Deflection testing shall be performed by the CONTRACTOR at no cost to the OWNER. No payment will be made for delays that result from the CONTRACTOR's performance of deflection testing.

The CONTRACTOR shall test all thermoplastic pipes for deflection by one of the following methods: 1. Mandrel, or 2. Laser Video.

Nominal diameter 27-in. or smaller shall be tested by mandrel. The mandrel shall be pulled through the pipe by hand to ensure that maximum allowable deflections have not been exceeded. Pipe with nominal ID larger than 27-in. may be tested by an alternate method as approved by the OWNER. If a mandrel is selected to test pipe 27-in. and larger, the minimum diameter, length and other requirements shall conform to the dimensions and requirements as stated below. Deflection measurement for ID's nominally larger than 27-in. shall be determined using a 1-in. diameter rigid, nonadjustable metal bar approved by the OWNER; a minimum-radius rigid template; or by a method approved by the OWNER.

508.6.6.1. Mandrel. Prior to use, the mandrel shall be certified by the OWNER. Mandrel requirements are as follows:

- (1) odd-number of legs with 9 legs minimum
- (2) effective length not less than its nominal diameter
- (3) fabricated of steel
- (4) fitted with pulling rings at each end
- (5) stamped or engraved on some segment other than a runner indicating the pipe specification, nominal size, and mandrel OD

If the mandrel fails to pass, the pipe shall be considered to be "overdeflected". Any overdeflected pipe shall be uncovered and, if not damaged, reinstalled. Damaged pipe shall not be reinstalled, but shall be removed and replaced. Any pipe subjected to any method or process other than removal, which attempts, even successfully, to reduce or cure any overdeflection, shall be uncovered, removed and replaced with new pipe. Final remediation to be approved by OWNER.

508.6.6.2. Laser Video Equipment. A combination color CCTV pipeline survey system with a cable distance counter, laser profiling system, non-contact video micrometer and measurement software shall be used to perform a measurement survey of thermoplastic pipelines with nominal inside diameter 60-in. or smaller. The equipment used shall be certified by a recognized independent testing group and includes a certified accuracy of 0.5% or better and a repeatability of 0.12% or better. Refer to ASTM E691 and ASTM E177 for equipment calibration.

508.6.7. Multiple Installations of Corrugated Thermoplastic Pipe. Multiple installations of corrugated thermoplastic pipe shall be laid with the center lines of individual barrels parallel. Unless otherwise indicated on the plans, the clear distances between outer surfaces of adjacent pipes are listed in Table 508.6.7.(a) Clear Distances shall be maintained.

The minimum clear distance should be established by the OWNER based on evaluation of specific project conditions or pipe manufacturer's recommendations.

Table 508.6.7.(a) Clear Distances

Diameter of Pipe (Inches)	Clear Distance Between Outside surfaces of Pipes – Full Circle (Inches)
18 and smaller	14 in.
24	17 in.
30	20 in.
36	23 in.
42	26 in.
48	29 in.
54	34 in.
60	38 in.
66	38 in.

508.7. MEASUREMENT AND PAYMENT FOR STORMWATER CONDUIT INSTALLATION

508.7.1. Measurement. Pipe, including corrosion protection, if in place on the pipe, or unless otherwise covered by a special bid item, shall be measured for payment in linear feet along the centerline of the pipe measured from centerline of manhole to centerline of manhole or to the end of the line in a case where no manhole exists. Deductions shall be made for special structures. Pipe which extends only through the wall of the structure shall be measured to the actual end of the pipe. No deductions shall be made for fittings, measurements being from center to center of fitting. Conduits shall not be classified for payment according to depth unless a separate trenching item is not included.

508.7.2. Payment. Pipe, including corrosion protection in place on the pipe, or unless otherwise covered by a separate bid item, shall be paid for at the contract unit price per linear foot, complete in place, as provided by the contract. The contract price per linear foot shall be the total compensation for furnishing of all labor, materials, tools, equipment, and incidentals necessary to complete the work in accordance with the plans and these specifications.

ITEM 509. CROSSINGS

509.1. GENERAL

This specification shall govern for the construction of underground conduits (water, wastewater, stormwater mains, etc.) on or across streets, alleys, highways or railroads, creeks or rivers as detailed in the plans. The CONTRACTOR shall provide and employ adequate warning signs, barricades, lights, watchmen, etc. to fully protect its workers and the traveling public as required in [Item 107.20](#), Protection of Work and of Persons and Property and [Item 107.19](#), Public Convenience and Safety. No changes shall be made in location as shown on the plans without prior authorization of the appropriate agency and the OWNER. Bore pits and related appurtenances are to comply with the requirements of the franchise owner. For crossings not mentioned below, the crossing requirements of the affected owner shall be followed.

509.2. STATE HIGHWAY CROSSINGS

All crossings shall conform to the TxDOT *Utility Accommodation Policy Manual Special Specifications*. Permits from TxDOT are required for all highway crossings. A copy of permits obtained from TxDOT shall be at the construction site available for the OWNER to review.

509.3. STREET AND ALLEY CROSSINGS

The construction of underground conduits on or across street and alley rights-of-way and the removal and replacement of pavement, curb and gutter, etc., shall be in accordance with the following requirements.

The CONTRACTOR shall protect the street and alley surface and all existing improvements from excavated materials, equipment operations and other construction operations. If jacking, boring or tunneling is indicated or specified, the work shall be performed in accordance with the requirements of [Item 503](#), Trenchless Installation. If open-cut method is indicated or specified, the construction operations shall be conducted in accordance with the requirements in [Item 504](#), Open Cut – Backfill.

509.4. RAILROAD CROSSINGS

All railroad crossings shall conform to the respective railroad company's requirements. The CONTRACTOR must obtain insurance and other requirements of the railroad company prior to beginning any work within the railroad right-of-way.

509.5. CREEK AND RIVER CROSSINGS

Creek crossing using pier construction shall be made in accordance with the details shown on the plans. River crossings, siphons and miscellaneous pipe structures as may be necessary shall be designed in detail on the plans.

509.6. MEASUREMENT AND PAYMENT OF CROSSINGS

Each crossing within the limits noted on the plans and/or set forth in the proposal shall constitute a separate pay item where indicated on the plans and specifications and shall be paid for as shown in the proposal. The contract price shall be the total compensation for the furnishing of all labor, materials, tools, equipment and incidentals necessary to complete the work, including all excavation, disposal of surplus materials and backfill, in accordance with the plans and these specifications. The contract price or combination of prices includes compensation for excavation for piers, erecting piers, stripping forms, erecting pipe and supporting pipe (if required), in accordance with the plans and specifications.

A close-up photograph of several white PVC conduits running vertically along a light-colored, textured wall. The conduits are held in place by metal clamps. The image is partially overlaid by a blue banner on the right side, which contains white text.

Division 600

Conduit and Appurtenance Rehabilitation

DIVISION 600 CONDUIT & APPURTENANCE REHABILITATION

TABLE OF CONTENTS

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
601.	<u>PIPELINE REHABILITATION</u>	<u>601-1 to 601-10</u>
601.1.	<u>Description</u>	
601.2.	<u>General</u>	
601.3.	<u>General Materials</u>	
601.4.	<u>General Methods</u>	
601.5.	<u>Section Held for Future Use</u>	
601.6.	<u>Section Held for Future Use</u>	
601.7.	<u>Cured-In-Place Pipe Liner (CIPP Liner)</u>	
601.8.	<u>Pipe Bursting With Polyethylene</u>	
601.9.	<u>Pipe Bursting With Rigid Pipe</u>	
601.10.	<u>Segmental Sliplining</u>	
601.11.	<u>Measurement and Payment</u>	
602.	<u>REHABILITATION OF MANHOLES OR UNDERGROUND VAULTS</u>	<u>602-1 to 602-4</u>
602.1.	<u>General</u>	
602.2.	<u>Submittals</u>	
602.3.	<u>Quality Assurance</u>	
602.4.	<u>Delivery, Storage and Handling</u>	
602.5.	<u>Rehabilitation</u>	
602.6.	<u>Inspection and Testing</u>	
602.7.	<u>Measurement and Payment</u>	
603.	<u>ABATEMENT OF COATINGS CONTAINING CERTAIN HEAVY METALS</u>	<u>603-1 to 603-4</u>
603.1.	<u>General</u>	
603.2.	<u>Job Plan</u>	
603.3.	<u>Testing</u>	
603.4.	<u>Monitoring</u>	
603.5.	<u>Protection</u>	
603.6.	<u>Lead-Based Coating Removal</u>	
603.7.	<u>Lead-Based Coating Encapsulation</u>	
603.8.	<u>Cleanup and Disposal</u>	
603.9.	<u>Payment</u>	
604.	<u>REMOVAL OF ASBESTOS-CEMENT PIPE (ACP)</u>	<u>604-1</u>
604.1.	<u>General</u>	
604.2.	<u>Job Plan</u>	
604.3.	<u>Procedures</u>	
604.4.	<u>Disposal</u>	
604.5.	<u>Payment</u>	

ITEM 601. PIPELINE REHABILITATION

601.1. DESCRIPTION

This item shall govern the rehabilitation of pipe using materials and methods that may be used as an alternative to pipeline replacement. Unless indicated otherwise, these methods shall be used for non-pressure (gravity flow) pipeline rehabilitation. Other processes not specified in this section may be approved for use by OWNER.

601.2. GENERAL

No pipe shall be reconstructed without prior notification of the OWNER. Work shall include the furnishing of all labor, equipment and materials necessary to complete the rehabilitation of pipelines and service reconnections as stipulated herein and as specified in Contract Documents. Work shall include the preparation of the construction site, including cleaning and flushing of existing piping; flow control bypass pumping; protection of existing conditions during installation work; unloading; hauling; distributing and installation; testing of all pipe, fittings, scaffolding, valves, boilers, etc. and other accessories as required for proper installation. It shall also include restoration or replacement of all removed or damaged pavement, curb, sidewalk, gutter, shrubbery, fence, sod or other disturbed surfaces or structures in a condition equal to that before the work began, to the satisfaction of the OWNER, and shall furnish all labor and material incidental thereto.

The OWNER shall locate and designate all manhole access points open and accessible for the work, and provide rights of access to these points. The OWNER shall also provide access to water hydrants for cleaning, inversion, and other work items requiring water.

601.2.1. Submittals. Submittals shall be made according to the OWNER'S schedule so that project schedules can be met.

CONTRACTOR shall submit the following to the OWNER:

- (1) Method of pipe rehabilitation and restoration of existing service connections. This shall include detail drawings and written description of the entire construction procedure to install pipe, bypass flow in the section of existing pipe to be reconstructed, and reconnection of service connections. Drawings shall include showing the cross sectional profile of the pipe wall and pipe joint details. For pipes larger than 12-in diameter, bypass specifications shall be sealed by a registered OWNER. The process shall not be detrimental to liner pipe material and its properties;
- (2) A complete list of all materials proposed to be furnished and installed, including manufacturer's name and catalog number for each item, complete information on material composition, physical properties, and dimensions of new pipe and fittings and technical data, and manufacturer's recommendations for handling, storage, installation, and repair of pipe and fittings damaged;
- (3) Manufacturer's design calculations, including minimum thickness of the pipe materials being supplied;
- (4) Prior to use of the materials, if required, written certification of the CONTRACTOR'S compliance with the manufacturer's standards and specifications for all materials;
- (5) After reviewing the site, but prior to starting any rehabilitation process, the CONTRACTOR shall make a plan of all work activities. If required by the OWNER, the CONTRACTOR shall plan its work after review of pre-construction television inspection tape and reports. If required by the OWNER, the CONTRACTOR shall furnish its work plan to the OWNER;
- (6) Flow control implementation plan shall be pre-approved by OWNER prior to any construction.

601.2.2. Inspections and Testing. Prior to all work, the CONTRACTOR shall carefully inspect the area for existing conditions.

Each pipe or pipe material shall be subject to inspection by the OWNER immediately before it is installed and defective pipe or pipe material may be rejected at no cost to the OWNER.

CONTRACTOR shall perform pre-construction and post-construction television inspection. Television inspection shall be performed according to [Item 507.5.2. Television Inspection](#), with the following modifications:

- (1) The interior of the pipeline shall be carefully inspected to determine the location of any condition that may prevent proper installation of the new pipe;

- (2) These conditions shall be indicated to the OWNER prior to installation and corrected as determined by the OWNER;
- (3) A digital file and suitable log shall be submitted to the OWNER prior to and after installation of the pipe, which become property of the OWNER.

Where applicable, the CONTRACTOR shall provide a pipe "coupon" specimen from each run of pipe for testing, after installation, by an approved laboratory. All expenses for the testing of these specimens will be paid by the OWNER. The cost of retests made necessary by the failure of the samples of specimens to meet the specified requirements shall be paid for by the CONTRACTOR. CONTRACTOR shall conduct Pre- and Post-TV inspections at no cost to the OWNER.

601.3. GENERAL MATERIALS

Materials shall be appropriate to the size of the existing pipeline to be reconstructed.

Pipe interior shall be a light color to facilitate video inspection.

The CONTRACTOR shall verify all existing pipe diameters prior to ordering pipe materials.

The CONTRACTOR shall not permit any pipe rehabilitation component to be brought onto the job site until it has been approved by the OWNER.

Tests for compliance with these specifications shall be made as specified herein and in accordance with applicable ASTM specifications. Upon request, the manufacturer shall furnish a certificate for all material furnished under this specification.

All materials shall be transported, handled, and stored as recommended by manufacturer.

Pipe, pipe materials, or fittings may be rejected for failure to meet any requirements of these specifications.

601.4. GENERAL METHODS

601.4.1. Pre-Construction. Methods used shall minimize disruption or interference with traffic flow, public right-of-way, local business, or adjacent private property in the area.

Any required excavation shall conform to the requirements of [Item 203](#). Site Preparation, including identification and protection of utilities.

Upon approval of the OWNER, the manufacturer's recommendations shall become the basis for acceptance or rejection of actual methods of installation.

The CONTRACTOR shall make every effort to maintain service usage throughout the duration of the project. In the event that a service connection will be out of service, the CONTRACTOR shall notify the OWNER and each customer whose service will be disrupted by construction in writing a minimum of 24-hours in advance of construction. Notice shall include the work to be conducted, work schedule including when service will be off-line, effect to each customer, and a local telephone number of the CONTRACTOR to call to discuss the project or any problems that could arise. The maximum amount of time of no service shall be 12-hours for any property served by the existing pipeline. The OWNER may also require the CONTRACTOR to attempt personal contact with affected residents prior to the beginning of work being conducted on the section relative to the residents affected. The CONTRACTOR shall attempt personal contact with any home or business that cannot be reconnected within the time schedule stated in the written notice.

601.4.2. General Construction Requirements. The CONTRACTOR shall certify it has a minimum of two (2) complete working units. Spare key components shall be on the site prior to construction.

The CONTRACTOR's supervisor shall be on the job full-time during any and all steps of the pipe installation.

The CONTRACTOR shall carry out its operations in strict accordance with all OSHA and manufacturer's safety requirements. Particular attention is drawn to those safety requirements involving working with hazardous/combustible material, scaffolding, and entering confined spaces.

In the event of a discrepancy, the CONTRACTOR shall immediately notify the OWNER. No work shall be performed in an area of discrepancy until it has been fully resolved by the OWNER.

The CONTRACTOR shall maintain in operating condition all active pipes encountered during the pipeline rehabilitation. The CONTRACTOR shall be responsible for continuity of service to each facility connected to the section of pipe being reconstructed during execution of the work. The CONTRACTOR, when necessary, shall provide for the flow around the section of pipe designated for rehabilitation. At no time shall wastewater be pumped into the streets, alleys, waterways or storm drain systems. Bypass shall be made by plugging the

line at an existing upstream manhole and pumping the flow into a downstream manhole or adjacent system. Pump and bypass lines shall be of adequate capacity and size to handle the flow. The CONTRACTOR shall ensure that no wastewater overflows from the existing pipe into access pit(s). If wastewater does overflow, the CONTRACTOR shall provide suitable means to contain the wastewater and return it to the existing pipe. If flow backup occurs and enters buildings, the CONTRACTOR shall be responsible for clean up, repair, property damage cost, and claims. CONTRACTOR shall be liable for any damages incurred as a result of inadequate flow bypass measures.

It shall be the responsibility of the CONTRACTOR to clear the existing pipeline of obstructions such as debris, a protruding service connection, dropped joint, or collapsed pipe that will prevent rehabilitation. Any required work must be approved in writing by the OWNER and done by the CONTRACTOR. The OWNER reserves the right to approve or disapprove of any point repairs identified. If inspection reveals an obstruction that cannot be removed by conventional pipe cleaning equipment, then the CONTRACTOR shall hydraulically reround the pipe or make a point repair excavation to uncover and remove or repair the obstruction. Extreme care shall be used to prevent debris from entering existing pipe prior to rehabilitation.

Pipe grades shall be maintained equal to the grade of the line being rehabilitated. The CONTRACTOR shall correct all grade deficiencies to the satisfaction of the OWNER at no additional cost to the OWNER.

In the event of damage caused to materials, the CONTRACTOR shall make all repairs and replacement necessary to the approval of the OWNER at no additional cost to the OWNER.

During the warranty period, defects that may affect the integrity or strength of the pipe, in the opinion of the OWNER, shall be repaired or the pipe replaced at the CONTRACTOR'S expense.

The CONTRACTOR shall make all required connections to existing pipes and manholes within 12-hours of pipe rehabilitation completion and carry out such work in accordance with local standards and requirements and as directed by the OWNER. The CONTRACTOR shall be responsible to confirm the active services prior to reconnection.

601.4.2.1. Point Repairs on Private Property. Point repairs may be required on private property. Point repairs on private property shall be excavated using mini equipment to cause as little damage as may be necessary to accomplish the work. If fences must be removed to accomplish the work, the CONTRACTOR shall install temporary fencing of like size and construction until permanent fence replacement is accomplished.

601.4.3. Post-Construction Requirements. After the installation work has been completed and all testing acceptable, the CONTRACTOR shall clean up the entire project area in accordance with [Item 107.25](#), Project Clean-Up. The CONTRACTOR shall remove surplus pipe, excess materials, tools and temporary structures. All dirt, rubbish and pipe material from the operation and debris collected as a result of cleaning shall be legally disposed of by the CONTRACTOR.

The CONTRACTOR shall restore or replace all removed or damaged pavement, curb, sidewalk, gutter, shrubbery, fence, sod or other disturbed surfaces or structures in a condition equal to that before the work began, to the satisfaction of the OWNER, and shall furnish all labor and material incidental thereto.

601.5. SECTION HELD FOR FUTURE USE.

601.6. SECTION HELD FOR FUTURE USE.

601.7. CURED-IN-PLACE PIPE LINER (CIPP LINER)

It is the intent of this specification to provide for the rehabilitation of pipelines and conduits by the installation of a resin-impregnated flexible tube, which is inverted into the original conduit by use of a hydrostatic head. The resin is cured by circulating hot water or steam within the tube.

601.7.1. Material. In case of conflicting requirements between this specification and referenced standards, this specification shall govern.

The tube shall consist of one or more layers of absorbent non-woven felt fabric and meet the requirements of ASTM D5813 Cured-In-Place Thermosetting Resin Sewer Pipe. The tube shall be constructed to withstand inversion pressures, have sufficient strength to bridge missing pipe, stretch to fit

irregular pipe sections, and shall invert smoothly around bends. The tube shall be made to a size that when installed, will tightly fit the internal circumference and length of the original pipe. Allowance should be made for circumferential stretching during inversion. Overlapped layers of felt that cause lumps in the final product shall not be allowed.

The outside layer of the tube (before wetout) shall be polyethylene- or polyurethane-coated, a translucent flexible membrane that clearly allows inspection of the resin impregnation (wetout) procedure. The plastic coating shall separate the resin inside the tube from the inversion water without leakage, accommodate inversion, stretch to size, and shall not delaminate before, during, or after curing. The wetout tube shall have a uniform thickness that when compressed at installation pressures will meet or exceed the design thickness.

The tube shall be homogeneous across the entire wall thickness containing no intermediate or encapsulated elastomeric layers. No material shall be included in the tube that may cause delamination in the cured CIPP. Seams in the tube shall be stronger than the unseamed felt. Where the length requires joining, the joint shall not be perpendicular to the long axis but spirally formed.

The outside of the tube shall be marked for distance at regular intervals along its entire length, not to exceed 5-ft. The manufacturer's name or identifying symbol shall also appear at intervals not exceeding 10-ft.

The resin system shall be a corrosion-resistant polyester, vinyl ester or epoxy, and catalyst system that when properly cured within the tube composite meets the requirements of ASTM D5813 Cured-In-Place Thermosetting Resin Sewer Pipe, the physical properties herein, and those specifications utilized in the design of the CIPP for a particular project.

The CIPP shall be designed as per ASTM F1216 Standard Practice for Rehabilitation of Existing Pipelines and Conduits by the Inversion and Curing of a Resin-Impregnated Tube, Appendix X1. The CIPP design shall assume no bonding to the original pipe wall.

The layers of the cured CIPP shall be uniformly bonded. It shall not be possible to separate any two layers with a probe or point of a knife blade so that the layers separate cleanly or the probe or knife blade moves freely between the layers. If separation of the layers occur during testing of field samples, new samples shall be cut from the work. Any reoccurrence may cause rejection of the work.

The cured pipe material (CIPP) shall conform to the minimum structural properties, as indicated in Table 601.7.1.(a) Cured-in-Place Pipe Liner Properties.

Table 601.7.1.(a) Cured-in-Place Pipe Liner Properties

1. Property	2. ASTM Test Method	3. Minimum Value	4. Materials with 5. 400,000 psi
Modulus of Elasticity	D790 Flexural Properties of Unreinforced and Reinforced Plastics and Electrical Insulating Materials	(short term) 250,000-psi	400,000-psi
Flexural Stress	ASTM D790 (same as above)	4500-psi	4500-psi

No dry or unsaturated layers shall be evident. Any layers of the tube that are not saturated with resin prior to insertion into the existing pipe shall not be included in the structural CIPP wall thickness computation.

The CIPP shall meet the chemical resistance requirements of ASTM F1216, Appendix X2. CIPP samples for testing shall be of tube and resin system similar to that proposed for actual construction. It is required that CIPP samples with and without plastic coating meet these chemical testing requirements.

Overall, the hydraulic profile shall be maintained as large as possible. The CIPP shall have a minimum of full flow capacity of the original pipe before rehabilitation. Calculated capacities may be derived using a commonly accepted roughness coefficient for the existing pipe material taking into consideration its age and condition. The roughness coefficient of the CIPP shall be verified by third party test data.

CIPP samples shall be prepared and physical properties tested in accordance with ASTM F1216 Section 8.1 using either method proposed. The flexural modulus must meet or exceed the value used in design (structural requirements for the pipe size and thickness furnished in design).

When requested by the OWNER, the CONTRACTOR shall submit test results from previous field installations in the USA of the same resin system and tube materials as proposed for the actual installation. These test results must verify that the CIPP physical properties specified in this section have been achieved in previous field applications. Testing samples for this project shall be made and tested as described in this specification.

601.7.2. Methods. The CIPP Liner shall be continuous and tight fitting. Installation shall be in accordance with manufacturer's recommendations.

601.7.2.1. Installation. CIPP installation shall be in accordance with ASTM F1216 Standard Practice for Rehabilitation of Existing Pipelines and Conduits by the Inversion and Curing of a Resin-Impregnated Tube, Section 7, or ASTM F1743 Standard Practice for Rehabilitation of Existing Pipelines and Conduits by Pulled-in-Place Installation of Cured-in-Place Thermosetting Resin Pipe (CIPP), or ASTM F2019 Standard Practice for Rehabilitation of Existing Pipelines and Conduits by the Pulled in Place Installation of Glass Reinforced Plastic (GRP) Cured-in-Place Thermosetting Resin Pipe (CIPP) with the following additional requirements:

The quantity of resin used for tube impregnation shall be sufficient to fill the volume of air voids in the tube with additional allowances for polymerization shrinkage and the loss of resin through cracks and irregularities in the original pipe wall. A vacuum impregnation process shall be used. After vacuum in the tube is established, a vacuum point shall be no further than 75-feet from the leading edge of the resin. The leading edge of the resin slug shall be as near to perpendicular as possible. A roller system shall be used to uniformly distribute the resin throughout the tube. If the installer uses an alternate method of resin impregnation, the method must produce the same results. Any alternate resin impregnation method must be proven.

Curing shall be accomplished by utilizing hot water under pressure.

601.7.2.2. Finishing. Branch connections to buildings shall be reopened without excavation utilizing a remotely controlled cutting device, monitored by a video TV camera.

No additional payment shall be made for excavations for the purpose of reopening connections, and the CONTRACTOR shall be responsible for all costs and liability associated with such excavation and restoration work.

Visual inspection of the CIPP shall be in accordance with ASTM F1216, Section 8.6 or ASTM F1743.

Leakage testing of the CIPP shall be accomplished during cure while under a positive head. CIPP products in which the pipe wall is cured while not in direct contact with the pressurizing fluid (e.g., a removable bladder) must be tested by an alternative method approved by the OWNER.

601.8. PIPE BURSTING WITH POLYETHYLENE

This section includes requirements to rehabilitate existing pipelines by the pipe bursting method, which splits the existing pipe and immediately installs a new polyethylene pipe. Hydraulically- pneumatically- and statically-operated equipment may be allowed for this replacement.

The CONTRACTOR shall be certified by the particular pipe bursting system manufacturer that such firm is a licensed installer of its system.

Polyethylene pipe jointing shall be performed by personnel trained in the use of thermal butt-fusion equipment and recommended methods for new pipe connections. Personnel directly involved with installing the new pipe shall receive training in the proper methods for handling and installing the polyethylene pipe. Training shall be performed by qualified representative.

601.8.1. Materials. Materials shall conform to the requirements of [Item 501.21](#). Solid Wall Polyethylene Plastic Pipe for Water, Wastewater, and Pipe Rehabilitation with modifications as stated herein.

The Polyethylene Plastic Pipe shall be high density polyethylene pipe and meet the applicable requirements of AWWA C906 Polyethylene Pressure Pipe and Fittings, 4-in through 63-in. for Water Distribution and Transmission for potable water pipe replacement, or ASTM F714 for Polyethylene (PE) Plastic Pipe (SDR-PR) Based on Outside Diameter for other applications. All pipe shall be made of virgin material. No rework except that obtained from the manufacturer's own production of the same formulation shall be used. The pipe shall be homogenous throughout and shall be free of visible cracks, holes, foreign material, blisters, or other deleterious faults.

Saddles shall be heat fusion saddles, unless otherwise approved by OWNER. Mechanical saddles made of polyethylene pipe compounds shall meet the requirements of pipe as stated above. Mechanical saddles shall have stainless steel straps and fasteners, neoprene gasket and backup plate. Sizes of the pipe insertions to be used shall be as shown on the plans or to renew the pipeline to its original or greater than flow capacity. The minimum wall thickness of the polyethylene pipe shall meet the greater of either the thickness required to meet internal pressure or the thickness determined by burial depth as indicated in Table 601.8.1.(a) Pipebursting (with PE) Required Pipe Thickness.

Table 601.8.1.(a) Pipebursting (with PE) Required Pipe Thickness

Depth of Cover	Standard Dimension Ratios (Ductile Iron Pipe Size): Minimum DR of Pipe
0 - 10.0-ft.	21
> 10.0-ft	17

601.8.2. Methods. All service connections shall be identified, located, and excavated prior to the pipe insertion to expedite reconnection.

601.8.2.1. Insertion. Insertion of launching pits shall only be allowed at locations of existing or proposed manholes, unless otherwise approved by OWNER.

Equipment used to perform the work shall be located away from buildings so as to minimize noise impact. CONTRACTOR shall provide silencers or other devices to reduce machine noise as required to meet requirements.

The CONTRACTOR shall install all pulleys, rollers, bumpers, alignment control devices, and other equipment required to protect existing manholes, and to protect the pipe from damage during installation. Lubrication may be used as recommended by the manufacturer. Under no circumstances shall the pipe be stressed beyond its elastic limit.

The design, selection considerations and installation procedures for the construction of new wastewater and storm conduit by the insertion of polyethylene pipe through existing pipe and along previously existing line and grade shall be performed in accordance with ASTM F585 Standard Practice for Insertion of Flexible Polyethylene Pipe into Existing Sewers.

Upon commencement, pipe insertion shall be continuous and without interruption from one manhole to another, except as approved by the OWNER.

The polyethylene pipe shall be assembled and joined at the site using the thermal butt-fusion method to provide a leak-free joint. Threaded or solvent-cement joints and connections are not permitted. All equipment and procedures used shall be used in strict compliance with the manufacturer's recommendations. Fusing shall be accomplished by personnel certified as fusion technicians by a manufacturer of polyethylene pipe and/or fusing equipment. The butt-fused joint shall be true alignment and shall have uniform roll-back beads resulting from the use of proper temperature and pressure. The joint shall be allowed adequate cooling time before removal of pressure. The fused joint shall be watertight and shall have tensile strength equal to that of the pipe. All joints shall be subject to acceptance by the OWNER prior to insertion. All defective joints shall be cut out and replaced at no cost to the OWNER. Any section of the pipe with a gash, blister, abrasion, nick, scar, or other deleterious fault greater in depth than ten-percent (10%) of the wall thickness, shall not be used and must be removed from the site. However, a defective area of the pipe may be cut out and the joint fused in accordance with the procedures stated above. In addition, any section of pipe having other defects such as concentrated ridges, discoloration, excessive spot roughness, pitting, variable wall thickness, or any other defect of manufacturing or handling as determined by the OWNER shall be discarded and not used.

The installed pipe shall be allowed the manufacturer's recommended amount of time, but not less than 4-hours, for cooling and relaxation due to tensile stressing prior to any reconnection of service lines, sealing of the annulus or backfilling of the insertion pit. Sufficient excess length of new pipe, but not less than 4-in., shall be allowed to protrude into the manhole to provide for occurrence.

601.8.2.2. Finishing. Following the relaxation period, the annular space shall be sealed. Sealing shall be made with material approved by the OWNER and/or its representative and shall extend a minimum of 8-in. into the manhole wall in such a manner as to form a smooth, uniform, watertight joint.

Terminal sections pipe that are joined within the insertion pit shall be connected with a full circle pipe repair clamp. The butt gap between pipe ends shall not exceed ½-in.

Once a saddle is secured in place, CONTRACTOR shall drill hole full inside diameter of saddle outlet in pipe liner. CONTRACTOR shall make both the inside and outside of drilled holes smooth.

At all points where the polyethylene pipe has been exposed, as in starter excavations, at service connection fittings, outside of manholes, etc., the CONTRACTOR shall encase the pipe and fittings in minimum of 6-in. of concrete or flowable backfill. If flowable backfill is used, the CONTRACTOR shall remove all debris and create a void along each side of the pipe at the spring line to undisturbed soil in preparation for the cement stabilized sand backfill. Width of the void shall not exceed (main O.D. + 2-ft.) or (service line O.D. + 2-ft.).

Reconnections shall be accomplished as described in the required submittals.

601.9. PIPE BURSTING WITH RIGID PIPE

For the purpose of this specification, pipe rehabilitation by bursting is defined as the trenchless installation of new wastewater pipe by bursting the pipe behind an apparatus which expands the existing wastewater pipe, tees, wyes, and couplings into the adjacent ground forming a clear space to insert the new wastewater piping.

601.9.1. Materials. Pipe shall meet or exceed the requirements of [Item 501.3](#). Vitrified Clay Pipe Used in Trenchless Applications.

All materials supplied under this section shall be warranted for a period of two (2) years by the manufacturer and CONTRACTOR. The materials shall be warranted to be free from defects in workmanship, design, and materials.

Packaging and shipping shall be done in accordance with manufacturer instructions. Each standard and random length of pipe shall be clearly marked with the following information: pipe size, class, profile number, and production code. Each box or package shall be properly marked to show its actual weight in addition to its contents.

601.9.2. Methods. Equipment employed in the pipe bursting procedure shall be approved by the OWNER and the pipe supplier prior to award of a contract.

A hydraulic or mechanical pipe-pushing device that exerts pressure on the jacking pipe may be used. The machine operator shall closely and continuously monitor and control the jacking load imposed on the new pipe. A jacking ring or device shall be used to distribute the jacking load evenly on the entire surface perimeter of the end of the jacking pipe. The CONTRACTOR shall also utilize a device capable of holding a nearly inserted joint of liner pipe without damage or danger while the following joint is shoved home to complete the joint makeup. Joints shall be made in full view of the operator and inspector.

601.9.2.1. Access Pits. It is the CONTRACTOR's responsibility to locate, design, and determine the necessary number of access pits, excavation methods, and all other items required for the successful completion of the work. CONTRACTOR shall submit an access pit(s) plan showing location(s), dimensions, equipment set up, sheeting, shoring, bracing, and calculations.

Earthwork for access pits shall be performed in accordance with [Item 504](#). Open Cut – Backfill.

The walls of the access pit(s) shall be vertical and supported by sheeting, shoring, and bracing in accordance with [Item 107.20](#). Protection of Work and of Persons and Property with the following additions:

- (1) No side sloping of pit walls shall be allowed.
- (2) All four walls of each pit shall be properly protected against inflow of groundwater or soil materials. The control of groundwater shall be such that softening of the bottom of excavations or formation of "quick" conditions or "boils" do not occur. Dewatering systems shall be designed and operated to prevent removal of the natural soils.

Access pit dimensions shall be constructed at the minimum size necessary to accommodate the maximum length and diameter of pipe used, in addition to auxiliary pushing equipment, and to provide sufficient working room on either side of the existing pipe to be replaced. The depth of the pit(s) shall be

sufficient to expose the existing pipe to the invert, allowing for the placement of concrete or shotcrete coating, whichever is necessary, at the bottom of the pit(s). The thickness of concrete or shotcrete shall be necessary to prevent groundwater infiltration into the pit and to prevent any wastewater from infiltrating into the soil.

Access pits shall be adequately covered when not in use to control odors and shall be securely fenced and barricaded to prevent unauthorized entry.

601.9.2.2. Installation. The CONTRACTOR shall be responsible for locating and exposing all service laterals and cleanouts prior to replacement pipe insertion.

The pipe shall be jacked or pushed into the existing pipe utilizing equipment as herein specified. An aqueous solution such as bentonite may be used to minimize the jacking load and provide lubrication during the new pipe installation. For each section to be rehabilitated, insertion shall be one continuous operation until the planned termination point is reached. Pipe jointing shall be accomplished in strict accordance with the pipe manufacturer's recommendations, and each joint shall be completely made-up in the access pit(s) in full view of the OWNER.

Total jacking loads shall not exceed 75% of the manufacturer's maximum recommendations. The CONTRACTOR shall provide a suitable means of measuring a jacking load and shall monitor the load as the new pipe is being installed. If, at any time, the load appears to rise erratically indicating possible obstruction of the pipe, jacking operations shall be terminated and the obstruction or other impediment removed before continuing. The entire cost for all work associated with an unanticipated access pit(s) shall be borne by the CONTRACTOR.

If portions of the line being jacked have curves with a radius of curvature less than 700-ft, the pipe manufacturer shall be consulted. In no case should a joint be pulled in excess of the maximum degrees of angular deflection recommended by the manufacturer for any given pipe diameter.

When the pipe is pushed through a manhole, the top half of the pipe within the manhole shall be removed using a saw and additional portions shall be removed to allow side connections to flow into the new pipe. The pipe shall be inserted through the manhole such that no pipe joint is located inside the manhole. The pipe shall be cut out at manholes as required after insertion and grouting. The methods of cutting shall be such as to leave smooth, clean, straight edges. The pipe shall be suitably blocked during grout and concrete placement so that no bowing or other deviation from a parallel-sided channel occurs.

601.9.2.3. Finishing. The CONTRACTOR shall reconnect all service connections to the new pipe. A portion of the existing pipe around each service connection shall be removed to expose the new pipe and provide sufficient working space for making the new service connections. The CONTRACTOR may propose alternative methods for reinstatement of service connections. Saddle stub-out dimensions shall be the same size or larger than the existing service lateral. Saddles shall be connected to existing service laterals by using flexible couplings.

At points where the liner has been exposed, the liner pipe and fittings shall be encased to prevent deflection due to earth loading or subsidence. In preparation for the placing of the encasement material, debris and soil shall be removed along each side of the existing pipe down to the spring line. After the encasement material is in place and accepted by the OWNER, CONTRACTOR shall place and compact backfill to required finished grades in accordance with these specifications.

601.10. SEGMENTAL SLIPLINING

This section includes requirements to rehabilitate existing wastewater pipelines, storm conduit and culverts by the method of segmental sliplining with pipe as specified in [Section 501](#). Segmental sliplining is defined as a trenchless installation of new liner pipe, which is either pushed or pulled inside an existing pipeline.

601.10.1. Materials. Appropriate pipe material shall meet or exceed all requirements of [Item 501.18](#). Polyvinyl Chloride (PVC) Profile Gravity Pipe and Fittings – For Direct Bury and Sliplining Applications.

Pipe joints shall be furnished in minimum 2½-ft joints to maximum 20-ft joint. The pipe wall must be smooth and consistent on the inside surfaces. The maximum outside diameter including the bell has to be such that the liner pipe can be inserted into the existing pipe without binding, damaging or deflecting the liner pipe.

Unless otherwise specified on the plans, the pipe shall be field connected with bell and spigot joints, or as recommended by the manufacturer. Gaskets suitable for the service intended and meeting the requirements of ASTM F477 Elastomeric Seals (Gaskets) for Joining Plastic Pipe shall be used. Joint shall be designed to meet the performance requirements of ASTM D3212 Joints for Drain and Sewer Plastic Pipes Using Flexible Elastomeric Seals.

601.10.2. Methods. The CONTRACTOR shall completely grout the annular void between the existing host pipe and the new liner pipe with grout as recommended by the manufacturer. Bypass pumping may not be necessary when the liner pipe is installed during live flow applications. CONTRACTOR shall adhere to the following conditions, unless approved otherwise by the OWNER.

601.10.2.1. Insertion/Access Pits. The location of the insertion pits shall be determined to facilitate sliplining the amount of pipe shown on the plans. The exact location and number of insertion/access pits must be planned by the CONTRACTOR and submitted in writing for approval by the OWNER prior to excavation. Pit locations shall coincide with existing pipe joints such that the total number of pits is minimized, and the footage of liner pipe installed in a single pull maximized. Location of damaged pipe/point repairs can be used for insertion pits if approved by the OWNER. Earthwork for access pits shall be performed in accordance with [Item 504](#). Open Cut – Backfill.

Access pits shall be adequately covered when not in use to control odors and shall be securely fenced and barricaded to prevent unauthorized entry.

The cost of the insertion is incidental to the bid price for sliplining and includes all work, equipment, labor, tools, etc., required for diverting and pumping flow, opening and closing the pit(s), and restoring the site satisfactory to the OWNER.

After completing the insertion pit excavation and diverting flow as necessary, CONTRACTOR shall remove the top of the existing wastewater pipe down to the spring line by neatly sawing the pipe and shall take care not to disturb the bottom portion of the existing pipe, thus providing a stable base for the liner pipe.

601.10.2.2. Installation. CONTRACTOR shall install sliplining material according to the manufacturer's written procedures and instructions.

Liner pipe sections shall be jointed prior to insertion of the complete pipe section into the host pipe. The liner pipe shall be equipped with a lead piece to help guide the pipe through without any disruption. Liner pipe may be pulled or pushed through the existing host pipe with aid of a backhoe or jacking device, providing the pushing or jacking loads are monitored and remain in accordance with the safe compressive/jacking loads as set forth by the manufacturer.

Once insertion is complete, CONTRACTOR shall reinstall the exiting top pipe section removed and construct new manhole at the end of the pipeline. CONTRACTOR shall connect liner pipe to new manhole according to manufacturer recommendations.

601.10.2.3. Grouting. The CONTRACTOR shall utilize the grout for solidification of the annular void between the host and liner pipe. Grout mixture shall have an approximate compressive strength of 150-psi unless specified otherwise by the OWNER, and a minimum density of 30-pcf. Grout mix shall have less than 1-percent (1%) shrinkage by volume. Materials for sliplining grout shall comply with the following:

- (1) Cement shall comply with ASTM C150 Portland Cement. Pozzolans and other cementitious materials may be permitted.
- (2) Fly Ash shall comply with ASTM C618 Coal Fly Ash and Raw or Calcined Natural Pozzolan for use as a Mineral Admixture in Concrete; either Type C or Type F shall be used.
- (3) Sand if utilized, shall conform to ASTM C144 Aggregate for Masonry Mortar, except as modified in Table 601.10.2.3.(a) Segmental Sliplining Grouting Sand.

Table 601.10.2.3.(a) Segmental Sliplining Grouting Sand.

U.S. Standard Sieve Size	% Passing by Weight
No. 16	100
No. 30	60 – 85
No. 50	10 – 35
No. 100	5 – 25
No. 200	0 – 10

- (4) Potable water free from deleterious amounts of alkali, acid and organic materials, which would adversely affect the set time, or strength of the sliplining grout.
- (5) Admixtures shall be selected by the manufacturer of the sliplining grout to meet the performance requirements, to improve pumpability, to control set time, and reduce segregation.

601.11. MEASUREMENT AND PAYMENT

Measurement shall be as specified in the proposal and contract documents. The unit price bid for rehabilitating pipe shall be full compensation for all materials, labor, equipment, and incidentals required to insert the liner pipe within the existing pipe or replace existing pipe. Payment shall also include the cost of flow bypass, sealing liners in the manholes, reworking the manhole inverts and benches, and other work necessary to complete installation. Payment shall be for actual linear footage of pipe installed in the field and shall be measured between the centerlines of the manholes. Cleaning, pre-construction television inspection, post-construction television inspection, testing and all relevant submittals shall be incidental to the pipe rehabilitation items. Retesting that results from failure to pass initial testing shall be at the CONTRACTOR'S expense.

If excavation is required for point removal or repair of obstructions, it shall be approved in writing by the OWNER prior to the commencement of the work and shall be considered as a separate pay item.

Reconnection of services shall be paid for per each reconnection made.

ITEM 602. REHABILITATION OF MANHOLES OR UNDERGROUND VAULTS

602.1. GENERAL

This specification covers work and materials required for protecting and/or rehabilitating manholes and other underground vaults to eliminate inflow, infiltration and exfiltration, provide corrosion protection, repair voids and restore structural integrity. Procedures for repair, surface preparation, application and testing are described herein.

602.2. SUBMITTALS

The following items shall be submitted:

- (1) Technical data sheet on each product used, including applicable ASTM test results indicating the product conforms to and is suitable for its intended use per these specifications.
- (2) Material Safety Data Sheets (MSDS) for each product used.
- (3) Manufacturer's product data, including physical properties, results of applicable ASTM tests for the material supplied, and requirements for surface preparation, repair, application, curing, and field quality control.
- (4) Project specific guidelines and recommendations.
- (5) Manufacturer Qualifications: Submit list of a minimum of ten (10) successful similarly sized manhole rehabilitation projects completed during past 3-years.
- (6) CONTRACTOR and Applicator Qualifications:
 - (a) Manufacturer certification that Applicator has been trained and approved by manufacturer in the handling, mixing and application of the specified products.
 - (b) Certification that the equipment to be used for applying the products has been manufactured or approved by the protective coating manufacturer and Applicator personnel have been trained and certified for proper use of the equipment.
 - (c) List of recently completed successful similarly sized manhole rehabilitation projects, including project name and location, names of OWNER, and description of products used, substrates, and application procedures.
 - (d) Proof of any necessary federal, state or local permits or licenses necessary for the project.
- (7) Design details for any additional ancillary systems and equipment to be used in site and surface preparation, application and testing.
- (8) Bypass pumping submittal will include, but not be limited to, pumps, piping materials, and emergency plan.

602.3. QUALITY ASSURANCE

CONTRACTOR shall initiate and enforce quality control procedures consistent with applicable ASTM, NACE and SSPC standards and the protective coating manufacturer's recommendations.

The OWNER will observe surface preparation, application and material handling procedures to ensure adherence to the specifications. Inspection by the OWNER or the waiver of inspection of any portion of the work shall not relieve the CONTRACTOR of responsibility to perform the work as specified.

Deficiencies in the finished coating shall be marked and repaired by the CONTRACTOR.

602.4. DELIVERY, STORAGE AND HANDLING

Materials shall be delivered to site in manufacturer's original, unopened containers and packaging, with labels clearly identifying product name and manufacturer. Containers shall be kept sealed until ready for use. Materials shall be kept dry, protected from weather and stored under cover and in accordance with manufacturer's instructions. Materials shall be handled according to their material safety data sheets. Material damage shall be prevented.

602.5. REHABILITATION

602.5.1. General. CONTRACTOR shall conform with all local, state and federal regulations including those set forth by OSHA, RCRA and the USEPA and any other applicable authorities. Method statements and design procedures are to be provided by CONTRACTOR when confined space entry, flow diversion or bypass is necessary to perform the specified work.

CONTRACTOR shall examine surfaces to receive manhole rehabilitation. CONTRACTOR shall notify the OWNER in writing if surfaces are not acceptable. Surface preparation, repair, or application shall not begin until unacceptable conditions have been corrected.

Contaminants such as oils, grease, incompatible existing coatings, waxes, form release, curing compounds, efflorescence, sealers, salts, or other contaminants shall be removed if necessary for successful rehabilitation, based on manufacturer's recommendations. Loose, unsound, and protruding brick, mortar, and concrete shall be removed and disposed of as described in [Item 203](#). Site Preparation.

Covers shall be placed over invert to prevent extraneous material from entering sewer lines.

602.5.1.1. Serious Structural Rehabilitation. Structural requirements of the rehabilitative method shall be specified by the OWNER per project. Methods of serious structural rehabilitation for high infiltration and/or gas deteriorated structures may be one of the following:

- (1) Pre-formed Fiberglass Inserts
- (2) Poured-in-place concrete rehab
- (3) Cured-in-place fiberglass Liner
- (4) Cast-in-place plastic liners

602.5.1.2. Other Structural Rehabilitation.

Methods where less serious problems exist because of infiltration or gas deterioration, but where rehabilitation, preventative maintenance, or protection of newly rehabilitated manholes is required may be one of the following:

- (1) Cured-in-place fiberglass Liner.
- (2) Epoxy coating.
- (3) Polyurea coating.
- (4) Polyurethane coating.
- (5) Calcium aluminate concrete or Calcium aluminate concrete with epoxy top coat.
- (6) Cured-in-place structural epoxy/fiberglass coating.

602.5.2. General Repair Procedures. Infiltration shall be stopped prior to any rehabilitative measures. Weep holes may be installed as required to localize infiltration during application of patching material or infiltration control material. Weep holes shall be plugged after application with infiltration control material before application of liner material. For severe infiltration, drill as required to pressure grout using a cementitious or chemical grout. Grout shall be applied in accordance with manufacturer's instructions.

Areas where structural steel has been exposed or removed shall be repaired in accordance with the OWNER's recommendations.

Inverts shall be repaired when there is visible damage, where infiltration is present, or when vacuum testing is specified.

Patching and repair materials should not be used unless their manufacturer provides information as to suitability and procedures for preparation of material to bond with the specified rehabilitative materials. Repair materials shall be applied and cured in accordance with the manufacturer's recommendations.

Repair materials shall be used to fill voids, structurally reinforce and/or rebuild surfaces, etc. as determined necessary by the OWNER and protective coating Applicator. At minimum, voids greater than 2-in in depth shall be repaired with approved patching material.

The repair material thickness shall be specified by the OWNER.

The repair materials shall be permitted to cure according to manufacturer recommendations. Curing compounds should not be used unless approved for compatibility with the specified protective coating.

Application of the repair materials shall be inspected by the protective coating certified Applicator to ensure proper finishing for suitability to receive the specified coating.

Before application of each material, surfaces to be rehabilitated shall be inspected by the OWNER. CONTRACTOR shall correct defects or deficiencies identified by the OWNER before application of subsequent material.

602.5.3. Surface Preparation. All concrete or mortar that is not sound or has been damaged by chemical exposure shall be removed to a sound concrete surface or replaced.

CONTRACTOR is to maintain strict adherence to published standards and recommendations of the National Association of Corrosion Engineers (NACE International) and the applicable published standards and recommendations of the Society of Protective Coatings (SSPC) with regard to proper surface preparation and compatibility with existing coatings. If recommended by the manufacturer of the specified rehabilitative materials, existing coatings shall be removed prior to application of the new protective coating(s).

Surface preparation method(s) shall be based upon the conditions of the substrate, service environment and the requirements of the protective coating to be applied.

At minimum, surfaces to receive rehabilitation shall be cleaned and abraded to produce a sound surface with adequate profile and porosity to provide a strong bond between the rehabilitative method and the substrate. Generally, this can be achieved with pressure water cleaning equipment capable of 5000-psi at 4-gpm. Other methods such as high pressure water jetting (refer to NACE Standard Nos. SSPC-SP WJ-1/NACE WJ-1, SSPC-SP WJ-2/NACE WJ-2, SSPC-SP WJ-3/NACE WJ-3, and SSPC-SP WJ-4/NACE WJ-4), abrasive blasting, shotblasting, grinding, scarifying or acid etching may also be used, as necessary. Detergent water cleaning and hot water blasting may be necessary to remove contaminants. Method(s), as approved, shall be performed in a manner that provides a uniform, sound clean neutralized surface that is not excessively damaged.

If abrasive blast and leak repair is performed, all surfaces shall be inspected for remaining laitance prior to protective coating application. Any evidence of remaining contamination or laitance shall be removed by additional abrasive blast, shotblast or other approved method.

602.5.4. Application of Rehabilitative and Protective Materials. Application procedures shall conform to the recommendations of the manufacturer of the specified rehabilitative materials, including material handling, mixing, environmental controls during application, safety, and equipment.

Spray equipment shall be specifically designed to accurately ratio and apply the specified materials, shall be regularly maintained, and in proper working order. Air assisted spray application equipment may be acceptable only if the air source is filtered to completely remove all oil and extraneous water.

Prior to and during application, care should be taken to avoid exposure of air movement and direct sunlight or other intense heat source to the structure being coated. Where varying surface temperatures do exist, care should be taken to apply the coating when the temperature is falling rather than when it is rising. The structure shall be covered if time between application of coats is to be longer than 15-minutes. Finished materials shall not be exposed to sunlight or air movement for longer than 15-minutes before covering or closing access.

If coatings do not bond properly to the manhole surfaces, such coating shall be removed and replaced at no expense to the OWNER.

Follow manufacturer's instructions whenever more than 12-hours have elapsed between layer applications.

Other than for application of cementitious products, surfaces shall be completely dry.

Thicknesses specified below are minimum thicknesses. The material thickness shall be specified by the OWNER.

602.5.4.1. Pre-Formed Fiberglass Inserts. Inserts shall meet requirements of ASTM D3753 Glass-Fiber-Reinforced Polyester Manholes and Wetwells. Chimney and corbel areas of the manhole shall be removed. Then the insert shall be lowered into position, back poured with concrete of the class specified by the OWNER, and completed at the surface area.

602.5.4.2. Poured-In-Place Concrete. This method shall use inside-the-manhole forming. The use of this process may be in conjunction with a synthetic liner material placed to the inside area of the manhole in the form in order to provide interior surface that is resistant to sewer gases and chemicals, as specified on the plans. Thickness shall be specified on the plans.

602.5.4.3. Cured-In-Place Fiberglass Inserts. A custom-manufactured liner shall be molded into place with a non-porous membrane bonded between the layers of structural fiberglass, forming a permanent barrier to stop future infiltration or gas deterioration to the existing structure. This system shall be bonded to the existing surface.

602.5.4.4. Cast-In-Place Plastic Liners. Liner may be polyvinyl chloride (PVC) or high density polyethylene (HDPE) as specified by the OWNER. Liner system shall be designed to eliminate infiltration.

602.5.4.5. Calcium Aluminate Concrete or Portland Cement Mixtures. Cementitious product shall be reinforced by adding approximately 10% by volume synthetic reinforcing fibers to material being used. Product shall be applied at least $\frac{3}{8}$ -in. thick, and applied in layers of approximately $\frac{1}{4}$ -inch during each application in order to minimize hair line cracks in the material as it cures.

602.5.4.6. Polyurethane Coating. Coating shall be applied properly and in multiple layers of thin coats to minimize shrinkage. Polyurethane layers shall be applied in thicknesses that prevent running, curing problems, or excessive shrinkage. Material applications shall provide a finish coat per the manufacturer's recommendations. Lower sections of the manhole may require additional thickness of coating to resist hydrostatic head of infiltration. Manhole surface must be dry for proper adhesion.

602.5.4.7. Epoxy Coating. 1-oz. of $\frac{1}{4}$ -in solid core, synthetic reinforcing fibers shall be used per gallon of epoxy resin. Epoxy layers shall be applied in thicknesses that prevent running, per the manufacturer's recommendations.

602.5.4.8. Polyurea Coating. Material applications shall provide a finish coat of per the manufacturer's recommendations. Manhole surface must be dry for proper adhesion.

602.5.4.9. Calcium Aluminate Coating with Epoxy Finish for Preventative Maintenance. Calcium aluminate concrete shall be applied in two separate layers totaling 375-mil thick. Epoxy shall be applied 60-mil thick in two coats of 30-mil each. The calcium aluminate concrete shall be blended with approximately 10% by volume synthetic reinforcing fibers. The epoxy top coat shall be blended with 1-oz. of $\frac{1}{4}$ -in synthetic reinforcing fibers per gallon of material in order to inhibit future cracks.

602.5.4.10. Epoxy/Fiberglass, Structural Coating for Preventative Maintenance. The coating shall be cured-in-place under heat and pressure. The structural coating shall contain 27-oz.-per-sq.-yard of laminated structural fiberglass and felt, stitched together and saturated with epoxy resin that will bond to wet or dry surfaces. Chopped glass may be substituted for fiberglass and felt if structural effects are equal upon approval from the OWNER.

602.5.4.11. Curing and Finishing. CONTRACTOR shall cure materials in accordance with manufacturer's instructions. Cure time before subjecting manholes to flows shall be as recommended by the manufacturer.

Opening to traffic shall be as recommended by the manufacturer, but not less than 24-hours after final application of rehabilitative or protective material.

602.6. INSPECTION AND TESTING

During application of epoxy coatings, a wet film thickness gage meeting ASTM D4414 Standard Practice for Measurement of Wet Film Thickness by Notched Gages, shall be used to ensure a monolithic coating and uniform thickness during application. All holiday testing shall conform to ASTM D5162 Standard Practice for Discontinuity (Holiday) Testing of Nonconductive Protective Coating on Metallic Substrates.

Measurement of bond strength of the coatings to the substrate shall be measured in accordance with ASTM D7234 Standard Test Method for Pull-Off Adhesion Strength of Coatings on Concrete Using Portable Adhesion Testers. Any areas detected to have inadequate bond strength shall be removed and replaced at no cost to the OWNER. Further bond tests may be performed in that area to determine the extent of potentially deficient bonded area and repairs shall be made by CONTRACTOR in strict accordance with manufacturer's recommendations.

Testing shall be conducted according to [Item 502.1](#). Manholes. Manholes lined in their entirety shall be vacuum tested unless specified otherwise by the OWNER. Manholes lined in their entirety (including invert) shall be subjected to an exfiltration test unless specified otherwise by the OWNER.

If the manhole fails the initial test due to extenuating circumstances (i.e. pipe joint, liner, plug sealing), repairs and adjustments necessary shall be made. Retesting shall proceed until a satisfactory test is obtained.

602.7. MEASUREMENT AND PAYMENT

Manhole rehabilitation shall be measured by depth of manhole from bottom of invert to top of ring seat of manhole cover. Payment shall be based on a vertical foot or a square-foot basis and shall include all work required including repair, surface preparation, bypass pumping, testing, and rehabilitative and protective measures.

ITEM 603. ABATEMENT OF COATINGS CONTAINING CERTAIN HEAVY METALS

603.1. GENERAL

This item shall consist of the removal or alternative abatement of coatings containing lead, chromium or cadmium prior to work performed on coated structures or materials. **For the purposes of this specification, “lead” shall be understood to mean lead, chromium or cadmium.** All methods described for treatment of lead, including methods described in referenced documents and regulations shall be followed for lead, chromium and cadmium. The OWNER shall specify abatement method. All methods shall at minimum conform to USEPA or TCEQ recognized methods prior to submittal to owner for consideration and approval. Where USEPA or TCEQ recognized methods are more stringent than those contained herein, the most stringent shall take precedence.

The CONTRACTOR shall submit with its bid documentation showing experience of a minimum of two years in the lead control, removal and abatement industry including but not limited to a listing of previously completed projects. It is further required that proof must be submitted that all key personnel involved in the removal of lead based coatings have at least six (6) months experience in this line of work. Key personnel shall be defined by the OWNER.

The CONTRACTOR shall be responsible for any soil contamination resulting from the removal, storage, handling and disposal of hazardous materials from the site. As a requirement for final acceptance the CONTRACTOR shall provide written certification that no soil contamination has occurred as a result of the CONTRACTOR's operations. In the event of such contamination the CONTRACTOR shall submit to the OWNER a plan for site remediation in accordance with all Federal, State and Local regulations to be enacted immediately upon approval by the OWNER at the CONTRACTOR's expense.

Exterior blasting and coating operations shall be limited to wind conditions less than 15-mph.

603.2. JOB PLAN

The CONTRACTOR must provide a job specific plan of the work procedures to be used in the removal and containment or alternative abatement of lead containing paint. The job plan shall be prepared and submitted prior to beginning the work and shall be subject to approval by the OWNER. The OWNER shall be notified in writing 30-days prior to the start of any lead-based coating abatement work. The job plan shall include the following:

- (1) Detailed work schedule.
- (2) Written quality control program.
- (3) Written worker health and safety program.
- (4) Methodology for protection of ground surface adjacent to work.
- (5) Methodology for collecting, containing and disposing of hazardous materials when removal is specified.
- (6) A copy of the technical data sheets for all products including manufacturer's name, addresses and phone numbers and product description. The product description shall include, but not be limited to basic use, limitations, precautions, recommended application methods specific to this project, and any known environmental hazards or constraints.
- (7) Name, address and phone number of the manufacturer's representative to be present on site during initiation of chemical stripper removal process, if used.

603.3. TESTING

The CONTRACTOR shall be responsible for soil testing, existing coating testing and waste testing for lead by an independent, approved testing laboratory at the CONTRACTOR's expense. All testing shall conform to USEPA criteria. The CONTRACTOR shall submit to the Engineer results of all testing as soon as it is available. Failure to perform testing or to submit test results shall be cause for all work to be stopped until testing is performed and results submitted.

603.3.1. Soil Testing. Eight soil samples shall be tested prior to beginning work to determine background lead levels and leachable lead levels. After substantial completion of project and prior to final acceptance eight soils samples shall be tested. The OWNER's representative shall determine locations of soil samples.

603.3.2. Existing Coating Testing. The CONTRACTOR is responsible for testing the existing paint coating for lead content. The OWNER's representative shall determine locations of existing coating samples.

603.3.3. Waste Testing. All waste materials including but not limited to spent abrasive materials and chemical strippers, solvents, etc. shall be tested for leachable lead by the TCLP or EP-TOX test methods in accordance with USEPA and TCEQ regulations. No waste materials may be removed from the site until test results are submitted and disposal method approved.

603.4. MONITORING

Monitoring of airborne concentrations of lead shall be in accordance with 29 CFR 1926.62 and as specified herein. Air monitoring, testing, and reporting shall be performed by a CIH (Certified Industrial Hygienist) or an Industrial Hygiene (IH) Technician. The CIH or the IH Technician shall be on the job site to perform the monitoring. Monitoring shall be performed during the entire paint removal operation. Results of air monitoring samples below 30-micrograms-per-cubic-meter of air shall be submitted to the OWNER within 3- days after the air samples are taken. The OWNER shall be notified immediately of exposure to lead at or in excess of 30-micrograms-per-cubic-meter of air.

603.4.1. Establishing Background Levels. Prior to lead abatement operations background lead levels for air, water, and soil shall be obtained.

603.4.2. Monitoring Personnel. Personnel air monitoring samples shall be obtained from employees who are anticipated to have the greatest risk of exposure as determined by the CIH or IH. If the employee exposure level exceeds 30-micrograms-per-cubic-meter of air, lead abatement work shall be stopped. The CONTRACTOR shall take immediate corrective action to reduce exposure levels below 30-micrograms-per-cubic-meter of air.

603.4.3. Monitoring Physical Boundary. A minimum of two (2) air monitoring samples shall be obtained outside the lead control area on a daily basis. If the inside or outside boundary lead levels meet or exceed 30-micrograms-per-cubic-meter of air, lead abatement work shall be stopped. The CONTRACTOR shall take immediate action to reduce lead levels below 30-micrograms-per-cubic-meter of air. At a minimum, conduct area monitoring on each shift in which lead-based paint removal operations are performed in areas immediately adjacent to the lead control area. For outdoor operations, at least one sample on each shift shall be taken on the downwind side of the lead control area. If adjacent areas should become inadvertently contaminated, clean and visually inspect the contaminated areas.

603.5. PROTECTION

603.5.1. Security of Construction Site. Construction site shall have a temporary security fence at least 6-feet high.

603.5.2. Establishing Control Area. Sufficient area shall be designated by the control area to ensure unprotected personnel outside the control area are not exposed above 30-micrograms-per-cubic-meter of air. Provide physical barrier around the lead control area to limit entry of unauthorized personnel.

603.5.3. Warning Signs and Labels. CONTRACTOR shall provide warning signs at approaches to lead control areas. CONTRACTOR shall locate signs at such a distance that personnel may read the sign and take the necessary precautions before entering the area. Signs shall comply with the requirements of 29 CFR 1926.62. The warning signs shall be posted at each control area at all approaches to the control area so that employees and/or the public may read the signs before entry and take necessary protective action.

603.5.4. Protection of Persons. PERSONNEL ENGAGED IN THE REMOVAL OF LEAD-BASED COATINGS, PERSONNEL OF OTHER TRADES, AND THE GENERAL PUBLIC SHALL NOT BE EXPOSED TO AIRBORNE CONCENTRATIONS OF LEAD-BASED PAINT IN EXCESS OF 30-MICROGRAMS-PER-CUBIC-METER.

Personnel shall wear and use protective clothing and equipment. The CONTRACTOR shall provide eye protection for personnel engaged in lead-based paint removal operations. Eating, smoking, or drinking is not permitted in the lead control area. Sanitary conditions shall be maintained at all times by the CONTRACTOR. No one will be permitted in the lead control area without appropriate training and protective equipment.

The CONTRACTOR shall provide clean change rooms within the physical boundary around the designated lead control area. Whenever personnel exit the lead-controlled area, they shall perform the following procedures and shall not leave the work place wearing any clothing or equipment worn during the workday.

- (1) Vacuum self-off.
- (2) Remove protective clothing and place in approved waste containers.
- (3) Utilize hand-washing facilities.
- (4) Shower (if required).
- (5) Change to clean clothes prior to leaving the physical boundary designated around the lead-contaminated job site.

Upon completion of initial employee exposure assessment, adjust requirements in accordance with 29 CFR 1926.62.

603.5.5. Care and Containment. The CONTRACTOR shall perform work without damage or contamination of adjacent areas. Where existing work is damaged or contaminated, the CONTRACTOR shall restore work to its original condition or better at the CONTRACTOR's expense. In addition to the requirements of 29 CFR 1926.62, the CONTRACTOR shall ensure the following:

- (1) No visible paint chips shall escape the lead control area.
- (2) Removal of hazardous paint from the control area shall be the responsibility of the CONTRACTOR.
- (3) All surrounding surfaces, ground cover, and plant life within the lead control area marked by the physical boundary are protected from lead contamination.
- (4) Lead-based paint debris shall be captured and stored for disposal on a daily basis in accordance with applicable regulations.

If shrouding is required, the CONTRACTOR shall submit to the Engineer a written plan describing the type and performance of the proposed shrouding method. Performance data shall include time required to raise and lower shroud and containment efficiency. This submittal shall be for informational purposes only.

Review of this submittal shall not constitute approval of the proposed method nor place any responsibility for the same upon the Engineer.

603.6. LEAD-BASED COATING REMOVAL

CONTRACTOR shall submit to the Engineer a written plan describing the materials and methods proposed for use in removal. A separate submittal shall be made for each method proposed. CONTRACTOR shall fully remove existing paint and coatings from all surfaces of the structure to be recoated. All coating removal, handling and disposal shall be performed in accordance with all applicable state and federal regulations and industry standards, including but not limited to the following:

- (1) Lead Base Coating Removal: ANSI Z88.2, 29 CFR 1910, 29 CFR 1920, and 29 CFR 1926.
- (2) Identification and Classifications of Wastes: 40 CFR 260, 40 CFR 261, 40 CFR 262.
- (3) Containment of Lead Base Coatings: SSPC-Guide 6 Guide for Containing Debris Generated During Paint Removal Operations, 30 TAC 111.
- (4) Transporting and Disposal of Lead Base Coatings and Contaminants: 40 CFR 263, 40 CFR 264, 40 CFR 265, 40 CFR 268, 49 CFR 171-173, 49 CFR 178.

603.7. LEAD-BASED COATING ENCAPSULATION

Coatings shall meet the requirements of ASTM E1795 Non-Reinforced Liquid Coating Encapsulation Products for Leaded Paint in Buildings for the purpose of encapsulating lead-based coatings. Encapsulation materials shall be guaranteed by the manufacturer to provide abatement results equal to other methods. The manufacturer's recommended methods shall be followed.

603.8. CLEANUP AND DISPOSAL

603.8.1. Consolidation. CONTRACTOR shall maintain surfaces of the lead control area free of accumulations of paint chips and dust; restrict the spread of dust and debris; keep waste from being distributed over the work area. Do not dry sweep or use compressed air to clean up the area. CONTRACTOR shall perform housekeeping at the end of each shift and when the coating removal operation has been completed by cleaning the lead control area of visible lead-based paint chips using an HEPA-filtered vacuum. Lead-containing coating residue shall be tested in accordance with 40 CFR 261 for hazardous waste.

603.8.2. Waste Classification. Test results for leachable lead and other hazardous components in waste materials shall be used by the CONTRACTOR to classify the waste material in accordance with USEPA hazardous waste; TCEQ non-hazardous, non-municipal, special waste; and TCEQ municipal waste requirements. Disposal requirements will be dictated by the waste classification. No waste materials may be removed from the site until test results are submitted and the CONTRACTOR's proposed disposal method is approved by the Engineer.

603.8.3. Final Inspection. Upon completion of work and prior to removal of the lead control area, the CONTRACTOR will notify the OWNER for a final lead inspection. As a minimum, the final lead inspection shall include air, water, and soil samples for verification of contamination, which may have occurred during the course of the project.

603.8.4. Disposal. Waste disposal shall be the responsibility of the CONTRACTOR. Waste shall be disposed in accordance with classification determined during testing (hazardous; non-hazardous, non-municipal, special waste; or municipal waste). The CONTRACTOR shall collect, store, and dispose of the lead contaminated waste and lead containing coating as follows.

603.8.4.1. Collection and Short-Term Storage. The CONTRACTOR shall collect lead waste, scrap, debris, bags, containers, equipment, and lead contaminated clothing and materials and store in Department of Transportation approved container systems. Each container shall be labeled to identify the waste and the date wastes were first put into the container.

As necessary, CONTRACTOR shall make deliveries of lead-based coating wastes to ensure containers do not remain on the job site longer than 90-days from the initial loading date affixed to the container. CONTRACTOR shall notify the OWNER at least 14-days prior to removal of the containers to inspect the containers and the hazardous waste manifest.

603.8.4.2. Handling and Disposal. Wastes shall be handled, stored, transported, disposed, recorded, and notifications made in accordance with all applicable State and Federal regulations. Land disposal restriction notification requirements must be followed as required by 40 CFR 268.

Disposal must be at a site approved by the Environmental Protection Agency and the TCEQ to accept lead-based coating waste per classification. The CONTRACTOR shall submit written evidence that the lead-based coating waste treatment, storage, or disposal facility (TSD) is approved for lead disposal by the USEPA and state or local regulatory agencies. CONTRACTOR shall submit one copy of the completed manifest, signed and dated by the initial transporter in accordance with 40 CFR 262.

603.9. PAYMENT

Payment for the removal or alternative abatement of coatings containing lead, chromium or cadmium shall be included within the lump sum bid price for the corresponding items contained in the proposal.

ITEM 604. REMOVAL OF ASBESTOS-CEMENT PIPE (ACP)

604.1. GENERAL

The work to be performed under this specification shall consist of providing all labor, equipment, materials, and incidentals necessary to remove and dispose of abandoned asbestos-cement pipe (ACP) water mains, as shown on the plans, directed by the OWNER.

604.2. JOB PLAN

The CONTRACTOR must provide a job specific plan of the work procedures to be used in the removal and containment or alternative abatement of asbestos. The job plan shall be prepared and submitted prior to beginning the work and shall be subject to approval by the OWNER. The OWNER shall be notified in writing 30-days prior to the start of asbestos abatement work. The job plan shall include the following:

- (1) Detailed work schedule
- (2) Written quality control program.
- (3) Written worker health and safety program.
- (4) Methodology for protection of ground surface adjacent to work.
- (5) Methodology for collecting, containing and disposing of hazardous materials when removal is specified.
- (6) A copy of the technical data sheets for all products including manufacturer's name, addresses and phone numbers and product description. The product description shall include, but not be limited to basic use, limitations, precautions, recommended application methods specific to this project, and any known environmental hazards or constraints.

604.3. PROCEDURES

CONTRACTOR shall comply with OSHA Construction Industry Standards for Occupational Exposure to Asbestos, 29 Code of Federal Regulations (CFR) 1926.1101, Subpart Z.

CONTRACTOR shall furnish and apply to broken pipe any required protective material such as plastic sheeting.

604.4. DISPOSAL

Wastes shall be handled, stored, transported, disposed, recorded, and notifications made in accordance with all applicable State and Federal regulations. Land disposal restriction notification requirements must be followed as required.

Disposal must be at a site approved by the Environmental Protection Agency and the TCEQ to accept asbestos waste material.

604.5. PAYMENT

The removal of ACP water mains shall be measured per linear foot and will be paid at the total unit price as shown in the bid proposal for the respective size, if specified. The bid price should include all excavation, backfill, compaction, protective materials, specialized equipment, abatement, transportation, disposal and any other work required to remove, protect, and dispose of the pipe as shown on the plans or as specified herein.

A close-up photograph of a large, industrial-grade metal bolt and nut assembly. The bolt is threaded and extends upwards from a hexagonal nut. The nut is stacked on top of another hexagonal component, which appears to be a washer or another nut. The metal has a weathered, greyish-silver finish with some visible rust and wear. The background is a blurred industrial setting with other metal structures.

Division 700

Structures

DIVISION 700 STRUCTURES**TABLE OF CONTENTS**

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
701.	GENERAL STRUCTURES	701-1 to 701-7
701.1.	Structural Wood Products	
701.2.	Structural Removal, Excavation, and Backfill	
701.3.	Structural Bolting	
702.	CONCRETE STRUCTURES	702-1 to 702-29
702.1.	Description	
702.2.	Concrete Structure Materials	
702.3.	Mix Design and Mixing Concrete for Structures	
702.4.	Mix Design and Mixing Lightweight Concrete for Structures	
702.5.	Constructing Concrete Structures	
702.6.	Prestressed Concrete for Structures	
702.7.	Pneumatically Placed Concrete (Gunite)	
702.8.	Drilled Shaft Foundations	
702.9.	Precast and Cast-In-Place Concrete Units	
703.	STEEL STRUCTURES	703-1 to 703-7
703.1.	Description	
703.2.	Materials for Steel Structures	
703.3.	Steel Structure Construction	
703.4.	Painting Metal Structures	
703.5.	Measurement and Payment	
704.	PILING	704-1 to 704-4
704.1.	Piling Materials	
704.2.	Driving Piling	
704.3.	Penetration	
704.4.	Bearing Resistance	
704.5.	Constructing Cast-In-Place, Prestressed Concrete Piling	
704.6.	Measurement and Payment	

ITEM 701. GENERAL STRUCTURES

701.1. STRUCTURAL WOOD PRODUCTS

No trees shall be removed unless so noted on the plans or upon the specific approval of the OWNER. Where trees, plants, shrubbery, etc., are adjacent to the line of the work and are not to be removed or are designated on the plans to be removed and replanted, the CONTRACTOR shall protect such trees, plants, shrubbery, and etc. in accordance to the contract documents. If, in the opinion of the OWNER, such trees, plants, shrubbery, etc., would be damaged by machinery, etc., hand excavation may be required. Shrubby, plants, etc. to be relocated or reused shall be removed with a ball of dirt about their roots and shall be carefully stored and given proper attention.

701.2. STRUCTURAL REMOVAL, EXCAVATION, AND BACKFILL

This item shall govern for the structural removal, excavation, and backfill.

701.2.1. Structural Removal. Removal of existing structures shall consist of the removal and satisfactory disposal of all existing structures and pavements, on the surface or below the ground, which are to be abandoned or removed or that interfere in any way with the new construction, which existing structures are designated for removal on the plans and in these specifications.

Existing structures shall be defined as buildings, foundations, bridges, culverts, headwalls, walls, linings, enclosures, manholes, inlets, cleanouts, valve boxes, pipes, conduits, junction structures, access structures, and other miscellaneous structures or portions thereof of various material composition.

Removal of existing structures shall include the furnishing of all labor, materials, and equipment to accomplish the work to the limits and requirements of the plans and these specifications.

701.2.1.1. Removal of Existing Structures. Materials or parts of the structures not designated for salvage shall become the property of the CONTRACTOR and shall be disposed of by the CONTRACTOR at CONTRACTOR'S own cost and expense at sites approved by the OWNER.

Existing structures which are to be abandoned shall be broken off or removed to a depth of not less than 1 foot below the foundation or subgrade of the new work, unless otherwise provided for in the plans and specifications or approved by the OWNER. Construction of bulkheads and structural plugs shall be done as directed by the OWNER and the cost of such work shall be considered incidental to the contract pay items provided. All operations that endanger new work shall be completed prior to the construction of the new work. Pavement shall be removed only between the lines indicated on the plans. Surface course and sub-base select materials shall be as nearly as practicable removed separately from earth or other excavated materials, stored and utilized as directed by the OWNER. The edges of all openings shall be trimmed smooth and to line, and the face shall be perpendicular to the subgrade.

After removal of structures, all excavations not to be occupied by new work, and all holes created, shall be backfilled in accordance with [Item 504](#). Open Cut-Backfill of these Standard Specifications with approved materials thoroughly compacted in place in lifts of no more than 8 inch thickness (before compaction) and to a density of at least 90 percent of the maximum density determined by ASTM D698 with moisture content within minus 2 to plus 4 of optimum, except that under paved areas, compaction shall be to a density of at least 95 percent.

Damages to adjacent property or structures shall be repaired in a timely fashion, as directed by the OWNER, and shall be repaired by the CONTRACTOR at his sole cost and expense, and to the satisfaction of the OWNER. Any unsightly places created shall be cleaned up and the site of the work left in a neat, clean, and orderly condition.

701.2.1.2. Removal of Existing Pavement. Existing concrete pavements, driveways, curbs, gutters, sidewalks, etc., to be removed shall be broken up and disposed of. Care shall be exercised to leave a neat, uniform edge or joint at the excavation limits or sections removed where only portions are to be removed. Removals shall be to the limits shown on the plans, as directed by the OWNER. Materials designated for salvage shall be salvaged in accordance with [Item 701.2.2](#). Removal and Salvage of Existing Structures. Any additional removal required after the initial removal has been made will be

performed to the limits directed by the OWNER and be paid for in the manner as prescribed under [Item 104.2](#), Change or Modification of Contract of these Standard Specifications.

Removal of asphalt and aggregate pavements shall be considered part of unclassified street excavation work, unless otherwise specifically provided for in the plans and specifications.

701.2.1.3. Measurement and Payment. When the removal work is called for in the plans and specifications, with separate pay items for such work included, measurement for payment shall be as required. Unless otherwise provided in the proposals, no payment shall be made for removal of structures and concrete pavements as such, but such work shall be considered as incidental work and the cost thereof shall be included in the contract pay items provided in the proposal and contract.

When provided for in the proposal and contract, payment for removal of existing structures shall be made at the unit price bid per each or per lump sum, as specified, for removal of existing structures, which price shall be full compensation for all excavation and backfill; for all breaking up and removal of concrete, steel and associated materials; for loading, hauling, unloading, storage, and disposal of materials and structures, including any disposal fees; and for all materials, labor, tools and incidentals necessary to complete the work in accordance with the plans and specifications.

When provided for in the proposal and contract, payment for removal of concrete pavement or modular block paver pavement, when not with concrete base, shall be made at the unit price bid per square yard of concrete or modular block paver pavement actually removed, to the limits shown in the plans and specifications and as directed by the OWNER. Payment for removal of composite block paver and concrete pavements shall be made per square yard of composite pavement actually removed to the limits authorized. Removal of concrete pavement includes removal of variable dimensioned, variable thickness, nonreinforced or reinforced concrete pavement, drives, slabs, integral curbs, and aprons. Pay limits shall be to the back of integral curb removed. Removal of integral curbs shall be considered incidental to removal of the pavement.

When provided for, payment for removal of nonreinforced or reinforced concrete sidewalk shall be made at the unit price bid per square foot of concrete sidewalk removed, to the limits shown in the plans and specifications and as directed by the OWNER. Payment for removal of concrete separate curb or curb with gutter shall be made at the unit price bid per linear foot of concrete curb or curb with gutter actually removed, to the limits shown in the plans and specifications and as directed by the OWNER.

The removal of structures, pavements, sidewalks, curbs, or curbs and gutter in excess of the limits shown in the plans and specifications or in excess of what is directed by the OWNER shall be at the entire cost and expense of the CONTRACTOR and such excess removal areas shall be replaced with adequate structure, pavement and materials as determined and directed by the OWNER, at the CONTRACTOR's entire cost and expense.

701.2.2. Removal and Salvage of Existing Structures. Removal and salvage of existing structures shall consist of the removal and salvage of all existing structures and pavements, on the surface, or below the ground, which are to be removed and salvaged, and which interfere in any way with the new construction and which are designated for removal and salvaging on the plans or in these specifications.

Existing structures shall be defined in [Item 701.2.1](#), Structural Removal, and [Item 701.2.2](#), Removal and Salvage of Existing Structures, shall include the furnishing of all labor, materials, and equipment to accomplish the work to the limits and requirements of the plans and these specifications.

701.2.2.1. Removal and Salvage of Existing Structures. All structures which are to be salvaged will be designated as such, and shall be removed by the CONTRACTOR under the direction of the OWNER, in such a manner as to prevent their being broken or unduly damaged.

Materials or parts of structures which are designated to be salvaged, such as lumber, pipe, brick, modular block pavers, concrete, gravel, castings, etc., shall be removed in a manner approved by the OWNER, and stacked at the site of their removal as directed by the OWNER, and shall remain the property of the City. The salvaged materials will be removed from the site by the City unless otherwise specified in the plans and specifications.

701.2.2.2. Measurement and Payment. If the removal and salvage work is called for in the plans and specifications, with separate bid items for such work included, measurement for payment shall be as required. Otherwise, no payment shall be made for removal and salvage of structures and concrete pavements as such, but such work shall be considered as incidental work and the cost thereof shall be included in the contract pay items provided in the bid proposal and contract.

If specifically provided for in the bid proposal and contract, payment for removal and salvage of existing structures shall be made at the unit price bid per each or per lump sum, as specified, for removal and salvage of existing structures which price shall be full compensation for all excavation and backfill; for all removal of concrete, steel and associated materials; for salvage and storage of materials and structures; and for all materials, labor, tools and incidentals necessary to complete the work in accordance with the plans and specifications.

When provided for in the proposal and contract, payment for removal and salvage of modular block paver pavement shall be made at the unit price bid per square yard of modular block paver pavement actually removed and salvaged, to the limits shown in the plans and specifications and as directed by the OWNER. Payment for removal and salvage of composite block paver and concrete pavements shall be made per square yard of composite pavement actually removed, to the limits authorized.

Payment for removal and salvage of concrete separate curb or curb with gutter performed shall be made at the unit price bid per linear foot of concrete curb or curb with gutter actually removed and salvaged, to the limits shown in the plans and specifications and as directed by the OWNER.

The removal and salvage of structures, pavements, curbs, or curbs and gutter in excess of the limits shown in the plans and specifications, or in excess of what is directed by the OWNER, shall be at the entire cost and expense of the CONTRACTOR and such excess removal areas shall be replaced with adequate structure, pavement and materials as determined and directed by the OWNER, at the CONTRACTOR's entire cost and expense.

701.2.3. Adjustment of Existing Structures. Adjustment of existing structures shall consist of the adjustment of all existing structures and pavements, on the surface, or below the ground, which are to be adjusted or rebuilt, and which interfere in any way with the new construction and which are designated for adjustment on the plans or in these specifications.

Adjustment of existing structures shall include the furnishing of all labor, materials, and equipment to accomplish the work to the limits and requirements of the plans and these specifications.

701.2.3.1. Construction Methods. Existing structures such as manholes, inlets, cleanouts, valve boxes, pipes, etc. which are designated for adjustment in the plans or specifications shall be adjusted, altered or reset to the required elevation and alignment shown in the plans and specifications, as directed by the OWNER. New materials and workmanship necessary shall conform to the requirements of these specifications covering the particular work. Where manholes are to be built up for 1-ft. or less, the walls may be carried up vertically where the walls are to be built up for more than 1-ft., the existing walls shall first be removed down to the bottom of the batter or draw-in section of the walls, or to such an elevation that the inside diameter of the manhole is not less than 3-1/2-ft., the manhole shall then be rebuilt in conformity with the size and shape requirements for new manholes. Salvaged materials in good condition may be used in rebuilding such structures with consent of the OWNER, provided the materials are thoroughly cleaned before their use.

701.2.3.2. Measurement and Payment. If the adjustment of existing structures work is called for in the plans and specifications, with separate bid items for such work included, measurement for payment shall be as required in this item. Otherwise, no payment shall be made for adjustment of structures and concrete pavements as such, but such work shall be considered as incidental work and the cost thereof shall be included in the contract pay items provided in the bid proposal and contract.

If specifically provided for in the bid proposal and contract, payment for adjusting of existing structures shall be made at the unit price bid per each or per lump sum, as specified, for adjusting of existing structures, which price shall be full compensation for all excavation and backfill; for all breaking up and removal of concrete, steel and associated materials; and for all materials, labor, tools and incidentals necessary to complete the work in accordance with the plans and specifications.

701.2.4. Structural, Excavation and Backfill. Structural excavation shall consist of the removal of material for the construction of foundations for bridges, retaining walls, head walls for culverts, or other structures and other excavation designated on the plans or in these specifications as structural excavation, along with the subsequent backfill of these same structures.

Structural backfill shall consist of furnishing material, if necessary, and placing and compacting backfill material around structures to the line designated on the plans, specifications, and/or as directed by OWNER.

Structural excavation and structural backfill shall include the furnishing of all materials and equipment, the construction or installation of all cofferdams in accordance with [Item 802.4](#). Cofferdams and other facilities that may be necessary to perform the work shall be removed, except where they are required or permitted to remain by the plans, specifications, and/or as directed by OWNER.

Structural excavation shall be considered subsidiary to each bid item for which structural excavation is necessary.

For structural excavation and backfill items not covered here, refer to TxDOT Item 400 Excavation and Backfill for Structures.

701.3. STRUCTURAL BOLTING

This item shall govern for the materials to be used and for the method of installation of high-strength bolts used in structural joints.

701.3.1. Materials. Materials shall be as specified and meet the requirements of [Item 806.6](#). Bolts, Nuts and Washers.

701.3.2. Construction Methods.

701.3.2.1. General Requirements. Surfaces of bolted parts in contact with the bolt head and nut shall not have a slope of more than 1:20 with respect to a plane normal to the bolt axis. Bolted parts shall fit solidly together when assembled and shall not be separated by gaskets or any other interposed compressible material. Holes shall be punched, sub-punched and reamed or drilled as required by [Item 703.3](#). Steel Structure Construction. Holes shall be of a nominal diameter not more than $\frac{1}{16}$ -in. in excess of the nominal bolt diameter. Field erection and fit-up of joints and splices shall conform to the requirements of [Item 703.3](#). Steel Structure Construction.

When assembled, all joint surfaces, including those adjacent to the washers, shall be free of dirt, rust, loose scale, burrs, and other defects that would prevent solid seating of the parts.

Contact surfaces shall be free of oil, paint, lacquer, or galvanizing.

701.3.2.2. Installation. Bolts shall be installed with a hardened washer under the nut or bolt head, whichever is the element turned in tightening. A hardened washer shall also be used under the head of regular semi-finished hexagon bolts and under finished hexagon nuts, even when these are not the elements turned in tightening. The washer may be omitted under the head of heavy semi-finished hexagon bolts, interference-body bolts, and heavy semi-finished hexagon nuts when these are not the elements turned.

701.3.2.3. Pre-Tightening. Prior to actual tightening of the bolts, the following procedures shall be followed:

- (1) A minimum of 20-percent of the holes at a connection point shall be filled with erection pins to "fair-up" all holes.
- (2) Install bolts in all remaining holes.
- (3) Tighten a minimum of 20-percent of the bolts, following a pattern of progression from the center or most rigid part of the joint toward the free edges, making sure that all plies of the metal in the connection are properly fitted and in contact.
- (4) Mark those bolts used for fit-up bolts.
- (5) Tighten all the remaining bolts per [Item 701.3.2.4](#). Tightening, then remove the erection pins.
- (6) Fill the remaining holes with bolts and loosen all bolts used for fit-up.
- (7) Tighten the rest of the bolts per [Item 701.3.2.4](#). Tightening.

701.3.2.4. Tightening. All fasteners shall be tightened to give at least the required minimum bolt tension values shown in Table 701.3.2.4.(a) Bolt Tension on completion of the joint.

Table 701.3.2.4.(a) Bolt Tension

Nominal Bolt Size (in.)	Minimum Tension (kips)	
	ASTM A325 Bolts	ASTM A490 Bolts
1/2	12	15
5/8	19	24
3/4	28	35
7/8	39	49
1	51	64
1-1/8	56	80
1-1/4	71	102
1-3/8	85	121
1-1/2	103	148

Tightening shall be done by one of the following methods:

- (1) The Turn-of-the-Nut Method.
- (2) The Calibrated-Power Wrench Method.
- (3) Gauge Washer Method.

701.3.2.4.1. Turn-of-the-Nut Method. This method indicates the following:

- (1) Tighten all bolts used as fit-up bolts to a “snug-tight” condition. (A snug-tight condition is indicated by the wrench when it ceases to spin and just begins to impact, or with a spud wrench by tightening with slight pressure.)
- (2) The nut shall be matched-marked with the protruding bolt point before final tightening, thus affording the inspector visual means of noting the actual nut rotation. Such marks shall be made by the operator with a keel, crayon or spot of paint, after the bolts have been brought up to snug-fit.
- (3) Tighten the nuts by the amount specified in Table 701.3.2.4.1.(a) Nut Rotation from Snug-Tight Condition. Impact wrenches shall be of adequate capacity and sufficiently supplied with air to perform the required tightening in approximately 10-seconds.

Table 701.3.2.4.1.(a) Nut Rotation from Snug-Tight Condition¹.

Bolt length (underside of head to end of bolt)	Disposition of Outer Face of Bolted Parts		
	Both faces normal to bolt axis	One face normal to bolt axis and other face sloped less than 1:20 (beveled washer not used)	Both faces sloped less than 1:20 from bolt axis (beveled washer not used)
Up to and including 4 bolt diameters	1/3 turn	1/2 turn	2/3 turn
Over 4 bolt diameters up to and including 8 diameters	1/2 turn	2/3 turn	5/6 turn
Over 8 bolt diameters up to and including 12 diameters	2/3 turn	5/6 turn	1 turn

1. Nut rotation is relative regardless of the element (nut or bolt) being turned. The tolerance is $\pm 30^\circ$ for bolts installed by 1/2 turn or less and 45° for bolts installed by 2/3 turn or more.

For bolt lengths greater than 12 diameters, determine the required rotation using the installation verification test in a simulated connection of solidly fitted steel.

- (4) Fill the remaining holes with bolts and loosen all bolts used for fit-up.
- (5) Tighten the rest of the bolts by the required amount.
- (6) Tightening crew to mark finished work with identifying symbol.
- (7) Inspector mark accepted work.

701.3.2.4.2. Calibrated-Power Wrench Method. When calibrated wrenches are used to provide the bolt tension, their settings shall be such as to induce a bolt tension of 1.05 of the value shown in Table 701.3.2.4.(a) Bolt Tension. The nut shall be matched-marked with the protruding bolt point before final tightening, thus affording the inspector visual means of noting the actual nut rotation. Such marks shall be made by the operator with a keel, crayon or spot of paint, after the bolts have been brought up to snug-fit.

A torque wrench shall be used to check bolts for tightness when the calibrated-power-wrench method is used. The following procedure shall be used to calibrate the torque wrench:

- (1) One bolt of the type, size and condition of thread as those to be inspected shall be tightened with the impact wrench, in a device capable of measuring actual bolt tension to the required minimum bolt tension required in Table 701.3.2.4.(a) Bolt Tension.
- (2) In this tightened condition, the inspector's torque wrench shall be used to rotate the nut slowly in the tightening direction to move just the nut. The amount required to move the unit shall be used for the inspection torque (use the average of 3 torque values).
- (3) When inspecting the bolts installed in the structure, the torque wrench shall be used to tighten the nut; and the torque read just as the nut is set in motion.

Readings higher than the required minimum tension required shall not be cause for rejection. Bolts giving values lower than the required value shall be removed and replaced.

One or two bolts of each size in every connection and a minimum of 10-percent of the bolts in large connections shall be checked. If one or more bolts in a connection are below the required value, all the bolts shall be re-impacted with the calibrated power wrench.

When the calibrated wrench body type of bolt is allowed and used, setting shall be such as to induce a bolt tension slightly in excess of the value shown. The wrenches shall be calibrated by tightening not less than 3 typical bolts of each size from the lot to be installed in a device capable of indicating actual bolt tension.

Power wrenches shall be adjusted to stall out or cut out complete at the selected tension.

When using calibrated wrenches to install bolts, the operator should return to "touch-up" bolts previously tightened, until all bolts are tightened to the prescribed tension. This shall include:

- (1) Tightening all bolts not used as fit-up bolts to the tension required by Table 701.3.2.4.(a) Bolt Tension.
- (2) Fill the remaining holes with bolts and loosen all bolts used for fit-up.
- (3) Tighten the rest of the bolts by the required amount.
- (4) Tightening crew to mark finished work with identifying symbol.
- (5) Inspector mark accepted work.

701.3.2.4.3. Gauge Washer Method. Use of gauge washers to determine torque shall follow manufacturer instructions.

701.3.3. Inspection. The OWNER shall approve the procedures for calibration of wrenches and installation of bolts. The inspector shall further observe the field installation to determine that these procedures are followed.

Bolts, nuts and washers are normally shipped with a light residual coating of oil. This coating is not detrimental to friction-type connections and need not be removed. Heavy coatings of oil shall be removed. Bolts tightened by the turn-of-the-nut method shall have the outer face of the nut marked along with the end of the bolt with permanent felt markers in order to determine the amount of turn. Close inspection shall be made to insure that the bolts are a tight fit; and that there is no movement of the head in the tightening operation. When the calibrated-wrench method of tightening is used, the CONTRACTOR shall furnish the calibration equipment (Skidmore Wilhelm bolt calibrator or equal).

For the turn-of-the-nut method, the CONTRACTOR shall not be required to furnish equipment or make tests for establishing bolt tension. Such tests, if required, shall be performed by the OWNER. However, the

CONTRACTOR shall not be relieved of the responsibility for re-tightening bolts in case tests indicate the required tension is not being obtained.

701.3.4. Measurement and Payment. No direct compensation shall be made for the installation of bolts. Payment shall be subsidiary to the pertinent item requiring the use of high-strength bolts.

ITEM 702. CONCRETE STRUCTURES

702.1. DESCRIPTION

This specification shall govern for the construction of all types of structures involving the use of structural concrete except where the requirements of this section are not applicable. All concrete structures shall be constructed in accordance with the design requirements and details shown on the plans, with the pertinent provisions of other applicable sections of the specifications, and with the requirements herein provided.

702.2. CONCRETE STRUCTURE MATERIALS**702.2.1. Aggregates for Portland Cement Concrete Structures.**

702.2.1.1. General Requirements. Aggregates shall conform to the provisions of [Item 303.2.1.1.](#) General Requirements in [Item 303.2.1.](#) Aggregates for Portland Cement Concrete Pavement.

702.2.1.2. Fine Aggregates. Fine aggregates shall conform to the provisions of [Item 303.2.1.2.](#) Fine Aggregates.

702.2.1.3. Coarse Aggregates. Coarse aggregates shall conform to the provisions of [Item 303.2.1.3.](#) Coarse Aggregates.

702.2.1.4. Lightweight Aggregates. Lightweight aggregates shall consist of expanded clay or shale having strong, durable particles; and conforming to the requirements of ASTM C330 Lightweight Aggregates for Structural Concrete.

702.2.1.4.1. Foreign Material and Deleterious Substances. Deleterious substances, elements, or components are those that are damaging, harmful, undesirable, or adulterating to the integrity or purity of the specified base material. The maximum permissible percentage, by weight, of deleterious substances shall not exceed the amounts in Table 702.2.1.4.1.(a) Deleterious Substances in Lightweight Aggregates.

Lightweight aggregates that, upon being subjected to the test for organic impurities, produce a color darker than the standard shall be rejected, unless it can be demonstrated that the discoloration is due to small quantities of materials not harmful to the concrete.

If, after a test for staining materials (ASTM C641 Staining Materials in Lightweight Concrete Aggregates), the aggregates are classified as “heavy stain” or darker, a test following the chemical procedure shall be performed. If 1.5-mg or more of ferric oxide (Fe_2O_3) per 200-g sample is found, the aggregate shall be rejected.

Table 702.2.1.4.1.(a) Deleterious Substances in Lightweight Aggregates

Substance	Maximum % by Weight
Loss on ignition	5%
Clay lumps	2%

702.2.1.4.2. Gradation. The lightweight aggregate shall be well graded in size from coarse to fine. When tested by standard laboratory methods lightweight aggregate shall meet the requirements in Table 702.2.1.4.2.(a) Grading Requirements for Lightweight Aggregates for percentage passing each sieve by weight.

Table 702.2.1.4.2.(a) Grading Requirements for Lightweight Aggregates

Sieve	Percent Passing
$\frac{3}{4}$ in. sieve (19.0 mm)	90 to 100%
$\frac{3}{8}$ in. sieve (9.5 mm)	20 to 55%
Passing No. 4 sieve (4.75 mm)	0 to 10%
Passing No. 8 sieve (2.36 mm)	0 to 5%

702.2.1.4.3. Natural Fine Aggregate. At the option of the CONTRACTOR, natural fine aggregate may be substituted for fine lightweight aggregate, provided such substitution does not result in producing concrete that has a weight in excess of the permissible maximum specified herein. Natural fine aggregate shall meet the grading requirements of Table 303.2.1.2.2.(a) Grading Requirements for Fine Aggregates. Natural fine aggregate shall have a percent of wear not more than 40 when tested according to ASTM C131 Resistance to Degradation of Small-Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine.

702.2.1.4.4. Rejection. Lightweight aggregates which fail to meet the requirements for these specifications may be rejected by the OWNER. Such rejection shall incur no cost to the OWNER.

If lightweight aggregate with properties not meeting these specifications are delivered to the project, the source of the material may be rejected as a further supply source by the OWNER. Such rejection shall incur no cost to the OWNER.

702.2.1.5. Pit-Run and Re-Mix Aggregate. Pit-run aggregate is the natural gravel and sand obtained from pits without the addition of other fine or coarse aggregates and shall consist of hard, durable, uncoated pebbles or stone particles mixed with sand. Pit-run aggregate shall not be used for high strength concrete of 3000-psi and above. Pit-run aggregate may be used only for concrete cushion, cradle and protection for pipe.

Re-mix aggregate is native rock and sand that has been washed and screened and meets the specified gradation. Re-mix aggregate shall not be used for high-strength concrete of 3000-psi and above. Re-mix aggregate may be used only as a substitute for pit-run aggregate or when specified.

702.2.1.5.1. Foreign Material and Deleterious Substances. Pit-run and re-mix aggregate shall be free from lumps of clay and from injurious amounts of dust, shale, soft or flaky particles, salt and alkali.

702.2.1.5.2. Gradation. Pit-run and re-mix aggregate shall be well graded from coarse to fine when tested by standard laboratory methods and shall meet the minimum requirements for percentages by weight in Table 702.2.1.5.2.(a) Grading Requirements for Pit-Run and Re-Mix Aggregate.

Table 702.2.1.5.2.(a) Grading Requirements for Pit-Run and Re-Mix Aggregate

Sieve	Percent Retained by Weight
$\frac{1}{4}$ -in. (6 mm) sieve	55 to 60%

702.2.1.5.3. Rejection. Pit-run and re-mix aggregate may be rejected for failure to meet any of the requirements of this specification. Such rejection shall incur no cost to the OWNER.

Aggregate sources from which materials with properties not meeting these specifications are delivered may be rejected as a further supply source to the project by the OWNER. Such rejection shall incur no cost to the OWNER.

702.2.1.6. Alkali-Silica Reactions (ASR) and Delayed Ettringite Formation (DEF) Mitigation. Refer to TxDOT Item 421 Hydraulic Cement Concrete.

702.2.2. Portland Cement. Portland Cement shall conform with the requirements of [Item 303.2.2](#). Portland Cement.

702.2.3. Concrete Additives and Modifiers. Concrete additives and modifiers shall conform to the applicable requirements of [Item 303.2.3](#). Chemical Admixtures, [Item 303.2.4](#). Mineral Admixtures, [Item 303.2.5](#). Mineral Filler, and/or [Item 303.2.6](#). Fibrous Reinforcement.

702.2.4. Water. Water shall conform to the requirements of [Item 303.2.7](#). Water.

702.2.5. Reinforcement. Reinforcement, if any, shall conform to the requirements of [Item 303.2.9](#). Steel Reinforcement, except that axle steel shall not be permitted on structures and the use of rail steel or axle steel shall not be permitted for use in railroad underpass structures. At the OWNER's option the use of welded wire fabric in accordance with [Item 303.2.10](#). Steel Wire Reinforcement may be used.

702.2.5.1. Epoxy Coated Bars. For use of epoxy coated bars, refer to TxDOT Standard Specifications for Construction and Maintenance of Highways, Streets, and Bridges.

702.2.6. Joint Filler and Joint Sealer. Joint filler shall conform to the requirements of [Item 303.2.12](#). Joint Filler. Joint sealer shall conform to the requirements of [Item 303.2.14](#). Joint Sealant.

702.2.7. Curing Materials. Curing materials shall conform to the requirements of [Item 303.2.13](#). Curing Materials.

702.2.8. Elastomeric Materials. Elastomeric materials shall conform to the requirements of [Item 303.2.15](#). Elastomeric Materials.

702.3. MIX DESIGN AND MIXING CONCRETE FOR STRUCTURES

702.3.1. Description. This section shall govern for the concrete used in bridges, box culverts, and such other miscellaneous structures and incidentals necessary to complete the work.

702.3.2. Equipment. All machinery and equipment necessary for the prosecution of the work specified herein shall be on the project and shall be approved by the OWNER as to condition before the CONTRACTOR shall be permitted to begin operations on which the machinery or equipment is to be used. All machinery and equipment shall be maintained in good condition to insure the completion of the work without excessive delays for repairs and replacements.

702.3.3. Concrete Mix Design and Control. The OWNER shall furnish plant control of the concrete by securing the services of an independent local testing laboratory. Within a period of not less than 10-days prior to the start of concreting operations, the CONTRACTOR shall submit to the OWNER a design of the concrete mix it proposes to use, together with samples of all materials to be incorporated into the mix and a full description of the source of supply of each material component. The design of the concrete mix shall produce a concrete complying with the requirements of concrete classes in Table 702.3.4.2.(a) Standard Classes of Structural Concrete or Table 702.3.4.3.(a) Performance Classes of Structural Concrete and slump in Table 702.3.4.4.(a) Structural Concrete Slump Requirements.

The dry loose volume of coarse aggregate shall not be more than 0.82 cubic-feet-per-cubic-foot of concrete, except in cases where the voids in the coarse aggregate as determined by standard test methods exceed 48-percent of the total dry loose volume. Where voids exceed 48-percent, the dry loose volume of coarse aggregate shall not exceed 0.85-cubic-feet-per-cubic-foot of concrete.

If the strength required for the class of concrete being produced is not secured with the cement specified in Table 702.3.4.2.(a) Standard Classes of Structural Concrete or Table 702.3.4.3.(a) Performance Classes of Structural Concrete, the CONTRACTOR may use, or the OWNER may require, an approved cement dispersing agent, or the CONTRACTOR shall furnish additional aggregates or aggregates with different characteristics which shall produce the required results. Additional cement may be required or permitted as a temporary measure until aggregates are changed and designs checked with the different aggregates or cement dispersing agent.

All material samples submitted to the OWNER shall be sufficiently large to permit laboratory batching for the construction of test beams to check the adequacy of the design. When the design mix has been approved by the OWNER, there shall be no change or deviation from the proportions thereof or sources of supply except as hereinafter provided. No concrete may be placed on the job site until the mix design has been approved by the OWNER in writing to the CONTRACTOR.

702.3.4. Quality of Concrete.

702.3.4.1. Consistency. In general, the consistency of concrete mixtures shall be such that:

- (1) the mortar shall cling to the coarse aggregate,
- (2) the aggregate shall not segregate in concrete when it is transported to the place of deposit,
- (3) the concrete, when dropped directly from the discharge chute of the mixer, shall flatten out at the center of the pile, but the edges of the pile shall stand and not flow,
- (4) the concrete and mortar shall show no free water when removed from the mixer,
- (5) the concrete shall slide and not flow into place when transported in metal chutes at an angle of 30° with the horizontal, and
- (6) the surface of the finished concrete shall be free from a surface film or laitance.

(7) The concrete shall be uniform and workable.

The cement content, maximum allowable water cement ratio, the average and maximum slump and the strength requirements of the various classes of concrete shall conform to the requirements of the tables below, and as required herein.

The consistency of the concrete as placed should allow the completion of all finishing operations without the addition of water to the surface. When field conditions are such that additional moisture is needed for the final concrete surface finishing operation, the required water shall be applied to the surface by misting only and shall be held to a minimum amount. The concrete shall be workable, cohesive, possess satisfactory finishing qualities and be of the stiffest consistency that can be placed and vibrated into a homogeneous mass. Excessive bleeding shall be avoided.

If the strength or consistency required for the class of concrete being produced is not secured with the minimum cement specified or without exceeding the maximum water/ cement ratio, the CONTRACTOR may use, or the OWNER may require, an approved cement dispersing agent (water reducer); or the CONTRACTOR shall furnish additional aggregates, or aggregates with different characteristics, or the CONTRACTOR may use additional cement in order to produce the required results. The additional cement may be permitted as a temporary measure, until aggregates are changed and designs checked with the different aggregates or cement-dispersing agent.

The CONTRACTOR is solely responsible for the quality of the concrete produced. The OWNER reserves the right to independently verify the quality of the concrete through inspection of the batch plant, testing of the various materials used in the concrete, and by casting and testing concrete cylinders or beams on the concrete actually incorporated in the structure.

Unless otherwise shown on the plans or detailed specifications, the Standard Classes of Concrete table shall be used.

702.3.4.2. Standard Classes. Standard classes of structural concrete shall meet the requirements in Table 702.3.4.2.(a) Standard Classes of Structural Concrete.

Table 702.3.4.2.(a) Standard Classes of Structural Concrete.

Class of Concrete ¹	Minimum Cementitious Lb./CY	Minimum Cementitious Sacks/CY	28 Day Min. Compressive Strength ² psi	28 Day Min. Beam Strength ^{2,3} psi	Maximum Water/ Cementitious Ratio	Coarse Aggregate Maximum Size ⁴
A	470	5.0	3000	500	0.58	1½"
B	376	4.0	2000	330	0.71	1½"
C	564	6.0	3600	600	0.53	1½"
D	282	3.0	1500	250	0.97	1½"
E	564	6.0	3000	500	0.62	1½"
F	611	6.5	4200	700	0.49	1½"
S	564	6.0	3600	600	0.44	1½"
H ⁵	611	6.5	As Specified On Plans	N/A	0.49	1"
M	As directed by the OWNER or as shown on the plans					

1. All exposed concrete shall have entrained – air (See [303.2.3](#), Chemical Admixtures).

2. Minimum Strength Required by OWNER [Compressive or Flexural]

3. ASTM C78 (Third-Point); Reduce by 10% when Type II Cement is Used

4. Smaller Nominal Maximum Size Aggregate May be Used if Strength requirement is Satisfied

5. Prestressed Concrete

702.3.4.3. Performance Classes. Performance Classes of structural concrete shall meet the requirements in Table 702.3.4.3.(a) Performance Classes of Structural Concrete.

Table 702.3.4.3.(a) Performance Classes of Structural Concrete

Class of Concrete ¹	Minimum Cementitious Lb./CY	Minimum Cementitious Sacks/CY	28-Day Compressive Strength ² psi	28-Day Flexural Strength ^{3,4} psi	Maximum Water/Cementitious Ratio ⁴	Coarse Aggregate Maximum Size ⁵
PA	423	4.5	3000	425	0.58	1½"
PB	350	4.0	2000	N/A	0.71	1½"
PC	517	5.5	3600	510	0.53	1½"
PD	250	3.0	1500	N/A	0.97	1½"
PE	470	5.0	3000	425	0.62	1½"
PF	564	6.0	4200	595	0.49	1½"
PS	517	5.5	3600	510	0.44	1½"
PH ⁶	611	6.5	As specified on plans	N/A	0.49	1"
PM	As directed by the OWNER or as shown on the plans					

1. All exposed concrete shall have entrained – air (See [303.2.3](#), Chemical Admixtures).

2. Calculated Average Required Compressive Strength Considering ACI 318 - Sec. 5.3.2.1 shall be strength shown times 1.15.

3. ASTM C78 (Third-Point); Reduce by 10% when Type II Cement is Used

4. Consistent with ACI 211.1 Table 6.3.4(a) Relationship between water-cementitious materials ratio and compressive strength of concrete

5. Smaller maximum size aggregate may be used if strength requirement is satisfied

6. Prestressed Concrete

702.3.4.4. Slump. Slump requirements for structural concrete shall be as specified in Table 702.3.4.4.(a) Structural Concrete Slump Requirements. No concrete shall be permitted with slump in excess of the maximums shown. Any concrete mix failing to meet the above consistency requirements, although meeting the slump requirements, shall be considered unsatisfactory, and the mix shall be rejected and changed to correct such unsatisfactory conditions at no cost to the OWNER.

Table 702.3.4.4.(a) Structural Concrete Slump Requirements.

Concrete Use	Avg. Slump (in.)	Max. Slump (in.)
Cased Drilled Shafts and Thin-walled Sections (9 in. or less)	6	7
Slabs, Caps, Wall Sections Over 9 in., etc.	3	4
Columns, Piers	4	5
Underwater or Seal Concrete	7	8
Other Miscellaneous Concrete	As specified by OWNER	

702.3.4.5. Tests. During the progress of the work, the CONTRACTOR shall cast test cylinders in accordance with ASTM C31 Standard Practice for Making and Curing Concrete Test Specimens in the Field to maintain a check on the compressive strengths of the concrete being placed. In accordance with ASTM C31 and ASTM C172 Standard Practice for Sampling Freshly Mixed Concrete, four test cylinders shall be taken from a representative portion of the concrete being placed for every 40-cubic-yards of concrete placed. After the cylinders have been cast, they shall remain on the job site and then transported, moist cured, and tested by the OWNER in accordance with ASTM C31 and C39 Standard Test Method for Compressive Strength of Cylindrical Concrete Specimens.

The CONTRACTOR shall provide and maintain curing facilities for the purpose of curing concrete test specimens on site in accordance with ASTM C31. The CONTRACTOR shall be responsible for the proper storage, maintenance, and any required curing of concrete test samples made by the OWNER, and any costs thereof.

In each set, two of the cylinders shall be tested at 7-days, two cylinders shall be tested at 28-days. If the 28-day test results indicate deficient strength, the CONTRACTOR may, at its option and expense, core the concrete in question and have the cores tested by an approved laboratory, in accordance with ASTM C42 Standard Test Method for Obtaining and Testing Drilled Cores and Sawed Beams of Concrete and ACI 318 protocol, to override the results of the cylinder tests.

Cylinders and/or cores must meet the specified strength in accordance with ACI 318 protocol. The testing does not in any way change the penalties imposed on the CONTRACTOR for deficient strength outlined elsewhere in these specifications.

At the OWNER'S direction, beam test may be required and utilized for acceptance of the final product.

702.3.5. Mixing.

702.3.5.1. General. Concrete shall be mixed in a machine, of approved design and capacity, which receives a complete charge of proportioned materials and thoroughly and evenly mixes the charge as a whole before any part is withdrawn from the machine. The mixing shall be continued until each particle of stone or gravel is completely covered with mortar and the batch is of uniform color and consistency. The manufacturer's recommended mixing time shall be adhered to or mixing shall continue until a uniform concrete mixture is obtained. The mixer shall be equipped with an attachment for satisfactorily locking the discharging device so as to prevent the emptying of the mixer until all the materials have been mixed together for the minimum time required. The entire contents of the drum shall be discharged before any materials are placed therein for the succeeding batch.

702.3.5.2. Transit Mix Concrete. Transit mix concrete shall meet the following conditions:

- (1) all requirements otherwise specified for mixing on the job shall apply,
- (2) sufficient transit mix equipment shall be assigned exclusively to the project as required for continuous operation,
- (3) satisfactory evidence shall be furnished so that the delivery of concrete shall be continuous at regular and uniform intervals, without stoppages or interruption,
- (4) the supplier of transit mix concrete shall furnish a written statement addressed to the OWNER, stating that the concrete shall be produced in accordance with these specifications and subject to the approval of the OWNER, and
- (5) concrete shall not be placed on the job after a period of 1½-hours after the cement has been placed in the mixer.

702.3.5.3. Continuous Volumetric Mix Concrete. For all miscellaneous concrete placements, a mobile, continuous, volumetric mixer of the rotating paddle type may be used when approved or specified by the OWNER.

These mixers shall be designed to receive all the concrete ingredients, including admixtures, required by the mix design in a continuous uniform rate and mix them to the required consistency before discharging. The mixers shall have adequate water supply and metering devices. Calibration of these mixers will be required.

The mixing time shall be in accordance with the recommendations of the manufacturer of the mixer unless otherwise revised by the Engineer.

For continuous volumetric mixers, the materials delivered during a revolution of the driving mechanism, or in a selected time interval, will be considered a batch, and the proportion of each ingredient will be calculated in the same manner as for a batch type plant.

702.4. MIX DESIGN AND MIXING LIGHTWEIGHT CONCRETE FOR STRUCTURES

702.4.1. Description. This item shall govern the equipment used; the storing, measuring and handling of materials; and for the mixing, placing, finishing and curing of lightweight concrete for bridges and other structures. The concrete shall be composed of Portland cement, natural sand fine aggregate, lightweight coarse aggregate, a cement dispersing agent, an air-entraining admixture and water, proportioned and mixed as hereinafter provided.

702.4.2. Quality of Concrete.

702.4.2.1. Consistency. Concrete shall be of such consistency so as to insure the required workability and result in compact masses having dense, uniform surfaces. The proportions of the ingredients shall be varied only with the approval of the OWNER. In general, the consistency of lightweight concrete should be similar to that of natural aggregate concrete. Batches which are harsh and unworkable shall be redesigned at the CONTRACTOR'S expense.

702.4.2.2. Classification and Proportions. Lightweight concrete shall be proportioned by weight in such manner as to secure a uniform and workable mix which shall produce cured concrete of the weight and strength specified herein. Prior to mixing any concrete which shall be used in the structure, the CONTRACTOR shall prepare trial batches, proportioned and tested in accordance with TxDOT Construction Bulletin C-11. Additional sand may be required to improve workability of the mix.

The cement content, maximum air content and slump of the various classes of concrete, shall conform to Table 702.4.2.(a) Classes of Lightweight Concrete. If the strength required for the class of concrete being produced is not secure with the minimum cement content specified, additional cement shall be used or other aggregates provided at the CONTRACTOR'S expense.

Table 702.4.2.(a) Classes of Lightweight Concrete

Class	Min. - Max. Bags Cement per C.Y.	Min. Comp. Strength 28-Day (psi)	Max. Slump (in.)	Air-Dried Weight Max. (lb./CF) ¹	Total Air Content, %	Use
X	5.5 - 7.5	3000	See note ²	110	6 – 9	General Structural
Y	5.5 - 7.0	5000	3	115	6 – 9	Prestressed Concrete
Z	5.5 - 8.0	As specified on plans	3	118	6 – 9	Prestressed Concrete

1. Air-dried weight shall be measured after 7-days moist curing at 100-percent relative humidity at 73°±2°F and stored for 21-days at 50±2-percent relative humidity.

2. Class X concrete shall be placed so that the average slump shall be maintained at approximately 3-in. No concrete shall be permitted with a slump in excess of 4-in.

702.4.2.3. Tests. During the progress of the work, the OWNER shall cast and test cylinders to maintain a check on the compressive strength of the concrete being placed.

For prestressed lightweight concrete, two tests (6-test cylinders) for each pertinent strength test required by Table 702.4.2.(a) Classes of Lightweight Concrete shall be required for each separate stressing line of beams, spans, piling, etc., as the case may be. Testing and curing of cylinders shall be in accordance with [Item 702.3.4.5. Tests](#). Job control cylinders may be tested on a hand operated compression machine. Equipment shall be furnished by the CONTRACTOR if required.

Air content shall be checked by use of a pressure type air meter in accordance with ASTM C231 Test Method for Air Content of Freshly Mixed Concrete by the Pressure Method.

Test for wet weight shall be made in accordance with ASTM C138 Test Method for Density (Unit Weight), Yield, and Air Content (Gravimetric) of Concrete.

The relationship between the air-dried weight of concrete and the wet weight of concrete shall be established by the OWNER, based upon trial batches and checks made during progress of the work.

For each change in batch design weight and for each 25-cubic-yards of concrete placed in the structure, two tests for weight shall be made. At any time that the average of these tests indicates a wet weight in excess of that which has been determined to produce air-dried concrete of the specified weight, the batch shall be adjusted to reduce the wet weight of concrete by the amount required.

702.4.3. Mixing. The following shall govern the mixing of lightweight concrete:

- (1) The cement dispersing agent and at least two-thirds of the total mixing water shall be introduced in the mixer and mixed for 15-seconds,

- (2) the fine and coarse aggregate shall be added and mixed for 45-second, and
- (3) the cement and final water shall be added and mixing completed. The minimum mixing time shall be determined by the OWNER for the concrete batch and the equipment used, but in no case shall the total mixing time be less than 3-minutes. Minimum mixing for concrete mixed in trucks shall be 100 revolutions of the drum.

The drum on truck mixers shall be operated at high speed while charging it with aggregate. Cement shall be introduced into the mixing drum while it is rotating at slow speed. Immediately prior to discharge of the concrete, the drum shall be rotated at high speed for 30-seconds.

702.5. CONSTRUCTING CONCRETE STRUCTURES

702.5.1. Submittals. Before starting work, the CONTRACTOR shall inform the OWNER fully of the methods of construction it proposes to follow and the amount and character of equipment it proposes to use, the adequacy of which shall be subject to the approval of the OWNER. Plans for forms and false-work for concrete piers and concrete superstructure spans over 20-ft. in length and for all widening details shall be submitted to the OWNER for review and approval. Similar plans shall be submitted for other units of the structure if required by the OWNER. The plans shall be prepared on standard 24-in. by 36-in. sheets or on mutually agreeable standard sheet sizes, such as, 11-in. by 17-in. sheets. Plans shall show all essential details of the proposed forms, false-work and bracing so that a structural analysis may be made. Six sets (or as directed by OWNER) of such plans, sealed by a Professional Engineer registered in the state of Texas shall be required.

Concurrence on the part of the OWNER in any proposed construction methods, approval of equipment or approval of form and false-work plans does not relieve the CONTRACTOR of the responsibility for the safety or correctness of its methods and adequacy of its equipment or from carrying out the work in full accordance with the contract.

702.5.2. Time Sequence. Unless otherwise provided, the following requirements shall govern for the time sequence in which construction operations may be carried on:

- (1) No superstructure members, forms, false-work or erection equipment shall be placed on the substructure before the substructure concrete has attained 75-percent design strength, as indicated by field-cured test specimens as approved by the OWNER.
- (2) The use of completed portions of a structure for storage of materials shall not be permitted until all curing requirements for the particular part of the structure have been met.
- (3) Forms for wall or columns shall not be erected on concrete footings until the concrete in the footing has cured at least 2-days. Concrete may be placed in the wall or column as soon as the forms and reinforcing steel placement are approved.
- (4) The support tie beam and/or cap forms by false-work placed on previously placed tie beams is permissible, provided such supporting beams have attained 75-percent design strength as indicated by field-cured test specimens as approved by the OWNER, curing requirements are completed, and the beams are properly supported to eliminate stresses not provided for in the design.

702.5.3. Drains. Weep hole drains and roadway drains shall be installed and constructed as shown on the plans in the designated locations. When the concrete is not formed at the weep hole location, a sheet of building paper shall be placed over the gravel to prevent the entrance of concrete into the pocket during operations.

702.5.4. Joints.

702.5.4.1. Expansion Joints. Expansion joints and devices to provide for expansion and contraction shall be constructed where indicated herein or on the plans.

The bearing area under the expansion ends of concrete slabs, prestressed concrete beams, girders and slab and girder spans shall be given a steel trowel finish. These areas shall be finished to the exact grades required. The material used in separate expansion surfaces shall be that shown on the plans and shall be placed carefully so that concrete or mortar cannot be subsequently worked around or under the material.

Immediately after the removal of forms and again when necessary after surface finishing, all projecting concrete shall be removed along exposed edges in order to secure full effectiveness of the expansion joints.

Refer to [Item 303.5.4.2](#), Expansion Joints for more information.

702.5.4.2. Construction Joints. The joint formed by placing plastic concrete in direct contact with concrete that has attained its initial set shall be deemed a construction joint. When concrete is to be placed monolithically, the term monolithic shall be interpreted to mean that the manner and sequence of concrete placing shall be such that construction joints shall not be created.

Construction joints shall be of the type and at the locations shown on the plans. Additional joints shall not be permitted without written authorization from the OWNER. Any additional construction joints shall have details equivalent to those shown on the plans for joints in similar locations.

Unless otherwise provided, construction joints shall be square and normal to the forms. Bulkheads shall be provided in the forms for all joints except horizontal joints.

Construction joints requiring the use of joint sealing material shall be as detailed on the plans. The material shall be specified on the plans without reference to joint type.

The top surface of a concrete placement which terminates at a horizontal construction joint shall have the surface roughened thoroughly as soon as practicable after the concrete has attained initial set. The surfaces at bulkheads shall be roughened as soon as the forms are removed.

Before joining plastic concrete to concrete that has already set, the surface of the concrete in place shall be free from all loose material, laitance, dirt or foreign matter; shall be washed, scrubbed clean and drenched thoroughly with water until saturated; and shall be kept moist until the plastic concrete has been placed. Immediately prior to the placing of additional concrete, all forms shall be drawn tight against the existing concrete and the existing joint surface shall be flushed with a coating of grout mixed in the proportions of one part of cement to two parts of sand.

Refer to [Item 303.5.4.4](#), Construction Joints for more information.

702.5.5. False-work. All false-work shall be designed and constructed to safely carry the maximum anticipated loads and to provide the necessary rigidity. Details of false-work construction shall be subject to review and approval by the OWNER in accordance with the provisions of [Item 702.5.6](#), Forms. When the false-work is no longer required, it shall be removed. False-work piling shall be pulled or cut off a minimum of 6-in. below finished ground level. False-work and piling in a stream or lake shall be removed completely to a point specified by the OWNER to prevent any obstruction to the waterway. Removal shall also be subject to the provisions of [Item 702.5.11](#), Removal of Forms and False-Work.

702.5.6. Forms.

702.5.6.1. General. Forming plans shall be submitted for approval. Forms shall be designed for the pressure exerted by a liquid weighing 150-lb-per-cubic-foot. The rate of placing the concrete shall be taken into consideration in determining the depth of the equivalent liquid. An additional live load of 50-lb-per-square-foot shall be allowed on horizontal surfaces. The maximum unit stresses shall not exceed 125-percent of the allowable stresses used by TxDOT for the design of structures.

Forms shall be of suitable material and of a type, size, shape, quality and strength to insure construction as designed. Wood products for use in forming concrete shall conform to ACI Standard SP-4 Formwork for Concrete. The forms shall be true to line and grade, mortar tight and sufficiently rigid to resist deflection during placing of the concrete. The responsibilities for adequacy shall rest with the CONTRACTOR. All dirt, chips, sawdust, nails and other foreign matter shall be completely removed from forms before any concrete is deposited therein. The surfaces of forms shall be smooth and free from irregularities, dents, sags and holes that would deface the finished surfaces. Forms previously used shall be thoroughly cleaned of all dirt, mortar and foreign matter before being reused. Before concrete is placed in forms, all inside surfaces of the forms shall be thoroughly treated with an approved releasing agent which shall leave no objectionable film on the surface of the forms that can be absorbed by the concrete. Care shall be exercised that no releasing agent is deposited on previously placed concrete, reinforcement or embedded metal items.

Forms for all surfaces that shall not be completely enclosed or hidden below the permanent surface of the ground shall be made of surfaced lumber or material which shall provide a surface at least equal to surfaced lumber or plywood. Any lumber or material which becomes badly checked or warped prior to placing concrete shall not be used.

Forms for all exposed surfaces of bridges, viaducts, over-crossings and similar structures shall be constructed of plywood or an approved equal. Plywood for forms shall be exterior type, of the grade "Concrete-Form Exterior," conforming to the specifications of the U.S. Department of Commerce, "National Bureau of Standards, Commercial Standards," latest edition. Plywood shall be furnished and placed in 48-in. widths and in uniform lengths of not less than 96-in., except where the dimension of the member formed is less than the specified panel dimension. Plywood shall be placed with the grain of the outer plies in the direction of the span. Where plywood is attached directly to the studs or joists, the panels shall not be less than $\frac{5}{8}$ -in. thick, and the studs or joists shall be spaced not more than 12-in. center to center. Plywood form panels otherwise conforming to the requirements specified herein may be used with a continuous backing of $\frac{3}{4}$ -in. sheeting. All form panels shall be placed in a neat, symmetrical pattern with the horizontal joints level and continuous. All joints shall be filled with an approved quick-setting compound and finished flush with the interior of the form.

Forms for round columns exposed to view shall be of steel, except that other materials shall be allowed with written permission of the OWNER.

Removal shall be accomplished according to the provisions of [Item 702.5.11](#). Removal of Forms and False-Work.

702.5.6.2. Molding. Molding specified for chamfer strips and other uses shall be made of redwood, cypress or white pine materials of such grade that it shall not split when nailed and which can be maintained to a true line without warping. The molding shall be mill-cut and dressed on all surfaces.

702.5.6.3. Form Ties and Spreaders. Metal form ties of an approved type or an approved substitute shall be used to hold forms in place. Pipe spreaders shall not be permitted. Metal and wooden spreaders which are separate from the forms shall be entirely removed as the concrete is being placed. All metal ties, wire or other appliances used inside the forms to hold them in correct alignment shall be removed to a depth of at least $\frac{1}{2}$ -in. from the surface of the concrete. Burning off of rods, bolts or ties shall not be permitted. The cavities produced shall be carefully cleaned and completely filled with retempered sand-cement mortar mixed in proportions of 1-to-3 and the concrete shall be left smooth and even.

702.5.6.4. Form Supports for Overhanging Slabs. Form supports which transmit a horizontal force to a steel girder or beam or to a prestressed concrete beam shall be permitted but shall not be used unless a structural analysis has been made of the effect on the girder or beam and approval is granted by the OWNER.

Holes in steel members for support of overhanging brackets may be punched or drilled full size or may be torch cut to $\frac{1}{4}$ -in. under size and reamed full size as provided for in [Item 703](#). Steel Structures. In no case shall the holes be burned full size. All such holes must be approved by the OWNER in writing prior to punching, drilling or burning. Holes shall be left open unless specified on the plans to be filled with a button head bolt. In no case shall the holes be filled by welding.

702.5.7. Placing Reinforcement. Reinforcement in concrete structures shall be placed carefully and accurately and rigidly supported as provided in [Item 303.5.3](#). Placing Reinforcing Steel, Tie, and Dowel Bars and as shown on the plans.

702.5.8. Placing Concrete.

702.5.8.1. General. The CONTRACTOR shall give the OWNER sufficient advance notice before starting to place concrete in any unit of the structure to permit the inspection of forms, the reinforcing steel placement and preparation for casting. No concrete shall be placed in any unit prior to the completion of the formwork, the placement of the reinforcement and approval by the OWNER. Concrete mixing, placing and finishing shall be done in daylight hours, unless adequate provisions are made to light the entire site of all operations.

The minimum temperature of all concrete at the time of placement shall be not less than 50°F. The maximum temperature of Class C, F, H, X, Y and Z or Class PC, PF, PH (as specified by the OWNER) cast-in-place concrete used in bridge superstructures shall not be more than 85°F at the time of placement. Concrete diaphragms, parapets, concrete portions of railings, curbs and sidewalks, unless monolithically placed with the slab, may not be subject to the preceding control if approved by the OWNER in writing. Other portions of structures, when so noted on the plans, shall require the temperature control specified thereon.

A retarding admixture shall be used when the continuous placing method is used in the deck of continuous units. The initial set of the concrete shall be retarded sufficiently to insure that the concrete remains plastic in not less than 3 spans immediately preceding the one being placed. For simple spans, retardation shall be required only if necessary to complete finishing operations or as required by [Item 303](#), Portland Cement Concrete Pavement. The retarding admixture shall be in accordance with the requirements of [Item 702.2.3](#), Concrete Additives and Modifiers.

The consistency of the concrete as placed should allow the completion of all finishing operations without the addition of water to the surface. When conditions are such that additional moisture is needed for finishing, the required water shall be applied to the surface by misting only and shall be held to a minimum amount.

The maximum time interval between the addition of cement or mixing water to the batch and the placing of concrete in the forms shall not exceed amounts shown in Table 702.5.8.1.(a) Interval Between Mixing and Placing Concrete.

Table 702.5.8.1.(a) Interval Between Mixing and Placing Concrete.

Type	Air or Concrete Temperature		Maximum Time ¹
	°F	°C	
Nonagitated Concrete			
	80°F or above	26.6°C or above	15 minutes
	38°F ² or 79°F	3.3° to 26.1°C	30 minutes
Agitated Concrete			
	90°F or above	32.2°C or above	45 minutes
	75°F to 89°F	23.9° to 31.6°C	60 minutes
	38°F ² to 74°F	3.3° to 23.3°C	90 minutes

1. The use of an approved cement dispersing agent in the concrete shall permit the extension of each of the temperature-time maximums by 30-minutes, except that for non-agitated concrete, the maximum time shall not exceed 30-minutes.
2. Minimum temperature is 38°F and rising.
3. The maximum temperature shall not be more than 85°F at the time of placement.

The sequence of placing concrete shall be as provided on the plans or in the specifications. The placing shall be so regulated that the pressures caused by the plastic concrete shall not exceed the loads used in the design of forms.

The method of handling, placing and consolidation of concrete shall minimize segregation or the displacement of the reinforcement and shall produce a compact mass of uniform texture. Concrete shall not have a free fall of more than 3-ft. except in the case of thin walls such as culvert walls. The spattering of forms or reinforcement bars shall be prevented if the concrete so spattered shall dry or harden before being incorporated into the mass.

Laitance or foreign matter of any kind shall not be permitted to accumulate inside the forms, and openings in forms necessary for removal of same shall be provided.

Any hardened concrete spatter ahead of the plastic concrete shall promptly be removed from the work.

Each part of the forms shall be filled by depositing concrete as near its final position as possible. The coarse aggregate shall be worked back from the face and concrete forced under and around the

reinforcement bars without displacing them. Depositing large quantities at one point in the forms and running or working it along the forms shall not be allowed.

After the concrete has taken initial set, the forms shall not be jarred or any strain placed on projecting reinforcement.

Chutes, troughs, conveyors or pipes used in placing concrete shall be arranged and used so that the ingredients of the concrete shall not be separated. When steep slopes are necessary, the chutes shall be equipped with baffle boards or made in short lengths that reverse the direction of movement, or the ends of such chutes shall terminate in vertical downspouts. Open troughs and chutes shall extend, if necessary, down inside the forms or through holes left in the forms. All chutes, troughs, conveyors and pipes shall be kept clean and free from coatings of hardened concrete by a thorough flushing with water before and after each placement. Water used for flushing shall be discharged clear of the concrete.

Concrete shall be deposited in the forms in layers of suitable depth but not more than 36-in. in thickness, unless otherwise directed by OWNER.

Holes for anchor bolts in piers, abutments, bents or pedestals may be drilled or may be formed by the insertion of oiled wooden plugs or metal sleeves in the plastic concrete. The plugs or sleeves shall be withdrawn after the concrete has set. Formed holes shall be of such diameter to permit horizontal adjustments of the bolts. The bolts shall be set carefully in mortar in lieu of the above methods of placing. Anchor bolts may be set to exact location in concrete when it is placed.

The placing of concrete for deck slabs shall be done from a mixing plant located off the structure. Carting or wheeling concrete batches over a completed slab shall not be permitted until the slab has reached its specified compressive strength. If carts are used, timber planking shall be required for the remainder of the curing period. Carts shall be equipped with pneumatic tires. Curing operations shall not be interrupted for the purpose of wheeling concrete over finished slabs.

702.5.8.2. Vibration. Successive layers or adjacent portions of concrete shall be placed in a sequence so that they can be vibrated into a homogeneous mass with the previously placed concrete without a cold joint. No more than one hour shall elapse between adjacent or successive placement of concrete. Unauthorized construction joints shall be avoided by placing required portions of abutments, piers, walls or superstructure in one continuous operation. For mass placements, placements on false-work where differential setting time may include stress cracking, placement in deep girder stems, etc., an approved retarder (cement dispersing agent) in accordance with [Item 702.2.3. Concrete Additives and Modifiers \(Chemical Admixtures\)](#) shall be used to control stress cracks and/or unauthorized cold joints.

All concrete shall be well consolidated and the mortar flushed to the surface of the forms by continuous working with mechanical vibrators of an approved type. Vibrators of the type which operate by attachment to forms or reinforcement shall not be permitted, except that external vibration may be allowed when the forms are of steel, but shall be subject to regulation by the OWNER.

At least one standby vibrator shall be provided for emergency use in addition to ones required for placement.

For lightweight concrete, vibrators of the high-frequency type, which produce a minimum of 7,000-impulses-per-minute, shall be required.

The vibrators shall be applied to the concrete immediately after deposit. Prior to the beginning of work, a systematic spacing of the points of vibration shall be established to insure complete consolidation of the concrete being placed and the thorough working of the concrete around the reinforcement, embedded fixtures and into the corners and angles of the forms. Immersion type vibrators shall be inserted vertically, at points 18-in. to 30-in. apart and slowly withdrawn.

For shallow slabs or for concrete inaccessible to vertical insertion of the vibrator, the vibrator may be inserted in a sloping horizontal position. The entire depth of each lift of concrete shall be vibrated, and the vibrator shall be allowed to penetrate several inches into the preceding lift of plastic concrete. New concrete placed against hardened concrete or against fresh concrete that is not plastic shall be thoroughly consolidated along the joint surface. The vibration shall be of sufficient duration to produce thorough consolidation and complete embedment of reinforcement and fixtures but shall not be done to an extent that shall cause segregation. Vibration may be supplemented by hand spading or rodding, if necessary, to insure the flushing of mortar to the surface of all forms.

702.5.8.3. Fogging. For Curing methods, see [Item 702.5.10.2.2. Water Curing](#).

702.5.8.4. Placing Concrete Under Adverse Weather Conditions. Concrete placement shall not be permitted when impending weather conditions may result in rainfall or low temperatures which shall impair the quality of the finished work. In case rainfall should occur after placing operations are started, the CONTRACTOR shall provide ample covering to protect the work. In case of a drop in temperature, the provisions set forth herein shall be applied.

Concrete for structures shall not be placed on frozen ground nor shall it be mixed or placed while the atmospheric temperature is below 40°F, unless adequate means are employed to heat the aggregates and water and satisfactory provisions have been made for protecting the work.

Concrete slabs shall not be placed on frozen ground, nor shall concrete be mixed or placed when the atmospheric temperature is below 40°F or when conditions indicate that the temperature may fall to 40°F within a 24 hour period, except with the written permission of the OWNER and only after such precautionary measures for the protection of the work have been taken as the OWNER may direct.

Concrete shall be effectively protected from freezing or frost for a period of 5 days after placing. When the temperature of the air is above 85°F, an approved retarding mixture shall be required in all concrete used in superstructures, top slabs of direct traffic culverts and cased drilled shafts.

Concrete placement shall be stopped when rainfall is sufficient to cause damage to the work.

702.5.8.5. Placing Concrete in Water. Concrete shall be deposited in water only when specified on the plans or with written permission of the OWNER. The forms, cofferdams or caissons shall be sufficiently tight to prevent any water current passing through the space in which the concrete is being deposited. Pumping shall not be permitted while the concrete is being placed, or until it has set for at least 36-hours.

The concrete shall be placed carefully in a compact mass by means of a tremie or other approved method that does not permit the concrete to fall through the water without adequate protection. The concrete shall not be disturbed after being deposited. Depositing shall be regulated to maintain approximately horizontal surfaces at all times.

When a tremie is used, it shall consist of a tube having a diameter of not more than 10-in., constructed in sections having watertight connections. The tremie shall be equipped with a device for sealing the bottom of the tube, the positive opening thereof and for the placing of the tremie through the water to the point of placement. The means of supporting the tremie shall permit the movement of the discharge over the entire surface of the work and shall permit the tremie to be lowered rapidly when necessary to choke off or retard the flow.

702.5.8.6. Placing Concrete in Superstructure. To insure operation and maintenance of grades and clearances, one or more passes of the screed shall be made over the section of bridge spans to be placed prior to the placement of concrete.

For transverse finishing, concrete in the superstructure shall be placed in transverse strips, beginning at the lowest end of the unit or length of spans to be placed and proceeding to the other end.

For longitudinal screeding, concrete shall be placed in longitudinal strips. Placing, preferably, shall be started at a point in the center of the section adjacent to one curb. The strip thus started shall be completed by depositing concrete uniformly in both directions toward the ends except that for spans on a grade of 1½-percent or more, the placing shall start at the lowest end. The width of strips shall be such that the concrete therein shall remain plastic until the adjacent strip is placed.

The forms for the bottom surface of concrete slabs, girders and overhangs shall be maintained true to the required vertical alignment during the concrete placing. For convenience in checking the vertical alignment, an approved system of "tell-tales" attached to the forms shall be installed and maintained by the CONTRACTOR. They shall provide a convenient means of match-marking with reference to points set on stakes or other suitable reference points set independently of the forms and false-work for the span being placed. Unless otherwise provided, the girders, slab and curbs of deck girder spans shall be placed in one continuous operation.

The filling of girder stems ahead of placing the concrete in the slab shall be permitted, provided the slab concrete is placed in the time as specified in [Item 702.5.8.1. General](#). The location of construction

joints and the sequence of placements of the slab on steel and prestressed concrete beams shall be as shown on the plans. Where plans do not specify a particular sequence, any logical placing sequence which shall not result in the over-stressing of any of the supporting members shall be permitted subject to the approval of the OWNER.

On steel truss spans the false-work under the span shall be released and the span swung free on its permanent supports before placing any concrete in the floor slab.

As soon as concrete is placed in a section of the slab of sufficient width to permit finishing operations, the slab shall be finished as specified in [Item 702.5.13](#). Finishing Exposed Surfaces. When the surface of the slab is to receive an additional wearing surface or level-up (widening), the slab shall be given a reasonably smooth float or screed finish and shall not be finished as stated above.

702.5.8.7. Placing Concrete in Box Culverts. In general, construction joints shall be permitted only at the points shown on the plans.

Where the top slabs and side-walls are placed monolithically in culverts more than 4-ft. in clear height, an interval of not less than 1-hour nor more than 2-hours shall elapse between the placing of the concrete in the walls and that in the top slab. Such interval is to allow for shrinkage in the wall concrete.

The top surface of the base slab shall be finished accurately at the proper time to provide a smooth uniform surface. The upper surface of the top slab which shall carry direct traffic shall be finished as specified for finishing roadway slabs in [Item 303.5.6](#). Finishing. On a fill-type culvert which does not carry direct traffic, the top slab shall be given a reasonably smooth finish.

702.5.8.8. Vaults. Vaults shall be provided as specified and/or detailed for access to manholes, gate valves, air release valves, etc.

702.5.8.8.1. Construction. Vaults may be of concrete, reinforced concrete, or precast reinforced concrete pipe as detailed in [Item 501.6](#). Reinforced Concrete Culvert, Storm Drain, Pipe and Box Section or as shown on the project plans. General construction shall include the following:

- (1) Vaults used for blow-off manhole applications shall be of water containment construction, utilizing either the monolithic pour-in-place concrete or precast reinforced concrete pipe with trapped O-ring gasket as further defined in [Item 501.6](#). Reinforced Concrete Culvert, Storm Drain, Pipe and Box Section.
- (2) Vaults used for non-water containment construction, such as for valve installations, shall be either pour-in-place 2500# reinforced concrete or precast reinforced concrete tongue-and-groove design pipe meeting ASTM C76 Reinforced Concrete Culvert, Storm Drain, and Sewer Pipe, Class III, using trapped O-ring type rubber seals.
- (3) Material requirements for vaults shall be as controlled under the material requirements of these specifications and the contract documents, as applicable, with specific inference placed on material specifications.

Walls. For in-place vaults, walls shall be formed on all sides to the thickness specified. Unless specified otherwise, walls shall not be less than 6-in. thick.

Top Slabs and Grade Adjustment. Top slabs shall normally be poured below final grade and grade rings used to achieve final grade ring elevations. Manhole grade rings, covers, vents, etc. shall be installed as detailed in [Item 502.1](#). Manholes, shown on project plans, or as directed by the OWNER.

Finish. The vault top slab invert and inside wall shall be given a rubbed finish in accordance with [Item 702.5.13](#). Finishing Exposed Surfaces.

702.5.8.8.2. Testing. Water-containment vault structures shall be tested for exfiltration as required in [Item 507.5.1.2](#). Exfiltration of this specification. In the event that leakage occurs in excess of allowable limits, the vault shall be completely sealed with an approved mastic sealer. Any visible seepage of free water shall require sealing on either water containment vaults or manholes.

702.5.8.8.3. Measurement and Payment for Vaults. Measurement and payment for vaults shall be as hereinafter defined, unless specified otherwise in the special contract documents.

Measurement for vault structures shall be on a per each basis complete in place with all accessories and shall include appurtenant work including excavation through backfill to provide for the structure complete in place as designed for the project. Each vault structure is to be complete in place with all system components to be housed as further outlined as follows:

- (1) Access Manhole Vault. Since the flanged access outlet and cover are usually furnished as a fitting for concrete cylinder pipe, the vault shall be the only item considered for payment under this bid item category in the proposal.
- (2) Air Valve or Combination Air and Vacuum Release Valve in Vault. Payment under this bid item category in the proposal shall include furnishing and installing the air valve or combination air and vacuum release valve, together with all subsidiary piping valves and other appurtenances complete in place as detailed as well as construction of the vault structure. The connecting taps on the main shall be included in the bid price for furnishing and installing fittings or shall be subsidiary to the price bid for furnishing and installing pipe, whichever is more applicable for a specified project.
- (3) Gate Valve in Vault. Payment under this bid item category in the proposal shall include the construction of the vault as well as furnishing and installing the gate valve complete in place on concrete blocking along with all appurtenances as detailed for complete and functional installation.
- (4) Blow-off and Vault. Payment under this bid item category in the proposal shall include the construction of a water containment vault structure as well as furnishing and installing piping (exclusive of the M.J. bell outlet on concrete mains or M.J. tee on cast iron mains), valves, blocking and other appurtenances as detailed with polyethylene wrapping.

702.5.8.9. Placing Concrete in Foundations and Substructure. Concrete shall not be placed in footings until the depth and character of the foundation has been inspected by the OWNER and permission has been given to proceed.

The placing of concrete bases above seal courses shall be permitted after the caissons or cofferdams are free from water and the seal course cleaned. Any necessary pumping or bailing during the concreting operations shall be done from a suitable sump located outside the forms.

All temporary wales or braces on the inside of cofferdams or caissons shall be constructed or adjusted as the work proceeds to prevent unauthorized construction joints in bases or shafts.

When footings can be placed in dry foundation pits without the use of cofferdams or caissons, forms may be omitted, if desired by the CONTRACTOR and approved by the OWNER, and the entire excavation filled with concrete to the elevation of the top of footing. Where this procedure is followed, no measurement for payment shall be made for concrete placed outside of the footing dimensions shown on the plans.

Concrete in columns shall be placed monolithically unless otherwise provided. Columns and caps and/or tie beams supported thereon may be placed in the same operation. To allow for shrinkage of the column concrete, it shall be placed to the lower level of the cap or each tie beam and placement delayed for not less than 1-hour nor more than 2-hours before proceeding.

702.5.9. Finishing Concrete. All upper horizontal surfaces not covered by forms shall be struck off to grade and finished. The use of mortar topping for surfaces under this classification shall not be permitted.

After concrete has been struck off as described above, the surface shall be floated with a suitable float. Bridge sidewalks shall be given a wood float or broom finish or may be striped with a brush, as specified by the OWNER. Unless otherwise specified, top of caps and piers shall be given a smooth finish with a steel trowel. Other surfaces shall be wood float finished and striped with a fine brush leaving a fine-grained texture.

702.5.10. Curing Concrete. Careful attention shall be given to the proper curing of all concrete. CONTRACTOR shall inform OWNER fully of the methods and procedures proposed for curing, shall provide proper equipment and material in adequate amounts, and shall have approval of the proposed method, equipment and material prior to placing concrete.

Inadequate curing facilities or lack of attention to the proper curing of concrete shall be cause for OWNER to stop all construction on the job until approved curing is provided.

702.5.10.1. Curing Period. All concrete shall be cured for a period of time noted in Table 702.5.10.1.(a) Curing Period, unless otherwise specified by the OWNER. In continuous placement of concrete, the required curing period shall begin when all concrete has been placed and has attained its initial set.

Table 702.5.10.1.(a) Curing Period

Concrete Structure	Curing Days ^{1,2}
Top Slabs of Direct Traffic Culverts	8-days
Other Structures	4-days

1. A curing day is defined as a day when the ambient temperature, taken in the shade away from artificial heat, is above 50°F for at least 19-hours, or the ambient temperature is 50°F or less; and if satisfactory provisions are made to maintain the temperature at all surfaces of the concrete above 40°F for the entire 24-hours.
2. In addition, concrete must meet 75-percent of the minimum compressive strength requirements.

702.5.10.2. Curing Methods. The following methods are permitted for curing concrete subject to the restrictions of Table 702.5.10.2.(a) Curing Methods, and the requirements of this specification for each method of curing.

Table 702.5.10.2.(a) Curing Methods

Structure Unit Description		REQUIRED		PERMITTED	
		Water for Complete Curing	Membrane for Interim Curing	Water for Complete Curing	Membrane for Interim Curing
1.	Top slabs of direct traffic culverts, top surface of any concrete unit upon which concrete is to be placed and bonded at a later interval (stub walls, risers, etc.). Other superstructure concrete (wing-walls, parapet walls, etc.).	X			
2.	Top surface of precast and/or prestressed piling	X	X		
3.	All substructure concrete, culverts, box sewers, inlets, manholes, retainer walls, riprap.			X ¹	X ¹

1. Polyethylene sheeting or burlap polyethylene mats fastened to prevent outside air from entering shall be considered equivalent to water or membrane curing per this item.

702.5.10.2.1. Form Curing. When forms are left in contact with the concrete, other curing methods shall not be required except for cold weather protection.

702.5.10.2.2. Water Curing. All exposed surfaces of the concrete shall be kept wet continuously for the required curing time. The water used for curing shall meet requirements for concrete mixing water as specified in [Item 303](#), Portland Cement Concrete Pavement.

Wet Mat. Cotton mats shall be used for this curing method. The mats shall not be placed in contact with the concrete until such time that damage shall not occur to the surfaces. Damp burlap blankets made from 9-oz. stock may be placed on the damp concrete surface for temporary protection prior to the application of the cotton mats. The mats may be placed dry and wetted down after placement. Mat curing, except for continuous placements, shall commence not later than 3-hours after finishing the roadway slab. The mats shall be weighted down adequately to provide continuous contact with all concrete surfaces where possible. The surfaces of the concrete shall be kept wet for the required curing time. Surfaces which cannot be cured by contact shall be enclosed

with mats, anchored positively to the forms or to the ground, so that outside air cannot enter the enclosure to keep all surfaces of the concrete wet.

Water Spray. This method shall be accomplished by overlapping sprays or sprinklers, so that all unformed surfaces are kept continuously wet.

Ponding. This method requires the covering of the surfaces with a minimum of 2-in. of clean granular material, kept wet at all times, or water to a minimum depth of 1-in. Satisfactory provisions shall be made to provide a dam to retain the granular material or water.

Fogging. All the unformed surfaces of slab concrete for bridge decks and the top slab of direct traffic culverts shall be protected against rapid surface drying by the use of fog sprays. Fog sprays, powered by pressure pumps and capable of covering the entire area of freshly placed concrete with a fine mist, shall be installed, ready for use prior to the start of placing operations.

On individual placements of 15-cubic-yards or less, hand operated spray nozzle equipment of the stirrup pump type may be substituted for the equipment specified above.

Fogging shall be carefully controlled to prevent accumulation of standing or flowing water on the surface of the fresh concrete. Fogging shall continue, as required, through the finishing operations and shall be used as interim curing until the selected curing medium is in place, except that in lieu of continuous fogging over the entire area, that portion of the finished concrete surface which is sufficiently hardened may be covered with wet burlap. The burlap shall be kept wet until the final curing media is in place.

702.5.10.2.3. Membrane Curing. Membrane curing shall not be applied to dry surfaces but shall be applied to horizontal surfaces just before free moisture has disappeared. Formed surfaces and surfaces which have been given a first rub shall be dampened and shall be moist at the time of application of the membrane. Unless otherwise shown on the plans, Type 2 membrane curing compound in accordance with [Item 303.2.13](#). Curing Materials may be used where permitted. Membrane shall be applied in a single, uniform coating at the rate of coverage recommended by the manufacturer and as approved by the OWNER. Tests for acceptance shall be at the specified rate of application.

When membrane is used for complete curing, the film shall remain unbroken for the minimum curing period specified. Membrane which is damaged shall be corrected immediately by re-application of membrane.

702.5.11. Removal of Forms and False-Work. Except as herein provided, forms for vertical surfaces may be removed when the concrete has aged not less than 1 curing day. A curing day is defined as a day when the ambient temperature, taken in the shade away from artificial heat, is above 50°F for at least 19-hours, or the ambient temperature is 50°F or less; and if satisfactory provisions are made to maintain the temperature at all surfaces of the concrete above 40°F for the entire 24-hours.

Weight supporting forms and false-work for all bridge components, culverts and slabs shall remain in place a minimum of 4-curing-days. Forms may then be removed if the concrete has attained 75-percent of design strength, as evidenced by strength tests using test specimens made from the same concrete and cured under the same conditions as the portion of the structure involved. Forms for other structural components may be removed as specified by OWNER. If all test specimens made for the purpose of form removal have been tested without attaining the required strength, forms shall remain in place for a total of 14-curing-days.

The above provisions relative to form removal shall apply only to forms or parts of forms which are so constructed as to permit removal without disturbing forms or false-work which are required to be left in place for a longer period on other portions of the structures.

702.5.12. Defective Work. Any defective work discovered after the forms have been removed shall be repaired or replaced as soon as possible. If the surface of the concrete is bulged, uneven or shows excess honeycombing or form marks which in the opinion of the OWNER cannot be repaired satisfactorily, the entire section shall be removed and replaced. In repairing honeycombed areas, all loose material shall be removed before the repair work is started. No extra compensation shall be allowed for extra work or materials involved in repairing or replacing defective concrete.

702.5.13. Finishing Exposed Surfaces. The type of surface finish shall be one of the types described herein and as designated on the plans. Where the plans do not specify the type of finish, a Type 1 Finish shall be required.

702.5.13.1. Type 1 Finish. The following areas shall require lined forms and shall receive a first and second rubbing:

- (1) The top, exterior and roadway faces of curbs; all concrete surfaces of railing, including the parapet types; the exterior vertical faces of slab spans, rigid frames, arches and box girders; the outside and bottom surfaces of fascia beams or girders (precast prestressed concrete beams excluded); the underside of overhanging slabs to the point of juncture of the supporting beam; all vertical surfaces of piers, columns, bent caps, (including the bottom sloped portions only of variable depth caps), abutments, wing-walls and retaining walls, which are exposed to view after all backfill and embankment are placed.
- (2) On slab spans and rigid frame structures, the underside of the slab shall be finished for a width of 2-feet in from the outer edge, but lined forms shall be required for the entire bottom surfaces.
- (3) For rigid frame structures, finishing shall be required on the inside sloping and vertical surfaces.
- (4) Culvert headwalls and wing-walls, inlets, manholes and sewer appurtenances shall receive a first rubbing only.

No rubbing shall be required on any area inside culvert barrels. Horizontal surfaces of bridge sidewalk slabs shall be finished in accordance with [Item 303.5.6](#). Finishing.

702.5.13.2. Type 2 Finish. All concrete surfaces of railing, including the parapet types, the top and roadway faces only of curbs, and wing-walls of bridges shall be given a first and second rubbing. All other surfaces described under Type 1 Finish shall be given a first rubbing only. Lining of forms shall be as required in a Type 1 Finish.

702.5.13.3. Type 3 Finish. All concrete surfaces of railing, including the parapet types, the top and roadway faces only of curbs, and wing-walls of bridges shall be given a first and second rubbing. All other surfaces described under Type 1 Finish shall not require rubbing but shall require lining of forms.

702.5.13.4. Type 4 Finish. All concrete surfaces of railing, including the parapet types, the top and roadway faces of curbs, and wing-walls of bridges and culverts shall be given a first rubbing only. Form lining shall not be required. Rubbing of culvert wing-walls shall not be required, provided lined forms are used.

702.5.13.5. Surface Finishing Methods. The first rubbing shall be done immediately upon removal of the forms. Membrane curing, if used, shall be applied after the first rub has been completed. Prior to the second rubbing, any remaining curing membrane shall be removed from the surface by brushing, buffing or other satisfactory methods. Removal of the membrane shall not be required except when a second rubbing is required.

After all repair work and pointing has set sufficiently, rubbing shall be performed as follows:

- (1) All surfaces to be finished shall be wet and given a first rubbing with a carborundum stone. The rubbing shall bring the surface to a paste and produce a smooth dense surface without pits, form marks or other irregularities. The use of cement to form a paste shall not be permitted.
- (2) Where a single rubbing is specified, the paste shall be spread uniformly, striped with a brush and allowed to take a reset, after which the surfaces shall be washed with clean water, leaving them with a neat and uniform appearance and texture. Chamfered corners shall also be rubbed.
- (3) When a second rubbing is required, striping with a brush and washing after the first rubbing shall not be required. Chambered corners generally should not be rubbed in the first rubbing.
- (4) The second rubbing shall be performed during the process of conditioning the structure for final acceptance. The surfaces requiring finish shall be cleaned of drip marks and discolorations and shall be given a final rubbing with a carborundum stone. The surface shall be striped neatly with a brush, and the mortar shall be allowed to take a reset, after which the surfaces shall be washed with clean water, leaving them with a neat and uniform appearance and texture.

Surfaces other than those specified herein shall not require rubbing unless they are not true or have porous or honeycombed areas which are not designated for replacement. When such defects occur,

the areas affected shall be given a first rubbing, which shall extend over a sufficient area to blend it into the surrounding unfinished surface. This shall not be construed to require the rubbing of large adjacent unblemished areas to gain absolute uniformity of color and texture on the structure part in question. All surfaces shall be free of discolorations and should present a uniform appearance. Unsightly discoloration shall be removed prior to acceptance.

702.5.13.6. Painting in Lieu of Rubbing. When so indicated on the plans, or with written permission of the OWNER, painting of concrete surfaces in lieu of rubbing shall be permitted. When painting is permitted, it shall be accomplished as follows or as according to the OWNER:

- (1) Soon after form removal, any porous spots, honeycombed areas, untrue surfaces and lines shall be corrected. All fins, form marks, runs, drips or mortar shall be removed, leaving a smooth and uniform surface.
- (2) When preparing the completed structure for final acceptance, all grease, dirt, mortar drips and remaining curing membrane shall be removed from the pertinent surfaces.
- (3) Surfaces shall be painted with a latex-base adhesive grout. The grout shall consist of one part latex-base adhesive, two parts white cement, two parts natural cement, two parts fine masonry sand and one part water. Mixture should have the consistency of a thick paint.
- (4) The finished surface shall have a uniform appearance and texture. Thickness of coating shall be approximately $\frac{1}{16}$ -in. to $\frac{1}{8}$ -in.

702.5.14. Measurement and Payment. The quantity of concrete which constitutes the completed structure shall be measured by the cubic yard of accepted work in place. The dimensions used shall be those shown on the plans or ordered in writing by the OWNER. No deductions in measurement shall be made for embedded reinforcing steel or for embedded portions of structural steel members.

The concrete quantities, measured as provided, shall be paid for at the unit price bid per cubic yard for concrete, which price shall be full compensation for furnishing, hauling and mixing all concrete materials, including trial batches; placing, curing and finishing all concrete; all grouting and joints; furnishing and placing all expansion and construction joints, except as hereinafter provided; furnishing and placing metal flashing strips and waterstops; and all forms and false-work, labor, tools, equipment and incidentals necessary to complete the work.

The above provision for payment for expansion joints shall not be interpreted to provide payment for cast steel or structural steel shapes and plates, used expansion joints and armored joints, or for structural steel, cast iron or cast bearing plates. Payment for these materials shall be as provided for in [Item 806](#). Metal Materials.

The preceding provisions for payment shall not be interpreted to provide payment for concrete in railing, piling, precast prestressed concrete units or other concrete items for which provision is otherwise made in these specifications or in the contract documents.

702.6. PRESTRESSED CONCRETE FOR STRUCTURES

702.6.1. Description. This item shall govern the complete construction, furnishing, storing, handling and erection of precast prestressed concrete structures, in accordance with the plans, with the exception of piling, which shall be in accordance with [Item 704.1.2](#). Concrete Piling. For additional information, refer to TxDOT Specifications and OWNER-provided specifications.

702.6.2. General. The method of construction and of prestressing shall be as shown on the project plans and on the approved shop drawings. Prior to beginning the casting of prestressed members, the CONTRACTOR shall give the OWNER notice.

702.6.3. Materials. Materials for concrete shall be in accordance with [Item 702.2](#). Concrete Structure Materials, and [Item 702.3](#). Mix Design and Mixing Concrete for Structures. Reinforcing steel, not prestressed, shall conform to the requirements of [Item 303.2.9](#). Steel Reinforcement. Structural steel bearing plates, fittings, etc. shall be in accordance with [Item 806](#). Metal Materials. Bearing pads shall be in accordance with TxDOT Item 435. Elastomeric Materials and with special specifications contained in the Contract.

702.6.4. Handling and Erection. Fabrication and erection plans shall indicate the method of handling and erecting prestressed members. An adequate factor of safety shall be included in all calculations for handling and erection to preclude over-stressing any part of the member due to dynamic forces or impact.

Prestressed concrete beams shall be maintained in an upright position at all times and shall be picked up and supported near the end of the beams only and in such a way as to prevent torsional stress in the beam. Beams may be lifted with the lifting devices as approved on the shop plans or by other methods approved by the OWNER in writing.

No prestressed concrete structural member shall be moved from the casting yard until all requirements for tensioning, curing and strength have been attained. The strength of a prestressed member shall be considered adequate after curing and tensioning requirements are fulfilled if the design strength compressive cylinders indicate that the required design strength has been attained.

702.6.5. Defects and Breakage. If any prestressing tendon or portion thereof is broken prior to placing concrete in the member, it shall be replaced with a satisfactory unit properly prestressed at no cost to the OWNER. The breaking of one wire of a 7-wire strand in a unit during concrete placing operations shall be subject to a structural review prior to acceptance.

Fine hair cracks or checks on the surface of the member which, as determined by the OWNER, do not extend to the plane of the nearest reinforcement, shall not be cause for rejection unless such cracks are so numerous and extensive as to indicate inadequate curing, in which case the members shall be rejected. Diagonal cracks on the vertical surfaces which indicate damage from torsion shall be subject to a structural review prior to acceptance or rejection by the OWNER. Vertical and horizontal cracks which are $\frac{1}{16}$ -in. or less in width and which tend to close upon release of stress are acceptable. Cracks in excess of this are subject to review prior to acceptance or rejection by the OWNER. Cracks which extend into the plane of reinforcing steel and/or prestressed tendons and are acceptable otherwise shall be repaired by sealing with a latex-base adhesive grout or with epoxy.

All replacements as herein specified as well as all other replacements due to faulty materials or construction methods shall be made at the CONTRACTOR'S expense.

702.6.6. Workmanship and Tolerance. Variations greater than specified shall be cause for rejection.

702.6.6.1. Prestressed Beams, Girders, Spans and Box Type Beams. Requirements shall include the following:

- (1) variation from shop plan lengths: plus or minus 1-in.
- (2) variation from plan height, box type beams: plus or minus $\frac{1}{4}$ -in. Others: plus or minus $\frac{1}{2}$ -in. maximum deviation of $\frac{1}{4}$ -in. per 10-ft. of length. Box-type beams $\frac{3}{4}$ -in total deviation.
- (3) out-of-square (vertical or horizontal) or deviation from plane skew angle: maximum $\frac{1}{8}$ -in.-per-ft. of dimension.
- (4) bearings. Requirements include:
 - (a) out-of-perpendicular with vertical axis: maximum $\frac{1}{16}$ -in.
 - (b) honeycomb in bottom soffit of beams at the bearing shall not exceed 15-percent of the bearing area (width x length). No tendon shall be exposed and the maximum depth of honeycomb shall not exceed 1-in. Honeycomb shall be chipped out to sound concrete and repaired satisfactorily prior to acceptance.
- (5) form fit-up. Where sections of forms are to be butt-jointed, an offset of $\frac{1}{16}$ -in. for flat surfaces and $\frac{1}{8}$ -in. for corners and bends shall be permitted.

702.6.6.2. Repair. Small areas of honeycomb which are purely surface in nature (not over 1-in.) may be repaired. Honeycomb extending to the plane of the prestressed strands shall be rejected tentatively, subject to structural review prior to acceptance or rejection by the OWNER.

702.6.6.3. Steel. Reinforcing steel shall not project above the top of the member more than $\frac{1}{2}$ -in. nor less than $\frac{3}{4}$ -in. from plan dimension. In the plane of the steel parallel to the nearest surface of concrete, bars shall not vary from plan placement by more than $\frac{1}{4}$ -in. or $\frac{1}{12}$ of the spacing between bars, whichever is greater. In the plane of the steel perpendicular to the nearest surface of the concrete, bars shall not vary from plan placement by more than $\frac{1}{4}$ -in.

702.6.7. Measurement and Payment.

702.6.7.1. Measurement. Precast, prestressed concrete beams or girders of the type specified, cast and stressed, as required on the plans, shall be measured by the linear foot complete in place.

Precast, prestressed concrete spans of the size and type specified, cast and stressed, as required by the plans, shall be measured as each prestressed span, complete in place.

Other precast, prestressed members of the type and size specified, cast and stressed, as required by the plans, may be measured by the linear foot or by each member as the case may be and as noted on the plans.

Cast-in-place structures (or structures where the CONTRACTOR has the option of casting-in-place) shall be measured as follows:

- (1) concrete, non-prestressed reinforcing steel and structural steel (except bearing and anchorage devices integrally a part of the post-tensioning system) shall be measured by the cubic yard or by the pound in accordance with the applicable specifications for these items. Grout and ducts for post-tensioning shall not be measured but shall be considered subsidiary to this item.
- (2) the prestressing steel required and the work involved in the prestressing of the cast-in-place structures or units shall not be measured but shall be considered as one unit for “prestressing” each different structure type or unit as itemized on the plans and in the proposal.

702.6.7.2. Payment. Precast, prestressed concrete beams or girders shall be paid for at the unit price bid per linear foot (m) for “prestressed concrete beams” of the type specified.

Precast, prestressed concrete spans shall be paid for at the unit price bid for each “prestressed concrete span.”

Other prestressed concrete members shall be paid for at the unit price bid per linear foot for “prestressed concrete members” (specify name and type) as the case may be.

A partial allowance shall be made for materials and for precast or prestressed concrete members cast, but not erected.

The above prices shall be full compensation for constructing the member; furnishing and tensioning prestressed steel; furnishing and placing reinforcing steel, conduit and attached bearing plates, etc. for same; grouting holes; and for all bars, anchorage plates, and other appurtenances which become an integral part of the precast structure and for any special treatment of end anchorages and shoes as indicated on the plans; and for furnishing all materials, tools, equipment, labor and incidentals necessary to fabricate, transport and erect the members in the structure as indicated on the plans. The cost of all materials used in the test specimens and the cost of providing and maintaining curing facilities shall be included in the unit price bid for the various prestressed concrete members.

702.7. PNEUMATICALLY PLACED CONCRETE (GUNITE)

702.7.1. Description. Pneumatically placed concrete shall consist of premixed sand and Portland cement pneumatically transported through a pipe or hose in a dry state to a nozzle where hydration takes place immediately prior to expulsion. For additional information, refer to TxDOT Specifications and OWNER-provided specifications.

702.7.2. Materials. The concrete shall conform to the requirements of [Item 702.2](#). Concrete Structure Materials. Bar reinforcement and wire fabric reinforcement shall conform to the requirements of [Item 303.2.9](#). Steel Reinforcement. Expansion joints shall conform to the relevant requirements [Item 303](#). Portland Cement Concrete Pavement.

Steel drive pins or studs used for the attachment of reinforcing when covering designed portions of concrete structures with pneumatically placed concrete shall be capable of being driven to the specified depth without deforming or otherwise becoming unsuitable for the purpose intended. The pins shall have a minimum diameter of 1/8-in. and a minimum length of 2-in. Size and location of drive pins or studs and method of attachment of reinforcing shall be as specified herein or as detailed on the plans.

702.7.3. Equipment and Workers. The gun mechanism should be operated at a minimum air pressure of 45-psi on the gun tank when 100-ft. or less of material hose is used and the pressure should be increased 5-psi for each additional 50-ft. of hose required. Nozzles used for guniting shall have a maximum size of 1½-

in. unless otherwise permitted by the OWNER. Water used for hydration shall be maintained at a uniform pressure, which shall be at least 15-psi above air pressure at the gun.

The equipment used for driving the pins or studs shall be of the type which uses an explosive for the driving force and shall be capable of inserting the stud or pin to the required depth without damage to the concrete. The OWNER may require that a test be made of equipment prior to approving it for use.

Only experienced foremen, gunmen, nozzlemen, and rodmen shall be employed, and satisfactory written evidence of such experience shall be furnished to the OWNER or its representative upon demand.

702.7.4. Proportions, Mixing, and Testing. Unless otherwise specified, the concrete shall consist of a mixture of cement and sand in the proportions by volume of 1 part of cement to 4½ parts of sand.

The sand shall contain not less than 3-percent nor more than 6-percent moisture by weight. The sand and cement shall be mixed thoroughly in a power mixer for at least 1½-minutes before placement in the chamber of the gun mechanism. The dry mixed material shall be used promptly after mixing. Any material that has been mixed for more than 45-minutes shall be rejected and removed from the worksite.

The use of approved admixtures conforming to the requirements of [Item 702.2.3](#). Concrete Additives and Modifiers shall be permitted at the option of the CONTRACTOR.

The mixer shall be cleaned at regular intervals to remove all adherent material from the mixing vanes and from the drum.

At the beginning of work the OWNER may require that cylinders be made to represent the quality of the pneumatically placed concrete. Additional cylinders shall be made during performance of the work as directed by the OWNER. If in the opinion of the OWNER, the cylinder strengths are indicating undesirable variation in the concrete, the CONTRACTOR may be required to change the mix design and/or method of placing so as to correct this condition. The CONTRACTOR shall furnish specially constructed cylinders 6-in. in diameter and 12-in. high, made of ¾-in square mesh hardware cloth. Test cylinders for pneumatically placed concrete shall be shot with the same air pressure and nozzle tip as the pneumatically placed concrete. At the end of the first 24-hour curing period, the hardware cloth form shall be removed and the cylinders stored and cured as directed by the OWNER.

702.7.5. Construction Methods. Concrete shall not be applied to a surface containing frost or ice. Where standing or running water is encountered, it shall be removed before applying the concrete. No work shall be done without the permission of the OWNER when the temperature is lower than 40°F. After placing, the concrete shall be protected from freezing or quick drying.

702.7.5.1. Placement. Earth surfaces to which concrete is to be applied shall be neatly trimmed to line and grade and shall be free of all loose material. The surface need not be compacted by slope rolling or other measure unless required by the plans or specifications.

No high subgrade shall be permitted. Excavation made below subgrade shall be backfilled with compacted fill or, at the CONTRACTOR'S option, with concrete. However, no additional compensation shall be allowed for such compacted fill nor for increased thickness of concrete placed because of low subgrade.

Asphaltic concrete surfaces shall be thoroughly cleaned of any organic material, silt and clay, or any other material detrimental to the concrete and then washed with water under pressure. Masonry, rock and concrete surfaces shall be examined and all loose material removed therefrom. The surface shall be thoroughly cleaned with steel scrapers or brushes to remove all dust, dirt, mortar, grease or other deleterious substances and then washed with water. Whenever brushing and scraping do not secure suitable results, sandblasting may be required.

All surfaces shall be wetted with water before application of concrete. Concrete shall not be applied to surfaces on which free water exists.

The velocity of the material as it leaves the nozzle shall be maintained uniformly at a rate determined for given job conditions. Material which rebounds and does not fall clear of the work, or which collects on the surfaces, shall be blown off or otherwise removed. Rebound shall not be used in any portion of the work, and no payment shall be made for rebound or other concrete losses.

The nozzle shall be held at such distance and position that the stream of flowing material shall impinge at approximately right angles to the surface being covered. Any portion of the placed concrete

which tends to sag or which shows soft or sandy pockets or is otherwise unsatisfactory shall be cut out and replaced with new concrete. Reinforcement damaged or destroyed by such repairs shall be replaced by trimming the concrete back and properly lapping and tying additional steel as may be required by the OWNER.

Reinforcement shall be firmly supported in the position shown on the plans. Mortar blocks, metal chairs, clips or spacers with wire ties or other acceptable means shall be used to anchor and place the reinforcement properly.

Where material is placed on overhead surfaces, the amount of water used shall be so adjusted that approximately $\frac{3}{4}$ -in. of the placed material shall adhere without support. The limit of thickness shall be considered to have been exceeded when the material begins to sag or slough.

702.7.5.2. Forms and Ground Wires. The forms shall be built in accordance with applicable provisions of the specifications, except all forms shall be built so as to permit the escape of air and rebound.

Ground wires shall be installed in such a manner that they accurately outline the finished surfaces as indicated on the plans. They shall be located at intervals sufficient to insure proper thickness throughout. Wire shall be stretched tight and shall not be removed prior to application of the finish coat.

Headers shall be required where the plans indicate a formed edge and at plane joints.

702.7.5.3. Joints. Construction joints shall be sloped off at an angle of approximately 45° to the surface to which the concrete is being applied. Before applying concrete in the adjacent sections, the sloped portion shall be thoroughly cleaned and wetted by means of air and water blast.

The plane joints shall be formed in accordance with and placed in the locations designated on the plans.

702.7.5.4. Finish. Upon reaching the thickness and shape outlined by forms and ground wire, the surface shall be rodded off to true lines. Any low spots or depressions shall be brought up to proper grade by placing additional concrete. Ground wires shall then be removed. Unless otherwise specified, the surface shall then be broom finished to secure a uniform surface texture. Rodding and working with a wood float shall be held to a minimum.

Rebound or accumulated loose sand shall be thoroughly cleaned up and disposed of by the CONTRACTOR. In no case shall they be floated into the surface of the work.

When a nozzle finish is specified on the plans, ground wires shall not be used, and the surface shall be left as uniform as possible without rodding. Nozzle finish shall not be permitted where the underlay has been floated.

702.7.5.5. Curing. Pneumatically placed concrete shall be cured in accordance with [Item 702.5.10.2. Curing Methods](#).

702.7.6. Measurement and Payment. Measurement for pneumatically placed concrete shall be made by the square foot in place. For encasement of structural steel members and covering portions of structures, the actual contact area shall be the basis for measurement.

Pneumatically placed concrete, measured as provided in this item, shall be paid for at the unit price bid per square-foot for “pneumatically placed concrete” of the type specified. The unit price bid per square-foot shall be full compensation for all cement, sand, water, reinforcement, furnishing and driving all steel drive pins, mixing and placing pneumatically placed concrete, and for all labor, tools, equipment and incidentals necessary to complete the work. Excavation for channel and canal lining shall be paid for in accordance with [Item 203.2. Unclassified Excavation](#). Shaping and fine grading of channel or canal slopes and floors are not to be paid for directly but shall be included in the unit price bid for “pneumatically placed concrete.” When header-banks upon which “pneumatically placed concrete” is to be placed have been built by prior contract, excavation for shaping of slopes shall be paid for in accordance with [Item 701.2. Structural Removal, Excavation, and Backfill](#).

702.8. DRILLED SHAFT FOUNDATIONS

702.8.1. Description. This item shall govern the construction of foundations consisting of reinforced concrete shafts with or without bell type concrete footings. Such foundations shall be constructed in

accordance with this item and in conformance with the details and governing dimensions shown on the plans.

702.8.2. Materials. All concrete materials and their preparations shall be in accordance with the requirements of [Item 702.2](#), Concrete Structure Materials, [Item 702.3](#), Mix Design and Mixing Concrete for Structures, and the additional requirements herein. All concrete shall be Class A or Class PA, as specified by the OWNER, unless otherwise shown on the plans.

When casing of the shaft is required, the following shall apply:

- (1) The maximum size coarse aggregate shall be 1½-in.
- (2) The elapsed time from beginning of placement of concrete in the cased portion of the shaft until extraction of the casing is begun shall not exceed 30 minutes. If a cement dispersing agent is used, this time shall not exceed one hour. If non-agitating equipment is used to haul the concrete from a central mixing plant, the elapsed time for discharge of concrete from the mixer to placement in the shaft shall not exceed 10-minutes. If a cement dispersing agent is used, this time shall not exceed 30-minutes.
- (3) When the temperature of the air or concrete is above 85°F., an approved cement reactive polymeric dispersant shall be required in all drilled shaft concrete. Reinforcing steel shall conform to the requirements of [Item 303.2.9](#), Steel Reinforcement.

702.8.3. Construction Methods.

702.8.3.1. Excavation. The CONTRACTOR shall do all excavation required for the shafts and bell footings, through whatever materials are encountered, and to the dimensions and elevations shown on the plans or required by the site conditions. Unless otherwise shown on the plans, all shafts shall be bored to plumb to a tolerance of 1-in. for depths up to and including 10-ft. For shafts over 10-ft., tolerance will be approved by OWNER. Shafts and bells shall be excavated so as to form a bearing area of the size and shape shown on the plans. Blasting methods shall not be used without prior written approval of the OWNER. If blasting methods are approved, methods shall conform to [Item 203.2.7](#), Alternate Methods of Excavation.

The plans indicate the expected depths and elevations at which satisfactory bearing material shall be encountered; this information shall be used as a basis for the contract. If satisfactory foundation materials are not encountered at plan elevations, the footings may be raised or lowered as determined by the OWNER. Alterations in plan depths shall be made as judged proper to satisfactorily comply with the design requirements.

Casings shall be required for shaft excavations when such provision is necessary to prevent caving of the material or when necessary to shut off seepage water. Casings shall be of ample strength to withstand handling stresses, along with the pressure of concrete and of the surrounding earth or backfill materials, and shall be watertight. The inside diameter of the casing shall not be less than the normal size of the shaft. No extra compensation shall be allowed for the concrete required to fill an oversize casing or oversize excavation.

When the drilling operation reaches a point where caving condition and/or excess ground water is encountered, no further drilling shall be allowed until a construction method is employed which shall prevent any caving that tends to make the excavation appreciably larger than the size of casings to be used. Construction methods that control the size of the excavation, such as drilling in a mud slurry without the removal of cuttings, shall be permitted.

If the elevation of the top of the shaft is below ground level at the time of concrete placement, an oversize casing from ground elevation to a point below the top of the shaft shall be required to control caving of any material into the freshly placed concrete.

Any excavation for the footing bells or shafts beyond the lines required shall be backfilled with Class A or Class PA concrete as specified by the OWNER at the CONTRACTOR'S expense. Where casings are used, the CONTRACTOR shall be permitted to backfill around the upper portion of the casing with pea gravel or other granular material. Where a double casing is required for a portion of the shaft, no material shall be placed between the casings but rather this area shall be filled with Class A or Class PA concrete as specified by the OWNER.

Under normal operations when the casing is to be removed, the removal shall not be started until concrete placement is completed in the shaft. Movement of the casing for short pulls of a few inches or rotating of the casing shall be permitted. When unusual conditions warrant, the casing may be pulled in partial stages. In all cases a sufficient head of concrete shall be maintained at all times above the bottom of the casing to overcome hydrostatic pressure. Extraction of the casing shall be at a slow, uniform rate and the full pull shall be in a truly vertical direction. If any upward movement of the concrete and/or inside the casing occurs at any time during the pulling operations, the following criteria shall govern:

- (1) if the upward movement is 1-in. or less, the casing shall be left in place. Vibration or rodding shall not be used to attempt to break the casing loose for extraction unless the entire shaft is to be replaced.
- (2) if the upward movement is greater than 1-in., all of the material shall be removed and the entire drilled shaft operation shall be redone.

Placing of drilled shaft concrete under water shall not be done without the permission of the OWNER.

Material excavated from shafts and bells and not used in the backfill around the completed bents or piers shall be disposed of as directed by the OWNER. The disposal of such material shall be in such manner as not to impair adjacent water bodies or otherwise impair the efficiency or appearance of the structure or other parts of the work.

At the time concrete is placed, the excavation shall be free from accumulated seepage water and all loose material shall be removed from the base area.

The CONTRACTOR shall provide suitable access and lighting for the OWNER to inspect the completed foundation excavation and check the dimensions and alignment of drilled shafts and the under-reamed excavation when under-reaming is required. Any required lighting shall be by electric lights. Any mechanical equipment used in the excavations shall be operated by air or electricity. The use of gasoline-driven engines placed in the excavation for pumping or drilling shall not be permitted.

In order that the OWNER may judge the adequacy of a proposed foundation, the CONTRACTOR, if requested, shall make soundings or take cores at its expense to determine the character of the supporting materials. The depth of such soundings or cores shall not be required to exceed 5-ft. below the proposed footing grade. It is the intent of this provision that soundings shall be made or cores taken at the time the excavation in each foundation is approximately complete.

When the plans require drilled shafts in the abutments, the embankment at the bridge ends shall be made to grade as shown and thoroughly compacted, as provided in the governing specifications, prior to drilling for abutment shafts.

702.8.3.2. Reinforcing Steel. The reinforcing steel cage for the shaft, consisting of longitudinal bars and spiral hooping or lateral ties, shall be completely assembled and placed into the shaft as a unit. Generally, the reinforcing steel unit shall not be placed until immediately before concreting operations are to be started. The longitudinal bars shall be tied to the spiral hooping at intervals not to exceed 12-in. on centers to provide a rigid unit. For cased shafts where the reinforcing steel cage is over 30-ft. in length, the longitudinal bars shall be tied at each intersection of the spiral hooping for a distance of $\frac{1}{5}$ the depth of shaft from the bottom of the cage. The cage of reinforcing steel shall be supported from the top by some positive method to prevent slumping downward during extracting of the casing.

In uncased shafts, side spacer blocks of concrete shall be used at intervals along the shaft to insure concentric spacing for the entire length of shaft. In cased shafts, concrete spacer blocks shall not be used, but instead metal "chair" type spacers shall be placed vertically at intervals around the steel cage to insure concentric spacing inside the casing.

702.8.3.3. Concrete. The work shall be performed in accordance with the provisions of [Item 702.5. Constructing Concrete Structures](#), and in conformance with the requirements herein.

Preferably concrete shall be placed immediately after all excavation is complete and reinforcing steel placed.

Concrete placing shall be continuous from the beginning of placement in the shaft or footing bell to the top of shaft or to a construction joint as may be indicated on the plans. Time intervals shall be

allowed for pulling casings, placing forms and other operations necessarily carried on in sequence with the placing operations. The reinforcing steel cage shall be held vertically in some manner to restrain the steel from slumping during the concrete placement operation. Concrete shall be placed through a suitable tube to prevent segregation of concrete materials and unnecessary splashing on the reinforcing steel cage. The tube shall be made in sections to permit the discharge and raising as the placement progresses. A non-jointed pipe may be used if sufficient openings of the proper size are provided to allow for the flow of concrete into the shaft.

Whenever a casing is used, the casing shall be smooth and well-oiled and shall extend sufficiently above the grade of the finished shaft to provide excess concrete to be placed for the anticipated slump due to the casing removal.

Where a casing is to be pulled, the concrete placed in casing shall be of such workability as to require no vibrating or rodding. Where a cap block or ground line strut is shown on the plans to be placed at the top of the drilled shaft, and the cap or strut is shown to be placed monolithic with the drilled shaft, a time interval shall be allowed for placing the required form and reinforcing after any necessary casing removal.

After a placement is completed, the top surface shall be cured and any construction joint area shall be treated as prescribed in [Item 702.5](#), Constructing Concrete Structures.

702.8.4. Test Holes. When shown on the plans, or when ordered by the OWNER in writing, test holes shall be required to establish elevation for “belling” to determine elevation of ground water or to determine other soil characteristics. The diameter and depth of test hole or holes shall be as shown on the plans or as directed by the OWNER.

702.8.5. Test Bells. When shown on the plan, or when ordered by the OWNER in writing, the under-reaming of bells on specified test holes shall be required to establish the ability to under-ream in the soil strata present. The diameter and shape of the test bell shall be as shown on the plans or as directed by the OWNER.

702.8.6. Measurement and Payment. Acceptable drilled shafts in place of the specified diameter shall be measured by the linear foot. At interior bents and piers, shafts shall be measured from 1-ft. below ground for drill shafts at stream crossings, and measured from a point of 6-in. below the ground elevation for grade crossings at the center of shaft unless otherwise indicated on the plans. At street grade separations and at railroad underpasses, the ground elevation shall be the completed roadway section under the structure. At stream crossings and at railroad overpasses, the ground elevation shall be considered as the elevation existing at the time drilling begins. At abutment bents, the length of shaft shall be measured from the bottom of cap elevation.

Footings bells, constructed to the specified dimensions or to the altered dimensions as authorized by the OWNER, shall be measured by the cubic yard of concrete in the acceptable footings placed. The bell shall consist of the authorized footing volume outside the dimensions of the drilled shaft, which for the purpose of measurement shall be considered as extending to the bottom of the bell.

Test holes of the specified diameter shall be measured from the elevation of the ground at the time drilling begins, by the linear foot of acceptable test hole drilled.

Test bells of the specified diameter and shape shall be measured by each test bell acceptably under-reamed.

Drilled shafts shall be paid for at the unit price bid per linear foot of the specified diameter of “drilled shafts,” measurements being made as hereinbefore outlined. Where vertical and spiral reinforcing bars from the shaft extend into footings, caps, columns or other concrete members, the cost of such reinforcing shall be included with and paid for as part of “drilled shafts.”

Payment shall include the following:

- (1) payment for individual completed shaft lengths, up to and including 5-ft. in excess of the maximum plan length shaft as defined herein, shall be made at the unit price bid per linear foot (m) of the specified diameter of “drilled shafts.”

- (2) payment for that portion of individual completed shaft length in excess of 5-ft. and up to and including 15-ft. more than the maximum plan length shaft as defined herein shall be made at a unit price equal to 115-percent of the unit price bid per linear foot of the specified diameter of “drilled shafts.”
- (3) payment for individual completed shaft lengths, over 15-ft. in excess of the maximum plan length shafts as defined herein, shall be in accordance with one of the following methods as determined by the OWNER:
 - (a) Method “A.” By unit prices agreed to in writing by the OWNER before said extra work is commenced, subject to all other conditions of the contract.
 - (b) Method “B.” By lump sum price agreed to in writing by the OWNER and the CONTRACTOR before said extra work is commenced, subject to all other conditions of the contract.

Footings bells, constructed to the specified dimensions or to the altered dimensions as authorized by the OWNER, shall be paid for at the contract unit price bid per cubic yard for “bell footing.”

Test holes, of the specified diameter, shall be paid for at the contract unit price bid per linear foot for “test hole.”

Test bells, of the specified diameter, shall be paid for at the contract unit price for each “test bell.”

The foregoing unit prices shall be full compensation for making all excavations; drilling all test holes and test bells; pumping, placing and removing any required casings; furnishing and placing all concrete and reinforcing steel; all backfilling; and furnishing all tools, labor, equipment, materials and incidentals necessary to complete the work. No extra payment shall be made for casings left in place.

702.9. PRECAST AND CAST-IN-PLACE CONCRETE UNITS

702.9.1. Description. This item shall govern the materials used and for constructing, furnishing and placing precast and cast-in-place concrete units at the locations shown and in accordance with the details shown on the plans. Unless otherwise shown on the plans, the CONTRACTOR shall have the option of furnishing cast-in-place, precast (formed) or precast (machine-made) concrete units.

702.9.2. General. Cast-in-place and precast (formed) concrete units shall conform to the requirements of [Item 702.2](#), Concrete Structure Materials, [Item 702.3](#), Mix Design and Mixing Concrete for Structures, [Item 702.5](#), Constructing Concrete Structures, and ASTM Designations C857 Minimum Structural Design Loading for Underground Precast Concrete Utility Structures, and C858 Underground Precast Concrete Utility Structures, as applicable. Concrete units shall be of the various types shown on the plans and designated by letters or numbers to indicate the particular design of each. Each type shall be constructed in accordance with the details shown on the plans or approved by the OWNER, to the depth required by the profiles and schedules given.

702.9.3. Materials.

702.9.3.1. Concrete. Unless otherwise shown on the plans, concrete for cast-in-place and precast formed concrete units shall be Class A or Class PA (as specified by the OWNER) conforming to the requirements of [Item 702.3](#), Mix Design and Mixing Concrete for Structures except that Class C or Class PC concrete (as specified by the OWNER) shall be required when a unit is used with monolithic pipe sewer construction.

Concrete for precast machine-made units shall meet the requirements of ASTM C76 Sections: Reinforced Concrete, Cement, Aggregate, Mixture and Concrete Test Requirements for Concrete and shall have a minimum 28-day compressive strength of 4,000-psi. Vibrating equipment used in making concrete test cylinders must be approved by the OWNER. Testing shall be conducted in accordance with [Item 702.3.4.5](#), Tests.

702.9.3.2. Steel Reinforcement. Steel reinforcement shall conform to the requirements of [Item 303.2.9](#), Steel Reinforcement and the details shown on the plans. A positive means of holding the steel cages in place throughout production of the concrete units shall be provided and shall be subject to approval of the OWNER. Welding of steel reinforcement will not be permitted unless specifically shown on the plan details and shall conform to the requirements of [Item 703.3.7](#), Welding. The maximum variation in the position of the reinforcement shall be plus or minus 10-percent of the wall thickness or plus or minus ½-in., whichever is lesser. In no case, however, shall the cover over the reinforcement be less than shown on the plans.

702.9.4. Forms, Precast Machine-Made Concrete Units. Forms for precast machine-made concrete units shall be made of steel and shall comply with the requirements of [Item 702.5.6](#). Forms.

The thickness of form metal shall be as required to maintain the true shape without warping or bulging. All bolt heads on the facing sides shall be countersunk. Clamps, pins or other connecting devices shall be designed to hold the forms rigidly together and to allow removal without injury to the concrete. Metal forms which do not present a smooth surface or which line up improperly shall not be used. Metal shall be kept free from rust, grease or other foreign materials. Metal forms shall be welded except that these will not require lining unless specifically noted on the plan.

702.9.5. Casting Tolerances. Allowable casting tolerances for concrete units shall not vary more than plus or minus 1/4-in. from the dimensions and configuration shown on the plans. Thickness in excess of that required shall not be cause for rejection, provided that such excess thickness does not interfere with proper jointing or operation as determined by the OWNER.

702.9.6. Marking. The following information shall be clearly marked on each section of precast unit prior to leaving the casting yard.

- (1) The date of manufacture.
- (2) The name or trademark of the manufacturer.

702.9.7. Storage and Shipment. Precast units shall be stored on level blocking in a manner acceptable to the OWNER. No loads shall be placed on them until design strength is reached. Shipment of acceptable units may be made when the 28-day strength requirements have been met.

702.9.8. Rejection. Precast units may be rejected for nonconformity with any part of these specifications and also for any of the following reasons:

- (1) Fractures or cracks passing through the shell, except for a single end crack that does not exceed the depth of the joint.
 - (2) Surface defects indicating honeycombed or open texture.
 - (3) Damaged or misshapen ends, where such damage would prevent making a satisfactory joint.
- All rejected units shall be so marked by the OWNER and shall be replaced by the CONTRACTOR with acceptable ones meeting the requirements herein. Rejected units shall be removed immediately from the site of work.

702.9.9. Repairs. Occasional imperfections in manufacture or accidental injury during handling may be repaired and will be acceptable if, in the opinion of the OWNER, the repairs are sound, properly finished and cured, and the repaired units conform to the requirements of this specification.

702.9.10. Construction Methods. All excavation shall be in accordance with the requirements of [Item 701.2](#). Structural Removal, Excavation, and Backfill or with excavation in [Item 203](#). Site Preparation.

Precast concrete units shall be bedded on foundations of firm and stable material accurately shaped to conform to their bases.

The CONTRACTOR shall provide adequate means to lift and place the concrete units. Lifting holes may be formed during production, or punched through the fresh concrete immediately after stripping forms; however, care shall be taken not to damage the unit by spalling large areas. All lifting holes shall be repaired in accordance with [Item 702.9.9](#). Repairs.

Connections to new or existing structures shall be made in accordance with details shown on the plans. Jointing material shall be in accordance with [Item 501.6](#). Reinforced Concrete Culvert, Storm Drain, Pipe and Box Section, or as specified in the plans.

Frames, grates, rings and covers, when required by the plans for use in a concrete unit, shall be installed in accordance with [Item 806](#). Metal Materials or [Item 502](#). Appurtenances, as applicable.

702.9.11. Measurement and Payment. Precast and cast-in-place units of each size and type, satisfactorily complete in accordance with the plans and specifications, will be measured by each concrete unit completed to the stage of construction required by the plans.

Excavations and backfill, unless otherwise noted on the plans, will be measured as required by [Item 701.2](#). Structural Removal, Excavation, and Backfill with excavation in [Item 203](#). Site Preparation, or [Item 504](#). Open Cut – Backfill, as appropriate.

Payment for precast concrete units of the types shown on the plans, complete, in place, and in accordance with this specification as measured above, shall be made at the unit bid price for each type

specified. Unless otherwise provided for in the proposal, payment for work performed under this specification shall be full compensation for furnishing, transporting, and placing all concrete, steel reinforcement, brick, mortar, castings for shaping of bed, jointing to new or existing structures, and all other materials, tools, equipment, labor, and incidentals necessary to perform the work prescribed above.

Excavation and backfill, unless otherwise provided in the proposals, shall be paid for as appropriate under [Item 701.2](#). Structural Removal, Excavation, and Backfill with excavation in [Item 203](#). Site Preparation, or [Item 504](#). Open Cut – Backfill.

ITEM 703. STEEL STRUCTURES

703.1. DESCRIPTION

This specification shall govern the fabrication and erection of structural steel and other metals (except reinforcing steel), which are used for steel structures or steel portions of structures.

703.2. MATERIALS FOR STEEL STRUCTURES

The metal used for the various portions of the structure shall be as specified and shall conform to the requirements of [Item 806](#). Metal Materials.

703.3. STEEL STRUCTURE CONSTRUCTION

703.3.1. General.

703.3.1.1. Shop Drawings. Unless otherwise provided on the plans, the CONTRACTOR shall prepare and submit detailed shop drawings for each detail of the general plans requiring the use of structural steel, forgings, wrought iron, castings or bearings. Camber and erection diagrams shall be required. The drawings shall be prepared on standard 24-in. by 36-in. sheets or on mutually agreeable standard sheet sizes, such as, 11-in. by 17-in. sheets.

All shop drawings shall be checked by the fabricator before being submitted for approval by the OWNER. The CONTRACTOR shall furnish to the OWNER as many prints of the drawings as are necessary for carrying out the work. At the request of the OWNER, shop drawings may be submitted electronically in lieu of printed copies, or a combination of printed and electronic copies.

The CONTRACTOR shall be responsible for the correctness and completeness of the drawings and for shop-fit and field connections, even though the drawings have been approved by the OWNER.

When required by the plans or specifications, the CONTRACTOR shall furnish to the OWNER, before formal acceptance of the work, detailed drawings of the structure as built. Inasmuch as the drawings shall be retained by the OWNER as permanent records, they must be in the form of printable transparencies of a quality satisfactory to the OWNER.

703.3.1.2. Methods and Equipment. Before starting work the CONTRACTOR shall inform the OWNER fully as to the method of erection it proposes to follow and as to the amount and character of the equipment it proposes to use, the adequacy of which shall be subject to the approval of the OWNER. The approval of the OWNER shall not be considered as relieving the CONTRACTOR of the responsibility for the safety or adequacy of its methods or equipment or from carrying out the work in full accordance with the plans and specifications. No work shall be done without the sanction of the OWNER.

The CONTRACTOR shall prepare and submit erection plans for the erection of all steel structures. The plans shall be completed in all details of procedure, sequence of work, equipment to be used, etc., and submitted to the OWNER for review.

703.3.1.3. Notice of Beginning Work. The CONTRACTOR shall give the OWNER ample notice of the beginning of work in the shop so that inspection may be provided. No work shall be performed in the shop before the OWNER has authorized fabrication. Any purchases of material prior to fabrication authorization shall be at the CONTRACTOR'S risk.

703.3.1.4. Inspection. An inspector or other authorized representative of the OWNER may examine the metals and metal items to be fabricated in the shop and may exercise constant surveillance over the work during the progress, with full power to reject all materials or workmanship not conforming to the plans and specifications.

The CONTRACTOR shall give the OWNER 5-days minimum advance notice before commencement of the fabricating operations to permit ample time for the inspection of the materials.

The OWNER shall be furnished complete copies of mill reports prior to commencing fabrication. The CONTRACTOR shall furnish ample means and assistance for sampling all materials. Arrangements shall be made for the OWNER to have free access at all times to any portion of the workshops where work is being done under these specifications.

No fabricating, machining, cutting, welding, assembling, or painting shall be done except with the knowledge of the OWNER. Any work done otherwise shall be subject to rejection.

The acceptance of any material or finished member by the OWNER shall not be a bar to subsequent rejection if it is later found to be defective. Rejected material and workmanship shall be promptly repaired or replaced by the CONTRACTOR.

Samples of materials, except castings, shall be cut from stock designated by the OWNER or shall be selected from items furnished. Gray iron, steel, and bronze castings shall be cast with test coupons.

Payment for structural steel shall not be made until shipping invoices indicating total weight of material used have been received and checked by the OWNER.

703.3.1.5. Workmanship. Workmanship and finish shall be equal to the best general practice in modern steel fabricating shops.

Rolling tolerances for rolled shapes, plates, and bars shall conform to the requirements of ASTM A6 General Requirements for Rolled Structural Steel Bars, Plates, Shapes, and Sheet Piling.

Before being laid out or worked, rolled material shall be straight. If straightening is necessary, it shall be done by methods approved by the OWNER. Kinks and bends in the material shall be cause for rejection. Heat shrinking of low alloy structural steels shall not be permitted.

If straightening is necessary in the field, only methods approved by the OWNER shall be used.

Following the straightening of a bend or buckle, the surface of the metal shall be carefully inspected for evidence of fracture.

Portions of the work exposed to view shall be finished neatly. Shearing, flame cutting, and chipping shall be done carefully and accurately.

Undercut gusset plates shall not be accepted. All sharp corners and edges, and edges that are marred, cut, or roughened in handling or erection, shall be slightly rounded by grinding or other suitable means.

703.3.2. Bolted Structures/Bolted Connections. High strength bolts conforming to [Item 806.6](#). Bolts, Nuts and Washers shall be used. Pitch and edge distance not shown on the plans shall be in accordance with AASHTO Load and Resistant Factor Design (LRFD) Bridge Design Specifications.

Spot welding for the purpose of eliminating field erection bolts or for holding steel parts together shall not be permitted. The CONTRACTOR shall provide the false-work and all tools, machinery and appliances, including drift pins and fitting-up bolts necessary for the expeditious handling of the work. Drift pins sufficient to fill at least one-quarter ($\frac{1}{4}$) of the field holes for main connections shall be provided.

703.3.2.1. Holes for Bolts. Holes shall be either punched full size, punched and reamed, or drilled. The finished hole shall be $\frac{1}{16}$ -in. larger than the nominal diameter of the bolt.

The accuracy of the punching shall be such that for any group of holes when assembled, 75-percent shall admit a rod equal to the diameter of the bolt at right angles to the plane of the connection. Otherwise, the holes shall be reamed. When the extent of the reaming is such that the holes cannot be properly filled or accurately adjusted after reaming, the faulty member shall be discarded and replaced at no cost to the OWNER.

Mispunched members shall not be corrected by welding without the approval of the OWNER.

Holes punched full size shall have all burrs and sharp edges removed. The diameter of the die shall not exceed that of the punch by more than $\frac{3}{32}$ -in. Holes shall be as follows:

703.3.2.1.1. Sub-Punched or Sub-Drilled Holes. Holes for bolts shall be sub-punched or sub-drilled at the fabricator's option, $\frac{1}{4}$ -in. less in diameter than that of the finished holes and shall be reamed to size with the parts assembled, with the following exceptions:

- (1) holes in material thicker than $\frac{7}{8}$ -in. shall not be punched; however, at the fabricator's option, they may be sub-drilled to the diameter specified for sub-punching or may be drilled full size with the parts assembled, provided that the parts are adequately bolted or clamped together.
- (2) holes in rolled beams and plate girders, including stiffeners and active fillers at bearing points, may be sub-punched $\frac{1}{8}$ -in. less in diameter than that of the finished holes, and reamed to size (after assembly) in material not thicker than the nominal diameter of the bolt less $\frac{1}{8}$ -in.

703.3.2.1.2. Holes for Bolts Which Do Not Transfer Stress. Holes in material not more than $\frac{7}{8}$ -in. thick for bolts which do not transfer stress caused by external vertical loading may be punched full size or, at the fabricator's option, may be sub-punched $\frac{1}{8}$ -in. less in diameter than the finished holes

and reamed to size after assembly. This applies to holes for lateral, longitudinal or sway bracing and connecting material, lacing stay plates, diaphragms which do not transfer shear or stress, inactive fillers and stiffeners not at bearing points. However, holes through assembled material shall not pass through both reamed plies and plies punched full size unless the reamed holes have been sub-punched for the fabricator's convenience, or the assembled material is not over 5 plies thick, of which the main material consists of not more than 3 plies.

703.3.2.1.3. Holes for Field Bolts. Holes for field bolts shall be sub-punched or sub-drilled at the fabricator's option, $\frac{1}{4}$ -in. less in diameter than that of the finished holes and shall be reamed to size through steel templates with hardened steel bushings, with the following exceptions:

- (1) field splices in plate girders and in the chords of trusses shall be reamed with the members assembled. Other field connections may be reamed with the members assembled, at the fabricator's option. Chord splices or truss members shall, in all cases, be reamed or drilled with at least 3 abutting sections assembled and with milled ends of compression chords in full bearing.
- (2) assemblies, such as floor systems to girders, complete trusses, rolled beam spans connected by diaphragms and portals to trusses shall be reamed with the members assembled if so indicated on the plans, or otherwise at the fabricator's option.
- (3) field connections of lateral, longitudinal or sway bracing shall conform to the requirements of holes for shop bolts.
- (4) holes in material thicker than $\frac{7}{8}$ -in. shall not be punched but shall be sub-drilled to the diameter specified for sub-punching or drilled full size with parts assembled.

703.3.2.2. Reamed Work. Reaming work shall be done after the pieces forming a built-up member are assembled and so firmly bolted together that the surfaces are in close contact. Burrs and sharp edges of each reamed hole under both bolts shall be removed with a counter-sinking tool making $\frac{1}{16}$ -in. fillets. The pieces shall be taken apart before bolting, if necessary, and any shavings removed. If it is necessary to take the members apart for shipping or handling, the pieces reamed together shall be so marked that they may be reassembled in the same position. Reamed parts shall not be interchanged.

703.3.3. Assembling Steel. Steel parts shall be assembled in the shop or in the field in accordance with the following specifications.

703.3.3.1. Shop Work. At the time of assembling, bolting or welding steel surfaces in contact for shop or field connection shall be thoroughly cleaned of rust, loose mill scale, dirt, grease or other material foreign to the steel. No paint shall be applied to contact surfaces prior to bolting or welding.

Bolted trusses, continuous plate girder and rolled shapes, skew portals, skew connections, rigid frames, bents and towers shall be completely assembled in the shop and accurately adjusted to line and camber and holes for field connections and shall be drilled or reamed while assembled. Holes for other field connections, except those in lateral, longitudinal and sway bracing, shall be drilled or reamed in the shop with the connecting parts assembled, or drilled or reamed to a metal template with hardened bushings, without assembling.

Long span truss work shall be assembled in lengths of not less than 3 abutting panels, the members adjusted for line and camber, and holes for field connections drilled or reamed while assembled. Field bolted joints for welded girders shall be completely assembled with the members adjusted for line and camber and prepared to fit for welding. All machinery shall be completely assembled. All bearings shall be fitted to the specified clearances and alignment. Gear reductions and all line gear shall have gear center distance set and the gears properly match-marked.

703.3.3.2. Field Work. The parts shall be accurately assembled as shown on the plans and all match-marks shall be followed. The material shall be carefully handled so that no part shall be bent, broken or otherwise damaged. Hammering which shall injure or distort the members shall not be permitted. Bearing surfaces and surfaces to be in permanent contact shall be cleaned before the members are assembled. Unless erected by the cantilever method, truss spans shall be erected on blocking so placed as to give the trusses proper camber. The blocking shall be left in place until the tension chord splices are fully bolted and all other truss connections pinned and bolted. Bolts in splices of butt joints

of compression members and bolts in railing shall not be driven or torqued until the span has been erected in place, temporarily bolted and the member is supporting its own weight. Splices and field connections shall have one-half ($\frac{1}{2}$) of the holes filled with bolts and cylindrical erection pins (half bolts and half pins) before bolting.

Splices and connections carrying traffic during erection shall have three-quarters ($\frac{3}{4}$) of the holes so filled.

Fitting-up bolts shall be of the same nominal diameter as the bolts, and cylindrical erection pins shall be $\frac{1}{32}$ -in. larger.

The drifting done during assembling shall be only such as to bring the parts into position and not sufficient to enlarge the holes or distort the metal. If any holes must be enlarged to admit the bolts, they shall be reamed.

Connecting parts assembled in the shop for the purpose of reaming holes in field connections shall be match-marked, and a diagram showing such marks shall be furnished to the OWNER.

703.3.4. Joints and Connections.

703.3.4.1. Edge Planing. Sheared edges of plates more than $\frac{5}{8}$ -in. in thickness and carrying calculated stress shall be planed to a depth of $\frac{1}{4}$ -in.

703.3.4.2. Facing of Bearing Surfaces. Surfaces of bearing and base plates and other metal bearing surfaces that are to come in contact with each other, with ground concrete surfaces or with sheet packing, shall be finish-machined flat to within $\frac{1}{32}$ -in. tolerance in 12-in. and to within $\frac{1}{16}$ -in. tolerance overall. Surfaces of bearing and base plates and other metal bearing surfaces that are to come in contact with preformed fabric pads, elastomeric and elastic bearing pads, or Portland cement grout, shall be finished machine flat to within $\frac{1}{8}$ -in. tolerance in 12-in. and to within $\frac{3}{16}$ -in. tolerance overall.

At the option of the CONTRACTOR, steel slabs, where not in contact with other metal bearing surfaces, may be heat straightened in lieu of machining, provided the above tolerances are met.

703.3.4.3. Abutting Joints. When shown on the plans, abutting joints shall be faced and brought to an even bearing. Where joints are not faced, the opening shall not exceed $\frac{1}{4}$ -in.

703.3.4.4. End Connection Angles. Floor beams, stringers and girders having end connection angles shall be built to exact length back-to-back of connection angles. If end connections are faced, the finished thickness of the angle shall be not less than that shown on the detail drawings.

703.3.4.5. Web Plates. In girders having no cover plates and which are not to be encased in concrete, the top edge of the web plate shall not extend above the backs of the flange angles and shall not be more than $\frac{1}{8}$ -in. below at any point.

703.3.4.6. Fit of Stiffeners. End stiffener angles of girders and stiffener angles intended as supports for concentrated loads shall be milled or ground to secure an even bearing against the flange angles. All fillers under stiffener angles shall be sufficiently tight to exclude water after being painted.

703.3.4.7. Pin and Bolted Connections. Pilot and driving nuts shall be used in driving pins. Pins shall be so driven that the members shall take full bearing on them. In field assembling, the pin nuts on pin connections and the bolts on bolted connections shall be screwed up tight and the threads, except when high-strength bolts are used, burred at the face of the nuts with a pointed tool.

703.3.4.8. Pins and Rollers. Pins and rollers shall be accurately turned to the dimensions shown on the drawings and shall be straight, smooth and free from flaws. The final surface shall be produced by a finishing cut.

Pins and rollers more than 7-in. in diameter shall be forged and annealed.

In pins larger than 9-in. in diameter, the forging shall be permitted to cool to a temperature below the critical range cooling, and a hole not less than 2-in. in diameter shall be bored full length along the axis of the pin before being annealed.

Pinholes in structural members shall be bored true to the specified diameter, smooth and straight, at right angles with the axis of the member and parallel with each other unless otherwise required. The final surface shall be produced by a finishing cut.

The distance outside-to-outside of holes in tension members and inside-to-inside of holes in compression shall not vary from that specified more than $\frac{1}{32}$ -in. Holes in built up members shall be bored after bolting or welding is completed. The diameter of the pinhole shall not exceed that of the pin by more than $\frac{1}{50}$ -in. for pins 5-in. or less in diameter, or $\frac{1}{32}$ -in. for larger pins.

703.3.4.9. Screw Threads. Screw threads shall make close fits in the nuts and conform to ASME B1.1-1989 Unified Inch Screw Threads (UN and UNR Thread Form).

703.3.5. Bearings and Anchorage. Anchor bolts shall be either headed bolts, installed with or without pipe sleeves, or swedge bolts installed in drilled holes, as detailed on the plans. The anchor bolts shall be carefully installed to permit true positioning of the bearing assemblies.

When anchor bolts are installed in pipe sleeves, the pipes shall be completely filled with grout at the time the grout pads are constructed or at the time the bearing assemblies on masonry plates are placed.

Swedge bolts installed in holes shall be either sulfured-in or grouted-in as shown on the plans.

All bearing assemblies shall be set level and to the elevations shown on the plans. Adjustments in the horizontal positions of bearing assemblies shall be made for temperature as directed by the OWNER.

In conformance with the details shown on the plans, masonry plates and the bearing plates of bearing assemblies shall be set on ground concrete surfaces, or elastomeric bearings, per [Item 303.2.15. Elastomeric Materials](#).

Immediately before setting bearing assemblies or masonry plates directly on ground concrete surfaces, the CONTRACTOR shall thoroughly clean the surfaces of the concrete and the metal to be in contact and shall apply a thick coating of approved paste to contact areas to provide full bedding of the metal in the approved paste.

703.3.6. Expansion and Rotation Assemblies. Before leaving the shop or foundry, the rockers or roller nests shall be completely assembled with the bearing plates for checking and approval by the OWNER.

703.3.7. Welding. All welding shall conform to the requirements of appropriate ANSI Standards, the requirements of these specifications. A welder must be qualified or certified per TxDOT Item 448. Structural Field Welding.

Inspection of welding made to control the quality of welds and workmanship shall be performed in accordance with the requirements of ANSI Standards. All welding shall be subject to radiographic and other non-destructive testing which shall be performed without charge to the CONTRACTOR, except that if a weld is shown to be defective, all costs involved in re-inspection shall be borne by the CONTRACTOR.

Weld metal shall be sound throughout except that very small gas pockets and small inclusions of oxide or slag may be permitted if well dispersed and if none exceeds $\frac{1}{16}$ -in. in greatest dimension; and provided further that the sum of the greatest dimension of all such defects in any square-inch of weld does not exceed $\frac{3}{8}$ -in.

All welding shall be performed in such a manner that the Brinnell hardness of the weld metal and heat-affected zone is within the limits in Table 703.3.7.(a) Brinnell Hardness Limits for Welded Structures.

Table 703.3.7.(a) Brinnell Hardness Limits for Welded Structures

Minimum	(Minimum specified tensile strength of parent metal/500) + 50
Maximum	(Maximum specified or tested tensile strength of parent metal/500) + 50

All welding of structural steel (ASTM Designations A36 Carbon Structural Steel, A242 High-Strength Low-Alloy Structural Steel and A808 High-Strength, Low-Alloy Carbon, Manganese, Columbium, Vanadium Steel of Structural Quality with Improved Notch Toughness) shall be performed by either the submerged or gas-shielded arc process or with low-hydrogen electrodes. Low-hydrogen electrodes for welding low-alloy steels shall conform to the requirements of the Federal Specifications for Electrodes (mineral covered, low hydrogen) for Welding Medium and High Tensile Steels, MIL-E-18038. All welding of low-alloy structural steel shall be qualified by procedure tests before fabrication is commenced.

Low-hydrogen electrodes shall be stored for holding in an approved low-hydrogen oven at a temperature of 300°F to 400°F to control the moisture in the coating on the electrode.

Low-hydrogen electrodes which have been removed from their moisture-proof containers shall be stored in an approved oven at a temperature of 300°F to 400°F after re-baking.

Areas contiguous to welding operations shall be preheated to a minimum temperature of 300°F when necessary to prevent distortion or weld cracking. Preheating to a temperature in excess of 400°F shall not be required.

Unless otherwise shown on the plans or specified, bearing assemblies that are to be machined after welding shall be stress relieved by heat treatment before machining, in accordance with AWS Specifications.

Portions of members in bearing assemblies or in direct bearing shall be straightened, planed or otherwise corrected after fabrication as necessary to provide full bearing on bearing assemblies or bearing areas on level bearing plates.

Where the end of a stiffener plate is shown “tight-fit” on the plans, the end of the plate shall be so fitted that it bears on the beam flange with at least point bearing. Local clearances between the end of the plate and flange shall not exceed $\frac{1}{16}$ -in.

Unless otherwise shown on the plans or specified, erection bolts required for welded splices or welded connections may be left in place, and the ends of all such erections bolts which project beyond the nut shall be burned off flush with the face of the nut. Where the bolt does not project, the end of the bolt and nut shall be tack welded to prevent loosening of the nut. Burning off projecting bolt ends and tack welding shall be performed prior to painting.

703.3.8. False-Work. The false-work shall be properly designed for the loads to be supported and shall be constructed substantially and maintained. The CONTRACTOR shall prepare and submit plans for false-work to the OWNER for approval.

The false-work plans shall be complete in all details of members, connection equipment, etc. so that a structural check can be made of the false-work.

Approval of the CONTRACTOR’S plans shall not be considered as relieving the CONTRACTOR of any responsibility.

703.3.9. Grading Deck on Continuous Units. Forms shall not be erected or concrete placed until after all welding or bolting is complete, the unit positioned and bearing properly set.

An accurate measurement shall be made of the elevation of girder or beam flanges at all grading control points as shown on the plans. Subsequent grading of forms and placing and finishing of concrete shall be governed by these measurements only, taking into account the dead load deflection of the slab and rail as shown on the dead load deflection diagram.

703.3.10. Misfits. Corrections of minor misfits and a reasonable amount of reaming and cutting of excess stock shall be considered a legitimate part of the operations. Any error in shop work which prevents the proper assembling and fitting-up of parts by the moderate use of drift pins or a moderate amount of reaming and slight chipping or cutting shall be reported immediately to the OWNER. OWNER approval of the method of correction shall be obtained. The correction shall be made in the presence of the OWNER, who shall check the material. Such work is to be done at the entire expense of the CONTRACTOR.

703.4. PAINTING METAL STRUCTURES

The application of shop paint shall conform to the requirements of [Item 804](#). Painting and Other Protective Treatments; Pavement Marking. Unless otherwise provided, the application of field paints shall conform to the requirements of [Item 804](#). Painting and Other Protective Treatments; Pavement Marking.

For structures that require that the steel be erected and assembled on false-work and moved into place as a unit, all field paint, except the final coat, shall be applied to the steel while on the false-work and prior to moving into final position. Those surfaces which are inaccessible for painting in the final position shall have the final paint coat applied prior to move-in. Touch-up of paint which is damaged due to move-in to final position shall be done, and the final field coat applied.

703.5. MEASUREMENT AND PAYMENT

Measurement and payment for quantities of structural metal, concrete, reinforcement, railing and other proposal items which constitute the completed and accepted structures shall be made in accordance with the provisions of pertinent specifications.

Payment for structural steel shall not be made until shipping invoices indicating total weight of material used have been received and checked by the OWNER.

ITEM 704. PILING

704.1. PILING MATERIALS

704.1.1. Steel Piling. Steel H and steel sheet piling shall conform to all provisions of TxDOT Item 407. Steel Piling.

704.1.2. Concrete Piling. Concrete piling shall be designed by the Engineer. Piling shall be cast-in-place and prestressed. Cast-in-place, prestressed concrete piling shall conform to TxDOT Item 409. Prestressed Concrete Piling and TxDOT Items referenced therein.

704.1.3. Rejection. Any piling not conforming to these specifications and applicable provisions of other sections shall be rejected. Any defect causing it to be unsuitable for its intended use shall be cause for rejection of the piling.

704.2. DRIVING PILING

704.2.1. Description. This specification shall govern the equipment to be furnished in order to perform the methods to be followed in the driving of piling.

The requirements herein are minimum. Strict compliance with these minimum requirements shall not relieve the CONTRACTOR of the responsibility for adopting whatever additional provisions may be necessary to insure the successful completion of the work.

704.2.2. General. Unless otherwise shown on the plans, the embankment at bridge ends shall be made to grade and thoroughly compacted as provided in the governing specifications prior to the driving of abutment piling. Foundation piling shall not be driven until after the excavation is approximately complete. All piling raised during the process of driving adjacent piling shall be driven again. Broken, split or misplaced piling shall be withdrawn and properly replaced or corrected as directed by the OWNER based on design analysis.

704.2.3. Tolerance for Driving. Piling shall be driven to the vertical or batter line indicated. The allowable variation from the plan alignment shall not exceed 4-in. in any direction. If the center of gravity of a pile group varies by more than 3-in. from the center of gravity determined from plan location, a structural analysis shall be required to see if the group shall be acceptable.

The minimum concrete cover for piling in footings shall be 5-in., and the pile shall be in such position to permit proper placement and cover of reinforcing steel.

704.2.4. Protection of Pile Heads. A structural steel driving head suitable for the type and size of pile being driven shall be used. Wood cushion blocks shall be used as necessary to prevent damage to the pile. Rope mat, belting or similar cushioning material may be used in addition to wood cushion blocks. Cushion blocks shall be changed as necessary to prevent damage to the pile.

704.2.5. Driving Equipment. The driving of piling shall be done with power hammers (steam or diesel). When specified on the plans, gravity hammers shall be permitted. Either steam or compressed air may be used as the operation medium for steam hammers.

Steam hammers shall be furnished with boiler or air compressor capacity at least equal to that specified by the manufacturers of the hammers to be used. The boiler or compressor shall be equipped with an accurate pressure gauge at all times.

Diesel hammers which have an enclosed ram shall be equipped with a gauge and charts which shall evaluate the equivalent energy actually being produced under any driving condition.

The valve mechanism and other parts of all power hammers shall be maintained in first-class condition so that the length of stroke and number of blows per minute for which the hammer is designed shall be obtained.

Power hammers shall be operated at not less than 80-percent of the manufacturer's rated capacity.

The driving equipment for steel sheet piling shall be of such size as required to drive the piling to the required depths with no damage to the piling. The equipment shall be equipped with a head suitable to the shape of the sheet pile.

When gravity (drop) hammers are used, the height of drop shall be regulated to avoid injury to the piling and in no case shall exceed the maximum drop shown in Table 704.2.5.(a) Size of Driving Equipment. The CONTRACTOR shall furnish the OWNER with a certified scale weight of the hammer to be used.

When rating diesel hammers for energy to determine compliance with the requirements of the table below, the height of fall of the ram of the single-acting (open end) hammer shall be 7-ft.

Table 704.2.5.(a) Size of Driving Equipment

Piling Type	Hammer Type		Minimum Hammer Energy (Foot - Pounds)	Weight of Ram lb.		Maximum Ram Stroke, ft.
				Min.	Max.	
Steel H or Steel Sheet	Gravity		250 x R ^{note 1} or 2.5 x Wp ^{note 2} (whichever is larger)	2000	5000	10
	Power	Steam, Air, Hydraulic		3000		5
		Diesel		2000		10

1. R = Design load in tons.

2. Wp = Weight of piling in pounds based on plan length.

Where test piling or test loads are required, the hammer used in driving all other piling shall be of the same type and size as the hammer used in driving the test piling.

Pile drivers shall be equipped with heads which are constructed in such manner as to afford freedom of movement of the hammer and which provide adequate support to the pile during driving. The vertical axis of the leads and hammer shall coincide with the vertical axis of the pile.

Except where piling is driven through water, the leads shall be of sufficient length that a follower shall not be necessary. Where a follower is required for the driving of piling under water, one piling out of every 10 shall be of sufficient length that a follower is not required. This piling shall be driven as a test piling for proper correlation of the follower-driven piling in the group.

704.3. PENETRATION

The length of piling shown on the plans is the length estimated to give the required bearing and is for estimating purposes only.

Piling shall be driven to the "minimum penetration" shown on the plans and to such greater depths required to obtain the specified bearing resistance. Where the plans indicate a "required penetration" into a particular stratum, this penetration into the strata shall be required although the strata may be found at a higher or lower elevation than is indicated on the plans.

Where no specific information is shown on the plans as to penetration and where test piling is not required, the pile lengths shown shall be considered as the "plan penetration" and shall be driven to this approximate elevation and to such greater depths required to obtain the specified bearing resistance.

When the specified penetration cannot be obtained without over-driving of the piling, pilot holes or jetting may be required.

704.4. BEARING RESISTANCE

The bearing resistance of all piling shall be determined by the following formulas:

For gravity hammers:

$$p = \frac{2WH}{S + 1.0}$$

When the energy delivered (W x H) by the gravity hammer is 24,000-foot-pounds or greater, and the penetration does not exceed 1/4-in. per blow for the last 40 blows delivered (without increasing), the bearing resistance shall be determined by:

$$p = \frac{2WH}{3S} \times N$$

For single-acting hammers:

$$p = \frac{2WH}{S + 0.1}$$

For double-acting hammers:

$$p = \frac{2E}{S + 0.1}$$

- where p = bearing resistance in pounds
- S = average penetration in inches per blow for the last 20 blows (40 blows for special formula for gravity hammer)
- W = weight of ram in pounds
- H = height of fall of ram in feet
- N = ratio of weight of ram to the weight of the pile. N shall not be used when greater than 1
- E = manufacturer's rated energy in foot-pounds
- (double-acting steam hammers)
- E = the equivalent energy in foot - pounds, determined by gauge attached to the hammer taken during the period when the average penetration in inches per blow is determined. Maximum E allowed for the double-acting (enclosed ram) hammer shall be manufacturer's rated energy in foot - pounds
- (enclosed ram diesel hammer.)

704.5. CONSTRUCTING CAST-IN-PLACE, PRESTRESSED CONCRETE PILING

Cast-in-place concrete piling shall be of the concrete class specified on the plans. Piling construction shall conform to TxDOT Item 409. Prestressed Concrete Piling and TxDOT Items referenced therein, unless otherwise specified by the OWNER.

704.6. MEASUREMENT AND PAYMENT

704.6.1. Measurement. Items specified in this section to be paid for as separate contract pay items shall be measured for payment as indicated in the following:

704.6.1.1. Steel Piling. Steel H Piling shall be measured for payment in linear feet of acceptable piling in place after all cut-offs and build-ups have been made. For that piling specified to be driven to a "minimum penetration," no measurement shall be made on that portion of piling below the elevation at which the penetration and bearing requirements were first obtained.

Steel sheet piling shall be measured for payment by the square foot of acceptable piling in place. Sheet piling driven below the elevation required by the plans or as directed by the OWNER shall not be measured for payment.

704.6.1.2. Concrete Piling. Cast-in-place prestressed concrete structures and units shall be measured as follows:

Prestressed concrete piling and prestressed concrete test piling will be measured for payment by the linear foot of acceptable piling in place after all cutoffs and buildups have been made. When the Contractor elects to drive piling deeper than required to meet the specified length and bearing requirements, no measurement will be made on that portion below the elevation at which length and bearing requirements were first obtained.

704.6.2. Payment. All items specified in this section shall be paid for as indicated below. The work performed and material furnished as prescribed herein, measured as provided under Measurement, shall be paid for at the contract unit price.

704.6.2.1. Steel Piling. Steel H piling shall be paid for at the contract unit price per linear foot for “steel H piling” or “steel H test piling,” as the case may be, of the specified size and weight. Steel sheet piling shall be paid for at the contract unit price per square foot for “sheet piling” of the specified weight and size required. No direct payment shall be made for cut-offs, pile heads, concrete collars, painting or for excavation and backfill required in placing the collars and in the painting or for excavation and backfill required in placing the collars and in the painting of portions of piling below ground line; such items shall be considered as incidental work, and the cost thereof shall be included in such contract pay items as are provided in the proposal and contract.

Splices for steel H piling shall be paid for each at two times the contract unit price for steel H piling of the size and weight on which the splice is made, except that no payment shall be made for any splice on any pile whose actual length left in place after all cut-offs, splices or build-ups have been made is not greater than the length shown on the plans or directed by the OWNER; nor shall payment be made for more than one splice on any one pile.

No payment shall be made for cut-off or build-up of sheet piling. The foregoing unit prices shall be full compensation for furnishing all materials, tools, labor, equipment, jetting, pilot holes, alignment holes and incidentals necessary to complete the work.

704.6.2.2. Concrete Piling. Payment for the work and all materials for prestressing of cast-in-place members as specified above shall be paid for at the unit price bid for “prestressed concrete piling” or “prestressed concrete test piling” of the size specified.

The preceding payment shall be full compensation for furnishing all prestressing steel, all materials, fabrication, transportation, erection, prestressing and for furnishing all metal encasing ducts, grout fittings, anchorage bearing plates and all tools, labor and incidentals necessary to complete the work unless otherwise specified by the OWNER.

A photograph of a long, straight concrete staircase with a green metal handrail, set against a backdrop of dense green trees and foliage. The staircase is made of reddish-brown concrete steps and is flanked by concrete curbs. The handrail is a bright green color and runs down the center of the stairs. The surrounding area is filled with lush green trees and bushes, with some fallen leaves scattered on the ground.

Division 800

Miscellaneous Construction and Materials

DIVISION 800 MISCELLANEOUS CONSTRUCTION & MATERIALS

TABLE OF CONTENTS

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
801.	<u>BARRIERS, WARNING AND DETOUR SIGNS, AND FENCES</u>	<u>801-1 to 801-6</u>
801.1.	<u>Barriers and Warning and Detour Signs</u>	
801.2.	<u>Metal Beam Guard Fence</u>	
801.3.	<u>Railing</u>	
801.4.	<u>Chain Link Fence</u>	
801.5.	<u>Wire Fence</u>	
802.	<u>STEPS AND RETAINING WALLS</u>	<u>802-1 to 802-8</u>
802.1.	<u>Concrete Steps</u>	
802.2.	<u>Concrete Retaining Walls</u>	
802.3.	<u>Segmental Retaining Wall Systems</u>	
802.4.	<u>Cofferdams</u>	
803.	<u>SLOPE AND CHANNEL PROTECTION</u>	<u>803-1 to 803-9</u>
803.1.	<u>Articulating Concrete Block</u>	
803.2.	<u>Gabion Structures</u>	
803.3.	<u>Riprap</u>	
803.4.	<u>Geotextiles Used in Drainage and Stabilization Applications</u>	
804.	<u>PAINTING AND OTHER PROTECTIVE TREATMENTS; PAVEMENT MARKING</u>	<u>804-1 to 804-7</u>
804.1.	<u>Description</u>	
804.2.	<u>Painting and Marking</u>	
804.3.	<u>Galvanizing</u>	
804.4.	<u>Measurement and Payment</u>	
804.5.	<u>Specialty Coatings</u>	
805.	<u>ELECTRICAL COMPONENTS AND CONDUIT</u>	<u>805-1 to 805-3</u>
805.1.	<u>Description</u>	
805.2.	<u>General Requirements for Electrical Components</u>	
805.3.	<u>Materials</u>	
805.4.	<u>Conduit Construction Methods</u>	
805.5.	<u>Measurement and Payment</u>	
806.	<u>METAL MATERIALS</u>	<u>806-1 to 806-3</u>
806.1.	<u>General</u>	
806.2.	<u>Structural Steel</u>	
806.3.	<u>Forgings</u>	
806.4.	<u>Castings</u>	
806.5.	<u>Copper</u>	
806.6.	<u>Bolts, Nuts, and Washers</u>	
806.7.	<u>Measurement and Payment</u>	

ITEM 801. BARRIERS, WARNINGS AND DETOUR SIGNS, AND FENCES

801.1. BARRIERS AND WARNING AND DETOUR SIGNS

801.1.1. Description. This item shall consist of the basic requirements which the CONTRACTOR must comply with in order to assure the safety of the public, the OWNER and the CONTRACTOR'S employees. The type and location of signs and barriers shall be provided as required in [Item 107.19](#), Public Convenience and Safety and [Item 107.20](#), Protection Work and of Persons and Property. Additional signs and/or barriers shall be erected if so directed by the OWNER in writing.

801.1.2. General. The amount of street space taken up by construction and maintenance work should be not more than is absolutely necessary, though this does not justify any failure to use such signs, warning devices and channelization as may be required in the roadway for public protection and guidance. The CONTRACTOR shall be held responsible for all damage to the work due to failure of barricades, signs, lights and watchmen to protect it. Whenever evidence is found of such damage, the OWNER may order the damaged portion immediately removed and replaced by the CONTRACTOR at its cost and expense. The CONTRACTOR'S responsibility for the maintenance of barricades, signs and lights and for providing watchmen shall not cease until the project is finally accepted by the OWNER.

801.1.3. Payment. The furnishing, placing and maintaining of barriers, warning devices, detour devices, lights, signs, or other precautionary measures required by law or by the OWNER for the protection of persons or property shall be paid for at the contract unit price for the time they are maintained by the CONTRACTOR until the project is finally accepted by the OWNER.

801.2. METAL BEAM GUARD FENCE

Metal beam guard fence shall conform to TxDOT Item 540. Metal Beam Guard Fence and current version of TxDOT CAD Standard Drawing Metal Beam Guard Fence (MBGF).

801.3. RAILING

801.3.1. Description. This item shall govern for the construction of steel, aluminum, cast iron or pipe railing, including necessary anchorages on bridges, walls or incidental structures as designated on the plans. For concrete railing, refer to TxDOT Item 450.3. Construction, Section B. Concrete Railing.

801.3.2. Materials. All materials shall conform to the requirements of [Item 806](#), Metal Materials.

Railing materials shall be stored above the ground on platforms, skids or other supports. The materials shall be kept free from grease, dirt and contact with dissimilar metals. Care shall be taken at all times to avoid scratching, marring, denting, discoloring or otherwise damaging the railing. Unpacking and storing of rail members, upon arrival at the job site, shall be in accordance with manufacturer's recommendations.

801.3.3. Construction Methods. Railing shall be of size and type shown on the plans and constructed in accordance with details shown on the plans and in conformance with the requirements herein. It shall be constructed to the alignment, grade and camber as designated on the plans. Shop fabricated railing shall be of such uniformity as to insure good joints and continuous lines after erection. Any appreciable amount of cutting, bending or filling required on erection to produce a reasonable fit shall be cause for rejection of the rail. Unless otherwise shown on the plans, rail posts shall be erected plumb, with the top rails parallel to the roadway grade indicated on the plans or to the surface of the structure on which the rail is mounted. The fabrication and erection of metal for railing shall conform to the pertinent provisions of [Item 703.3](#), Steel Structure Construction, and to the requirements of this specification.

Shop drawings shall be prepared and forwarded for approval in accordance with the requirements of [Item 703.3](#), Steel Structure Construction. Splicing of members shall be permitted only as provided by the contract plans.

Splices shall be at rail posts only. All splice locations and details shall be shown on the shop drawings.

The vertical members of the railing may be placed in the correct position and alignment at the time of placing the concrete, or oversize sleeves may be embedded in the proper location and position for subsequent installation of the railing in the sleeves. If sleeves are used, the railing shall be placed in the sleeves and set with molten sulfur compound.

Unless otherwise indicated, aluminum members shall be separated from concrete or steel by a bearing pad conforming to the requirements for preformed rubber fabric pads as described in [Item 703.3](#), Steel Structure Construction. The material shall be 1/8-in. in thickness, unless otherwise specified. All welding shall conform with the recommendations of the American Welding Society. Welding of aluminum material shall be done by an inert gas shielded electric arc welding process in which no flux is used. Torch or flame cutting of aluminum shall not be permitted.

After erection, the railing shall be painted with one prime coat of the type of paint specified on the plans and two field coats of aluminum paint conforming to the requirements of [Item 804.2](#), Painting and Marking. Aluminum railings shall not require field painting. Prior to acceptance, all extrusion marks, grease, dirt and grime shall be cleaned from aluminum railing.

Steel railing shall be given a top coat of the type of paint specified on the plans. This coating shall be of sufficient quality and coverage to protect the metal from corrosion. After erection, the railing shall be cleaned, spot painted and painted in accordance with [Item 804.2](#), Painting and Marking.

If galvanized rail is used, all parts of the rail on which the galvanizing has become scratched, chipped or otherwise damaged shall be thoroughly cleaned painted according to the requirements of [Item 804.3.5](#), Repair of Damaged Zinc Coating. No compensation shall be made for repairing damaged coatings.

Unless otherwise provided, railing shall not be placed until after the false-work for the span has been released. During the construction of railing, care shall be exercised to insure proper functioning of expansion joints, if any.

801.3.4. Measurement and Payment. Railing shall be measured as the number of linear feet of satisfactorily completed railing. Payment shall be made at the contract price bid per linear foot for "railing," which price shall be full compensation for all pipe structural shapes, paint, labor, tools and equipment, and all incidentals necessary for completing the railing in conformity with the plans and these specifications.

801.4. CHAIN LINK FENCE

801.4.1. Description. This item shall consist of one line of chain link fabric supported on posts and constructed as prescribed by this specification at such places as shown on the plans or as designated by the OWNER. The fence overall height and the fabric height shall be as shown on the plans.

801.4.2. Materials. This item covers materials used to construct chain link fencing in accordance with the plans and any typical details which may be shown on the plans. All fence materials furnished shall be in accordance with these specifications, unless otherwise shown on the plans. Failure to meet any of the specifications contained in this section or on the plans shall be cause for rejection and materials shall be replaced at no cost to the OWNER.

801.4.2.1. Chain Link Fencing Fabric. The base metal of the fabric shall be a good commercial quality of steel wire. The wire shall be woven throughout in the form of approximately uniform square mesh, having parallel sides and horizontal and vertical diagonals of approximately uniform dimensions. The top and bottom of the fabric shall be knuckled or barbed as specified. The sizes of wire and mesh shall be as specified. The entire fabric shall be one of the following types:

- (1) zinc coated in accordance with ASTM A392 Zinc-Coated Steel Chain-Link Fence Fabric and [Item 804.3](#), Galvanizing;
- (2) aluminum coated in accordance with ASTM A491 Standard Specification for Aluminum-Coated Steel Chain-Link Fence Fabric; or
- (3) PVC vinyl coated in accordance with ASTM F668 Standard Specification for Poly (Vinyl Chloride) (PVC) and Other Organic Polymer-Coated Steel Chain-Link Fence Fabric and colored in accordance with ASTM F934 Standard Specification for Standard Colors for Polymer-Coated Chain Link Fence Materials.

801.4.2.2. Posts. Posts may be rolled, formed or tubular in cross section and shall be in accordance with ASTM F1043 Strength and Protective Coatings on Metal Industrial Chain Link Fence Framework. All posts shall meet the weight and length requirements as shown on the plans.

801.4.2.3. Rails, Gates, Braces and Fittings. Rails, gates and braces may be rolled, formed or tubular in cross section and shall be in accordance with ASTM F1083 Standard Specification for Pipe, Steel,

Hot-Dipped Zinc-Coated (Galvanized) Welded, for Fence Structures. Colored rails, gates, and braces shall be in accordance with ASTM F1043 Strength and Protective Coatings on Metal Industrial Chain Link Fence Framework. Fittings and appurtenances shall be in accordance with ASTM F626 Standard Specification for Fence Fittings.

801.4.2.4. Concrete. Concrete footings shall be Class B or Class PB, as specified by the OWNER, in accordance with [Item 702](#), Concrete Structures.

801.4.3. Construction Methods.

801.4.3.1. General. The chain link fence shall be constructed in accordance with the details on the plans and ASTM F567 Standard Practice for Installation of Chain-Link Fence, and as specified herein, with new materials unless specified otherwise. Chain Link Fence for Tennis Courts shall be constructed in accordance with ASTM F969 Standard Practice for Construction of Chain-Link Tennis Court Fence. Chain link fence for ballfields and other sports facilities shall be constructed in accordance with ASTM F2000 Standard Guide for Fences for Ballfields and Other Sports Facilities. All work shall be performed in a workmanlike manner satisfactory to the OWNER. Prior to the beginning of the work, the CONTRACTOR shall locate the position of the work by establishing and marking the line and grade for the fences according to the plans.

801.4.3.2. Clearing Fence Line. The site of the fence shall be sufficiently cleared of obstructions, and surface irregularities shall be graded so that the fence shall conform to the general contour of the ground. The fence line shall be cleared to a minimum width of 2-ft on each side of the centerline of the fence. This cleaning shall consist of the removal of all stumps, brush, rocks, trees or other obstructions which shall interfere with proper construction of the fence. Stumps within the cleared area of the fence line shall be grubbed or excavated.

The bottom of the fence shall be placed a uniform distance above the ground and as specified on the plans. When shown on the plans, or as directed by the OWNER, the existing fences which coincide with or are in a position to interfere with the new fence location shall be removed by the CONTRACTOR as a part of the construction work, unless such removal is listed as a separate item in the bid schedule. All holes remaining after post and stump removal shall be refilled with suitable soil, gravel or other material acceptable to the OWNER and shall be compacted properly with tampers. The work shall include the handling and disposal of all material cleared, excavated or removed, regardless of the type, character, composition or condition of such material encountered.

801.4.3.3. Installing Posts. All posts shall be spaced not more than 10-ft. apart and as shown on the plans. Terminal (end, corner, and pull) posts, gate posts and line posts shall be set in concrete footings of the diameter and depth as shown on the plans. The concrete footings for the posts shall be of sufficient depth to provide a minimum of 2-in. of concrete below the bottom of the posts. The top of the concrete footings shall be slightly above the ground and sloped to drain away from the posts. Holes of full depth and size for the concrete footings for posts shall be dug to the size and depth as shown on the plans. All post settings shall be made carefully so that all posts shall be vertical, in true alignment, centered in the footing, and rigidly secured in position. On terminal (end, corner, and pull) posts and gate posts, the post tops and brace rail clamps around the posts shall be placed before setting the posts in the concrete footings or at such a time that heavy clamps can be installed without spreading them to accommodate the post.

In setting the gate posts, great care must be taken to make sure that gate posts are set apart by the distance shown on the plans. A line drawn across from the top of one gate post to the other must be level regardless of the grade of the groundline. If the ground is not level, the upgrade posts shall be set first to get the proper height for the downgrade gate post. The concrete for post setting shall be allowed to cure for 3-days. Stretcher bar bands and truss bands shall be spread and slipped on end, corner, pull, brace and gate posts as the next operation. Post tops are then inserted on all other posts. Pull posts shall be placed not over 500 ft. apart in straight runs and at each vertical angle point, all as directed by the OWNER. Corner posts shall be placed at each horizontal angle point. Corner and pull posts shall have horizontal braces and truss rods as shown on the plans or as specified. Posts to be

placed in concrete structures shall be placed in previously embedded oversize pipe sleeves and then packed with sulfur compound.

801.4.3.4. Installing Fabric. The fabric shall be placed on the outward facing side of the posts and shall be installed so that the top edge projects over the top rail of the fence. The fabric shall be stretched taut and securely fastened to the post, the top rail and the bottom tension wire. The tension wire shall be installed parallel to the line of the fabric. The bottom of the fabric shall extend to within 2-in. of the natural ground or paved surface. However, over irregular ground, this distance may vary between 1-in. and 6-in. for a distance not to exceed 8-ft. High points of ground shall be excavated to clear the bottom of the fabric; depressions shall be filled and compacted to within 2-in. of the bottom fabric; both shall be considered as incidental work. In locations where chain link fence is installed as a guard or barrier in or on concrete structures such as retaining walls and headwalls, the fabric shall extend to within 6-in. above the concrete surface for structures.

The fabric shall be fastened to end, corner, slope and gate posts with high carbon steel tension bars and steel tension bar bands spaced at 16-in. intervals; and to line posts, top rail and tension wire with tie wires or metal bands. Tie wires or metal bands shall be placed on line posts at intervals of approximately 16-in. and top rail and tension wire at intervals of approximately 24-in.

801.4.3.5. Installing Gates. The widths of any gates to be installed shall be indicated on the plans or in the special provisions.

Gates with fabric 7-ft or more in height shall have a horizontal stiffener. Vertical stiffeners shall be installed at a maximum of 8-ft. centers. A $\frac{3}{8}$ -in. adjustable tension rod shall be installed on all gates over 4-ft. in width. The corners of gate frames shall be fastened together and reinforced with a fitting designed for the purpose or by welding. All welds shall be ground smooth.

Chain link fence fabric shall be attached to the gate frame by the use of tension bars and tie wires as specified and by suitable tension connectors spaced at approximately 16-in. intervals. The swing gates shall be hung up by at least two (2) steel or malleable iron hinges, so designed as to securely clamp to the gate post and permit the gate to be swung back 180° from the closed position. Gates shall be provided with a combination steel or malleable iron catch and locking attachment of approved design. Stops to hold gates open and a center rest with catch shall be provide where required.

801.4.3.6. Existing Fence Connections. Wherever the new fence joins an existing fence, either at a corner or at the intersection of straight fence lines, a corner post with a brace post shall be set at the junction and braced the same as for corner posts. If the connection is made at other than the corner of the new fence, the last span of the old fence shall contain a brace span.

801.4.3.7. Repair of Damaged Coating. On all galvanized parts where zinc coating has been omitted, chipped off or removed, the steel or iron left exposed shall be repaired. Damaged zinc coating shall be repaired by cleaning and coating according to the requirements of [Item 804.3.5](#). Repair of Damaged Zinc Coating. No compensation shall be made for repairing damaged coatings.

801.4.4. Measurement and Payment. Chain link fence shall be measured in place from center to center of end posts or corner post and shall be the length of fence actually constructed, except the space occupied by the gates. Gates shall be measured in units for each gate installed and accepted.

Payment shall be made at the contract price per linear foot for chain or guard-link fences. This price shall be full compensation for furnishing all material; for all preparation, erection and installation of these materials; and for all labor, equipment, tools and incidentals necessary to complete the work.

Payment shall be made at the contract unit price per each for gates. This price shall be full compensation for furnishing all materials; for all preparation, erection and installation of these materials; and for all labor, equipment, tools and incidentals necessary to complete the work.

Gates measured as provided in this item shall be paid for at the unit price bid for "gate" of the type, height and opening shown on the plans, which price shall be full compensation for furnishing all materials; fabricating; all preparation, hauling, and erection; and for all labor tools, equipment and incidentals necessary for a complete in- place gate installation.

801.5. WIRE FENCE

801.5.1. Description. “Wire fence” shall consist of constructing fence supported on metal or wood posts in accordance with the details and at the locations shown on the plans. The fence shall consist of woven wire fence fabric with or without barbs as specified on the plans.

801.5.2. Materials. This item covers materials used to construct wire fencing in accordance with the plans and any typical details which may be shown on the plans. All materials furnished shall be in accordance with these specifications unless otherwise shown on the plans. Failure to meet all of the specifications contained in this section shall be cause for rejection and materials shall be replaced at no cost to the OWNER.

801.5.2.1. Wire Fencing Fabric. The base metal of the fabric shall be of a good commercial quality of steel or iron as specified. The wire shall be the height and design shown on the plans. The top and bottom wires shall be a minimum No. 10 AWS gauge, and the intermediate wires and vertical stays shall be No. 12½ AWS gauge. The entire fabric shall be zinc coated in accordance with ASTM A116 Zinc-Coated (Galvanized) Steel Woven Wire Fence Fabric and [Item 804.3](#). Galvanizing.

801.5.2.2. Posts.

801.5.2.2.1. Metal. Metal posts may be rolled, formed or tubular in cross section and shall be in accordance with ASTM A702 Standard Specification for Steel Fence Posts and Assemblies, Hot Wrought. All posts shall meet the weight and length requirements as shown on the plans. All posts not galvanized shall be painted with an anti-corrosive paint approved by the OWNER.

801.5.2.2.2. Wood. Wood posts shall be the length and dimensions shown on the plans. The timbers shall be sound and free from all decay, shakes, splits, unsound or excessive knots or any other defects that might impair their strength or durability. Knots shall not exceed one-third of the small dimension or diameter of the post. A line drawn between the center of each end shall not fall outside the center of the post at any point more than by 2-in. Knots shall be trimmed flush and the ends cut square. Untreated posts may be cedar, redwood, cypress or live oak. Treated posts may be pine, spruce or fir. Posts shall be preservative treated according to American Wood-Preservers' Association (AWPA) Standards.

801.5.2.3. Rails, Gates, Braces and Fittings. Rails, gates, and braces may be rolled, formed or tubular in cross section and shall be in accordance with ASTM F669 Strength Requirements of Metal Posts and Rails for Industrial Chain Link Fence. Fittings and appurtenances shall be in accordance with ASTM F626 Fence Fittings. All rails, braces and fittings not galvanized shall be painted with an anti-corrosive paint approved by the OWNER.

801.5.2.4. Barbed Wire. Barbed wire shall be two strand twisted No. 12½ AWS gauge galvanized steel wire with two-point barbs of No. 14 AWS gauge galvanized steel wire and conforming to Class 1 ASTM A121 Metallic Coated Steel Barbed Wire.

801.5.3. Construction Methods. Fence posts shall be spaced at intervals as shown on the plans and set to a minimum depth of 2-ft for wood posts and 2½-ft. for metal posts. Posts shall be set in a vertical position. Corner and pull posts shall be braced in two (2) directions. End and gate posts shall be braced in one (1) direction. Where alignment changes 30° or more, a corner post shall be installed. At alignment angles varying from 15° to less than 30°, the angle post shall be braced to adjacent line posts by diagonal tension wires. Where steel posts are specified, a pull post assembly shall be installed at approximately 500-ft. intervals; where wooden posts are specified, the spacing of pull-post assemblies shall be approximately 1,000-ft. Metal line posts may be driven in place, provided such driving does not damage the posts. Metal corner, end, pull post and braces shall be set in portland cement concrete footings crowned at the top to shed water. All posts shall be placed the minimum depth below ground. Posts shall be set plumb and firm to the line shown on the plans. Backfill shall be thoroughly tamped in 4-in. layers. The timber post braces shall be notched.

The corner, end angle post assembly shall be installed before stretching the wire between the posts. At all grade depressions where stress tends to pull the posts out of the ground, the fencing shall be snubbed or guyed at the critical point by means of a double No. 9-gauge galvanized wire connected to each horizontal line of barbed wire or to the top and bottom wire or wire mesh fabric and to a deadman weighing not less

than 100-lb., buried in the ground. The fencing shall be stretched before being snubbed and guyed. Existing cross fences shall be connected to the new fences and corner posts with braces which shall be placed at junctions with existing fences. The barbed wire and wire fabric shall be drawn taut and fastened to posts with galvanized ties or staples.

801.5.4. Measurement and Payment. Fencing shall be measured by the linear foot of wire fence, measured at the bottom of the fabric along the centerline of the fence from center to center of end posts, excluding gates. Gates shall be measured per each gate, complete in place.

The work performed and material furnished as prescribed by this item, measured as provided in this item, shall be paid for at the unit price bid for "wire fence," which price shall each be full compensation for furnishing and installing all fencing materials (except gates); for all preparation, hauling and installing of same; and for all labor, tools, equipment and incidentals necessary to complete the work, including excavation, backfilling and disposal of surplus material.

Gates measured as provided in this item shall be paid for at the unit price bid for "gate" of the type, height and opening shown on the plans, which price shall be full compensation for furnishing all materials; fabricating; all preparation, hauling and erection; and for all labor, tools, equipment and incidentals necessary for a complete in place gate installation.

ITEM 802. STEPS AND RETAINING WALLS

802.1. CONCRETE STEPS

802.1.1. Description. This item shall govern the construction of reinforced concrete steps with or without buttress walls at the location(s) shown on the plans or as directed by the OWNER.

802.1.2. Materials. Material requirements shall be the same as those for [Item 303](#). Portland Cement Concrete Pavement.

802.1.3. Construction Methods.

802.1.3.1. General. Concrete steps shall be constructed at the location(s) shown on the plans or as directed by the OWNER and as detailed on the plans.

802.1.3.2. Finishing. Concrete steps may be finished by the use of mortar topping and shall be troweled and lightly brushed.

802.1.3.3. Curing. Concrete steps shall be cured in accordance with the requirements of [Item 305.1](#). Concrete Curb and Gutter.

802.1.4. Measurement and Payment. Concrete steps shall be measured by the sq.ft. of tread complete in place. If buttress walls are included, they shall be measured by the sq.ft. of wall top.

Concrete steps and buttress walls shall be paid for at the contract unit price bid, which price shall be full compensation for all excavation sand cushion; furnishing and placing all materials, including reinforcement and expansion joint material; and for all labor, tools, equipment and incidentals necessary to complete the work.

802.2. CONCRETE RETAINING WALLS

802.2.1. Description. This item shall govern the construction of concrete retaining walls of the size and shape detailed on the plans and at the location(s) shown on the plans. The requirements of [Item 701.2](#). Structural Removal, Excavation, and Backfill, shall apply to the construction of retaining walls.

802.2.2. Materials.

802.2.2.1. Concrete. Concrete shall be of the grade specified on the plans and shall conform to the requirements of [Item 702](#). Concrete Structures.

802.2.2.2. Reinforcing Steel. Reinforcing steel shall be of the size and type shown on the plans.

802.2.3. Construction Methods. Concrete retaining walls shall be constructed in accordance with the details shown on the plans and in conformance with the requirements of [Item 701.2](#). Structural Removal, Excavation, and Backfill, and [Item 702](#). Concrete Structures.

802.2.4. Measurement and Payment. Concrete used in the construction of retaining walls shall be measured by the cubic yard. Calculations shall be based upon plan dimensions and quantities.

Structural excavation shall be measured in accordance with [Item 701.2](#). Structural Removal, Excavation, and Backfill.

Reinforcing steel shall be measured by unit weight or as specified on the plans.

Payment for all work prescribed under this item shall be made at the unit prices bid for the various items. This price shall be full compensation for all labor, tools, equipment, materials and incidentals necessary to complete the work.

When pay items are not provided for structural excavation and/or reinforcing steel, these items shall be subsidiary to the pay item for concrete for retaining walls.

802.3. SEGMENTAL RETAINING WALL SYSTEMS

802.3.1. Description. This item shall govern furnishing and installing segmental retaining wall (SRW) units to the lines and grades designated on the construction drawings or as directed by the OWNER. Site preparation, furnishing appurtenant materials, and installing appurtenant materials required for construction of the retaining wall as shown on construction plans and drawings are also included.

802.3.2. General. Segmental retaining wall systems are to be engineered on a site-specific basis only. The OWNER shall specify the special material and construction requirements for each location. Should the soil

conditions encountered during construction differ from those used for the design, the OWNER shall review the design, and provide the CONTRACTOR with any design revisions.

Wall systems that are found to be deficient and not in conformance with the construction drawings must be corrected at the CONTRACTOR'S expense.

802.3.3. Materials.

802.3.3.1. General. The CONTRACTOR shall submit manufacturers' certifications two weeks prior to start of work stating that the SRW units and geotextile reinforcement meet specified requirements. The CONTRACTOR shall furnish one (1) unit in the color and face pattern specified by the OWNER for approval. The approved unit shall be one of three (3) replacement units that the CONTRACTOR shall furnish the OWNER. The CONTRACTOR shall also furnish a square 12-inches-per-side or larger piece of the geotextile reinforcement specified if requested by the OWNER.

802.3.3.2. Delivery, Storage and Handling. The CONTRACTOR shall check materials upon delivery to assure that specified type and grade of materials have been received and proper color and texture of SRW units have been received. SRW units shall be sound and free of cracks or other defects that would interfere with the proper placing of the unit or significantly impair the strength or permanence of the structure. Units showing cracks longer than ½-inch shall not be used within the wall.

Retaining wall units shall be stored above ground on wood pallets or blocking, shall protect materials from damage, and shall prevent excessive mud, wet cement, epoxies, and like materials which may affix themselves from coming in contact with retaining wall materials.

802.3.3.3. Segmental Retaining Wall (SRW) Systems.

802.3.3.3.1. Unit Production. Color, texture, finish, face pattern geometry, type (solid or hollow), strength and structural requirements, maximum moisture absorption, size and weight dimensions and ratios of SRW units shall be specified per project and indicated on the plans. If units are not solid, fill which is contained within the dimensions of the units shall be included as effective weight. SRW units shall include an integral concrete shear connection flange/locator or pins, clips or some other device to provide proper setback and shear resistance.

Segmental retaining wall units shall be machine formed, Portland cement concrete blocks specifically designed for retaining wall applications and shall conform to applicable standards in Table 802.3.3.3.1.(a) Segmental Retaining Wall Unit Standards. Where values specified on the plans disagree with referenced standards, the plans shall take priority. All vertical surfaces that will be exposed after completion of wall shall have a split face, textured surface.

Table 802.3.3.3.1.(a) Segmental Retaining Wall Unit Standards

Standard Designation	Topic
ASTM C90 Standard Specification for Load bearing Concrete Masonry Units	Hollow Load Bearing Masonry Units
ASTM C1262 Test Method for Evaluating the Freeze-Thaw Durability of Dry Cast Segmental Retaining Wall units and Related Concrete Units	Freeze-Thaw Durability of Manufactured Concrete Masonry Units and Related Concrete Units
ASTM C1372 Standard Specification for Segmental Retaining Wall Units	Segmental Retaining Wall Units

802.3.3.3.2. SRW System Testing. Segmental retaining wall system testing shall conform to standards listed in Table 802.3.3.3.2.(a) Segmental Retaining Wall Unit Tests. Compressive strength test specimens shall conform to the saw-cut coupon provisions of Section 5.2.4 of ASTM C140 Test Methods for Sampling and Testing Concrete Masonry Units and Related Units, with the following exception: Coupon shall be taken from the least dimension of the unit of a size and shape representing the geometry of the unit as a whole.

Table 802.3.3.3.2.(a) Segmental Retaining Wall Unit Tests

Test Designation	Topic
National Concrete Masonry Association SRWU-1	Test Method for Determining Connection Strength of Segmental Retaining Wall
National Concrete Masonry Association SRWU-2	Test Method for Determining Shear Strength of Segmental Retaining Wall
ASTM C140 Standard Test Methods for Sampling and Testing Concrete Masonry Units and Related Units	Sampling and Testing Concrete Masonry Units

802.3.3.3.3. Backfill Soils. The backfill soils shall be tested in accordance with the standards listed in Table 802.3.3.3.3.(a) SRW Backfill Soil Tests.

Table 802.3.3.3.3.(a) SRW Backfill Soil Tests

Test Designation	Title
ASTM D698	Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft ³)
ASTM D422	Standard Test Method for Particle-Size Analysis of Soils
ASTM D4318	Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils

Backfill soil shall be free of debris. Native materials may be used provided they meet design criteria unless otherwise specified. The backfill material shall consist of the inorganic USCS soil types GP, GW, SW, SP, SM meeting the gradation described in Table 802.3.3.3.3.(b) SRW Backfill Soil Gradation, as determined in accordance with ASTM D422. The maximum particle size of poorly graded gravels (GP) (no fines) should not exceed ¾-in (1.9-cm) unless field tests have been performed to evaluate potential strength reductions to the geotextile due to damage from larger sized aggregate. The plasticity of the fine fraction shall be less than 20.

Table 802.3.3.3.3.(b) SRW Backfill Soil Gradation

Sieve Size	Percent Passing
2-in	100
¾-in	100-75
No. 40	0-50
No. 200	0-35

802.3.3.3.4. Drainage Aggregate. Aggregate shall be angular, clean stone or granular fill meeting the gradation in described in Table 802.3.3.3.4.(a) SRW Drainage Aggregate Gradation as determined in accordance with ASTM D422.

Table 802.3.3.3.4.(a) SRW Drainage Aggregate Gradation

Sieve Size	Percent Passing
1-in	100
¾-in	75-100
No. 4	0-60
No. 40	0-50
No. 200	0-5

802.3.3.3.5. Drainage Pipe. Pipe shall be a perforated or slotted PVC, or corrugated HDPE pipe, and shall meet relevant requirements under [Item 501](#), Underground Conduit Materials. Owner may require video inspection of completed underdrain.

802.3.3.3.6. Leveling Pad/Base. Material for leveling pad (base) shall be as shown on the construction drawings. Material may consist of compacted sand, gravel, crushed stone or combination thereof. Lean, unreinforced concrete with a strength of 200-psi to 300-psi may also be used as a leveling pad material. A reinforced footing may also be required.

802.3.3.3.7. Geotextiles. Geotextile reinforcement used in segmental retaining wall systems may consist of polyester fiber geogrid or geotextile, polyethylene expanded sheet geogrid, polypropylene woven geotextile or other appropriate geotextiles manufactured for use as soil reinforcement. Geotextile manufacture shall conform to applicable standards. The geotextile manufacturer shall have a manufacturing quality control program that includes independent laboratory testing of Tensile Strength, Melt Flow Index (HDPE), and Molecular Weight (Polyester). Geotextile testing shall conform to standards Table 802.3.3.3.7.(a) SRW Geotextile Tests.

Geotextiles used for segmental retaining walls shall resist peeling, cracking, and stripping, and shall be treated as necessary to meet this requirement.

Table 802.3.3.3.7.(a) SRW Geotextile Tests

Test Designation	Title/Topic
ASTM D4595	Standard Test Method for Tensile Properties of Geotextiles by the Wide-Width Strip Method
ASTM D5262	Test Method for Evaluating the Unconfined Tension Creep Behavior of Geosynthetics
Geosynthetic Research Institute GRI-GG4	Determination of Long Term Design Strength of Geogrids
Geosynthetic Research Institute GRI-GG5	Determination of Geogrid Pullout
National Concrete Masonry Association SRWU-1	Test Method for Determining Connection Strength of SRW

802.3.4. Construction Methods. Construction methods for each type unit shall be provided by the manufacturer and approved by the OWNER based on the site-specific use.

802.3.4.1. Inspections. The CONTRACTOR shall examine the areas and conditions under which the retaining wall is to be erected and notify the OWNER in writing of conditions detrimental to the proper and timely completion of the work. Work shall not proceed until unsatisfactory conditions have been corrected. The CONTRACTOR shall promptly notify the OWNER of any site conditions that may affect wall performance or may require a reevaluation of the wall design.

CONTRACTOR'S field construction supervisor shall have demonstrated experience and be qualified to direct all work at the site.

802.3.4.2. Excavation. Excavation shall be carried out to the lines and grades as shown on the plans and in accordance with methods in [Item 701.2](#), Structural Removal, Excavation, and Backfill.

802.3.4.3. Foundation Soil and Base Preparation.

802.3.4.3.1. Foundation Soil. Following the excavation, the foundation soil shall be examined by the OWNER to assure actual foundation soil strength meets or exceeds the assumed design bearing strength. Soils not meeting the required strength shall be removed and replaced with backfill soils, as directed by the OWNER. Foundation soil shall have adequate moisture content, be proof rolled, and compacted to 95% standard Proctor density, or density specified on the plans, and inspected by the OWNER'S Representative prior to placement of leveling pad materials. Standard Proctor density shall be determined per ASTM D698.

802.3.4.3.2. Leveling Pad/Base. Base materials shall be installed upon undisturbed soils or prepared foundation soils. The leveling pad (base) shall be placed as shown on the construction drawings with a minimum thickness of 6-in when composed of aggregate and a minimum of 3-in when composed of concrete. The leveling pad shall extend laterally at least a distance of 6-inches from the toe and heel of the lower most SRW Unit. Soil leveling pad material shall be compacted to provide a firm, level-bearing surface on which to place the first course of units. Base materials shall be prepared to ensure complete contact of retaining wall unit. When approved by the OWNER, well-graded sand may be allowed to smooth the top, but shall not exceed ½-in of leveling sand.

802.3.4.4. Segmental Retaining Wall Unit Installation. All SRW units shall be installed at the proper elevation and orientation as shown on the wall profiles and details on the construction plans or as directed by the OWNER. The SRW units shall be installed in general accordance with the manufacturer's recommendations, including the sequence of SRW unit, drainage material and backfill courses. Typically, the maximum stacked vertical height of wall units, prior to unit drainage fill and backfill placement and compaction, shall not exceed two (2) courses. The specifications and drawings shall govern in any conflict between the two (2) requirements.

Lay out of curves and corners shall be installed in accordance with the plan details or in general accordance with SRW manufacturer's installation guidelines. Walls meeting at a corner shall be interlocked and continuous.

First course of SRW units shall be leveled side-to-side, front-to-rear and with adjacent units, and aligned to ensure intimate contact with the leveling pad. Excess debris shall be cleaned from the top of units before installation of the next course.

Damaged units shall be replaced with new units during construction.

SRW units shall have positive horizontal interlock. Shear/connecting devices shall be installed according to manufacturer's recommendations.

802.3.4.5. Drainage Materials Placement. Drainage aggregate shall be installed to the line, grades, and sections shown on the final plans. All voids between and within concrete wall units shall be filled with drainage aggregate. Drainage fill shall be placed to the thickness shown on the construction plans behind units, minimum 12-in. Drainage collection pipes shall be installed to maintain gravity flow of water outside the reinforced soil zone. The drainage collection pipe shall daylight into a storm water conduit manhole or other location along a continuous slope at an elevation lower than the lowest point of the pipe within the aggregate drain, as approved by the OWNER.

802.3.4.6. Geotextile Reinforcement Placement. The type and strength of the reinforcing geotextile shall be as shown on the construction plans. All geotextile reinforcement shall be installed in accordance with manufacturer's recommendations at the proper elevation and orientation as shown on the wall profiles and details on the construction plans or as directed by the OWNER.

At the elevations shown on the final plans, the geotextile reinforcement shall be laid horizontally on compacted backfill and on top of the concrete SRW units. Embedment of the geotextile in the SRW units shall be consistent with SRW manufacturer's recommendations. Correct orientation of the geotextile reinforcement shall be verified by the CONTRACTOR to be in accordance with the geotextile manufacturer's recommendations. The highest strength direction of the geotextile must be perpendicular to the wall face.

Geotextile reinforcement layers shall be one continuous piece for the entire embedment length. Overlap of the geotextile in the design strength direction (perpendicular to the wall face) shall not be permitted.

Tracked construction equipment shall not be operated directly on the geotextile reinforcement. A minimum of 6-in of backfill is required prior to operation of tracked vehicles over the geotextile.

802.3.4.7. Backfill Placement. The reinforced backfill shall be placed as shown in the construction plans in the maximum compacted lift thickness of 10-in, or 6-in where hand compacted, and shall be compacted at a moisture content within 2% of optimum to 95% standard Proctor density, or density specified on the plans. Standard Proctor density shall be determined per ASTM D698. The backfill shall be placed and spread in such a manner as to eliminate wrinkles, movement or damage of the geotextile reinforcement and the SRW units.

Only hand-operated compaction equipment shall be allowed within 3-ft of the back of the SRW unit.

At the end of each day's operation, the CONTRACTOR shall slope the last level of backfill away from the wall units to direct water runoff away from the wall face. The CONTRACTOR shall not allow surface runoff from adjacent areas to enter the wall construction site.

At completion of wall construction, final backfill shall be placed to the lines and grades indicated on the plans.

802.3.4.8. SRW Cap Unit Installation. When SRW caps are specified, they shall be properly aligned and glued to underlying units with a suitable, flexible, high-strength all-weather adhesive recommended by the manufacturer. Rigid adhesive or mortar is not acceptable. Cap units may be cut to obtain the proper fit.

802.3.4.9. Completion. The retaining wall will not be considered complete until accepted by the OWNER.

If final grading, paving, landscaping, and/or storm drainage installation adjacent to the wall is not placed immediately after wall completion, the CONTRACTOR shall provide temporary surface drainage to ensure water runoff is not directed at the wall nor allowed to collect or pond behind the wall until final grading and surface drainage construction adjacent to the wall is completed.

CONTRACTOR shall remove debris caused by SRW construction and leave adjacent paved areas broom clean.

802.3.5. Measurement and Payment. Measurement of segmental retaining wall shall be on an installed square foot basis computed on the total face area of wall installed. Wall height is taken from the top of the leveling pad to the top of the wall.

Payment for the wall will be made on an installed square foot basis at the contract unit price. Payment shall include all labor, preparation, equipment, materials, tools, testing, and incidentals necessary to complete the work.

802.4. COFFERDAMS

802.4.1. Description. Cofferdam is a temporary watertight chamber used for construction underwater.

802.4.2. General. Cofferdams for foundation construction shall be carried well below the bottom of the footings and shall be well braced and reasonably watertight. The interior dimensions of cofferdams shall provide sufficient clearance inside the walls for constructing forms and driving piles and to permit pumping outside the forms.

If, in the judgment of the CONTRACTOR, the clearance provided on the plans between the outside line of the footing and any pipe or interior wall or surface is not sufficient to permit the driving of piles or building of forms, it may provide such necessary clearance, structuring the cofferdam sufficiently large to provide such clearance as it may deem necessary. Any such enlargement in excess of 1-ft outside the dimensions of the footing as shown on the plans shall be considered as being for the sole purpose of expediting the work of the CONTRACTOR, and such excavation and backfill shall be at the CONTRACTOR'S expense.

Cofferdams which are tilted or moved out of position by any cause during the process of sinking shall be plumbed or enlarged so as to provide the necessary clearance and proper pier location, and such work shall be at the CONTRACTOR'S expense.

In streams at a time of probable flood, cofferdam walls shall be vented at low water elevation to insure equal hydrostatic head both inside and outside of the cofferdam during the period of pouring and settings of seals.

No shoring shall be permitted in cofferdams which shall induce stress, shock or vibration in the permanent structure.

When permitted by the OWNER, cross struts or bracing may extend through foundation concrete. Struts or bracing shall be removed and the resulting space filled with concrete of the same mix as that specified for the surrounding concrete.

For substructure work, the CONTRACTOR shall submit sealed drawings prepared by an OWNER showing its proposed method of cofferdam construction and other details left open to its choice or not fully shown on the plans. The type and clearance of cofferdams, insofar as such details affect the character of the finished work, shall be subject to the approval of the OWNER, but other details of design shall be left to the CONTRACTOR who shall be responsible for the successful construction of the work. The drawings shall be submitted at least 30-days in advance of the time the CONTRACTOR begins construction of the cofferdams.

After completion of the substructure, the cofferdams with all sheeting and bracing shall be removed at least 2-ft below the level of the streambed by the CONTRACTOR at its expense, and such removal shall be performed in a manner that shall not disturb or mar the finished concrete or masonry.

802.4.3. Construction Methods.

802.4.3.1. Excavation. Excavation shall include the following:

- (1) When concrete or masonry footings are to rest upon rock, the rock shall be removed to a depth sufficient to expose sound rock. The rock shall be roughly leveled off or cut to approximate horizontal and vertical steps, and shall be roughened. Seams in the rock shall be grouted under pressure or treated as the OWNER may direct. The cost thereof shall be included for payment in the quantities for the unit of the structure for which the excavation is made. When concrete or masonry footings are to rest on an excavated surface other than rock, care shall be taken not to disturb the bottom of the excavation, and the final removal of the foundation material to grade shall not be made until just before the concrete or masonry is placed.
- (2) Excavated material required to be used for backfill may be deposited by the CONTRACTOR in storage piles at points convenient for the rehandling of the material during the backfill operations. The location of storage piles shall, however, be subject to the approval of the OWNER, who may require that the survey centerline of the structure and the transverse or hub line of any unit of the structure be kept free of any obstruction.
- (3) Excavated material required to be wasted shall be disposed of as directed by the OWNER, and the disposal shall be in such manner as not to obstruct the stream or otherwise impair the efficiency or appearance of the structure or other part of the work.
- (4) Trench safety provisions of [Item 107.20](#). Protection of Work and of Persons and Property shall be followed.
- (5) For all single and multiple box culverts, pipe culverts and pipe arch culverts, where the soil encountered at established footing grade is a quicksand, muck or similar unstable material, the following procedure shall be used unless other methods are called for on the plans: All unstable soil shall be removed below the bottom of the culvert. Such excavation shall be carried at least 1-ft beyond the horizontal limits of the surface on all sides. All unstable soil so removed shall be replaced with suitable stable material, placed in uniform layers of suitable depth for compaction as directed by the OWNER. Each layer shall be wetted, if necessary, and compacted by rolling or tamping as required to provide a stable foundation for the structure.
- (6) When the material encountered at footing grade of a culvert is found to be partially rock or incompressible materials and partially a soil or material that is compressible but otherwise satisfactory for the foundation, the incompressible material shall be removed for a depth of 6-in below the footing grade and backfilled with a material similar to the compressible foundation used for the rest of the structure.

- (7) When the material encountered at footing grade of a bridge bent or pier is found to be partially of rock or incompressible material, and partially of a compressible material, the foundation shall not be placed until the OWNER has inspected the footing and authorized such changes found necessary to provide an adequate foundation.

802.4.3.2. Backfill. No backfill shall be permitted to be placed except in the presence of the OWNER. Structural backfill shall not be placed until the structure footings or other portions of the structure or facility have been inspected by the OWNER and approved for backfilling. As soon as practicable, all spaces excavated under this item and not occupied by the permanent structure shall be backfilled, except that no backfill shall be placed until the concrete has reached the design strength required. When called for on the plans, special backfill material, such as pit run gravel, shall be placed at the locations and in the manner called for on the plans. All other backfill material shall be earth, free of any appreciable amount of stone or gravel particles more than 4-in in the greatest dimension, large or frozen lumps, wood or other extraneous material, and shall be of such gradation as to permit thorough compaction as required by the OWNER. Class C or Class PC concrete as specified by the OWNER will be used in inaccessible locations when a mechanical device cannot compact to required densities and as directed by the OWNER, i.e., under pipes, roads, washouts, paving, etc. Compaction testing will be performed by the OWNER or its approved testing laboratory. If the compacted material does not meet the specified compaction, the CONTRACTOR will be required to rework the material and pay the cost of retesting.

802.4.4. Measurement and Payment. Measurement for payment when payment is provided in the special provisions shall be for material excavated within the limits shown on the plans or as directed by the OWNER. Unless otherwise provided in the special provisions or proposals, no payment shall be made for structural excavation or backfill as such, the cost thereof under normal circumstances being considered as included in the price bid for the construction or installation of the item to which such excavation or backfill pertain. Payment shall be made only when provided for in the special provisions or proposal. When provided for, payment for work performed under this specification shall be made at the unit price bid per cubic yard for unclassified structural excavation, which price shall be full compensation for all excavation and backfill and for all materials, labor, tools and incidentals necessary to complete the work.

ITEM 803. SLOPE AND CHANNEL PROTECTION

803.1. ARTICULATING CONCRETE BLOCK

Articulating concrete blocks or block mattresses may be used for slope protection in wet or dry applications.

Cabled articulated concrete block (mattress) shall be used for underwater installations, channels or crossings.

803.1.1. Submittals. Any/all products submitted for use shall include the following:

- (1) Product Information Sheet(s) containing product description, statement of intended/ designed use of product and product photographs.
- (2) Hydraulic Stability Test Report shall be submitted which complies with the Simon's Li and Associates, Inc. test procedures under Federal Highway Guideline Report FHWA-RD-88-181 or FHWA-RD-89-199.
- (3) Suitable samples of the blocks, revetment rope, any required anchoring hardware and geotextile shall be submitted to the OWNER for approval.
- (4) Factor of Safety Calculations in accordance with Hydraulic Engineering Circular 23, FHWA HI-97-030 HEC 23, *Bridge Scour and Stream Instability Countermeasures*.
- (5) Physical Testing Reports of Sample Submittals
- (6) Detail Drawings showing:
 - (a) Hardware Anchoring Details (if applicable)
 - (b) Typical Cross-sections
 - (c) Attachment to Structures (if applicable)
 - (d) Product Shop Drawings
 - (e) Product Application on Bends (if applicable)
 - (f) Anchor Trench Details
 - (g) System Articulation (showing achievable contour radius)
 - (h) Product's ability to Expand and Contract
 - (i) Typical Interlocking Relationship of at least seven (7) Grids in an interlocked matrix.
 - (j) Grouted Seam Details (if applicable)
- (7) Any other evidence of compliance to the specifications herein and in the plans as deemed necessary by OWNER for approval.

803.1.2. Materials. The Articulating concrete block revetment system shall exhibit a capacity to withstand the specified hydraulic bed shear stress with a Factor of Safety of not less than 1.5.

803.1.2.1. Blocks, General. Manufacturer shall provide data showing manufactured products meet or exceed the specifications.

Individual grids shall consist of a homogeneous mass of consolidated concrete and shall be machine-made by a vibration and compression process composed of approved aggregates with a no-slump concrete mix. The mix water used shall be clean, fresh, free from oil, acids, soluble salts and organic impurities. Cement shall conform to ASTM C150 Portland Cement. Aggregates shall conform to ASTM C33 Concrete Aggregates.

Finished block shall meet the requirements in Table 803.1.2.1.(a) Articulating Concrete Block Requirements.

Table 803.1.2.1.(a) Articulating Concrete Block Requirements

Characteristic	Value	ASTM Designation
Compressive Strength	4000-lbs/in ² minimum	ASTM C140 Standard Test Methods for Sampling and Testing Concrete Masonry Units and Related Units
Water Absorption	7% maximum	ASTM C140 (same as above)
Specific Weight	130-lbs/ft ³ minimum	ASTM C140 (same as above)
Freeze-Thaw Durability	<1% / 50 cycles	ASTM C67 Standard Test Methods for Sampling and Testing Brick and Structural Clay Tile

Articulating concrete blocks shall meet the minimum physical characteristics as shown on the plans for the following characteristics.

- (1) Total transmissive area percentage defined as system's total open area at base and top of block.
- (2) System weight
- (3) Minimum Coverage defined as Minimum Coverage for any given block component within the system
- (4) Articulation
- (5) Block's critical shear value derived from flume testing (lbs/ft²)

803.1.2.2. Blocks, Non-cabled. The blocks shall be multi-directional, positive, interlocking type and, when installed, the interlocked grid matrix shall exhibit the ability to expand and contract with the underlying terrain.

803.1.2.3. Blocks, Cabled. The individual blocks shall exhibit the ability to physically interlock in two or more horizontal directions without requiring a connection device such as but not limited to: cables, ropes, grids or clips.

Each block shall exhibit one cable tunnel produced in a manner which provides for binding, by use of revetment cables, the blocks into an integrated matrix of grids. When installed, the interlocked grid matrix shall exhibit the ability to expand and contract with the underlying terrain.

803.1.2.4. Prefabricated Mats. Articulating concrete block revetment mats may be fabricated in widths up to 8-ft with lengths up to 40-ft or may be individually placed and post cabled. Special size and shape mats may be fabricated on-site or in-place as needed and as approved by the OWNER.

803.1.2.5. Cable and Fittings. Cable used in the fabrication of articulating concrete block revetment systems shall be made of galvanized steel aircraft cable or polyester, continuous fiber, jacketed cable with a minimum lifting safety factor of 5 to 1. All compression sleeve type fittings used to splice cable ends together shall be made of aluminum. In lieu of compression sleeves, galvanized steel "U" clips may be used.

803.1.2.6. Anchor Hardware. Articulating concrete blocks/mats anchor hardware such as but not limited to Helix Anchors, Duckbill Anchors and Shear Pins shall be specified in the plans and as approved by the OWNER, and any additional anchoring devices (other than cable) shall be of a galvanized steel type.

803.1.2.7. Geotextile (Filter Fabric) Underlayment. Filter fabric shall be a continuous sheet of woven or non-woven geotextile fabric, as selected by the OWNER and shall consist of long chain polymeric filaments, mono-filaments, or yarns such as polypropylene, polyethylene, polyester, polyamide, or polyvinylidene-chloride formed into a stable network such that the filaments or yarns retain relative position to each other.

The geotextile shall be inert to chemicals commonly encountered in natural water and soil conditions. Selection(s) of geotextile shall be made by the OWNER in accordance to a gradation and permeability analysis of the soil and/or fill material on which the grids are to be placed. When woven geotextile is used, the side edges of the panels shall be selvaged or otherwise finished to prevent filaments from pulling away from the edges.

The geotextile shall meet or exceed the minimum requirements in Table 803.1.2.7.(a) Articulated Concrete Block Revetment System Geotextile Requirements.

Table 803.1.2.7.(a) Articulated Concrete Block Revetment System Geotextile Requirements

Characteristic	Value	Standard Test Method
Mullen Burst	* (psi)	ASTM D3786 Hydraulic Bursting Strength of Textile Fabrics-Diaphragm Bursting Strength Tester Method
Trapezoidal Tear	* (lbs)	ASTM D4533 Trapezoid Tearing Strength of Geotextiles
Apparent Opening Size	min 10 sieve number	ASTM D4751 Determining Apparent Opening Size of a Geotextile
Flow Rate	min 70-gal/ft/min	ASTM D4491 Water Permeability of Geotextiles by Permittivity
Permittivity	* (min)	ASTM D4491 Water Permeability of Geotextiles by Permittivity

**These values are to be determined by the Project Engineer*

803.1.3. Articulating Concrete Block Revetment System Construction.

803.1.3.1. Preparation of Surface. All side slope to bed slope radius transitions shall be equal to or greater than the specified block's minimum articulation radius. Areas on which geotextile and articulating concrete blocks are to be placed shall be constructed to the lines and grades shown on the plans. Where such areas are below the allowable grade they shall be brought to grade by placing layers not to exceed 8-in of select material and compacted. The depth of layers and amount of compaction shall be as required to obtain a density equal to the adjoining undisturbed soil, or as specified by the OWNER. All obstructions, such as but not limited to: roots, lumps and projecting stones, shall be removed; and soft or low-density pockets of material shall be removed with the resulting void to be filled with select, compacted material.

The finished sub-grade shall be constructed to exhibit a raked, rolled or otherwise smooth planar profile from a 0-in to + $\frac{1}{2}$ -in tolerance within a 10-ft straight edge. The subgrade for the cellular concrete blocks shall be free of voids, pits and depressions. Obstructions, such as roots and projecting stones larger than 1-in remaining on the surface, shall be removed. Depressions or areas where obstructions have been removed shall be filled with select material, brought to grade and compacted to plus or minus 3% of a 95% standard proctor density.

Immediately prior to placing the geotextile and cellular blocks, the prepared area shall be inspected by the OWNER and approved before the fabric or blocks are placed thereon.

803.1.3.2. Geotextile Placement. Geotextile shall be placed within the limits shown on the plans. It shall be placed directly on the prepared area. Longitudinal and transverse joints shall be overlapped at least 2-ft. Panels shall be placed so that the upstream strip of fabric will overlap the downstream strip. Securing staples, as needed, shall be inserted through both strips of overlapped fabric along one line through the midpoint of the overlap as needed to temporarily hold panels in place until the subsequent courses of materials can be placed. Each securing staple shall be pushed through the fabric until it bears against the fabric and secures it firmly to the ground. Job site sewing of fabric panels shall be allowed in lieu of overlapping methods as approved by OWNER.

803.1.3.3. Placement of Articulated Concrete Blocks and Mats. Articulating concrete block, revetment blocks, or mats shall be placed within the limits shown on the plans in a manner that produces a level surface.

803.1.3.3.1. Blocks. The Articulating Concrete Blocks shall be placed individually on the geotextile in such a manner as to produce a continually interlocking surface free from field seams and non-interlocked connections, except as approved by the OWNER and/or as shown in the plans. Articulating concrete blocks shall be constructed within the specified lines and grades shown on the plans.

803.1.3.3.2. Mats. Articulating concrete block revetment mats shall be attached to a spreader bar or other approved device and placed on the prescribed area by use of a crane or other approved equipment. The mats shall be placed side by side within a maximum distance of 2-in of each other; any voids greater than 2-in shall be grouted with approved material. When placing mats end to end, a gap of 4-in to 6-in shall be left as to enable connection of mat end loops from one mat to the other (the resulting voids shall be grouted with approved material).

803.1.3.4. Anchoring Articulated Concrete Block and Mat. Articulating concrete block revetment systems shall be anchored according to the plans.

803.1.3.4.1. Trenches. Anchor trenches such as toe trenches, top trenches, upstream termination trenches and downstream termination trenches shall be according to the plans.

803.1.3.4.2. Anchor Hardware. Anchoring devices used in the laboratory testing shall be installed in the field in accordance with the manner in which they were used during the hydraulic stability testing.

803.1.3.5. Finishing Articulating Concrete Blocks and Mats. Articulated concrete blocks that are below the normal waterline and exhibit an average open area greater than 5% shall be backfilled with crushed stone as approved by the OWNER.

Open cell articulating concrete blocks that are above the normal waterline shall be overfilled with material approved by the OWNER to a minimum depth of 35% of the specified block vertical thickness above the grid top surfaces. The surface shall subsequently be hydraulically seeded with a wood fiber mulch and binding agent combination meeting the requirements of [Item 204.6.4.4](#). Hydraulic Mulching acceptable to the OWNER at a rate of 2000- to 2500-lbs./acre with fertilizer and seed added at a rate specified in the plans.

803.2. GABION STRUCTURES

803.2.1. Description. Gabions consist of rectangular, compartmented wire baskets filled with stone used for slope or bank protection and erosion control on open channels. This item shall govern the materials, construction and assembly of gabion structures conforming to the lines, grades, locations and designs as indicated on the plans and specifications, or as established by the OWNER.

803.2.2. Materials. Geotextile, if required, shall be as indicated on the plans. Gabions may be rejected for failure to meet any of the requirements of this specification.

803.2.2.1. Baskets. Gabion baskets shall consist of uniform hexagonal twisted wire mesh or welded wire mesh, coated as specified on the plans. Basket materials shall conform to requirements of ASTM A975 Double-Twisted Hexagonal Mesh Gabions and Revet Mattresses (Metallic-Coated Steel Wire or Metallic-Coated Steel Wire With Poly(Vinyl Chloride) (PVC) Coating), or ASTM A974 Welded Wire Fabric Gabions and Gabion Mattresses (Metallic Coated or Polyvinyl Chloride (PVC) Coated), except as modified by these specifications.

Uniform hexagonal wire mesh shall be woven in double twist pattern with openings fabricated in such a manner as to be nonraveling, or uniform rectangular welded mesh and designed to provide the required flexibility and strength. The perimeter edges of the twisted wire mesh shall be woven around a reinforcing wire in a manner designed to prevent slippage, and the edges of the mesh shall be securely selvaged. All corners shall be reinforced by heavier wire.

Welded wire mesh shall be composed of a series of longitudinal and transverse steel wires arranged substantially at right angles to each other and welded together at the points of intersection by the process of resistance welding to form fabricated sheets with a mesh opening of 3-in. x 3-in.

Gabions shall be so fabricated that the sides, ends, lid, base and diaphragms can be readily assembled at the construction site into rectangular baskets with a minimum thickness of one (1)-ft.

Where the length of the gabion exceeds one-and-one-half times its horizontal width, the gabion shall be divided by diaphragms, of the same mesh and gauge as the body of the gabion, into equal cells whose length does not exceed the horizontal width. Diaphragms shall be secured in the proper position on the base section.

All dimensions for twisted wire mesh gabions are subject to tolerance limit of five-percent.

All dimensions for welded wire mesh gabions are subject to tolerance limit of one-percent.

803.2.2.2. Stone. The stone shall be graded from greater than 3-in. and up to 8-in. in diameter and shall meet the requirements of [Item 504.2.2.1](#). Crushed Stone Embedment. The stone shall have a specific gravity of at least 2.40 and shall have a percent of wear not more than 40 when tested in accordance with TxDOT Test Method TEX-410-A Abrasion of Coarse Aggregate Using the Los Angeles Machine. If required by the OWNER, results of selected tests in accordance with ASTM D5313 Standard Test Method for Evaluation of Durability of Rock for Erosion Control Under Wetting and Drying Conditions shall be provided to the OWNER.

803.2.3. Gabion Construction.

803.2.3.1. Geotextile Filter Layer. If specified on the plans, a geotextile fabric or aggregate filter shall be designed by a registered professional engineer specializing in geotechnical engineering. Geotextile fabric for use as a filter media shall be placed along the gabion structure as shown in the plans. The geotextile fabric shall be placed with a minimum overlap of 18-in. Fabric shall be secured as necessary by pins or other suitable means before placing gabion baskets. Aggregate filter layer shall be constructed as designed.

803.2.3.2. Gabion Basket Assembly. Gabion baskets shall be assembled as instructed by the basket manufacturer or per approved shop drawings.

803.2.3.3. Gabion Basket Placement. Gabion baskets shall be placed in position empty and shall be bound together, each to its neighbor, along all contacting edges in order to form a continuous connecting structural unit. Binding shall be in the same manner as that used to assemble baskets and shall produce a joint that is as strong as the body of the mesh.

Twisted wire mesh gabions 3-ft high that are to be placed in a straight row are to be stretched in the following manner before being tied to the adjacent gabions. Tie together approximately 100-ft of gabion baskets end to end. Secure one end of the row by tying to gabions already filled or fill the end gabion with stone and then stretch baskets sufficiently to remove kinks. While maintaining tension, tie the row of baskets to its neighbor and then fill with stone.

803.2.3.4. Gabion Stone Placement. When the assembled empty gabion baskets have been installed, the gabion stone shall then be placed in the following manner. The gabion baskets may be filled by machine with sufficient additional handwork to accomplish a maximum density and a minimum amount of voids. Vertical outside surfaces shall be placed by hand with select stone in order to achieve the best appearance. Baskets are to be filled in 12-in. layers in order to install a looped inner tie wire in each cell connecting to front and back faces every 12-in. of vertical height in any unsupported face. Individual cells may not be filled more than 1-ft. above any adjacent cell unless looped inner tie wires run in both directions.

803.2.3.5. Gabion Basket Closure.

803.2.3.5.1. Twisted Wire Mesh. Each twisted wire mesh gabion basket shall be filled to its maximum, which is approximately 1½-in. higher than the sides, and the surface leveled with a minimum amount of voids, the lids shall be pried down and over with a bar until the edge of the lid and edge of the basket are together. The heavy projecting wire on the lid shall be twisted around the heavy wire on the sides two complete turns, and the lid shall then be tied to the edges and tops of diaphragms in the same manner as the baskets are assembled so that the finished joint is as strong as the body of the mesh. The lids of the gabion baskets shall also be tied together, each to its neighbor along all connecting edges to insure the formation of a continuous connecting structural unit. Special attention shall be given that all projecting sharp ends of wire are turned in.

803.2.3.5.2. Welded Wire Mesh. Each welded wire mesh gabion basket shall be filled to its maximum height, even with the top and sides and leveled with a minimum amount of voids. The lids shall be closed such that the edges of the lid panel is within 1-in of the top edge of the side front and back panels. The lid shall be connected to these panels using the as instructed by the basket manufacturer or per approved shop drawings.

803.2.4. Gabion Measurement and Payment. Gabions shall be measured for payment either in square yards of the specified minimum thickness or in cubic yards, based on the dimensions shown on the plans or on revised dimensions, where changes are ordered or approved by the OWNER or by ton of material in place. Gabions shall be paid for at the contract unit price complete in place, as provided in the proposal and contract. The contract unit price shall be the total compensation for preparing the subgrade, including excavation; for furnishing, placing and assembling all materials; for furnishing, placing, shaping and tamping backfill; for disposal of all surplus materials; and for all labor, tools, equipment and incidentals necessary to complete the work, all in accordance with the plans and these specifications.

803.3. RIPRAP

803.3.1. Description. This section shall cover work consisting of riprap or reinforced concrete slope protection, all complete in place in conformity with the lines, grades and details shown on the plans and in accordance with these specifications. Riprap shall be used for slope, bank and ditch bottom protection, for erosion control at the ends of pipes and structures, and at other designated locations.

803.3.2. Riprap Materials. Materials used in the performance of the work herein specified shall conform to the requirements of these specifications and as shown on the plans.

803.3.2.1. Geotextiles. If geotextiles are shown in the plans, they shall conform to the requirements of [Item 803.4.](#) Geotextiles Used in Drainage and Stabilization Applications unless otherwise specified.

803.3.2.2. Stone.**803.3.2.2.1. Types.**

Broken Concrete. The stone used may consist of broken-up concrete removed under contract or obtained from other approved sources. Broken-up concrete shall be as nearly uniform in section as practicable.

Field Stone and Quarry Stone. Natural stone for riprap shall consist of field stone or rough unhewn quarry stone as nearly uniform in section as is practicable. The natural stone shall be dense, resistant to the action of air and water, and suitable in all other respects for the purpose intended.

803.3.2.2.2. Dimensions.

Dry Riprap. Individual material for unmortared riprap shall have a minimum thickness of 4-in. and minimum surface dimensions of 12-in by 24-in. Smaller fragments may be used only to fill the voids between the above minimum size of riprap materials.

Mortared Riprap. Stone for mortared riprap shall be not less than ⅓-cubic-foot in volume and not less than 4-in in length dimensions. The width of the stones shall not be less than twice the thickness.

803.3.2.2.3. Weight.

Dry Riprap, Type A and Type B. Unless otherwise specified, all stones used in these types of riprap shall weigh between 50-lbs and 150-lbs each, and at least 60-percent of the stones shall weigh more than 100-lbs each.

Dry Riprap, Type C and Type D. Fifty-percent of the mass shall be of stones weighing between 100-lbs and 150-lbs each.

Grouted Riprap, Type A and Type B. Stones used in these types of riprap shall weigh between 40-lbs and 150-lbs each.

Grouted Riprap for Foundation Protection. Stones for foundation protection shall range in weight up to 300-lbs each, unless otherwise specified or shown on the plans.

Mortar Riprap. Stones for this purpose shall be fairly large and flat-surfaced. Fifty-percent of the mass shall be of broad flat stones weighing between 100-lbs to 150-lbs each.

803.3.2.3. Concrete, Grout, and Mortar. Materials for concrete, grout and mortar shall conform to the requirements of these specifications. The class of concrete shall be specified on the plans and shall be in accordance with [Item 702](#). Concrete Structures. Mortar and grout required for the several types of riprap shall consist of one part of Portland cement and three parts of sand, thoroughly mixed with water. Mortar shall have a consistency such that it can be handled easily and spread by trowel. Grout shall have a consistency such that it shall flow into and completely fill all joints.

803.3.2.4. Pneumatically Placed Concrete. The strength and design of pneumatically placed concrete riprap shall be specified on the plans as either Type I or Type II in accordance with the [Item 702.7](#). Pneumatically Placed Concrete (Gunite).

803.3.2.5. Reinforcement. Bar reinforcement shall conform to the requirements of the [Item 702.9.3.2](#). Steel Reinforcement. Wire reinforcement shall consist of welded fabric meeting the requirements of ASTM A1064 Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete.

803.3.2.6. Expansion Joint Material. Pre-molded expansion joint material shall conform to the requirements of [Item 303.2.12](#). Joint Filler.

803.3.2.7. Rejection. Materials that fail to meet the requirements of these specifications may be rejected by the OWNER. Such rejection shall incur no cost to the OWNER.

Materials sources from which materials with properties not meeting these specifications are delivered may be rejected as further supply sources to the project by the OWNER. Such rejection shall incur no cost to the OWNER.

803.3.3. Riprap Construction Methods.

803.3.3.1. Surface Preparation, Base Course, and General Construction. Prior to the placing of riprap, the slopes and other areas to be protected with riprap shall be excavated and/or filled, as necessary, compacted and dressed to the line and grade shown on the plans.

The base course or layer of riprap shall be bedded well into the ground with edge-to-edge contact.

Each succeeding course or layer shall be well bedded into and placed on even contact with its preceding course or layer. The finished surface shall present an even, tight surface to line and grades of typical sections.

803.3.3.2. Dry Riprap, Type A and Type B. Dry riprap Type B differs from dry riprap Type A only in that a toe wall of concrete, having dimensions and reinforcement as shown on the plans, shall be used for Type B.

The stones shall be placed in a single layer with close joints. The upright axis of the stones shall make an angle of approximately 90° with the embankment slope. The courses shall be placed from the bottom of the embankment upwardly, the larger stones being placed in the lower courses. Open joints shall be filled with spalls. Stones that project more than the allowable amount in the finished work shall be replaced, embedded deeper or chipped.

803.3.3.3. Dry Riprap, Type C and Type D. Dry riprap Type D differs from dry riprap Type C only in that a toe wall of concrete, having dimensions and reinforcement as shown on the plans, shall be used for Type D.

Stones having one broad flat surface shall be used when possible, this surface being placed on a horizontal earth bed prepared for it and so placed as to overlap the underlying course, the intent being to secure a lapped or “shingled” surface. These stones shall be placed first and roughly arranged in close contact. The spaces between the large stones then shall be filled with stone of suitable size so placed as to leave the surface evenly stepped, conforming to the contour required, and capable of shedding water to the maximum degree practicable.

803.3.3.4. Grouted Riprap, Type A and Type B. The stones shall be placed in the same manner as specified above for Dry Riprap Type A and Type B, with care being taken to prevent earth or sand from filling the spaces between the stones. After the stones are in place, the stones shall be wetted thoroughly and the spaces between the stones shall be completely filled with grout. The surface of the riprap shall be swept with a stiff broom after grouting.

No riprap shall be grouted in freezing weather. The work shall be protected from the sun and kept moist for at least 3-days after grouting. Grouted riprap Type B shall have a concrete toe wall as specified for Dry Riprap Type B.

803.3.3.5. Grouted Riprap for Foundation Protection. Stones for foundation protection shall be graded and so placed as to produce a minimum of voids. The top 6-in shall be of graded smaller stones and shall be grouted, which grout and grouting shall be in conformity with the requirements and methods outlined for Grouted Riprap, Type A and Type B.

803.3.3.6. Mortar Riprap. Stone for this purpose shall be fairly large and flat-surfaced, laid with a true and even surface and a minimum of voids. Broad flat stones shall be placed with the flat surface uppermost and parallel to the slope. The largest stones shall be placed near the base of the slope.

Before placing mortar, the stones shall be wetted thoroughly. As each of the larger stones is placed, it shall be surrounded by fresh mortar, and the adjacent stones shall be shoved into contact. After the larger stones are in place, all of the spaces or openings between them shall be filled with mortar and the smaller stones then placed by shoving them into position, forcing excess mortar to the surface and insuring that each stone is carefully and firmly embedded laterally. All excess mortar forced up shall be spread uniformly to completely fill all surface voids. All surface joints then shall be pointed up roughly either with flush joints or with shallow, smooth-raked joints.

803.3.3.7. Concrete Riprap. Concrete shall be placed in accordance with the details and to the dimensions shown on the plans or as established by the OWNER. Unless otherwise shown by a note on the plans, concrete riprap shall be reinforced using deformed steel bar reinforcement.

Reinforcement shall be properly supported throughout placement of concrete.

Expansion joints shall be placed as shown on the plans.

803.3.3.8. Pneumatically Placed Concrete (Gunite) Riprap Type I and Type II. Pneumatically placed concrete shall be placed in accordance with [Item 702.7](#). Pneumatically Placed Concrete (Gunite) to the dimensions shown on the plans or as established by the OWNER. Reinforcement shall be supported properly throughout placement of concrete. All subgrade surfaces shall be moist when concrete is placed. The surface shall be given a wood float finish or gun finish as directed by the OWNER.

The riprap shall be cured with membrane-curing compound in accordance with [Item 702.5.10](#). Curing Concrete immediately following the finishing operation.

803.3.3.9. Geotextiles. Geotextiles shall be placed and anchored as directed on the plans.

803.3.4. Measurement and Payment. Riprap shall be measured for payment either in square yards of the specified minimum thickness or in cubic yards, based on the dimensions shown on the plans or on revised dimensions, where changes are ordered or approved by the OWNER or by ton of material in place. Riprap shall be paid for at the contract unit price complete in place, as provided in the proposal and contract. The contract unit price shall be the total compensation for preparing the subgrade, including excavation; for furnishing and placing all materials; for furnishing, placing, shaping and tamping backfill; for proper disposal

of all surplus materials; and for all labor, tools, equipment, and incidentals necessary to complete the work, all in accordance with the plans and these specifications.

803.4. GEOTEXTILES USED IN DRAINAGE AND STABILIZATION APPLICATIONS

803.4.1. Geotextile Material Requirements. The geotextile fabric shall be inert to commonly encountered chemicals and hydrocarbons. The fabric shall be packaged, stored and handled in a manner to prevent damage or deterioration which may be caused by moisture, excess sunlight, rodents or other vermin.

The fabric shall conform to the average roll minimum values (lot mean-2 standard deviations), as determined by Federal Highway Administration Task Force 25 guidelines cited below, measured in the weakest direction, as indicated in Table 803.4.1.(a) Geotextile Requirements.

Table 803.4.1.(a) Geotextile Requirements

Designation (Test Method)	Characteristic	Drainage		Stabilization			
		PR ¹	UPR ²	LOADING			
				Low	Med.	Hi	VHI
ASTM D4632 Grab Breaking Load and Elongation of Geotextiles	Grab Strength (lbs.)	80	180	90	130	180	270
ASTM D4632	Grab Elongation	NA	NA	NA	NA	NA	NA
ASTM D4533 Trapezoid Tearing Strength of Geotextiles	Trapezoidal Tear (lbs.)	25	50	30	40	50	75
ASTM D751 Standard Test Methods for Coated Fabrics	Burst (psi)	130	290	145	210	290	430
ASTM D751	Puncture (psi)	25	80	30	40	75	110
ASTM D4751 Determining Apparent Opening Size of a Geotextile	Apparent Opening Size (AOS) (mm) - soil retention.						
<u>For Soils in Which:</u>		<u>AOS:</u>					
50% or less passes a #200 mesh sieve		Greater than a #30 sieve					
More than 50% passes a #200 mesh sieve		Greater than a #50 sieve					
ASTM D4491 Water Permeability of Geotextiles by Permittivity	Permeability (k):						
<u>Type of Application:</u>		<u>Required Permeability:</u>					
Critical/Severe:		k (fabric) > 10k (soil)					
Normal Applications:		k (fabric) > k (soil)					

1. PR: Protected Application (used in conjunction with a buffer)

2. UPR: Unprotected Application (used with no protective buffer)

803.4.2. Construction Using Geotextiles. Construction using geotextiles shall be in accordance with the plans, with applicable specifications contained herein [Item 803.4. Geotextiles Used in Drainage and Stabilization Applications](#), or as directed by the OWNER.

803.4.3. Measurement and Payment. If provided as a separate contract item, geotextile shall be measured by the square-yard, complete in place.

Geotextile, when provided as a separate pay item, shall be paid for by the square-yard, complete in place, which price shall include materials, hauling, placing, anchoring, and all other work necessary to achieve a functional geotextile layer in the slope or channel protection. If not provided as a separate contract item, geotextile shall be considered subsidiary to those items provided for slope and channel protection.

ITEM 804. PAINTING AND OTHER PROTECTIVE TREATMENTS; PAVEMENT MARKING**804.1. DESCRIPTION**

This item shall govern for the type, quality and application of paint or appropriate coatings or treatments to structures, materials, and pavement surfaces. Such applications include liquid coatings and galvanizing. Items to receive applications may include, but are not limited to, concrete structures, bridges, aerial crossing steel carrier pipes, fences, barriers, concrete pavement, and asphalt pavement. Water tanks and towers are exceptions to these specifications; material specifications and instructions for preparation, cleaning, coating/painting water tanks and towers shall be specified by the OWNER. Painting, coating and other protective treatments shall include, unless otherwise provided in the contract, the preparation and testing of the surfaces; the application, protection and drying of the paint, coating(s) or treatments; the protection of all traffic upon, underneath, or near the structure, material or pavement; the protection of all parts of the structure, material or pavement against disfigurement by any and all painting operations; and the supplying of all tools, tackle, scaffolding, labor, workmanship, paint, coating and/or other materials necessary for the completion of the entire work in accordance with the plans and these specifications.

The intent of the design herein specified is to procure the paints, coatings or treatments in and on structures, materials and surfaces so that the durability and protective value of these designs shall be realized in service. Accordingly, the best quality materials and workmanship are implied throughout. Surface conditions and application requirements are specified with the intent to obtain full adhesion of paint, coatings or treatments to clean, dry, firm surfaces. This shall require careful attention to preparation of surface, to the prevention of contamination and marring of the coating during and after drying, and to uniform, skilled application.

804.2. PAINTING AND MARKING

804.2.1. Safety. Some paints are harmful to the health. All paints shall be handled according to the information contained on the paint safety data sheet. The CONTRACTOR shall be responsible for safety during all cleaning and painting operations.

Unless shown otherwise on the plans, the CONTRACTOR shall be responsible for necessary precautions to contain refuse, dust and paint overspray generated during cleaning and painting operations. Containment shall be such that all falling material is contained and collected for disposal. Noncontainment of airborne particles is permissible provided they are not visible over 100-feet from the actual cleaning or painting operation. A skimmer shall be used when cleaning and painting is over bodies of water. Disposal of collected refuse shall be in accordance with Federal, State and Local rules and regulations.

If spray application is used, workers shall be adequately protected with respirators, and provisions shall be made to prevent infliction of harm upon all other humans and/or animals that might be exposed to the fumes or might eat food upon which the fumes have deposited. This warning shall absolve the OWNER from blame in the event of harm to persons or property from the named cause, and full responsibility for any such harm shall rest upon the CONTRACTOR.

804.2.2. Paint and Marking Materials. All materials used in the painting and marking herein specified shall conform to the material and composition requirements of the applicable TxDOT Material Specification:

- DMS-8100 Structural Paints - Formula
- DMS-8101 Structural Steel Paints- Performance
- DMS-8200 Traffic Paint
- DMS-8220 Hot Applied Thermoplastic
- DMS-8240, Permanent Prefabricated Pavement Markings
- DMS-8241, Temporary Removable, Prefabricated Pavement Markings
- DMS-8242, Temporary Flexible, Reflective Roadway Marker Tabs
- DMS-8290, Glass Traffic Beads,

including any official TxDOT amendment or modification of these specifications, where reference to TxDOT or its representatives shall mean the OWNER. The CONTRACTOR shall certify to the OWNER that paint or coatings provided meet TxDOT material requirements.

804.2.2.1. Testing. All paint and paint materials shall be sampled and tested prior to use. All tests shall be conducted in accordance with the methods specified by ASTM or methods set forth in Federal

Standard FED-STD-141C/GEN Paint, Varnish, Lacquer, and Related Materials: Methods of Inspection, Sampling, and Testing. In the absence of any such methods, other suitable methods may be designated and utilized by the OWNER.

804.2.2.2. Rejection. Raw materials and finished products that fail to meet any requirements of these specifications shall be subject to rejection. Final acceptance or rejection shall be based on results of tests on samples of raw materials and finishes as soon as practicable after their arrival at the shipping destination. Approval of materials, as a result of preliminary testing prior to manufacture into finished coatings, shall not be binding upon final approval or rejection. The judgment of the OWNER shall be final in all questions relative to conformance with the provisions of these specifications.

804.2.3. Preparing Structures for Paint.

804.2.3.1. Descaling, Cleaning and Preparation of Surface. Throughout paint application, including shop and field painting, no paint shall be applied over a surface that evidences a loose or scaly condition. Every effort shall be made by means of the most effective and practical methods to remove all loose mill scale, rust, dirt, oil and grease, as well as all other foreign surfaces which would be deleterious to the procurement of the firm paint coating. The original cleaning and preparation of the surface necessarily must be done at the fabricating plant before application of the shop coat, but the same general requirements for painting over a clean, firm surface shall be applicable to all coats.

The OWNER shall look for evidence of faulty surface preparation preceding the shop coat by close inspection of the surface directly prior to application of first field coat, likewise, between first and second field coats. This careful inspection directly in advance of paint application may disclose not only loose, scaly conditions on the surface as a result of faulty preparation but also failure of the paint to harden because of contamination and changes which might have taken place beneath the paint film as a result of rusting and loosening of mill scale after paint has been applied.

The OWNER will test and make determination of the presence of lead or asbestos in the coatings of existing structures. These findings will be addressed via specifications set by the OWNER. Refer to [Item 603](#). Abatement of Coatings Containing Certain Heavy Metals for additional information for information regarding heavy metals.

Therefore, whenever the OWNER has the slightest doubt as to the firm condition of the surface at any time throughout the application of any coats, OWNER shall be expected to explore underneath the surface of any paint coats already applied so as to uncover evidence of infirmity and to direct remedial measures. Any effective methods for removal of rust, scale and dirt, such as through the use of sandblast, hand or rotating metal brushes, scrapers, chisels, hammers or other effective means, shall be acceptable. Undesirable contaminants, which are not allowed to be present on the surface directly prior to paint application and which shall prevent proper hardening and adhesion of the paint film, are grease, oil, oily grime and moisture. Condensed moisture shall be avoided, and other grease-like contaminants shall be removed with solvents, applied with clean rags in such a manner that the oily substance is actually removed and not simply diluted or spread out over a greater area. Particular attention shall be given to the cleaning of fillets, riveted areas, rivet-heads, bolt heads, nuts, washers, drilled or punched holes and welds where loose mill scale, rust, oil and flux are likely to be present.

Unless cleaning is to be done by sandblasting, all weld areas shall be flushed thoroughly with clean water before painting so as to remove any alkaline residue. The flushed surface shall be allowed to thoroughly dry before paint application.

804.2.3.2. Weather Conditions and Dryness of Surface. Paint shall not be applied to any surface where moisture is present and discernible to the eye. Paint shall not be applied at air temperatures below 40°F nor when there is a likelihood of change in weather conditions within 2-hrs after application which would result in air temperatures below 40°F or depositing of moisture in the form of rain. Paint shall not be applied when, in the OWNER'S opinion, impending weather conditions might result in injury to the fresh paint. Weather condition requirements may be waived if the OWNER approves dehumidification or other climate control methods to successfully control the painting environment so as to ensure an equal or improved product.

804.2.3.3. Protecting Surrounding Features. The CONTRACTOR shall protect pedestrian, vehicular and other traffic in the vicinity, and also all portions of the structures not intended to receive paint, against damage or disfigurement by spatters or splashes of paint or paint materials.

804.2.4. Paint Handling and Application.

804.2.4.1. Stirring, Mixing and Care of Paints. All mixed paints shall be made ready for use through reincorporating settled pigment by means of thorough stirring, boxing and straining so that the paint is in its original homogeneous form, free from large agglomerates and skins greater than 9.8-mil in diameter. Paint in mixing pots shall be kept tightly covered when not in use so as to reduce volatile losses and skinning. Paint always shall be in a complete mixed condition when filled into painter's pots, and this filling always shall be through a strainer of 20 mesh cloth or wire or finer. Paint from the painter's pots shall be concentrated into tightly covered mixing pots at the end of the day and shall at no time during application contain skins or large agglomerates, and the interior sides of pots shall be periodically cleaned free of soft skins which might cling to brushes.

804.2.4.2. Thinning. At temperatures above 70°F, all of the paints herein specified for use, when freshly opened from sealed containers and thoroughly stirred, are of normal consistency suitable for good brush application without thinning. At temperatures below 70°F, the consistency may be heavy enough to require some thinning for proper brush application. Adjustments of paint consistency shall be accomplished by heating in hot water or on steam radiators. Adjustments of paint consistency by thinning so as to meet any and all conditions shall be done only at the discretion of the OWNER and with the OWNER's specific permission. The general rule which shall be applied for thinning paints shall be that the full hiding coat can be applied so as to thoroughly obscure the surface being painted, whether bare metal or undercoat, without sags and runs. Proper use of paints should remove the necessity for thinning because of evaporated volatiles as a result of allowing the paints to stand in uncovered containers.

804.2.4.3. Brush Application. Painting shall be done by workers skilled in the craft of structural metal painting. Good workmanship by skilled workers is evidenced by the following outstanding features: all crevices, sharp angles, etc., are first traced; the entire surface is then coated without attempt to "layoff" the paint in one direction; lastly, runs from crevices are picked up and the paint is laid off in one direction so as to leave a uniform film free from runs, sags or brush marks caused by not "feathering" or blending one lap into another. Brushes preferably shall be round or oval in shape, but if flat brushes are used, they shall not exceed 4-in in width; brushes should be springy and not flabby. Brushes shall not be permitted to become seedy from skins.

804.2.4.4. Spray Application. The equipment used for spray painting shall meet the approval of the OWNER and shall have adequate provisions for separation of moisture from the air stream in contact with the paint. Before thinning for spray application is permitted by the OWNER, at least 50-psi air pressure shall be present at the gun, the gun is not clogged with dried or semi-dried paint, and the spray gun is adequate for the work and has a proper spray head for application of paints used. A spray gun correctly held is approximately 8-in from and always perpendicular to the surface being painted. The painter shall steadily move the gun through a deliberate pattern that permits overlapping of the previous pass by 50-percent and at a speed that shall produce a full uniform coat. Over spray shall be held at a minimum.

804.2.5. Painting New Structures.

804.2.5.1. Number of Coats and Color. Except for surfaces specified herein or otherwise provided for on the plans, all structural steel shall be painted with one (1) shop coat of primer, one (1) field coat primer and two (2) field coats of paint as specified on plans. The paint shall be omitted from the surface of structural steel which shall be in contact with concrete in the finished structure. At the time concrete is placed, such surfaces of structural steel shall be free from dirt, scale, rust, paint, oil or other foreign material.

804.2.5.2. Shop Coat. It shall be mandatory to apply the shop coat by brushing or rolling, unless the surfaces to be painted are cleaned by sandblasting, in which case spray application of the shop coat shall be permitted. When all fabrication work is completed and has been tentatively accepted as such,

all surfaces not painted before assembling shall be cleaned as provided in [Item 804.2.3.1](#). Descaling, Cleaning and Preparation of Surface and painted with one coat of primer. Pieces shall not be loaded for shipment until thoroughly dry. No painting shall be done after loading material on cars. Erection marks for the field identification of members shall be painted on previously painted surfaces. The top of the top flange of stringers shall not be painted. Machine finished surfaces shall be coated as soon as practicable after being accepted.

Surfaces of iron and steel castings milled for the purpose of removing scale, scabs, fins, blisters or other surface deformations shall generally be given the shop coat of paint.

All metal surfaces which shall be within 2-in of field welds shall be coated with linseed oil in advance of the application of shop coat paint and left bare of paint until field welding has been completed. The shop coat shall be applied as uniformly as possible by brushing with the intent of securing an average wet film thickness of 3.5-mils or 468-sq.ft.-of-surface-per-gallon of paint. The corresponding dry film thickness shall be 2.1-mils.

Portions of structures entailing difficult application of the field coats after erection may be completely painted before assembling or erection at the discretion of the OWNER.

804.2.5.3. Field Cleaning and Spot Painting. When the erection work is complete, including straightening of bent metal, etc., the shop-coated surface shall be restored to a serviceable condition acceptable to the OWNER by means of preparation of surface as outlined in [Item 804.2.3.1](#). Descaling, Cleaning and Preparation of Surface and smoothing and touching up marred places in the shop coat film with primer. Field welds, heads of field rivets and bolts and any other surfaces to be painted which have not yet been shop coated shall be painted with primer.

The coating of linseed oil specified in [Item 804.2.5.2](#). Shop Coat shall be thoroughly removed, as directed for removal of grease and oil in [Item 804.2.3.1](#). Descaling, Cleaning and Preparation of Surface, immediately prior to erection.

804.2.5.4. First Field Coat. When field cleaning and restoration of shop coat has been completed and all shop coat is thoroughly dry, the first field coat of primer may be applied. Finished surfaces intended for sliding contact shall be given a coat of approved graphite grease immediately prior to being placed in the structure. Graphite grease shall be composed of dry graphite flakes mixed with sufficient light grease or heavy oil so as to form a thick paste suitable for the purpose. Field coats shall not be required on the bottom surface of shoe castings or bearing plates in direct contact with concrete nor on the top surfaces of beams, girders, etc. on which a concrete slab is to be placed in direct contact. The first field coat shall be applied as uniformly as possible, either by spraying, rolling, brushing, or a combination of these with the intent of securing an average wet film thickness of 3.5-mils.

804.2.5.5. Finish Coats. When the first field coat, including all touched-up marred places, has thoroughly hardened, the finishing field coats of finish paint may be applied. Cracks and cavities which have not been sealed in a watertight manner by the first field coat shall be suitably corrected. This correction shall be allowed to sufficiently surface dry before the second field coat is applied so as not to work up into finish paint. After application of the finishing field coat, the painted portion of the structure shall present a uniform color and appearance throughout.

The finish paint coat shall be applied as uniformly as possible by spraying, rolling, or brushing, with the intent of securing an average dry film thickness of 1.5-mils for each coat of paint applied.

804.2.6. Cleaning and Painting Existing Structures. All structures to be painted shall be cleaned thoroughly in accordance with [Item 804.2.3.1](#). Descaling, Cleaning and Preparation of Surface to prepare the surfaces to receive new paint. Rust spots shall be cleaned to bare metal. Structures shall be spot painted with primer in accordance with [Item 804.2.5.3](#). Field Cleaning and Spot Painting prior to application of paint to the entire surface unless otherwise specified. After the cleaning and spot-paint have dried thoroughly, the application of two (2) field coats of paint shall be applied. The application of paints shall conform to the pertinent articles of this specification.

804.2.7. Removal of Paint Improperly Applied. All paint which has been improperly applied and fails to dry and harden properly, or to adhere tightly to underlying metal or other paint film, or does not evidence a normal, workmanlike appearance in conformance with the intent of these specifications, shall be remedied or

thoroughly removed and replaced at the expense of the CONTRACTOR. When the final field coat does not have a uniform color and appearance throughout the structure, it shall be corrected by the use of whatever additional coats are necessary. Removal of freshly applied paint which has not yet set shall be effected with the use of appropriate solvents. Removal of dried paint films shall be effected either by means of sandblasting or scraping, meeting the approval of the OWNER.

804.2.8. Cleaning and Marking Pavements. When the CONTRACTOR is responsible for marking pavements, as identified in the plans, cleaning and marking shall conform to these specifications and the Texas Manual on Uniform Traffic Control Devices.

Markings shall be applied only when the pavement surface is dry and clean, which may be accomplished with machinery specialized to prepare pavement in front of the marking operation. The CONTRACTOR shall be comply with all environmental condition restrictions recommended by the manufacturer of pavement paints or other markings. Glass beads or other refractive material and application rates shall be as identified on the plans.

Temporary markings shall be thoroughly removed to the satisfaction of the OWNER using an approved method prior to the application of permanent markings.

804.3. GALVANIZING

804.3.1. General. Zinc used for galvanizing shall be grade Prime Western conforming to ASTM B6 Zinc (Slab Zinc). Except as otherwise specified, materials shall be galvanized by the hot-dip or electro-depositing process.

804.3.2. Coating Requirements. The minimum weight of coating and other requirements shall be as shown in Table 804.3.2.(a) Galvanizing Minimum Weight. The weight shown is ounces per square foot of the surface area. All surfaces, when tested separately, shall meet the minimum requirement.

804.3.3. Workmanship. The zinc coating shall adhere tenaciously to the surface of the base metal. The finished product shall be free from blisters and excess zinc, and the coating shall be even, smooth and uniform throughout. Machine work, die work, cutting, punching, bending, welding, drilling, thread cutting, straightening and other fabricating shall be done as far as is practicable before the galvanizing. All members, nuts, bolts, washers, etc. shall be galvanized before a structural unit is assembled. All uncoated spots or damaged coatings shall be cause for rejection.

Products that are warped or distorted to the extent of impairment for the use intended shall be rejected.

804.3.4. Testing. Test coupons for determining the quantity and quality of galvanizing shall be of such size and shall be wired to the materials to be galvanized before immersion so as to represent the amount of coating deposited on the finished product.

The weight of coating shall be determined in accordance with ASTM A90 Test Method for Weight [Mass] of Coating on Iron and Steel Articles with Zinc or Zinc-Alloy Coatings, modified to determine the coating of each surface separately.

Nondestructive tests for uniformity of coating may be made by the OWNER with a magnetic instrument in accordance with ASTM E376 Standard Practice for Measuring Coating Thickness by Magnetic-Field or Eddy-Current (Electromagnetic) Test Methods.

Table 804.3.2.(a) Galvanizing Minimum Weight

Material	ASTM Designation	Min. Weight of Coating oz./sq.ft.
Steel product including structural shapes, tie rods, handrails, and miscellaneous items	A123, Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products	2.00
Hardware including casting, rolled, pressed, and forged articles	A153, Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware	2.00
Bolts, screws, nuts, and washers	A153 Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware	1.25
Chain link fence fabric (galvanized after fabrication)	A392, Standard Specification for Zinc-Coated Steel Chain-Link Fence Fabric	1.20
Chain link fence fittings & accessories	F626 Standard Specification for Fence Fittings	1.20
Chain link fence post, gates, rails, and braces	F1083 Standard Specification for Pipe, Steel, Hot-Dipped Zinc-Coated (Galvanized) Welded, for Fence Structures	1.80
CMP culverts and underdrains	A929 Standard Specification for Steel Sheet, Metallic-Coated by the Hot-Dip Process for Corrugated Steel Pipe	1.00
Steel pipe	A53 Standard Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated, Welded and Seamless	1.80
Iron or steel wire fencing	A116, Standard Specification for Metallic-Coated, Steel Woven Wire Fence Fabric	0.80
Steel or iron sheets	A653 Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process	0.63
Barbed wire	A121 Standard Specification for Metallic-Coated Carbon Steel Barbed Wire	0.80
Electrolier standards, 7-gauge steel and over	A123 Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products	2.00
Electrolier standards, under 7-gauge steel	A123 Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products	1.50

804.3.5. Repair of Damaged Zinc Coating. Zinc coating, which has been field or shop cut, burned by welding, abraded, or otherwise damaged to such extent as to expose the base metal, shall be repaired and recoated by one of the following methods:

804.3.5.1. Hot-Dip Process. The damaged areas shall be thoroughly stripped and cleaned, and a coating of zinc shall then be applied by the hot-dip process.

804.3.5.2. Metalizing Process. The damaged area shall be thoroughly cleaned by blasting with sharp sand or steel grit. The blasted area shall lap the undamaged zinc coating at least ½-in.

Zinc wire containing not less than 99.98-percent zinc shall be used in the metalizing operation. A zinc coating shall be applied to the damaged area with a metalizing gun to a thickness of not less than 0.005-in. on the damaged area and shall taper to zero thickness at the edge of the blasted undamaged section.

804.3.5.3. Zinc Rich Paint. The damaged area shall be thoroughly cleaned by wire brushing and all traces of welding flux and loose or cracked zinc coating removed prior to painting. The cleaned area shall be painted with two coats of zinc oxide-zinc dust paint. The coating thickness shall be 50-percent

greater than the surrounding coating thickness, but not more than 4.0-mils. Zinc-rich paints shall be based on organic binders, premixed and formulated specifically for use on steel surfaces and shall provide a dried film containing a minimum of 92-percent zinc dust, by weight.

804.3.6. Rejection. Raw materials and finished products that fail to meet any requirements of these specifications shall be subject to rejection. Final acceptance or rejection shall be based on results of tests on samples of raw materials and finishes as soon as practicable after their arrival at the shipping destination. Approval of materials, as a result of preliminary testing prior to manufacture into finished coatings, shall not be binding upon final approval or rejection. The judgment of the OWNER shall be final in all questions relative to conformance with the provisions of these specifications.

804.4. MEASUREMENT AND PAYMENT

Unless otherwise provided in the plans and special provisions, painting, coating, marking, or other treatments such as galvanizing shall not be measured for payment, nor shall payment be made as a separate contract item. The cost thereof shall be included in the contract pay items as are provided for the item to be painted, treated or marked, which prices shall be the total compensation for cleaning, spot painting or treatment, application of paint, coating, marking or treatment, and for furnishing all labor, equipment, material, scaffolding, protection of traffic, tools and incidentals necessary to complete the work, all in accordance with the plans and these specifications.

804.5. SPECIALTY COATINGS

Manufacturer's specifications shall be followed when applying specialty coatings, such as shown in the contract documents.

ITEM 805. ELECTRICAL COMPONENTS AND CONDUIT

805.1. DESCRIPTION

This item shall govern the furnishing and installation of electrical components and/or conduit of the size and at the locations as indicated on the plans.

805.2. GENERAL REQUIREMENTS FOR ELECTRICAL COMPONENTS

805.2.1. General. The material shall provide complete and operative electrical installations as well as that necessary to interface and operate with all other materials as designated. Unless otherwise indicated in the plans or contract specifications, electrical components shall meet the requirements specified herein.

805.2.2. Drawings. Drawings are not intended to and do not show all materials such as junction boxes, outlet boxes, conduit fittings and similar components. Even though such material components may not be specifically mentioned in the specifications, shown on the drawings, or noted on shop drawings, if they are necessary to make a complete installation, they shall be included in the materials required under these specifications.

805.2.3. Codes and Standards. All electrical material and tests shall be in conformity with the applicable current standard rules, regulations and specifications of the following authorities:

- (1) National Board of Fire Underwriters (NBFU)
- (2) National Fire Protection Association (NFPA)
- (3) National Electric Code (NEC)
- (4) National Electrical Manufacturers Association (NEMA)
- (5) Institute of Electrical and Electronic Engineers (IEEE)
- (6) Insulated Power Cable Engineers Association (IPCEA)
- (7) American National Standards Institute (ANSI)
- (8) National Electrical Contractor's Association (NECA)
- (9) Association Edison Illuminating Companies (AEIC)
- (10) Rural Electrification Administration (REA)
- (11) Such other codes and standards as specified on the plans or in the contract specifications.

805.3. MATERIALS

805.3.1. Material General. All electrical component or conduit materials provided shall be in accordance with the plans, special provisions, contract documents and these specifications.

All material shall be new unless otherwise specified. All materials of a type for which the Underwriters' Laboratories (UL) have established a standard shall be listed by the Underwriters' Laboratories, Inc., and shall bear its label. The OWNER may approve other products with product listing or certification from other agencies, such as but not limited to ETL Testing Laboratories, Inc. or Canadian Standards Association (CSA.)

805.3.2. Luminaries. Luminaries shall be as shown on the plans and special provisions of the specifications. Lamps, housings, reflectors, mountings, ballast and other required items shall be provided to present a complete operable unit.

805.3.3. Electroliers. Poles, arms and bases to provide support for the electric lamps shall be as shown on the plans and presented in the special provisions, contract documents and these specifications.

805.3.4. Conduit.

805.3.4.1. Plastic Conduit. All plastic conduit shall be schedule 40, rigid, high impact polyvinyl chloride, conforming to Underwriters' Laboratories, Inc., Standard UL-514B for conduit fittings, UL-514C for nonmetallic boxes, UL-651 for Schedule 40 and 80 conduit, and UL-651A for concrete encased PVC conduit.

805.3.4.2. Rigid Steel Conduit. All rigid steel galvanized conduit shall be hot-dipped galvanized inside and out and shall conform in all respects to ANSI C80.1 and Underwriters' Laboratories Safety Standard #6.

805.3.4.3. Flexible Conduit. All flexible conduit shall be American Metal Hose with a neoprene jacket and Appleton Sealtite fittings or other approved equal.

805.3.4.4. Aluminum Conduit. All Aluminum conduit shall conform to all codes and standards for the materials use.

805.3.4.5. Indoor Cable Tray. Cable Tray shall be constructed of pregalvanized steel or aluminum and shall meet the requirements of NEMA Standard VE1 and NEC Article 318. The tray shall be furnished complete with the necessary splices, connections, supports, end plates and other accessories as required.

805.3.4.6. Underground Trench Duct. The trench duct shall consist of precast concrete framing members, side sections and removable cover sections assembled to form a completely enclosed trench, except with open earth bottom having a 4-in bedding of sand. Trench shall be constructed so its top is even with finished grade. The trench shall be of width shown on the plans by 18-in deep inside. The precast sides of the trench shall be held in place by the pressure of the external earth backfill.

Cast in place and Precast trench members shall utilize 3000-psi or greater strength concrete.

Manufacturer's noncorrosive metal cable clips shall be furnished to support ground wire and control cables on each framing member. Manufacturer's precut ½-in thick asbestos cement board supported by special slot in framing member for segregation of voltages shall be furnished.

Entrance into buildings from the trench duct shall be by means of aluminum cable risers furnished by the manufacturer of the trench duct. Lids shall be field notched to fit and the necessary support hardware for side mounting shall be furnished by the manufacturer.

Where road crossings are indicated on the plans, they shall consist of precast road crossing modules, 5.0-ft long and designed for HL-93 load capacity. Modules shall be furnished with steel covers and shall be of a width as indicated on the plans.

805.3.5. Wire. Copper wire shall conform to the applicable portions of ASTM B3 Soft or Annealed Copper Wire and ASTM B8 Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft. Wire sizes shall be based on American Wire Gauge (AWG) Conductors, hard, medium-hard, or soft, ASTM B3 and B8, respectively.

Insulated conductors shall be of a size indicated on the plans. Such conductors shall conform to the current standards at time of bid.

805.3.6. Rejection. Any electrical component or conduit specified in this section may be rejected for failure to meet any of the provisions of these specifications or for any defect causing said material to be unsuitable for its intended use.

805.4. CONDUIT CONSTRUCTION METHODS

Prior to the installation of conduit, the OWNER shall be notified so that a representative will be present to inspect the installation of the conduit. Failure to contact the OWNER shall constitute grounds for rejecting conduit which has been installed without the presence of a representative of the OWNER.

All conduit shall be placed in accordance with lines and grade, details and dimensions as shown on the plans, or as directed by the OWNER. All ends of pipe shall be reamed to remove burrs. All splicing of conduit shall be done by using standard couplings manufactured for this purpose. All bare ends of conduit for future connections by others shall be capped with standard conduit caps. The location of ends of all conduit for future electrical circuits in structures shall be marked by a "Y" at least 3-in high, cut into the face of curb, gutter or wall directly above the conduit.

Conduit in medians or under pavements shall be placed at a minimum depth of 30-in from the top of curb as shown on the plans. Installation under existing pavements shall be accomplished by boring. Conduit shall extend 6-in. behind back of curb unless otherwise called for on the plans. Where pull boxes or junction boxes are required in medians which are to be surfaced, they shall be installed by the CONTRACTOR at the location and grade as shown on the plans or as directed by the OWNER.

Unless otherwise specified in the special provisions or on the plans, all pull-boxes shall be furnished by the CONTRACTOR. All necessary fittings for proper installation of conduit in the pull-box shall be furnished and installed by the CONTRACTOR. Where it is required that pull-boxes be installed, the conduit shall be fitted with sweeping 90° fittings to enter the pull-box from the bottom. A nipple shall be attached to the fitting of sufficient length so that the distance from the top of the pull-box to the end of the nipple shall be 8-in.

A No. 9 galvanized pull wire shall be placed in all conduit prior to the placement of paving, the wire shall be moved back and forth to insure that the conduit is free from obstructions. Before final acceptance of the conduit work, this method of checking shall again be incorporated to insure that the paving operations have not rendered the conduit useless. It shall be the CONTRACTOR'S responsibility to remove and replace all damaged conduit at its own expense.

Conduit bends, except factory bends, shall have a radius of not less than seven (7) times the inside diameter of the conduit. Where factory bends are not used, conduit shall be bent, without crimping or flattening, using a portable hydraulic pipe bender. The radius of the pipe shall conform to the dimensions shown on the plans; if not designated on the plans, the longest radius practicable shall be used.

Conduit locations shown on the plans are for bidding purposes only and may be changed with permission of the OWNER to avoid underground obstacles. The CONTRACTOR shall furnish and install conduit to an electrical service point to be determined by the OWNER prior to the beginning of any construction.

805.5. MEASUREMENT AND PAYMENT

Conduit of the size specified on the plans shall be measured by the linear foot along the main line of conduit. Fittings shall not be measured directly but shall be considered subsidiary to this item.

Conduit, as measured in this item, shall be paid for at the unit price bid for "conduit" of the size specified, which prices shall be full compensation for furnishing and installing all conduit, all excavation, all gravel backfill, furnishing and installing all fittings, installing pull-boxes and for all labor, materials, tools, equipment and incidentals necessary to complete the work.

Electrical components shall be measured and paid for at the contract price, which price shall be full compensation for furnishing and installing all electrical components and testing as necessary to ensure full functioning.

ITEM 806. METAL MATERIALS

806.1. GENERAL

Miscellaneous metals not specified in this section shall meet the requirements as shown on the plans and Contract Documents.

806.1.1. Storing Materials. All materials shall be handled in such a manner that no injury shall result. Material to be stored shall be placed on skids above the ground and shall be kept clean and properly drained. Girders and beams shall be placed upright and shored. Long members, such as columns, shall be supported on skids placed closely enough to prevent excessive deflection.

806.1.2. Marking and Shipping. All structural members shall be marked in accordance with the erection diagram. The markings shall be over the painted surface and in no case shall shop paint be left off in order to preserve markings on unpainted steel. Match-marks shall be made with paint in addition to the requirements of [Item 804.2. Painting and Marking](#). Members weighing more than 3-tons shall have the weight marked thereon. Bolts of one length and diameter and loose nuts or washes of each size shall be packed separately. Pins, small parts and small packages of bolts, washers, and nuts shall be shipped in boxes, crates, kegs or barrels. A list and description of the contained material shall be plainly marked on the outside of each package.

Anchor bolts, washers and other anchorage or grillage materials shall be shipped in time to suit the requirements of the masonry construction. The loading, transportation, unloading and storing of structural material shall be conducted so that the metal shall be kept clean and free from injury.

806.1.3. Rejection. Any metal or material specified in this section may be rejected for failure to meet any of the provisions of this specification or for any defect causing said material to be unsuitable for its intended use. Rejected materials shall be removed and replaced at no cost to the OWNER.

806.2. STRUCTURAL STEEL

Unless otherwise indicated in the plans or contract specifications, structural steel shall meet the requirements specified herein.

806.2.1. Carbon Steel. Carbon steel shall meet the requirements of ASTM A36 Carbon Structural Steel.

806.2.2. Copper Bearing Structural Steel. Where copper bearing structural steel is specified, the steel shall contain not less than 0.2-percent copper.

806.2.3. High-Strength Low-Alloy Steel. High-strength low-alloy steel shall meet the requirements of ASTM A588 High-Strength Low-Alloy Structural Steel with 50-ksi Minimum Yield Point to 4-in thick.

The producer shall make and report one impact test from the thickest material in each lot furnished. This test shall be longitudinal Charpy V-notch at + 40°F meeting the requirements of ASTM A370-97a Standard Test Methods and Definitions for Mechanical Testing of Steel Products, Paragraph 23.

Prior to furnishing A588 steel, the producer may furnish to the OWNER impact test data on previously produced steel from the mill from which the steel is to be furnished. The tests shall represent the range of plate thickness and shape sizes required by the project. The data shall indicate that longitudinal Charpy V-notch values of at least 15-ft-lbs at plus 40°F are consistently obtained. If these dates are satisfactory, impact test data shall still be required but shall be for informational purposes only and shall not be used for acceptance or rejection of the steel.

If prequalified data is not submitted, or the data submitted is not acceptable, impact data required shall be used for acceptance or rejection of steel. In this case 95-percent of the tests shall indicate values of not less than 25-ft-lbs at plus 40°F.

A lot, for purposes of impact testing, shall consist of 50-tons or fraction thereof of finished material from a single heat which is rolled in the same mill and is the same grade, type of product (plate, bar, wide flange, I, H, angle, etc.) and which is within one of the following thickness classifications:

- (1) Differing not more than $\frac{3}{8}$ -in in thickness, if the thickness of the lot does not exceed 2-in.
- (2) Differing not more than 1-in in thickness when the least thickness in the lot exceeds 2-in.
- (3) The governing thickness for wide flange, I, H, and T sections shall be the average thickness of the flange.

Test specimens for shapes shall be taken at a point one-third the distance from the outer edge of the flange or leg to the web or heel of the section.

806.2.4. Stainless Steel. Stainless steel shall meet the ASTM requirements for the application.

806.3. FORGINGS

Unless otherwise indicated in the plans or contract specifications, forgings shall meet the requirements as specified herein.

Carbon steel forgings shall meet the requirements of ASTM A668 Steel Forgings, Carbon and Alloy, for General Industrial Use, Class B.

Heat-treated forgings shall meet the requirements of ASTM A668, Class F.

Alloy-steel forgings shall meet the requirements of ASTM A668, Class G.

806.4. CASTINGS

Steel, iron, and bronze castings shall meet the requirements specified herein and shown on the plans and contract documents.

806.4.1. Types of Castings.

806.4.1.1. Steel Castings. High-strength steel castings shall meet the requirements of ASTM A148, Steel Castings, High Strength, for Structural Purposes, Grade as specified.

Mild steel castings shall meet the requirements of ASTM A27, Steel Castings, Carbon, for General Application, Grade as specified.

806.4.1.2. Iron Castings. All castings shall be cast with an approved foundry's name, part number, country of origin, and production date (example: mm/dd/yy). Manufacturer shall certify that all castings conform to the ASTM and AASHTO Designations, as applicable, in Table 806.4.1.2.(a) Iron Castings Standards.

Table 806.4.1.2.(a) Iron Castings Standards

MATERIAL	ASTM	AASHTO	GRADE
Gray Iron Castings to include Valve Boxes, Non-Traffic Inlet Rings, Covers, and Grating	A48	N/A	Class 30B Minimum
Gray Iron Castings to include Traffic Bearing Manhole Rings and Covers, and Grating	A48	M-306-07	Class 35B Minimum
Gray Iron Castings for Valves, Flanges, and Pipe Fittings	A126	N/A	Class B

1. AASHTO M-306-07 Standard Specification for Drainage Structure Castings was implemented in 2005 and requires that municipal castings conform to the requirements of "Gray Iron Castings" AASHTO M105-06/ASTM A48 Class 35B.

806.4.1.3. Iron Rockers and Bearing Plates. Rockers and bearing plates shall be cast iron of the type and grade indicated on the plans and contract documents.

806.4.1.4. Bronze Expansion and Bearing Plates. Bronze bearing and expansion plates shall meet the requirements of ASTM B22 Bronze Castings for Bridges and Turntables, Alloy B.

806.4.1.5. Railings and Posts. Fittings and castings for steel railing shall be of malleable iron or cast steel and shall meet the requirements of ASTM A47 Ferritic Malleable Iron Castings, Grade 35018, or ASTM A27 Steel Castings, Carbon, for General Application, Grade 70-36. All fittings and castings shall be galvanized, and the galvanizing shall meet the requirements of ASTM Designation A153 Zinc Coating (Hot-Dip) on Iron and Steel Hardware.

806.4.1.6. Ornamental Tablets and Miscellaneous Castings. Ornamental tablets and miscellaneous castings shall meet the requirements of ASTM B584 Copper Alloy Sand Castings for General Applications.

806.4.2. Workmanship. All casting shall be true to pattern in form and dimension, free from pouring faults, sponginess, cracks, blow holes and other defects in positions affecting strength and value for the service intended. Angles shall be filleted, and arises shall be sharp and true.

806.4.3. Coatings. Castings shall not be coated unless otherwise specified in the plans and contract documents.

806.5. COPPER

Sheet copper shall meet the requirements of ASTM B152 Copper Sheet, Strip, Plate, and Rolled Bar.

806.6. BOLTS, NUTS AND WASHERS

806.6.1. General. Bolts, nuts and washers shall conform to the requirements of these specifications. Bolts shall be of the type and size specified on the plans and shall be furnished with suitable nuts and washers where required.

The values Table 806.6.1.(a) Grip Determination allow for manufacturing tolerances; provide for the inclusion of either one (1) or two (2) flat circular washers; and the use of either a heavy or finished nut with adequate "strike-through" at the end of the bolt. For each required beveled washer, add an additional $\frac{1}{8}$ -in. To determine the required length of interference-body bolts, the value shown in Table 806.6.1.(a) Grip Determination, less $\frac{1}{8}$ -in, shall be added to the grip.

Table 806.6.1.(a) Grip Determination¹

Determination Of Grip: To determine the required hexagon head bolt length, the value shown in the following table shall be added to the grip; i.e., the total thickness of all connected material, exclusive of washers.									
Bolt Size (inches)	$\frac{1}{2}$	$\frac{5}{8}$	$\frac{3}{4}$	$\frac{7}{8}$	1	$1 \frac{1}{8}$	$1 \frac{1}{4}$	$1 \frac{3}{8}$	$1 \frac{1}{2}$
To determine required bolt length add to grip² (inches)	$\frac{13}{16}$	$1 \frac{1}{16}$	$1 \frac{3}{16}$	$1 \frac{5}{16}$	$1 \frac{9}{16}$	$1 \frac{13}{16}$	$1 \frac{13}{16}$	$2 \frac{1}{16}$	$2 \frac{1}{16}$

1. More information can be found at ASTM A325 A490
2. The total length of bolts shall be adjusted to the next $\frac{1}{4}$ -in increment up to 5-in in length and to the next $\frac{1}{2}$ -in increment for lengths over 5-inches.

806.6.2. Unfinished Bolts. Unfinished bolts shall meet the requirements of ASTM A307 Carbon Steel Bolts and Studs, Grade A.

806.6.3. High-Strength Bolts. High-strength bolts shall meet the requirements of ASTM A325 (A325M) Structural Bolts, Steel, Heat Treated, 120/105 ksi Minimum Tensile Strength (High-Strength Bolts for Structural Steel Joints.)

806.6.4. Anchor Bolts. Unless otherwise specified, plain and threaded bars used for anchorage purposes shall meet the requirements of ASTM A36 Carbon Structural Steel, or ASTM A663 Steel Bars, Carbon, Merchant Quality, Mechanical Properties, Grade 65. Headed bolts and nuts shall meet the requirements of ASTM A307 Carbon Steel Bolts and Studs, Grade A. Anchor bolts shall not be galvanized unless otherwise noted on the drawings.

A mill test report or certification shall be required indicating that the material meets these requirements. When heat-treated material is specified or required, the test report for certification shall include the necessary certification relative to the heat treating process.

806.6.5. Washers. Washers may be gauge washers to facilitate torque testing. [Section 701.3.2.4.](#) Tightening.

806.7. MEASUREMENT AND PAYMENT.

Structural steel shall be measured and paid for by the pound. The bolts, nuts, and washers shall not be paid for as a separate contract item. These items are considered incidental and subsidiary to other items.

INDEX

A

Abbreviations	101-1, 101-4
Abrasion	
Los Angeles Abrasion	301-16, 302-2
Resistance to Abrasion	502-21, 502-23
Wet Track Abrasion	404-3
Admixture	303-6
Air-Entraining Admixture	303-6
Chemical Admixture	303-5
Mineral Admixture	303-6, 601-9, 702-2
Water-reducing Admixture	303-6
Aggregate	
Coarse Aggregate	302-1, 302-2, 303-1, 303-3, 303-4, 303-13, 702-2
Dry Aggregate	302-9, 404-2, 404-4
Fine Aggregate	302-2, 302-18, 302-19, 302-20, 303-2, 303-3, 303-4, 303-13, 303-23, 404-2, 702-1, 702-2, 702-6
Mineral Aggregate	403-1
Wet Aggregate	302-9
Alley	204-2, 303-23, 402-1, 402-2, 405-4, 509-1
Alley Crossings	405-4, 509-1
Alley Paving	303-23
Anchor Bolts	501-15, 702-12, 703-5, 806-1, 806-3
Articulating Concrete Blocks	803-1, 803-2, 803-3, 803-4
Asphalt	
Asphalt Binders	302-3, 302-4, 302-5, 302-6, 302-17, 302-19
Asphalt Storage	302-23
Emulsified Asphalt Treatment	302-16
Asphaltic Concrete	302-24, 403-1, 403-2, 702-22
Assignments	108-2
Authority of the Engineer	105-4
Axle Steel	303-8, 702-2

B

Backfill	
Backfill Soil	802-3, 802-5
Earth Backfill	805-2
Final Backfill ..	101-1, 101-2, 402-3, 405-3, 504-1, 504-2, 504-3, 504-4, 504-11, 508-10, 802-6
Gravel Backfill	805-3
Initial Backfill ..	101-2, 504-1, 504-6, 504-7, 504-8, 504-9, 504-10, 504-11
Open Cut Backfill	504-1, 508-1, 508-4, 508-7, 508-10, 509-1, 601-7, 601-9, 702-28, 702-29
Reinforced Backfill	802-6
Structural Backfill	701-4, 802-8
Barricades	107-6, 503-2, 505-1, 509-1, 801-1

Bituminous Material	204-2, 302-3, 302-6, 302-8, 302-15, 302-16, 302-17, 302-19, 302-26, 302-27, 303-10, 403-1, 404-6, 404-7, 501-12, 508-6

Bonds

Maintenance Bond	303-26
Payment Bonds	103-2
Performance Bond	101-3, 103-1, 103-2
Surety Bonds ..	101-1, 102-2, 102-3, 103-1, 103-2, 103-4, 103-5

Boring

Guided Boring	503-3
Jacking or Tunneling	503-1, 503-2, 503-4, 509-1
Pilot Hole Boring	503-3
Soil Borings	107-9
Borrow	110-2, 203-1, 203-3, 203-5, 204-1

C

Carbon steel	
forgings	806-2
Carbon Steel	806-1
Bolts	501-15, 501-16, 502-9, 503-1, 806-3
Plates	501-10
tension bars	801-4
Castings	
Bronze Castings	703-2, 806-2
Copper Alloy Sand Castings	502-11, 806-2
Ductile Iron Castings	502-2, 502-10, 502-14, 502-25
Gray Iron Castings	502-2, 502-14, 502-25, 806-2
Iron Castings	502-3, 806-2
Steel Castings	804-4, 806-2
Cement	
Asphalt Cement	302-3, 302-5, 302-6, 302-7, 302-10, 302-17, 302-19, 404-1
Cement Dispersing Agent ..	303-13, 702-3, 702-4, 702-6, 702-7, 702-11, 702-12, 702-24
Cement Mortar	501-3, 501-9, 702-10
Cement Treated Base	301-9, 301-10
Plant-Mixed Cement	301-9, 301-10
Portland Cement	204-2, 301-7, 301-8, 301-11, 302-3, 302-27, 303-1, 303-3, 303-5, 303-6, 303-23, 303-26, 305-1, 305-2, 305-3, 305-4, 305-5, 402-2, 405-1, 405-2, 507-1, 508-3, 601-9, 602-4, 702-1, 702-2, 702-6, 702-11, 702-16, 702-21, 703-4, 801-5, 802-1, 802-2, 803-1, 803-7
Solvent Cement	501-19
Change Order ...	101-1, 103-1, 104-1, 104-2, 104-3, 105-1, 105-2, 107-12, 109-2
Channel Excavation	203-2
Check Dam	
Filter Tube Check Dam	202-6
Rock Check Dam	202-5
Chip Seal	305-2, 404-6, 404-7, 404-8

Cleanouts	405-2, 502-6, 502-7, 502-8, 502-29, 507-2, 601-8, 701-1, 701-3
Clearing and Grubbing	110-2, 203-3, 204-1
Cofferdam	107-7, 701-4, 702-13, 702-15, 704-2, 802-6, 802-7
Compost.....	202-12, 204-2, 204-3, 204-7
Conductors	805-2
Conduit	
Electric Conduit	107-5, 201-2
Existing Conduit	506-4, 506-8
Pressure Conduit.....	502-10
Stormwater Conduit.....	501-11, 501-21, 802-5
Structural Plate Conduit	501-14, 501-15, 508-5
Underground Conduit.....	501-1, 502-12, 503-1, 504-12, 505-1, 506-1, 507-1, 509-1, 802-4
Wastewater Conduit..	405-2, 405-3, 501-5, 501-19, 501-20, 501-22, 502-21, 502-23, 502-28, 502-30, 507-1, 507-2, 507-3, 507-4, 507-7, 507-8
Water Conduit	405-3, 502-26, 502-27, 506-1, 506-2, 506-4, 506-5, 506-7, 507-1
Continuous Mixing Plant.....	302-25, 302-26
Copper Bearing Structural Steel.....	806-1
Cotton Mats.....	303-10, 702-16
Crack Sealing.....	401-1
Culvert	
Arch Culvert	501-6
Box Culvert.	501-14, 508-6, 508-7, 702-3, 702-14, 802-7
Direct Traffic Culvert.....	702-13, 702-16, 702-17
Elliptical Culvert.....	501-6
Reinforce Concrete D-Load Culvert	501-4, 501-5, 501-6
Reinforced Concrete Culvert	405-2, 501-4, 501-5, 501-6, 508-1, 702-14, 702-28
Curb	
Concrete Curb and Gutter	204-2, 301-17, 2, 305-1, 305-4, 802-1
Curb Inlets	508-1
Curb Stop	502-12, 502-27, 502-28, 506-4
Integral Curb	305-2, 701-2
Monolithic Curb	303-23
Superimposed Curb	303-23
Curing Concrete	303-10, 303-24, 303-25, 405-3, 702-5, 702-15, 702-16, 803-8
Curing Materials	303-9, 303-10, 303-11, 303-22, 405-1, 702-3, 702-17

D

Default of Contractor	108-5
Dehumidification.....	804-2
Dewatering	202-8, 202-9, 203-2, 502-29, 506-4, 601-7
Dike	
Diversion Dike	202-2, 202-4, 202-8
Triangular Sediment Filter Dike	110-2, 202-4
Disputed Work....	101-1, 104-2, 104-3, 104-4, 107-8, 108-8, 109-2
Dust Control ..	110-2, 201-3, 203-5, 204-7, 302-10, 302-16, 402-2

E

Embankment	
Earth Embankment	203-4
Railroad Embankment.....	503-2
Rock Embankment.....	203-4
Rolling of Embankment	301-1, 301-2, 302-24, 404-8
Stone Embankment.....	202-7, 202-8
Temporary Embankment.....	202-2
Emulsion	
Anionic Emulsion.....	302-7, 302-8, 302-9
Asphalt Emulsion	301-11, 301-14, 301-15, 303-11, 404-2, 404-3, 404-5
Polymer Emulsion	302-7, 302-10
Road Sealing Emulsion.....	302-11
Specialty Emulsion.....	301-11, 302-12, 302-16, 302-18, 302-20, 403-1
Erosion Control	110-2, 202-8, 202-11, 202-12, 203-5, 204-2, 204-3, 301-6, 301-10, 302-10, 302-11, 302-16, 803-5
Erosion Control Blanket	110-2, 202-4, 202-8, 202-11
Erosion Control Compost	202-12, 204-2, 204-3
Excavation	107-8, 110-2, 203-2, 203-5, 204-1, 305-1, 305-3, 305-4, 402-1, 405-3, 502-7, 502-30, 504-1, 504-5, 508-1, 508-4, 508-5, 508-6, 508-10, 604-2, 701-1, 701-4, 702-22, 702-23, 702-24, 702-28, 702-29, 802-1, 802-4, 802-7
Extra Work	101-3, 101-1, 101-2, 104-1, 104-2, 104-3, 104-4, 105-1, 107-8, 107-9, 107-10, 108-3, 108-8, 109-1, 109-2, 702-17, 702-27

F

False-work	702-9
Fence	
Chain Link Fence	202-7, 704-2, 801-2, 801-3, 801-5, 804-6
Fence Posts	202-3, 801-5
Metal Beam Guard Fence	801-1
Wire Fence.....	202-3, 704-2, 801-5, 801-6, 804-6
Fertilizer	110-2, 204-3, 204-4, 204-5, 204-7
Fibrous Reinforcement.....	303-7, 405-1, 702-2
Filler	
Active Filler.....	703-2
Cotton Filler.....	303-10
Filler Block.....	405-1
Inactive Filler.....	703-3
Inert Filler	303-11
Joint Filler.....	303-9, 303-19, 702-3
Mineral Filler.....	302-3, 303-6, 404-2
Sealing Filler	303-20
Fire Hydrants...	107-5, 201-2, 405-2, 502-8, 502-9, 502-10, 504-6, 506-4, 506-6
Fly Ash	303-6, 303-13, 303-16, 504-4, 601-9
Forgings	704-2, 806-2

G

Gabion	
Fabric Gabions	803-4
Gabion Basket.....	202-7, 202-8, 803-4, 803-5, 803-6
Gabion Mattresses	803-4
Gabion Measurement and Payment.....	803-6
Gabion Stone	803-5
Gabion Structures	704-2, 803-4
Galvanizing ...	501-16, 502-25, 704-2, 801-2, 801-5, 804-5, 804-6
Geotextile	202-3, 202-5, 202-6, 202-7, 202-10, 301-18, 504-5, 802-4, 802-5, 802-6, 803-2, 803-3, 803-4, 803-5, 803-9, 803-10
Governing Law	101-2, 107-2
Grading ..	301-16, 302-17, 302-20, 302-21, 302-22, 302-25, 303-2, 303-3, 303-4, 1, 305-3, 403-1, 403-2, 405-1, 702-1, 702-2, 703-6
Gunite.....	604-2, 702-21, 803-7, 803-8

H

HDPE	101-5, 501-19, 501-22, 502-2, 502-5, 502-25, 503-1, 508-9, 602-4, 802-4
HDPE Adjustment Riser	502-2
HDPE Casing Spacers	503-1
Honeycombing	303-21
Hydraulic Mulching	204-6, 204-7, 803-4

I

Indemnification ...	101-2, 103-3, 103-4, 105-3, 107-1, 107-7
Inlets	
Combination Inlets.....	202-9, 202-11
Curb Inlets.....	202-9, 202-10
Grate Inlets.....	202-9, 202-10
Inlet Protection	110-2, 202-9
Pipe Inlets	202-10, 202-11
Interceptor Swale	110-2, 202-4

J

Joints	
Chemically Welded Joints	501-19, 507-1
Cold Joints	303-6, 702-12
Compression Joints.....	501-1, 507-1
Construction Joints ..	303-20, 303-21, 305-2, 402-1, 404-4, 405-1, 405-2, 502-3, 702-9, 702-12, 702-14, 702-15, 702-19, 702-23
Contraction Joints.....	303-20, 303-26, 402-2
Expansion Joints	303-18, 303-19, 303-23, 305-1, 305-2, 305-4, 402-1, 502-20, 702-8, 702-9, 702-19, 702-21, 801-2, 803-8
Gasket Joints.....	501-9
Longitudinal Joints.	301-14, 303-9, 303-17, 303-20, 404-5

Mechanical Joints.	501-8, 501-9, 501-18, 502-9, 502-11, 502-13
Pavement Joints.....	303-11, 303-20, 305-1
Pipe Joints.....	405-3, 501-2, 501-22, 506-1
Rubber-Gasket Joints	405-2, 501-4, 502-10, 502-11, 502-13, 506-1, 507-1
Sand-filled Joints	3
Shouldered Joints	501-9, 501-10
Transverse Joints.....	301-10, 303-9, 803-3
Weakened Plane Joints	405-2

L

Liens	101-3, 109-1
Lime	
Hydrated Lime.....	301-3, 301-4, 301-5, 301-6, 301-7
Lime Application.....	301-5
Lime Storage.....	301-4
Lime Treatment.....	204-2, 301-3, 301-4, 301-5
Quicklime	301-4, 301-5, 301-6, 301-7
Limestone	302-2, 302-3, 1, 404-2, 404-7
Linseed Oil	804-4
Luminaries	805-1

M

Manholes	
Exfiltration Testing Manholes	502-5
Fiberglass Manholes	502-1, 502-4
Precast Manholes	502-3
Rehabilitation of Manholes	602-1
Sealed Manholes	502-4
Shallow Manholes	502-4
Vacuum Testing Manholes.....	502-5
Median	303-14, 303-23, 305-4
Mulch	110-2, 204-7, 204-8

N

New Billet Steel.....	303-8
Notice to Proceed.....	101-1, 103-5

P

Painting	
Painting and Marking	704-2, 801-2, 804-1, 806-1
Painting Concrete Surfaces.....	702-19
Painting in Lieu of Rubbing	702-19
Painting Metal Structures	604-2, 703-6
Spot Painting.....	804-4, 804-7
Pavement Testing	204-2, 303-17, 303-23
Piling ..	107-7, 202-2, 604-2, 702-7, 702-9, 702-16, 702-19, 703-2, 704-1, 704-2, 704-3, 704-4
Pipe	
Aluminized Steel Pipe	501-11
Aluminum Pipe	501-12, 501-13
Cast Iron Pipe	502-8, 502-26, 506-5

Concrete Pipe	501-4, 501-6, 501-7, 502-6, 502-20, 502-21, 503-4, 504-10, 506-1, 507-1, 508-1, 508-3, 702-14
Corrugated Metal Pipe	405-2, 405-3, 501-11, 501-12, 508-3, 508-4
Corrugated Steel Pipe	501-11, 501-12, 501-13, 501-15, 804-6
Drainage Pipe	501-17, 802-4
Ductile-Iron Pressure Pipe	405-2, 501-8, 501-9, 502-10, 502-11
Fiberglass Pressure Pipe	501-22
Galvanized Steel Pipe	501-13
Gravity Sewer Pipe	501-18
Gravity Wastewater Pipe	405-2, 501-19
HDP Pipe	501-19, 601-5
HDPE Pipe	501-22, 802-4
Iron Pipe	501-8, 501-9, 502-12, 505-2
PE Pipe	501-19, 501-20, 501-21, 506-2, 506-3, 506-4, 601-5, 601-6, 601-7
PE Pressure Pipe	501-19, 501-20
Pipe Marking	501-7, 501-13
Pipe-Arch	501-6, 501-11, 501-12, 501-14, 508-4, 802-7
Plastic Pressure Pipe	501-18, 502-11
PVC Composite Pipe	405-2, 501-19, 507-6
PVC pressure-rated pipe	501-18
PVC Wastewater Pipe	501-18, 505-3
PVC water pipe	501-17
PVCO pipe	501-18, 505-3
PVCO water pipe	501-18
Reinforced Concrete Pressure Pipe	502-12
Sewer Pipe	501-4, 501-5, 501-6, 501-18, 501-22, 502-6, 502-7, 502-20, 601-3, 601-4, 702-14
Steel Pipe	202-7, 405-2, 501-9, 501-10, 501-11, 501-12, 501-13, 502-21, 502-25
Steel Water Pipe	501-10, 501-11
Thermoplastic Pipe	405-3, 501-20, 505-3, 508-9, 508-12
Water Pipe	501-1, 501-17, 501-19, 502-12, 502-24, 601-5
Pipe Bursting	501-1, 505-3, 509-2, 601-5, 601-7
Pipe Fittings	502-11, 506-1, 508-1
Plugging	204-4, 204-5, 502-15, 502-16, 506-3, 506-6, 601-2
Pneumatically Placed Concrete	604-2, 702-21, 803-7, 803-8
Pozzolan	303-6, 601-9
Prime Coat	204-2, 302-16, 302-20, 302-27
Primer	403-1, 508-2

Q

Quarry Stone	803-6

R

Railings	702-11, 801-2, 806-2
Recycled Material	301-11

Recycled/Reclaimed Asphalt Pavement	301-4, 301-7, 301-11
Reinforced Concrete Header	305-5
Reinforcement Bar Chairs	303-9
Retainage	101-3, 109-1, 109-3, 109-4
Retaining Wall	704-2, 802-1
Riprap	
Concrete Riprap	803-8
Dry Riprap	202-7, 202-10, 803-6, 803-7, 803-8
Grouted Riprap	803-7, 803-8
Mortared Riprap	803-6
Stone Riprap	202-10
Rolling	
Embankment	301-1, 301-2, 302-24, 404-8
Methods	301-3
Proof Rolling	301-1, 301-2

S

Safety Record	102-1
Salvageable Material	106-1, 701-2, 701-3
Saw Cutting	405-2
Sediment Trap	110-2, 202-7
Seeding	
Broadcast Seeding	204-6
Disced Seeding	204-6
Hydraulic Seeding	204-8
Turfgrass	110-2, 204-5, 204-6
Segmental Retaining Wall	704-2, 802-1, 802-2, 802-3, 802-5
Service Clamps	502-24, 502-25
Shoring	107-7, 107-8, 503-4, 503-5, 601-7, 802-7
Sidewalk	303-15, 305-3, 402-1
Silt Fence	110-2, 202-3, 202-4, 202-10
Slag	301-11, 302-1, 302-2, 303-3, 404-2, 404-6, 703-5
Slip Form Paving	303-15, 303-16, 303-23
Sliplining	405-2, 501-1, 501-19, 501-22, 505-3, 509-2, 601-8, 601-9, 601-10
Slump	303-7, 303-14, 303-15, 702-3, 702-5, 702-7
Sodding	110-2, 204-4, 204-5
Stabilized Construction Exit	110-2, 202-6, 202-7
Storm Sewers	107-9, 203-1, 502-3
Subbase	
Flexible Subbase	204-2, 301-15, 402-4, 404-6
Non-stabilized Subbase	303-26
Stabilized Subbase	303-26
Subcontracts	101-3, 107-4, 108-2, 108-6
Subgrade	101-2, 101-3, 203-4, 204-3, 301-1, 301-2, 301-3, 301-4, 301-5, 301-6, 301-7, 301-8, 301-9, 301-10, 301-11, 301-12, 301-13, 301-14, 301-15, 301-17, 301-18, 302-16, 302-19, 302-24, 302-27, 303-1, 303-18, 303-19, 303-20, 303-21, 1, 305-1, 305-2, 305-3, 305-4, 403-2, 403-3, 404-8, 405-2, 502-30, 504-1, 504-5, 504-10, 504-11, 701-1, 702-22, 803-3, 803-6, 803-8
Sureties	101-3, 103-2, 107-4
Suspension	
Suspension by Court Order	101-3, 108-6

Temporary Suspension 108-3

T

Thin Water Suspension..... 301-5, 301-13

Thrust Restraint..... 405-2, 502-10

Topsoil

 Manufactured Topsoil..... 204-2, 204-3

Trenchless Installation... 503-1, 508-1, 509-1, 601-7, 601-8

Tunneling

 Microtunneling..... 501-1

V

Valves

 Air Release Valves 502-19

 Air Valves 501-2, 502-16, 502-19, 502-20

 Brass Wheel Valves 502-16

 Butterfly Valves 502-18, 502-19

 Bypass Valves..... 502-14, 502-16

 Cutoff Valves..... 203-5

 Gas Valves..... 107-5

Gate Valves.... 502-10, 502-13, 502-15, 502-16, 502-19, 702-14

Geared Valves 502-14, 502-15

Horizontal Valves 502-13, 502-14, 502-15

Mainline Valves 501-2

Tapping Valves 502-14, 502-16, 502-25

Underground Service Line Valves.....502-11

Vacuum Release Valves 502-19

Water Valves.....107-5, 303-15

Vegetation..... 110-2, 201-1, 202-2, 203-1, 204-1

W

Waterproof Paper 303-10

Waterworks Service 501-10, 502-11, 502-13, 502-15, 502-25

Z

Zinc 202-7, 501-14, 501-15, 501-16, 502-29, 801-2, 801-3, 801-4, 801-5, 804-5, 804-6, 804-7, 806-2

Appendix A

Model Forms



APPENDIX A. MODEL FORMS**TABLE OF CONTENTS**

<u>Item #</u>	<u>Subject</u>	<u>Pages</u>
A.1.	BID BOND	App A –1
A.2.	STANDARD CONSTRUCTION CONTRACT	App A –2
A.3.	PERFORMANCE BOND	App A –3
A.4.	PAYMENT BOND	App A –4
A.5.	MAINTENANCE BOND	App A –5
A.6.	CERTIFICATE OF INSURANCE	App A –6
A.7.	CHANGE ORDER CHANGE ORDER INSTRUCTIONS	App A –7 App A –8
A.8.	INSPECTION OVERTIME	App A –9
A.9.	CONTRACTOR'S AFFIDIVAT Of FINAL PAYMENT	App A -10
A.10.	PRIVATE DEVELOPMENT CONTRACT (LESS THAN \$25,000.00)	App A –11-12
A.11.	CONTRACTOR LETTER CONCERNING DEVELOPER'S ABILITY TO PAY (LESS THAN \$25,00.00)	App A – 13
A.12.	PRIVATE DEVELOPMENT CONTRACT (MORE THAN \$25,000.00)	App A – 14-15
A.13.	DEVELOPMENT BOND	App A –16
A.14.	SCHEDULE FOR PHASE-IN OF TIER 1 TIER 4 NON-ROAD ENGINES	App A –17
A.15.	LOW-USE EXEMPTION WEEKLY REPORTING FORM	App A –18
A.16.	CONTRACT EQUIPMENT INVENTORY	App A –19-20

Form A.1.

BID BOND**STATE OF TEXAS**§
§
§**KNOW ALL MEN BY THESE PRESENTS:****COUNTY OF** _____

THAT _____, a corporation organized and existing under the laws of the State of _____, and fully authorized to transact business in the State of Texas, whose address is _____ of the City of _____, County of _____, State of _____, (hereinafter referred to as "Principal"), and _____ (hereinafter referred to as "Surety"), a corporation organized under the laws of the State of _____ and authorized under the laws of the State of Texas to act as Surety on bonds for principals, are held and firmly bound unto _____ (hereinafter referred to as "OWNER") in the penal sum of \$_____ in lawful money of the United States, for the payment whereof, the said Principal and Surety bind themselves, and their heirs, administrators, executors, successors, and assigns, jointly and severally, firmly by these presents:

SIGNED, SEALED and DATED this _____ day of 20_____**WHEREAS**, the Principal is herewith submitting its proposal for _____

the condition of the above obligations are such that if the aforesaid Principal shall be awarded the Contract, the said Principal will, within the time required, enter into a Contract and give Bonds, if required, for the faithful performance of the Contract and the prompt payment for labor and materials in the prosecution thereof, then this obligation shall be null and void; otherwise the Principal and Surety will pay unto the OWNER the full penal sum hereof, as liquidated damages, it being difficult and impractical to determine accurately the actual amount of damages occurring to OWNER by reason of Principal's failure to execute said Contract and Bonds.

PROVIDED FURTHER, that if any legal action be filed upon this Bond, venue shall lie exclusively in _____ County, Texas.

The Resident Agent of the Surety for delivery of notice and service of process is:

Name: _____

Address: _____

Phone number: _____

WITNESS

WITNESS

PRINCIPAL

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

SURETY

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

NOTE: CERTIFIED COPY OF POWER-OF-ATTORNEY SHOULD BE ATTACHED HERETO.

Form A.2.

STANDARD CONSTRUCTION CONTRACT

STATE OF TEXAS

§
§
§

KNOW ALL MEN BY THESE PRESENTS:

COUNTY OF _____

THIS CONTRACT is made and entered into on this the _____ day of _____, 20____
by and between the _____ (hereinafter referred to as "OWNER") and _____
_____ (hereinafter referred to as "CONTRACTOR"). In consideration of the mutual covenants
hereinafter set forth, the OWNER and CONTRACTOR agree as follows:

Article I. Work

The CONTRACTOR shall perform all of the work as specified in the Contract Documents. The work is generally described as follows: _

Plans and Specifications prepared by: _____

All extra work shall be performed as specified or indicated in the Contract Documents; and, at the CONTRACTOR'S own cost and expense, the CONTRACTOR shall furnish all the materials, supplies, machinery, equipment, tools, superintendence, labor, insurance, and other accessories and services as may be necessary in order to complete the construction, as described above and in accordance with the Contract Documents unless otherwise agreed to by the OWNER.

Article II. Contract Documents

The Contract Documents may only be altered, amended or modified as provided in the General Conditions. The Contract Documents consist of: this written agreement setting forth the work to be performed; advertisement, if any; instructions to bidders, if any; proposal; addendum; specifications, including the general, special, and technical conditions, provisions, plans, or working drawings; any supplemental changes or agreements pertaining to the work or materials therefor; bonds; the Standard Specifications for Public Works Construction published by the North Central Texas Council of Governments, as amended; and, any additional documents incorporated by reference. These form the Contract Documents and all are as fully a part of the Contract as if attached to this agreement or repeated herein.

Article III. Contract Time

The CONTRACTOR shall perform and complete all the items of work listed and referred to in the Contract Documents within _____ calendar days. All limitations of time set forth herein are material and are of the essence of this Contract.

Article IV. Contract Price

The OWNER shall pay the CONTRACTOR for completion of the work in accordance with the Contract Documents using current funds. Such payments shall be subject to the General and Special Conditions to the Contract, as contained in the Contract Documents.

Article V. Debts

The OWNER may, at its option, offset any amounts due and payable under this Contract against any debt (including taxes) lawfully due to OWNER from CONTRACTOR, regardless of whether the amount due arises pursuant to the terms of this Contract or otherwise and regardless of whether or not the debt due to OWNER has been reduced to judgment by a court.

Article VI. Miscellaneous Provisions

The terms used in this Contract shall have the same meaning as designated in the General Provisions of the Standard Specifications for Public Works Construction, North Central Texas Council of Governments, as amended. The Contract Documents, which constitute the entire agreement between the OWNER and CONTRACTOR, are listed in Article II. No assignment by either party hereto of any rights under or interests in the Contract Documents will be binding on the other party hereto without the written consent of the party sought to be bound. The OWNER and CONTRACTOR each binds itself, its partners, successors, assigns, and legal representatives hereto to the covenants, agreements, and obligations contained in the Contract Documents.

IN WITNESS WHEREOF, the OWNER and CONTRACTOR have executed this Contract in duplicate and on the date aforementioned. All portions of the Contract Documents have been signed or identified by the OWNER and CONTRACTOR.

CONTRACTOR:

ATTEST:

OWNER:

ATTEST:

By: _____

Printed Name: _____

By: _____

Printed Name: _____

Title: _____

Title: _____

Form A.3.

PERFORMANCE BOND

STATE OF TEXAS

§
§
§

KNOW ALL MEN BY THESE PRESENTS:

COUNTY OF _____

THAT _____, a corporation organized and existing under the laws of the State of _____, and fully authorized to transact business in the State of Texas, whose address is _____ of the City of _____, County of _____, State of _____, (hereinafter referred to as "Principal"), and _____ (hereinafter referred to as "Surety"), a corporation organized under the laws of the State of _____ and _____ authorized under the laws of the State of Texas to act as Surety on bonds for principals, are held and firmly bound unto _____ (hereinafter referred to as "OWNER") in the penal sum of \$_____ (not less than 100% of the approximate total amount of the Contract as evidenced in the proposal plus 10-percent of the stated penal sum as an additional sum of money representing additional court expenses, attorneys' fees, and liquidated damages arising out of or connected with the below identified Contract) in lawful money of the United States, for the payment whereof, the said Principal and Surety bind themselves, and their heirs, administrators, executors, successors, and assigns, jointly and severally, firmly by these presents:

WHEREAS, the Principal has entered into a certain written Contract with the OWNER, dated the _____ day of _____, 20_____, to which said Contract is hereby referred to and made a part hereof and as fully and to the same extent as if copied at length herein for the construction of _____.

NOW, THEREFORE, the condition of this obligation is such, that if the said Principal fully and faithfully executes the work and performance of the Contract in accordance with the plans, specifications, and Contract Documents, including any extensions thereof which may be granted with our without notice to Surety, during the original term thereof, and during the life of any guaranty required under the Contract, and according to the true intent and meaning of said Contract and the plans and specifications hereto annexed, if the Principal shall repair and/or replace all defects due to faulty materials or workmanship that appear within a period of one year from the date of final completion and final acceptance of the work by OWNER; and if the Principal shall fully indemnify and save harmless the OWNER from all costs and damages which OWNER may suffer by reason of failure to so perform herein and shall fully reimburse and repay OWNER all outlay and expense which the OWNER may incur in making good any default or deficiency, then this obligation shall be void; otherwise, to remain in full force and effect; and in case said CONTRACTOR shall fail to do so, it is agreed that the OWNER may do said work and supply such materials and charge the same against said CONTRACTOR and Surety on this obligation. Provided further, that if any legal action be filed on this Bond, venue shall lie in _____ County, Texas.

PROVIDED, HOWEVER, that this Bond is executed pursuant to the provisions Texas Government Code, Chapter 2253, as amended, and Article 7.19-1 of the Insurance Code, as amended., and all liabilities on this bond shall be determined in accordance with the provisions of said articles to the same extent as if they were fully copied at length herein.

Surety, for value received, stipulates and agrees that the bond shall automatically be increased by the amount of any change order or supplemental agreement which increases the Contract price with or without notice to the Surety, but in no event shall a Change Order or Supplemental Agreement which reduces the Contract price decrease the penal sum of this Bond. And further that no change, extension of time, alteration, or addition to the terms of the Contract, or to the work performed thereunder, or the plans, specifications, or drawings accompanying the same shall in any way affect its obligation on this bond, and it does hereby waive notice of any such change, extension of time, alteration, or addition to the terms of the Contract or to the work to be performed thereunder.

Surety agrees that the bond provides for the repairs and/or replacement of all defects due to faulty materials and workmanship that appear within a period of one (1) year from the date of completion and acceptance of the improvement by the OWNER.

The undersigned and designated agent is hereby designated by Surety herein as the agent resident to whom any requisite notice may be delivered and on whom service of process may be had in matters arising out of such suretyship.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument on this the _____ day of _____, 20_____.

WITNESS

PRINCIPAL

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

WITNESS

SURETY

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

The Resident Agent of the Surety for delivery of notice and service of process is:

Name: _____

Address: _____

Phone number: _____

Note: Date of Bond must NOT be prior to date of Contract.

Form A.4

PAYMENT BOND

STATE OF TEXAS

§
§
§

KNOW ALL MEN BY THESE PRESENTS:

COUNTY OF _____

THAT _____, a corporation organized and existing under the laws of the State of _____, and fully authorized to transact business in the State of Texas, whose address is _____ of the City of _____, County of _____, State of _____, (hereinafter referred to as "Principal"), and _____ (hereinafter referred to as "Surety"), a corporation organized under the laws of the State of _____ and _____ authorized under the laws of the State of Texas to act as Surety on bonds for principals, are held and firmly bound unto _____ (hereinafter referred to as "OWNER") and unto all persons, firms and corporations who may furnish materials for or perform labor upon the buildings, structures or improvements referred to in the attached Contract, in the penal sum of \$_____ (not less than 100% of the approximate total amount of the Contract as evidenced in the proposal) in lawful money of the United States, for the payment whereof, the said Principal and Surety bind themselves, and their heirs, administrators, executors, successors, and assigns, jointly and severally, firmly by these presents:

WHEREAS, the Principal has entered into a certain written Contract with the OWNER, dated the _____ day of _____, 20_____, to which said Contract is hereby referred to and made a part hereof and as fully and to the same extent as if copied at length herein for the construction of _____.

NOW, THEREFORE, the condition of this obligation is such, that the bond guarantees the full and proper protection of all claimants supplying labor and material in the prosecution of the work provided for in said Contract and for the use of each claimant, and that conversely should the Principal faithfully perform said Contract and in all respects duly and faithfully observe and perform all and singular the covenants, conditions, and agreements in and by said Contract, agreed to by the Principal, and according to the true intent and meaning of said Contract and the claims and specifications hereto annexed, and any and all duly authorized modifications of said Contract that may hereafter be made, notice of which modification to Surety being hereby waived, then this obligation shall be void; otherwise, to remain in full force and effect. Provided further, that if any legal action be filed on this Bond, venue shall lie in _____ County, Texas.

PROVIDED, HOWEVER, that this Bond is executed pursuant to the provisions Texas Government Code, Chapter 2253, as amended, and Article 7.19-1 of the Insurance Code, as amended, and all liabilities on this bond shall be determined in accordance with the provisions of said articles to the same extent as if they were fully copied at length herein.

Surety, for value received, stipulates and agrees that the bond shall automatically be increased by the amount of any Change Order or supplemental agreement which increases the Contract price with or without notice to the Surety and that no change, extension of time, alteration, or addition to the terms of the Contract, or to the work performed thereunder, or the plans, specifications, or drawings accompanying the same shall in any way affect its obligation on this bond, and it does hereby waive notice of any such change, extension of time, alteration, or addition to the terms of the Contract or to the work to be performed thereunder.

The undersigned and designated agent is hereby designated by Surety herein as the agent resident to whom any requisite notice may be delivered and on whom service of process may be had in matters arising out of such suretyship.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument on this the _____ day of _____, 20_____.

WITNESS

PRINCIPAL

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

WITNESS

SURETY

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

The Resident Agent of the Surety for delivery of notice and service of process is:

Name: _____

Address: _____

Phone number: _____

Note: Date of Bond must NOT be prior to date of Contract.

Form A.5.

MAINTENANCE BOND

STATE OF TEXAS

§
§
§

KNOW ALL MEN BY THESE PRESENTS:

COUNTY OF _____

THAT _____, a corporation organized and existing under the laws of the State of _____, and fully authorized to transact business in the State of Texas, whose address is _____ of the City of _____, County of _____, State of _____, (hereinafter referred to as "Principal"), and _____ (hereinafter referred to as "Surety"), a corporation organized under the laws of the State of _____ and _____ authorized under the laws of the State of Texas to act as Surety on bonds for principals, are held and firmly bound unto _____ (hereinafter referred to as "OWNER") in the penal sum of \$_____ in lawful money of the United States, for the payment whereof, the said Principal and Surety bind themselves, and their heirs, administrators, executors, successors, and assigns, jointly and severally, firmly by these presents:

WHEREAS, the Principal has entered into a certain written Contract with the OWNER, dated the _____ day of _____, 20_____, to which said Contract is hereby referred to and made a part hereof and as fully and to the same extent as if copied at length herein for the construction of _____.

NOW, THEREFORE, the condition of this obligation is such, that the bond guarantees the full and proper maintenance and repair of the work herein contracted to be done and performed for a period of _____ year(s) from the date of acceptance and Principal will do all necessary backfilling that may arise on account of sunken conditions in ditches, or otherwise, and do and perform all necessary work and repair any defective condition growing out of or arising from the improper laying or construction of same, or on account of any breaking of same caused by said CONTRACTOR in construction of same, or on account of any defect arising in any of said work laid or constructed by said CONTRACTOR or on account of improper excavation or backfilling, it being understood that the purpose of this section is to cover all defective conditions arising by reason of defective materials, work or labor performed by said CONTRACTOR, then this obligation shall be void; otherwise, to remain in full force and effect; and in case said CONTRACTOR shall fail to do so, it is agreed that the OWNER may do said work and supply such materials and charge the same against said CONTRACTOR and Surety on this obligation. Provided further, that if any legal action be filed on this Bond, venue shall lie in _____ County, Texas.

PROVIDED, HOWEVER, that said Surety, for value received, stipulates and agrees the bond shall automatically be increased by the amount of any Change Order or supplemental agreement which increases the Contract price with or without notice to the Surety and that no change, extension of time, alteration, or addition to the terms of the Contract, or to the work performed thereunder, or the plans, specifications, or drawings accompanying the same shall in any way affect its obligation on this bond, and it does hereby waive notice of any such change, extension of time, alteration, or addition to the terms of the Contract or to the work to be performed thereunder.

The undersigned and designated agent is hereby designated by Surety herein as the agent resident to whom any requisite notice may be delivered and on whom service of process may be had in matters arising out of such suretyship.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument on this the _____ day of _____, 20_____.

WITNESS

PRINCIPAL

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

WITNESS

SURETY

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

The Resident Agent of the Surety for delivery of notice and service of process is:

Name: _____

Address: _____

Phone number: _____

Note: Date of Bond must NOT be prior to date of Contract.

Form A.6.

CERTIFICATE OF INSURANCE

PRODUCER		ISSUE DATE (MM/DD/YY) THIS CERTIFICATE IS ISSUED AS A MATTER OF INFORMATION ONLY AND CONFERS NO RIGHTS UPON THE CERTIFICATE HOLDER. THIS CERTIFICATE DOES NOT AMEND, EXTEND, OR ALTER THE COVERAGE AFFORDED BY THE POLICIES BELOW	
COMPANIES AFFORDING COVERAGE			
CODE	SUB-CODE	COMPANY LETTER A	
INSURED		COMPANY LETTER B	
		COMPANY LETTER C	
		COMPANY LETTER D	

COVERAGES THIS IS TO CERTIFY THAT THE POLICIES OF INSURANCE LISTED BELOW HAVE BEEN ISSUED TO THE INSURED NAMED ABOVE FOR THE POLICY PERIOD INDICATED, NOTWITHSTANDING ANY REQUIREMENT, TERM, OR CONDITION OF ANY CONTRACT OR OTHER DOCUMENT WITH RESPECT TO WHICH THIS CERTIFICATE MAY BE ISSUED OR MAY PERTAIN, THE INSURANCE AFFORDED BY THE POLICIES DESCRIBED HEREIN IS SUBJECT TO ALL THE TERMS, EXCLUSIONS, AND CONDITIONS OF SUCH POLICIES. LIMITS SHOWN MAY HAVE BEEN REDUCED BY PAID CLAIMS.				
Type of Insurance	Policy Number	Effective Date (MM/DD/YY)	Expiration Date (MM/DD/YY)	All Limits <u>in Thousands</u>
General Liability				
Commercial General Liability				
Claims Made Occur.				General Aggregate \$ _____
Owner's & Contractor's Prot.				Products-Comp/Ops Aggregate \$ _____
				Personal & Advertising Injury \$ _____
				Each Occurrence \$ _____
Automobile Liability				Fire Damage (Any one fire) \$ _____
Any Auto				Medical Expense (Any one person) \$ _____
All Owned Autos				Combined Single Limit \$ _____
Scheduled Autos				Bodily Injury (Per person) \$ _____
Hired Autos				Bodily Injury (per accident) \$ _____
Non-Owned Autos				Property Damage \$ _____
Garage Liability				
Excess Liability				
Other Than Umbrella Form				Each Occurrence Aggregate
				\$ _____ \$ _____
				Statutory
Workers Compensation				\$ _____ (Each Accident)
And				\$ _____ (Disease – Policy Limit)
Employers Liability				\$ _____ (Disease – Each Employee)
Other				
Description of Operations/Locations/Vehicles/Restrictions/Special Items 				

CERTIFIED HOLDER	CANCELLATION SHOULD ANY OF THE ABOVE DESCRIBED POLICIES BE CANCELLED BEFORE THE EXPIRATION DATE THEREOF, THE ISSUING COMPANY WILL ENDEAVOR TO MAIL _____ DAYS WRITTEN NOTICE TO THE CERTIFICATE HOLDER NAMED TO THE LEFT, BUT FAILURE TO MAIL SUCH NOTICE SHALL IMPOSE NO OBLIGATION OR LIABILITY OF ANY KIND UPON THE COMPANY, ITS AGENTS, OR REPRESENTATIVES AUTHORIZED REPRESENTATIVE

Form A.7.

CHANGE ORDER

No. _____

Project: _____

Date of Issuance: _____

Contract For: _____

OWNER: _____

Contract No. _____

Address: _____

CONTRACTOR: _____

Engineer: _____

Engineer's Project No. _____

You are directed to make the following changes in the Contract Documents. Each Change Order shall be specific and final as to prices with no reservation or other provisions allowing for future additional money or time as a result of the particular changes identified and fully compensated in the Change Order.

Description: _____

Purpose of Change Order: _____

Attachments: _____

CHANGE IN CONTRACT PRICE:	CHANGE IN CONTRACT TIME:
Original Contract Price \$ _____	Original Contract Time: _____ (Days or Date Range)
Net price change from previous Change Order(s)	Net change from previous Change Orders:
Extras to date \$ _____	_____ (Days)
Credits to date \$ _____	
Net \$ _____	
Contract Price prior to this Change Order: \$ _____	Contract Time prior to this Change Order: _____ (Days or Date Range)
Net Increase (Decrease) of this Change Order: \$ _____	Net Increase (Decrease) of this Change Order: _____ (Days)
Contract Price with all approved Change Orders: \$ _____	Contract Time with all approved Change Orders:
Cumulative Contract Increase (Decrease) _____ %	_____ (Days or Date Range)
Original Funds Available For Change Orders: \$ _____	
Remaining Funds Available For Change Orders: \$ _____	
Additional Funding, If Necessary: \$ _____	

Signature of the CONTRACTOR indicates that he/she has read this Change Order from and any referenced attachments and that he/she is in agreement herewith, including any adjustment in the Contract Price or Contract Time.

Recommended:**Approved:****Approved:**

(Engineer)

(OWNER)

(CONTRACTOR)

Date:**Date:****Date:**

CHANGE ORDER INSTRUCTIONS

GENERAL INFORMATION

This document was developed to provide a uniform format for handling contract changes that affect Contract Price or Contract Time. Changes that have been initiated by a Work Directive Change must be incorporated into a subsequent Change Order if they affect Price or Time.

Changes that affect Contract Price or Contract Time should be promptly covered by a Change Order. The practice of accumulating change order times to reduce the administrative burden may lead to unnecessary disputes.

For supplemental instructions and minor changes not involving a change in the Contract Price or Contract Time, a Field Order may be used.

COMPLETING THE CHANGE ORDER FORM

Engineer initiates the form, including a description of the changes involved and attachments based upon documents and proposals submitted by CONTRACTOR, or requests from OWNER or both.

Once Engineer has completed and signed the form, all copies should be sent to CONTRACTOR for approval. After approval by CONTRACTOR, all copies should be sent to OWNER for approval. Engineer should make distribution of executed copies after approval by OWNER.

If a change only applies to price or to time, cross out the part of the tabulation that does not apply.

Form A.8.

INSPECTION OVERTIME

Date: _____ (Request must be **submitted at least two working days in advance** of planned overtime work)

To: Program Manager
Public Works/Transportation Department

Re: Overtime Reimbursement for

(Project)

From: _____
(CONTRACTOR)

We request permission to work beyond the normal 8-hour-day/ 40-hour-week to perform the following:

Estimated number of hours (Hours will be calculated portal to portal):

and date(s):

We agree to reimburse OWNER at the overtime rate for the pay of the inspector(s) assigned for this work, or for alternate inspection costs if the OWNER chooses. The OWNER will provide a detailed invoice, and payment will be made within 10-days. The check will be made payable to _____ (OWNER) and will be mailed or delivered to the Program Manager.

Signed: _____

Title: _____

Form A.9.

CONTRACTOR'S AFFIDAVIT OF FINAL PAYMENT

THE STATE OF TEXAS)
)
 COUNTY OF _____)

KNOW ALL MEN BY THESE PRESENTS:

BEFORE ME, the undersigned authority, on this day personally appeared _____
 ("Affiant"), who, after being by me duly sworn, deposes, and says that it is _____, a
 _____ (corporation, partnership, trade name) of _____ County, State
 of Texas (the "CONTRACTOR"), which said CONTRACTOR was awarded the Contract dated the _____ day of
 _____, 20____, for the construction of _____
 at _____ (the "Work"), for a total consideration of _____ Dollars
 to be paid to the said CONTRACTOR (the "Contract"), and that Affiant has full power of authority to make this
 affidavit.

That _____ (the "OWNER") has approved the final estimate on said
 Work, and that the said CONTRACTOR has fully satisfied and paid any and all claims that may be covered by Texas
 Government Code, Chapter 2253, as amended, or any other applicable statutes or charter provisions, and that all
 just bills for labor and materials have been paid and discharged by said CONTRACTOR insofar as they pertain to the
 work in question.

That in addition to any funds which may have been previously paid by the OWNER, the CONTRACTOR hereby
 accepts the amount of _____ Dollars as FULL AND FINAL PAYMENT under the
 aforementioned Contract, and hereby waives and releases any right Affiant and/or the CONTRACTOR may have to
 pursue claims of any nature against the OWNER arising out of or in any manner connected with the performance of
 the Work and/or the Contract, including but not limited to claims of third parties that supplied material and/or labor
 for the Work for or through the CONTRACTOR ("Subcontractors"), as well as claims for delay, additional
 compensation or for recovery of liquidated damages which may have been withheld by the OWNER. The
 CONTRACTOR shall defend, hold harmless and indemnify the OWNER from any such claims of such Subcontractors.
 The CONTRACTOR further releases the OWNER from any claim or liability arising from any act or neglect of the
 OWNER related to or connected with the Contract. This affidavit is given pursuant to the final payment provisions
 of the Contract, and shall not be deemed to alter or modify the terms and provisions of said Contract.

 By _____
 (Affiant)

 (Printed Name)

SUBSCRIBED AND SWORN TO BEFORE ME, this the _____ day of _____, A.D. 20_____.

By _____
 (Notary Public in and for the State of Texas)

[Notary Seal]

 (Printed Name of Notary)

My commission expires _____

Article VI. Indemnity

Developer and CONTRACTOR do hereby covenant and contract to waive all claims, release, indemnify, defend and hold harmless Town/City and all of its officials, officers, agents, employees and invitees, in both their public and private capacities, from any and all liability, claims, suits, demands or causes of action, including all expenses of litigation and/or settlement which may arise by reason of injury to or death or debt of any person, or for loss of, damage to or loss of use of any property arising out of or in connection with this contract. Such indemnity will apply whether the claims, suits, losses, damages, causes of action or liability arise in whole or in part from the negligence of CONTRACTOR and/or Developer or any of its officers, officials, agents, employees or invitees, whether said negligence is sole negligence, contractual comparative negligence, concurrent negligence, joint negligence, gross negligence, active negligence, passive negligence or any other form of negligence. It is the express intention of the parties hereto that the indemnity provided for in this paragraph is indemnity by Developer and CONTRACTOR to indemnify and protect Town/City from the consequences of Town/City's own joint negligence, where that negligence is a concurring cause of any injury, death or damage or whether said negligence is sole negligence, contractual comparative negligence, concurrent negligence, joint negligence, gross negligence, active negligence, passive negligence or any other form of negligence. Also, it is understood by Developer and CONTRACTOR that such indemnity is indemnity by Developer and CONTRACTOR to indemnify and protect Town/City from any liability, claims, suits, losses, damages or causes of action due to CONTRACTOR's or Developer's negligence, error or omission, or the negligence, error or omission of any other person(s).

Article VII. Ownership of Improvements

Upon completion of the Work and its acceptance by the Town/City, in accordance with Town/City's plans and specifications and after approval thereof by the designated representative of the Town/City, the Work, as described above, shall become the sole property of the Town/City provided that the Work is located within a public street, alley easement, or other Right-of-Way belonging to the Town/City. The Town/City takes the Work free from any liens or encumbrances thereon upon final acceptance.

Article VIII. Governance

This contract shall be governed by and construed in accordance with the laws of the State of Texas, and the Charter, Ordinances, Rules and Regulations of the Town/City. This contract is performable in _____ County, Texas, and exclusive venue for any action under this contract shall lie in _____ County, Texas.

IN WITNESS WHEREOF, this contract has been executed on the date stated above by _____, Developer, (through its duly authorized officials), and by _____, CONTRACTOR (through its duly authorized officials), thereby binding themselves, their heirs, successors, assigns, and representatives to the full and faithful performance of the terms of this contract.

WITNESS

WITNESS

DEVELOPER

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

Phone Number: _____

GENERAL CONTRACTOR

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

Phone Number: _____

Form A.11.

CONTRACTOR LETTER CONCERNING DEVELOPER'S ABILITY TO PAY (LESS THAN \$25,000.00)

Date: _____

To: Private Development Coordination

(City or Town)

Re: _____ (Development Name)

File No. _____

Plat No: _____

We have satisfied ourselves to the financial integrity of the Development owner of the above referenced project.
We have confidence in Developer's ability to meet its obligations to us in a timely manner.

Respectfully submitted,

Signed: _____, CONTRACTOR or Authorized Representative

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

Phone Number: _____

contract No. _____

PRIVATE DEVELOPMENT CONTRACT (MORE THAN \$25,000.00)

www

COUNTY OF _____

Article I. Work

Street Name and/or Alley Between and/or Storm Drain (Pipe Size) and/or Water Pipe (Pipe Size) and/or Wastewater Pipe (Pipe Size) and/or Trench Safety	From	To	Length	Width	Thickness

Article II. Construction Documents

Article III. Price and Payment

Article IV. Bonds

Article V. Liability

Last Updated October 2004

Article VI. Indemnity

Developer and CONTRACTOR do hereby covenant and contract to waive all claims, release, indemnify, defend and hold harmless Town/City and all of its officials, officers, agents, employees and invitees, in both their public and private capacities, from any and all liability, claims, suits, demands or causes of action, including all expenses of litigation and/or settlement which may arise by reason of injury to or death or debt of any person, or for loss of, damage to or loss of use of any property arising out of or in connection with this contract. Such indemnity will apply whether the claims, suits, losses, damages, causes of action or liability arise in whole or in part from the negligence of CONTRACTOR and/or Developer or any of its officers, officials, agents, employees or invitees, whether said negligence is sole negligence, contractual comparative negligence, concurrent negligence, joint negligence, gross negligence, active negligence, passive negligence or any other form of negligence. It is the express intention of the parties hereto that the indemnity provided for in this paragraph is indemnity by Developer and CONTRACTOR to indemnify and protect Town/City from the consequences of Town/City's own joint negligence, where that negligence is a concurring cause of any injury, death or damage or whether said negligence is sole negligence, contractual comparative negligence, concurrent negligence, joint negligence, gross negligence, active negligence, passive negligence or any other form of negligence. Also, it is understood by Developer and CONTRACTOR that such indemnity is indemnity by Developer and CONTRACTOR to indemnify and protect Town/City from any liability, claims, suits, losses, damages or causes of action due to CONTRACTOR's or Developer's negligence, error or omission, or the negligence, error or omission of any other person(s).

Article VII. Ownership of Improvements

Upon completion of the Work and its acceptance by the Town/City, in accordance with Town/City's plans and specifications and after approval thereof by the designated representative of the Town/City, the Work, as described above, shall become the sole property of the Town/City provided that the Work is located within a public street, alley easement, or other Right-of-Way belonging to the Town/City. The Town/City takes the Work free from any liens or encumbrances thereon upon final acceptance.

Article VIII. Governance

This contract shall be governed by and construed in accordance with the laws of the State of Texas, and the Charter, Ordinances, Rules and Regulations of the Town/City. This contract is performable in _____ County, Texas, and exclusive venue for any action under this contract shall lie in _____ County, Texas.

IN WITNESS WHEREOF, this contract has been executed on the date stated above by _____, Developer, (through its duly authorized officials), and by _____, CONTRACTOR (through its duly authorized officials), thereby binding themselves, their heirs, successors, assigns, and representatives to the full and faithful performance of the terms of this contract.

WITNESS

WITNESS

DEVELOPER

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

Phone Number: _____

GENERAL CONTRACTOR

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

Phone Number: _____

Form A.13.

DEVELOPMENT BOND

STATE OF TEXAS

§
§
§

KNOW ALL MEN BY THESE PRESENTS:

COUNTY OF _____

THAT _____, a corporation organized and existing under the laws of the State of _____, and fully authorized to transact business in the State of Texas, whose address is _____ of the City of _____, County of _____, State of _____, (hereinafter referred to as "Principal"), and _____ (hereinafter referred to as "Surety"), a corporation organized under the laws of the State of _____ and _____ authorized under the laws of the State of Texas to act as Surety on bonds for principals, are held and firmly bound unto _____ a municipal corporation organized and existing under the laws of the State of Texas (hereinafter referred to as "Town/City") and unto all persons, firms and corporations who may furnish materials for or perform labor upon the buildings, structures or improvements referred to in the attached Contract, in the penal sum of \$_____ (not less than 100% of the approximate total amount of the contract for improvements as evidenced in the proposal plus 10-percent of the stated penal sum as an additional sum of money representing additional court expenses, attorneys' fees, and liquidated damages arising out of or connected with the below identified obligations) in lawful money of the United States, for the payment whereof, the said Principal and Surety bind themselves, and their heirs, administrators, executors, successors, and assigns, jointly and severally, firmly by these presents:

THE OBLIGATION TO PAY SAME is conditioned as follows:

WHEREAS, the Principal has filed a plat for approval by Town/City of the _____ Addition, a real estate development located within Town/City and County of _____ Texas (hereinafter called "the development"); and

WHEREAS, in accordance with the applicable plat and development regulations of Town/City, Principal has entered into a private development contract numbered _____, dated _____ for construction of certain public improvements (to be dedicated to Town/City) for the benefit of the development; and

WHEREAS, in the event of bankruptcy, default or other nonperformance by Principal, claims against Principal or the development may be left without adequate satisfaction.

NOW, THEREFORE, if the Principal shall well, faithfully and timely make payment to the construction contractor for work properly performed under the aforementioned private development contract in accordance with the terms and conditions of said contract for payment, and, if Principal shall fully indemnify and save harmless Town/City from all costs and damages which Town/City suffer by reason of failure to make payment and shall fully reimburse and repay Town/City all outlay and expense which Town/City may incur in making good any default or deficiency, then this obligation shall be void; otherwise, it shall remain in full force and effect.

PROVIDED FURTHER, that this Bond shall automatically be increased by the amount of any change order, Supplemental Agreement or Amendment which increases the price of the aforementioned contract, but in no event shall a Change Order, Supplement Agreement or Amendment which reduces the contract price decrease the penal sum of this Bond; and that the said Surety, for value received hereby stipulates and agrees that no change, extension of time alteration or addition to the terms of any contract for public improvements for the benefit of the development shall in any way affect its obligation on this Bond, and it does hereby waive notice of any such change, extension of time, alteration or addition to the terms of such contracts.

PROVIDED FURTHER, that if any legal action be filed upon this Bond, exclusive venue shall lie in _____ County, State of Texas.

This Bond is given pursuant to the provisions of Article 212.073 of Texas Local Government Code, as may be amended.

The undersigned and designated agent is hereby designated by Surety herein as the agent resident to whom any requisite notice may be delivered and on whom service of process may be had in matters arising out of such suretyship, as provided by Article 7.19-1 of the Insurance Code.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument on this the _____ day of _____, 20____.

WITNESS

PRINCIPAL

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

WITNESS

SURETY

Printed/Typed Name _____

Title: _____

Company: _____

Address: _____

The Resident Agent of the Surety for delivery of notice and service of process is:

Name: _____

Address: _____

Phone number: _____

Note: Date of Bond must NOT be prior to date of Contract.

Form A.14.

Reference Item 110. Air Quality Requirement for Equipment for use.

Schedule for Phase-In of Tier 1 - Tier 4 Non-Road Engines

Horse Power and KiloWatt Engine Size Group								
HP	25-49	50-74	75-99	100-174	175-299	300-599	600-750	750+
KW	19-37	38-55	56-74	75-130	131-223	224-447	448-560	560+
1995	T0	T0	T0	T0	T0	T0	T0	T0
1996	T0	T0	T0	T0	T1	T1	T1	T0
1997	T0	T0	T0	T1	T1	T1	T1	T0
1998	T0	T1	T1	T1	T1	T1	T1	T0
1999	T1	T1	T1	T1	T1	T1	T1	T0
2000	T1	T1	T1	T1	T1	T1	T1	T1
2001	T1	T1	T1	T1	T1	T2	T1	T1
2002	T1	T1	T1	T1	T1	T2	T2	T1
2003	T1	T1	T1	T2	T2	T2	T2	T1
2004	T2	T2	T2	T2	T2	T2	T2	T1
2005	T2	T2	T2	T2	T2	T2	T2	T1
2006	T2	T2	T2	T2	T3	T3	T3	T2
2007	T2	T2	T2	T3	T3	T3	T3	T2
2008	T4i	•T3 •T4i (option 1)	T3	T3	T3	T3	T3	T2
2009	T4i	•T3 •T4i (option 1)	T3	T3	T3	T3	T3	T2
2010	T4i	•T3 •T4i (option 1)	T3	T3	T3	T3	T3	T2
2011	T4i	•T3 •T4i (option 1)	T3	T3	T4i	T4i	T4i	T4i
2012	T4i	•T3 •T4i (option 1) •T4i (option 2)	T4i	T4i	T4i	T4i	T4i	T4i
2013	T4	T4	T4i	T4i	T4i	T4i	T4i	T4i
2014	T4	T4	T4i	T4i	T4	T4	T4	T4i
2015	T4	T4	T4	T4	T4	T4	T4	T4
2016	T4	T4	T4	T4	T4	T4	T4	T4
2017	T4	T4	T4	T4	T4	T4	T4	T4
2018	T4	T4	T4	T4	T4	T4	T4	T4
2019	T4	T4	T4	T4	T4	T4	T4	T4
2020	T4	T4	T4	T4	T4	T4	T4	T4

TT4i= Tier 4 interim

Note: as an alternative to introducing the required percentage of Tier 4 compliant engines, manufactures may verify all their engines to an alternative NOx limit in each model year during the phase-in period.

T4 option 1 = Manufacture's selecting Tier 4 Option 1 will be meeting Tier 4 standards

T4 option 2 = Manufacture's selecting Tier 4 Option 2 must meet Tier 3 standards in the indicated model years

Reference Item 110. Air Quality Requirement for Equipment for use.

4. Usage Log: Complete the table below for each piece of equipment which is designated as low-use equipment. Add rows or make additional copies as necessary.

[illegible]

Form A.16.

Reference Item 110. Air Quality Requirement for Equipment for use.**[Jurisdiction] Clean Construction Specification****Contract Equipment Inventory**

This form must be completed and presented to the [jurisdiction] Representative on or before the day construction activity commences. If any additional equipment is brought on-site after construction begins, an additional form must be submitted to the Representative on or before the day the additional equipment begins work.

Equipment owned and/or operated by subcontractors must also be included in the project reporting. Each company's equipment should be submitted on separate forms.

This form will be retained by the Representative and may be used to conduct occasional on-site inspections and/or verify compliance with the [jurisdiction] Clean Construction Specification.

1. Contract: _____

2. Company/Organization Name: _____

3. Did your company/organization have to purchase new equipment or upgrade existing equipment in order to comply with the Clean Construction Specification?

(Check all that apply)

- _____ Yes, purchased new equipment
 _____ Yes, repowered existing engines to a cleaner standard
 _____ Yes, retrofitted existing equipment
 _____ Yes, rented equipment to comply with specification
 _____ No action necessary, already had enough compliant equipment in fleet

4. Complete the table below for all equipment in use on the public works contract. Add additional rows/pages as necessary.

Equipment Serial Number <i>(last five digits)</i>	Type	Engine Model Year	Horse-power	Retrofit Make/Model <i>(if applicable)</i>	Claiming Low-Use Exemption? ¹ <i>(Complete Item 5 for each unit marked "yes")</i>	Claiming Usage or Reporting Requirement Exemption? <i>(Complete Item 6 for each unit marked "yes")</i>
<i>Example 1</i>	<i>Excavator</i>	<i>2007</i>	<i>46</i>	<i>N/A</i>	<i>N/A (compliant)</i>	<i>N/A (compliant)</i>
<i>Example 2</i>	<i>Wheel Loader</i>	<i>1997</i>	<i>124</i>	<i>N/A</i>	<i>No</i>	<i>Yes</i>
<i>Example 3</i>	<i>Trencher</i>	<i>1992</i>	<i>56</i>	<i>N/A</i>	<i>Yes</i>	<i>No</i>

¹Note that additional reporting/documentation will be required throughout the project using the Clean Construction Specification Low-Use Exemption Reporting Form.

Form A.16.

5. Low-Use Exemption: Complete the table below for each piece of equipment which is designated as low-use equipment. Add rows or make additional copies as necessary.

Equipment Serial Number <i>(last five digits)</i>	Estimated Hours of Use per Week <i>(on this job only)</i>	Hour Meter Reading at Start of Job	Explanation/Description
<i>Example 3</i>	<i>7</i>	<i>250</i>	<i>Specialized equipment</i>


6. Use/Reporting Requirements Exemption: Complete the table below for each piece of equipment for which an exemption is being claimed based upon usage or reporting requirements associated with a grant program or other clean air initiative. Add rows or make additional copies as necessary.

Equipment Serial Number <i>(last five digits)</i>	Funding Agency	Grant Program/Clean Air Initiative	Explanation of Use/Reporting Requirements
<i>Example 2</i>	<i>TCEQ</i>	<i>TERP</i>	<i>Must use at least 1500 hours/year through 2014</i>

Section II

Standard Drawings

Fifth Edition
Amended August 2023



Section II Standard Drawings as of August 2023.


The *Public Works Construction Standards North Central Texas, Amended Fifth Edition* updates the Standard Drawings from the 2004 Second Edition. The NCTCOG anticipates that reviewing and updating the Standard Specifications may be a priority for the PWC within the next few years.

DIVISION 1000 EROSION AND SEDIMENT CONTROL


TABLE OF CONTENTS

<u>Drawing #</u>	<u>Subject</u>	<u>Section I: Item #</u>
<u>1020A</u>	<u>Silt Fence</u>	202.5
<u>1020B</u>	<u>Silt Fence, General Notes</u>	202.5
<u>1030A</u>	<u>Interceptor Swale</u>	202.6
<u>1030B</u>	<u>Interceptor Swale, General Notes</u>	202.6
<u>1040A</u>	<u>Diversion Dike</u>	202.7
<u>1040B</u>	<u>Diversion Dike with Swale</u>	202.7
<u>1040C</u>	<u>Diversion Dike, General Notes</u>	202.7
<u>1050A</u>	<u>Triangular Sediment Filter Dike</u>	202.8
<u>1050B</u>	<u>Triangular Sediment Filter Dike, General Notes</u>	202.8
<u>1060A</u>	<u>Rock Check Dam</u>	202.9
<u>1060B</u>	<u>Rock Check Dam, General Notes</u>	202.9
<u>1070A</u>	<u>Stabilized Construction Exit</u>	202.11
<u>1070B</u>	<u>Stabilized Construction Exit, General Notes</u>	202.11
<u>1080</u>	<u>Sack Gabion Check Dams</u>	N/A
<u>1090</u>	<u>Filter Tube Check Dam</u>	202.10
<u>1100A</u>	<u>Excavated Stone Outlet Sediment Trap</u>	202.12
<u>1100B</u>	<u>Excavated Stone Outlet Sediment Trap, General Notes</u>	202.12
<u>1110</u>	<u>Bermed Stone Outlet Sediment Trap</u>	202.12
<u>1120</u>	<u>Sediment Basin with Overflow Riser</u>	N/A
<u>1130A</u>	<u>Pipe Slope Drain</u>	202.13
<u>1130B</u>	<u>Pipe Slope Drain, General Notes</u>	202.13
<u>1140</u>	<u>Filter Tube Curb Inlet Protection</u>	202.14
<u>1150A</u>	<u>Wire Weir Curb Inlet Protection</u>	202.14
<u>1150B</u>	<u>Wire Weir Curb Inlet Protection</u>	202.14
<u>1160</u>	<u>Curb Rock Sock On-Grade Curb Inlet Protection</u>	202.14

<u>1170</u>	<u>Filter Tube Area Inlet Protection</u>	202.14
<u>1180</u>	<u>Area Inlet Protection Excavated Impoundment</u>	202.14
<u>1190</u>	<u>Area Inlet Protection Filter Barrier</u>	202.14
<u>1200A</u>	<u>Temporary Erosion Control Blankets</u>	202.15
<u>1200B</u>	<u>Temporary Erosion Control Blankets, Anchor Examples</u>	202.15
<u>1200C</u>	<u>Temporary Erosion Control Blankets, General Notes</u>	202.15
<u>1210A</u>	<u>Permanent Turf Reinforcement Mats</u>	N/A
<u>1210B</u>	<u>Permanent Turf Reinforcement Mats</u>	N/A
<u>1210C</u>	<u>Permanent Turf Reinforcement Mat Anchoring</u>	N/A
<u>1220</u>	<u>Velocity Dissipation Device Dewatering</u>	202.13
<u>1230</u>	<u>Controls</u>	203.2
<u>1240</u>	<u>Concrete Washout Containment Grouted</u>	N/A
<u>1250A</u>	<u>Rock Rip-Rap</u>	803.3
<u>1250B</u>	<u>Grouted Rock Rip-Rap</u>	803.3
<u>1255</u>	<u>Temporary Trash Screen</u>	N/A
<u>1260</u>	<u>Outlet Trash Screen Bag</u>	N/A
<u>1265A</u>	<u>Multiple Outlet Trash Screen Bag System</u>	N/A
<u>1265B</u>	<u>Multiple Outlet Trash Screen Bag System</u>	N/A
<u>1265C</u>	<u>Multiple Outlet Trash Screen Bag System</u>	N/A
<u>1270A</u>	<u>Multiple Outlet Trash Screen Basket System</u>	N/A
<u>1270B</u>	<u>Multiple Outlet Trash Screen Basket System</u>	N/A



SILT FENCE
N.T.S



SILT FENCE OVERFLOW STRUCTURE
N.T.S

SILT FENCE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

202.5

DATE
AUG '23

STANDARD DRAWING NO.
1020A

SILT FENCE GENERAL NOTES:

1. DESIGN SHALL SHOW ON THE DRAWINGS THE LOCATIONS WHERE OVERFLOW STRUCTURES SHALL BE INSTALLED. OVERFLOW STRUCTURES ARE REQUIRED AT ALL LOW POINTS AND AT A SPACING OF APPROXIMATELY 300 FEET WHERE NO LOW POINT IS APPARENT.

2. DESIGNER SHALL SHOW ON THE DRAWINGS THE LOCATIONS WHERE SILT FENCE IS TO BE TURNED UPSLOPE AT THE ENDS. UPSLOPE LENGTHS SHALL BE A MINIMUM OF 10 FEET.

3. POST WHICH SUPPORT THE SILT FENCE SHALL BE INSTALLED ON A SLIGHT ANGLE TOWARD THE ANTICIPATED RUNOFF SOURCE. POST MUST BE EMBEDDED A MINIMUM OF ONE FOOT.

4. THE TOE OF THE SILT FENCE SHALL BE TRENCHED IN WITH A SPADE OR MECHANICAL TRENCHER, SO THAT THE DOWNSLOPE FACE OF THE TRENCH IS FLAT AND PERPENDICULAR TO THE LINE OF FLOW.

5. THE TRENCH MUST BE A MINIMUM OF 6 INCHES DEEP AND 6 INCHES WIDE TO ALLOW FOR THE SILT FENCE FABRIC TO BE LAID IN THE GROUND AND BACKFILLED WITH COMPACTED MATERIAL.


6. SILT FENCE SHOULD BE SECURELY FASTENED TO EACH SUPPORT POST OR TO WIRE BACKING, WHICH IN TURN IS ATTACHED TO THE FENCE POST. THERE SHALL BE A 3 FOOT OVERLAP, SECURELY FASTENED WHERE ENDS OF FABRIC MEET.


7. INSPECTION SHALL BE AS SPECIFIED IN THE SWPPP. REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.

8. SILT FENCE SHALL BE REMOVED WHEN FINAL STABILIZATION IS ACHIEVED OR ANOTHER EROSION OR SEDIMENT CONTROL DEVICE IS EMPLOYED.


9. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES A DEPTH OF HALF THE HEIGHT OF THE FENCE. THE SILT SHALL BE DISPOSED OF AT AN APPROVED SITE AND IN SUCH A MANNER AS TO NOT CONTRIBUTE TO ADDITIONAL SILTATION.

10. SEE NCTCOG STANDARD SPECIFICATIONS (2017), SECTION 202.5

SILT FENCE	 North Central Texas Council of Governments	STANDARD SPECIFICATION REFERENCE 202.5	
GENERAL NOTES		DATE AUG '23	STANDARD DRAWING NO. 1020B



N.T.S.




FOR SWALE MATERIAL, SEE NOTE -6

INTERCEPTOR SWALE CROSS SECTION

N.T.S.

INTERCEPTOR SWALE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

202.6

DATE
AUG '23


STANDARD DRAWING NO.
1030A

INTERCEPTOR SWALE GENERAL NOTES:

1. ALL TREES, BRUSH, STUMPS, OBSTRUCTIONS AND OTHER MATERIAL SHALL BE REMOVED AND DISPOSED OF SO AS NOT TO INTERFERE WITH THE PROPER FUNCTIONING OF THE SWALE.
2. THE SWALE SHALL BE EXCAVATED OR SHAPED TO LINE, GRADE AND CROSS-SECTION AS REQUIRED TO MEET CRITERIA SPECIFIED HEREIN AND BE FREE OF BANK PROJECTIONS OR OTHER IRREGULARITIES WHICH WILL IMPEDE NORMAL FLOW.
3. ALL EARTH REMOVED AND NOT NEEDED IN CONSTRUCTION SHALL BE DISPOSED OF IN AN APPROVED SPOILS SITE SO THAT IT WILL NOT INTERFERE WITH THE FUNCTIONING OF THE SWALE.
4. DIVERTED RUNOFF FROM A DISTURBED OR EXPOSED UPLAND AREA SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE.
5. THE ON-SITE LOCATION MAY NEED TO BE ADJUSTED TO MEET FIELD CONDITIONS IN ORDER TO UTILIZE THE MOST SUITABLE OUTLET.
6. FOR LONGITUDINAL SLOPES LESS THAN 2 PERCENT AND VELOCITIES LESS THAN 6 FEET PER SECOND, THE MINIMUM REQUIRED SWALE STABILIZATION SHALL BE GRASS, EROSION CONTROL MATS OR MULCHING. FOR LONGITUDINAL SLOPES IN EXCESS OF 2 PERCENT OR VELOCITIES EXCEEDING 6 FEET PER SECOND, STABILIZATION IS REQUIRED IN THE FORM OF TURF REINFORCEMENT MATS (OR STABILIZED RIP-RAP WITH APPROPRIATE SIZE, GRADATION, AND THICKNESS AS SPECIFIED IN THE PLANS). SEE NOTES 9 AND 10.
7. MINIMUM COMPACTION FOR THE SWALE SHALL BE 95 PERCENT STANDARD PROCTOR.
8. INSPECTION SHALL BE AS SPECIFIED IN THE SWPPP.
9. FOR TEMPORARY STABILIZATION RIP-RAP; WIDTH, DEPTH, AND SURFACE WATER ELEVATION SHOULD BE DESIGNED BY OWNER OR OWNER'S REPRESENTATIVE
10. REFER TO DRAWING 1210A, B, AND C FOR TURF REINFORCEMENT MAT.
11. SEE INTEGRATED STORMWATER MANAGEMENT MANUAL FOR MORE INFORMATION ON INTERCEPTOR SWALE.

INTERCEPTOR SWALE
GENERAL NOTES

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE



202.6

DATE

AUG '23

STANDARD DRAWING NO.


1030B



CROSS SECTION
N.T.S

DIVERSION DIKE

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


202.7

DATE
AUG '23

STANDARD DRAWING NO.
1040A




DIVERSION DIKE WITH SWALE PLAN VIEW
N.T.S



DIVERSION DIKE WITH SWALE CROSS SECTION
N.T.S

DIVERSION DIKE WITH SWALE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

202.7

DATE
AUG '23


STANDARD DRAWING NO.
1040B

DIVERSION DIKE GENERAL NOTES:

1. ALL DIKES SHALL BE PLACED IN 8" LIFTS OR LESS AND COMPACTED TO 95% STANDARD PROCTOR DENSITY.
2. ALL DIVERSION DIKES SHALL HAVE POSITIVE DRAINAGE TO A CONTROLLED OUTLET.
3. DIVERTED RUNOFF FROM A PROTECTED OR STABILIZED AREA SHALL HAVE ITS OUTLET FLOW DIRECTED TO AN UNDISTURBED STABILIZED AREA OR INTO A LEVEL SPREADER OR GRADE STABILIZATION STRUCTURE. REFER TO ITEM 202.7 IN THE STANDARD SPECIFICATIONS.
4. DIVERTED RUNOFF FROM A DISTURBED OR EXPOSED AREA SHALL BE CONVEYED TO A SEDIMENT TRAPPING DEVICE.
5. FOR LONGITUDINAL SLOPES LESS THAN 2 PERCENT AND VELOCITIES LESS THAN 6 FEET PER SECOND, THE MINIMUM REQUIRED SWALE STABILIZATION SHALL BE GRASS, EROSION CONTROL MATS OR MULCHING. FOR LONGITUDINAL SLOPES IN EXCESS OF 2 PERCENT OR VELOCITIES EXCEEDING 6 FEET PER SECOND, STABILIZATION IS REQUIRED IN THE FORM OF TURF REINFORCEMENT MATS (OR STABILIZED RIP-RAP WITH APPROPRIATE SIZE, GRADATION, AND THICKNESS AS SPECIFIED IN THE PLANS). SEE NOTES 8 AND 9.
6. INSPECTION SHALL BE AS SPECIFIED IN THE SWPPP.
7. SEE INTEGRATED STORMWATER MANAGEMENT MANUAL FOR MORE INFORMATION ON INTERCEPTOR SWALE.
8. FOR TEMPORARY STABILIZATION RIP-RAP; WIDTH, DEPTH, AND SURFACE WATER ELEVATION SHOULD BE DESIGNED BY OWNER OR OWNER'S REPRESENTATIVE.
9. REFER TO DRAWING 1230A AND B FOR TURF REINFORCEMENT MAT.

DIVERSION DIKE
GENERAL NOTES

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

202.7


DATE

AUG '23

STANDARD DRAWING NO.


1040C

6" X 6" OR 4" X 4" WELDED WIRE MESH STRUCTURE



ISOMETRIC PLAN VIEW

N.T.S




1. TOE-IN 6" MIN.
2. FABRIC SKIRT WEIGHTED WITH FILTER STONE
(ROCK BAGS MAY BE SUBSTITUTED FOR FILTER STONE)
3. TRENCHED IN 4"

CROSS SECTION OF INSTALLATION OPTIONS

N.T.S

TRIANGULAR SEDIMENT FILTER DIKE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

202.8

DATE
AUG '23

STANDARD DRAWING NO.
1050A

TRIANGULAR SEDIMENT FILTER DIKE GENERAL NOTES:

1. DIKES SHALL BE PLACED IN A ROW WITH ENDS TIGHTLY ABUTTING THE ADJACENT DIKE.
2. THE FABRIC COVER AND SKIRT SHALL BE A CONTINUOUS EXTENSION OF THE FABRIC ON THE UPSTREAM FACE, AND FABRIC SHALL BE OVERLAPPED A MINIMUM OF 12".
3. THE SKIRT SHALL BE WEIGHTED WITH A CONTINUOUS LAYER OF TYPE 'A' RIP RAP, OR TOED-IN 6" WITH MECHANICALLY COMPACTED MATERIAL. OTHERWISE, THE ENTIRE STRUCTURE SHALL BE TRENCHED TO A DEPTH OF 4 INCHES.
4. DIKES AND SKIRT SHALL BE SECURELY ANCHORED IN PLACE USING 6-INCH WIRE STAPLES ON 2-FOOT CENTERS ON BOTH EDGES AND SKIRTS.
5. FILTER MATERIAL SHALL BE LAPPED OVER ENDS 6" TO COVER DIKE TO DIKE JOINTS. JOINTS SHALL BE FASTENED WITH GALVANIZED SHOAT RINGS.
6. THE DIKE STRUCTURE SHALL BE W2.9-6" X 6" OR 4" X 4" WELDED WIRE MESH, 18" ON A SIDE.
7. INSPECTION SHALL BE AS SPECIFIED IN THE SWPPP. REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED BY THE CONTRACTOR.
8. THE FILTER DIKE SHALL BE REMOVED WHEN FINAL STABILIZATION IS ACHIEVED OR ANOTHER EROSION OR SEDIMENT CONTROL DEVICE IS EMPLOYED.
9. ACCUMULATED SILT SHALL BE REMOVED WHEN IT REACHES APPROXIMATELY 6-INCHES IN DEPTH. THE SILT SHALL BE DISPOSED OF AT AN APPROVED SITE AND IN SUCH A MANNER AS TO NOT CONTRIBUTE TO ADDITIONAL SILTATION.

TRIANGULAR SEDIMENT FILTER DIKE

GENERAL NOTES

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


202.8

DATE

AUG '23


STANDARD DRAWING NO.

1050B




ROCK CHECK DAM VIEW LOOKING UPSTREAM

N.T.S.



CROSS SECTION A-A

N.T.S.



SPACE BETWEEN ROCK CHECK DAMS


N.T.S.

NOTES:

ACTUAL DIMENSIONS OF THE CHECK DAMS SHALL BE DESIGNED BASED ON FLOW CONDITIONS IN THE DRAINAGE SWALE OR DITCH. HEIGHT (H) AND SPACING (L) OF CHECK DAM AS PROVIDED IN PLANS BY OWNER OR OWNER'S REPRESENTATIVE. PROVIDE CALCULATIONS UPON REQUEST OF THE REVIEWING AGENCY.

ROCK CHECK DAM

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

202.9

DATE

AUG '23

STANDARD DRAWING NO.


1060A

ROCK CHECK DAM GENERAL NOTES:

1. SEE NCTCOG STANDARD SPECIFICATIONS (2017), SECTION 202.9 CHECK DAM (ROCK)
2. STONE SHALL BE WELL GRADED WITH SIZE RANGE FROM $1\frac{1}{2}$ TO $3\frac{1}{2}$ INCHES IN DIAMETER DEPENDING ON EXPECTED FLOWS.
3. THE CHECK DAM SHALL BE INSPECTED AS SPECIFIED IN THE SWPPP AND SHALL BE REPLACED WHEN THE STRUCTURE CEASES TO FUNCTION AS INTENDED DUE TO SILT ACCUMULATION AMONG THE ROCKS, WASHOUT, CONSTRUCTION TRAFFIC DAMAGE, ETC.
4. WHEN SILT REACHES A DEPTH EQUAL TO ONE—THIRD OF THE HEIGHT OF THE CHECK DAM OR ONE FOOT, WHICHEVER IS LESS, THE SILT SHALL BE REMOVED AND DISPOSED OF PROPERLY.
5. WHEN THE SITE HAS ACHIEVED FINAL STABILIZATION OR ANOTHER EROSION OR SEDIMENT CONTROL DEVICE IS EMPLOYED, THE CHECK DAM AND ACCUMULATED SILT SHALL BE REMOVED AND DISPOSED OF IN AN APPROVED MANNER.

ROCK CHECK DAM
GENERAL NOTES

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

202.9


DATE
AUG '23

STANDARD DRAWING NO.
1060B



PROFILE VIEW

N.T.S.



PLAN VIEW

N.T.S.

WIDTH (W)

20' MIN. FOR < 5 AC SITES


30' MIN. FOR > 5 AC SITES

EXIT MUST BE SLOPED SO THAT
STORM WATER IS NOT ALLOWED TO
LEAVE THE SITE AND ENTER
ROADWAYS

STABILIZED CONSTRUCTION

EXIT

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


202.11


DATE
AUG '23

STANDARD DRAWING NO.
1070A

STABILIZED CONSTRUCTION EXIT GENERAL NOTES:


1. SEE NCTCOG STANDARD SPECIFICATIONS (2017), SECTION 202.11
2. THE THICKNESS SHALL NOT BE LESS THAN 6 INCHES.
3. STONE SHALL BE 3 TO 5 INCH DIAMETER COURSE AGGREGATE, NO CRUSHED PORTLAND CEMENT CONCRETE ALLOWED.
4. LENGTH SHALL BE SHOWN ON PLANS, WITH A MINIMUM LENGTH OF 50 FEET.
5. THE WIDTH SHALL BE NO LESS THAN 20' FOR SITES LESS THAN 5 AC, AND 30' FOR SITES GREATER THAN 5 AC, AT ALL POINTS OF INGRESS OR EGRESS.
6. WHEN NECESSARY, VEHICLES SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO A PUBLIC ROADWAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE WITH DRAINAGE FLOWING AWAY FROM BOTH THE STREET AND THE STABILIZED EXIT. ALL SEDIMENT SHALL BE PREVENTED FROM ENTERING ANY STORM DRAIN, DITCH OR WATERCOURSE USING APPROVED METHODS.
7. THE EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PAVED SURFACES. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND. ALL SEDIMENT SPILLED, DROPPED, WASHED, OR TRACKED ONTO PAVED SURFACES MUST BE REMOVED IMMEDIATELY.
8. THE EXIT MUST BE PROPERLY GRADED OR INCORPORATE A DRAINAGE SWALE TO PREVENT RUNOFF FROM LEAVING THE CONSTRUCTION SITE.
9. INSPECTION SHALL BE SPECIFIED IN THE SWPPP.

STABILIZED CONSTRUCTION EXIT, GENERAL NOTES	 North Central Texas Council of Governments	STANDARD SPECIFICATION REFERENCE 202.11	
		DATE AUG '23	STANDARD DRAWING NO. 1070B




SACK GABION CHECK DAM PLAN VIEW
N.T.S.

3/4" DIA REBAR STAKES
3' MAX SPACING



SACK GABION CHECK DAM VIEW LOOKING UPSTREAM
N.T.S.



TYPICAL SACK GABION
N.T.S.

SACK GABION CHECK DAM GENERAL NOTES:


1. ACTUAL DIMENSIONS OF THE CHECK DAMS SHALL BE DESIGNED BASED ON FLOW CONDITIONS IN THE DRAINAGE SWALE OR DITCH.
2. HEIGHT (H) AND SPACING (L) OF CHECK DAM AS PROVIDED IN PLANS BY OWNER OR OWNER'S REPRESENTATIVE. PROVIDE CALCULATIONS UPON REQUEST OF THE REVIEWING AGENCY.

NOTES:

ACTUAL DIMENSIONS OF THE CHECK DAMS SHALL BE DESIGNED BASED ON FLOW CONDITIONS IN THE DRAINAGE SWALE OR DITCH. HEIGHT (H) AND SPACING (L) OF CHECK DAM AS PROVIDED IN PLANS BY OWNER OR OWNER'S REPRESENTATIVE. PROVIDE CALCULATIONS UPON REQUEST OF THE REVIEWING AGENCY.

SACK GABION CHECK DAMS

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

NA


DATE
AUG '23

STANDARD DRAWING NO.
1080




FILTER TUBE CHECK DAM VIEW LOOKING UPSTREAM

N.T.S.



FILTER TUBE CHECK DAM PROFILE

N.T.S.



EMBEDMENT DETAIL FOR FILTER TUBE CHECK DAM


N.T.S.

GENERAL NOTES:

1. ACTUAL DIMENSIONS OF THE CHECK DAMS SHALL BE DESIGNED BASED ON FLOW CONDITIONS IN THE DRAINAGE SWALE OR DITCH.
2. HEIGHT (H) AND SPACING (L) OF CHECK DAM AS PROVIDED IN PLANS BY OWNER OR OWNER'S REPRESENTATIVE. PROVIDE CALCULATIONS UPON REQUEST OF THE REVIEWING AGENCY.

FILTER TUBE CHECK DAM

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

202.10

DATE
AUG '23

STANDARD DRAWING NO.
1090




EXCAVATED STONE OUTLET SEDIMENT TRAP ISOMETRIC VIEW
N.T.S.

NOTE: ACTUAL DIMENSIONS OF THE SEDIMENT TRAP SHALL BE DESIGNED BASED ON FLOW CONDITIONS AND SITE TOPOGRAPHY. PROVIDE CALCULATIONS THAT DOCUMENT THE FOLLOWING PARAMETER USED TO DESIGN THE TRAP.

- SIZE OF CONTRIBUTING DRAINAGE AREA
- DESIGN STORM VOLUME AND FLOW RATE AT THE TRAP
- HEIGHT, SLOPE, AND LENGTH OF STONE OUTLET
- STORAGE VOLUME
- EXTENT OF GRADING TO PROVIDE THE CONTROLLED OUTLET

EXCAVATED STONE OUTLET
SEDIMENT TRAP

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


202.12

DATE
AUG '23

STANDARD DRAWING NO.
1100A



EXCAVATED STONE OUTLET SEDIMENT TRAP VIEW
LOOKING UPSTREAM
N.T.S.




EXCAVATED STONE OUTLET SEDIMENT TRAP SECTION VIEW
N.T.S.

NOTES:

- ACTUAL DIMENSIONS OF THE SEDIMENT TRAP SHALL BE DESIGNED BASED ON FLOW CONDITIONS AND SITE TYPOLOGY.
- PROVIDE CALCULATIONS UPON REQUEST OF THE REVIEWING AGENCY.
- DESIGN VOLUME, HEIGHT, SLOPE, AND LENGTH AS PROVIDED IN PLANS PROVIDED BY OWNER OR OWNER'S REPRESENTATIVE.

EXCAVATED STONE OUTLET
SEDIMENT TRAP, GENERAL NOTES

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

202.12

DATE
AUG '23


STANDARD DRAWING NO.
1100B

CONTAINMENT BERM CONSTRUCTED FROM BOTTOM MATERIAL EXCAVATED TO CREATE AN AVERAGE POND DEPTH OF AT LEAST 30" WHEN MEASURED FROM THE BOTTOM OF THE SWALE TO THE LOW POINT IN THE TOP OF THE ROCK OUTLET



BERMED STONE OUTLET SEDIMENT TRAP PLAN VIEW

N.T.S.



BERMED STONE OUTLET SEDIMENT TRAP SECTION VIEW


N.T.S.

GENERAL NOTES:

1. ACTUAL DIMENSIONS OF THE SEDIMENT TRAP SHALL BE DESIGNED BASED ON FLOW CONDITIONS AND SITE TOPOGRAPHY.
2. PROVIDE CALCULATIONS UPON REQUEST OF THE REVIEWING AGENCY.
3. DESIGN OF VOLUME, HEIGHT, SLOPE, AND LENGTH AS PROVIDED IN PLANS PROVIDED BY OWNER OR OWNER'S REPRESENTATIVE.

BERMED STONE OUTLET
SEDIMENT TRAP

North Central Texas Council of Governments





STANDARD SPECIFICATION REFERENCE

202.12

DATE
AUG '23

STANDARD DRAWING NO.
1110




REFERENCE: NCTCOG ISWM CRITERIA MANUAL FOR SITE DEVELOPMENT AND CONSTRUCTION, SECTION 3.9 SEDIMENT BASIN.

NOTE:

1. PIPE SIZE, ROCK SIZE, AND BERM HEIGHT AS PROVIDED IN PLANS BY OWNER OR OWNER'S REPRESENTATIVE.
2. OPTIONAL: A COLLAR OF 1.5 - 3 INCH, WELL GRADED GRAVEL (NOT SHOWN) MAY BE PLACED AROUND THE PERFORATED RISER.

SEDIMENT BASIN
WITH OVERFLOW RISER

North Central Texas Council of Governments





STANDARD SPECIFICATION REFERENCE

N/A


DATE
AUG '23

STANDARD DRAWING NO.
1120



PIPE SLOPE DRAIN

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

202.13

DATE
AUG '23

STANDARD DRAWING NO.
1130A

GENERAL NOTES:

1. DIMENSIONS OF THE PIPE SLOPE DRAIN AND APPURTENANCES SHALL BE DESIGNED BASED ON SITE TOPOGRAPHY AND FLOW CONDITIONS.
2. H, L, AND D AS SHOWN SHALL BE PROVIDED IN PLANS BY OWNER OR OWNER'S REPRESENTATIVE.
3. PROVIDE CALCULATIONS THAT DOCUMENT THE FOLLOWING PARAMETERS USED TO DESIGN THE PIPE SLOPE DRAIN UPON REQUEST OF THE REVIEWING AGENCY.
 - 3.1. PIPE MATERIAL AND SIZE
 - 3.2. DISCHARGE VELOCITY
 - 3.3. STONE SIZE AN DIMENSIONS OF RIPRAP APRON
 - 3.4. PIPE LENGTH AND SLOPE

PIPE SLOPE DRAIN
GENERAL NOTES

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

202.13


DATE
AUG '23

STANDARD DRAWING NO.
1130B

NOT ALLOWED ON
ACTIVE CITY
STREETS UNLESS
APPROVED BY CITY


EXTENDED WRAPPED
FILTER MATERIAL
24" MIN. BEYOND
END OF CURB OPENING
ON BOTH SIDES

NOTE: PLASTIC OR
WIRE TIES AROUND
WIRE OR PLASTIC
MESH EVERY
12"-18" OR MORE
AS NEEDED



PLAN VIEW
N.T.S.

1. DOUBLE WRAP OF FLEXIBLE WIRE MESH WITH MESH OPENING 3/4" MAX., OR PLASTIC NETTING DOUBLE WRAPPED WITH 1/2" MAX. OPENING, OR GEOSYNTHETIC TUBES




CROSS SECTION
N.T.S.

NOTE: VERTICAL PANEL BARRICADES TO BE PLACED WHEN LOCATED ON AN ACTIVE STREET.


TYPE A CURB INLET PROTECTION N.T.S.

EXTENDED WRAPPED
FILTER MATERIAL
24" MIN. BEYOND
END OF CURB OPENING
ON BOTH SIDES

NOTE: SEE NCTCOG STANDARD
SPECIFICATIONS (2017),
SECTION 202.14 AND 202.18



PLAN VIEW
N.T.S.



CROSS SECTION
N.T.S.

CURB OPENING	MIN. NO. BLOCKS
4'-6'	1
8'-10'	2
12'-14'	3
16'-20'	4

ALTERNATIVE FORM FOR TYPE A CURB INLET PROTECTION N.T.S.

FILTER TUBE CURB
INLET PROTECTION

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


202.14

DATE
AUG '23

STANDARD DRAWING NO.
1140



WIRE WEIR CURB INLET PROTECTION ISOMETRIC VIEW
N.T.S.




WIRE WEIR CURB INLET PROTECTION CROSS SECTION
N.T.S.

NOTE: THIS CONTROL WILL DECREASE THE CAPACITY OF THE INLET. IT SHALL ONLY BE USED WHEN AN ENGINEER HAS DETERMINED THERE IS ADEQUATE STORAGE OR POSITIVE OVERFLOW.

WIRE WEIR CURB
INLET PROTECTION

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

202.14

DATE
AUG '23

STANDARD DRAWING NO.
1150A



WIRE WEIR CURB INLET PROTECTION PLAN VIEW
N.T.S

TABLE EC1

INLET OPENING	MINIMUM NUMBER OF ROCK BAGS	
	TOP	FRONT
5'-0"	2	3
10'-0"	3	3
15'-0"	3	4
20'-0"	4	4


NOT ALLOWED ON
ACTIVE CITY
STREETS UNLESS
APPROVED BY CITY

NOTES:

1. A SECTION OF FILTER FABRIC SHALL BE REMOVED AS SHOWN ON THIS DETAIL TO PROVIDE A 2" MINIMUM CLEAR OPENING. FABRIC MUST BE SECURED TO WIRE BACKING WITH CLIPS OR HOG RINGS AT THIS LOCATION.
2. INSPECTION SHALL BE MADE BY THE CONTRACTOR AND SILT ACCUMULATION MUST BE REMOVED WHEN DEPTH REACHES 2".
3. INLET PROTECTIONS SHALL BE REMOVED AS SOON AS THE SOURCE OF SEDIMENT IS STABILIZED.

WIRE WEIR CURB
INLET PROTECTION

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


202.14

DATE
AUG '23

STANDARD DRAWING NO.
1150B




ROCK SOCK SECTION
N.T.S.



ROCK SOCK PLAN
N.T.S.

NOT ALLOWED ON
ACTIVE CITY
STREETS UNLESS
APPROVED BY CITY




CURB ROCK SOCK ON-GRADE CURB
INLET PROTECTION DETAIL
N.T.S.

CURB ROCK SOCK ON-GRADE CURB INLET PROTECTION GENERAL NOTES:

1. THIS DETAIL IS INTENDED FOR USE WITH ON-GRADE INLETS (NOT A LOW POINT) TO TRAP SEDIMENT.
2. DO NOT INSTALL ON INLETS WHERE THE ROCK SOCKS WOULD EXTEND INTO AN ACTIVE TRAVEL LANE.
3. ROCK SOCKS MAY BE USED ON PAVED OR UNPAVED SURFACES.
4. MAXIMUM ROCK SOCK SIAMETER 4" TO 6".
5. MINIMUM OF 2 CURB ROCK SOCKS.

CURB ROCK SOCK ON-GRADE
CURB INLET PROTECTION

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


202.14

DATE
AUG '23


STANDARD DRAWING NO.
1160



**FILTER TUBE AREA
INLET PROTECTION PLAN VIEW**
N.T.S.




**FILTER TUBE "Y" INLET
PROTECTION CROSS SECTION**
N.T.S.



NOTE: COMPACT EXCAVATED SOIL TO PREVENT UNDERCUTTING.

**EMBEDMENT EXAMPLE
FOR FILTER TUBE**
N.T.S.



**FILTER TUBE DROP INLET
PROTECTION CROSS SECTION**
N.T.S.

**FILTER TUBE AREA
INLET PROTECTION**

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


202.14

DATE
AUG '23


STANDARD DRAWING NO.
1170



EXCAVATED INLET PROTECTION "Y" INLET SECTION A-A
N.T.S.



EXCAVATED INLET PROTECTION GRATE INLET SECTION A-A
N.T.S.




- NOTES:
1. STORAGE VOLUME SHALL BE DESIGN STORM VOLUME OR 3,600 CUBIC FEET PER ACRE DISTURBED.
 2. CONCENTRATED DITCH FLOW COMING FROM ONE OR MORE SIDES TOWARD THE INLET MAY REQUIRE A STONE OVERFLOW STRUCTURE TO BE CONSTRUCTED ON ONE SIDE OF THE INLET.

EXCAVATED INLET PROTECTION PLAN VIEW
N.T.S.

AREA INLET PROTECTION
EXCAVATED IMPOUNDMENT

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

202.14

DATE
AUG '23

STANDARD DRAWING NO.
1180



STANDARD DRAWING NO.
1190

REFER TO SHEET 2 OF 3 OF THIS DETAIL FOR CHOICE ANCHORING; OR FOLLOW MANUFACTURE RECOMMENDATIONS

FOR SLOPE PROTECTION, NOT CHANNELS

4 INCH MINIMUM SIDE OVERLAP OR PER MANUFACTURER'S RECOMMENDATIONS

EROSION CONTROL BLANKET


STAPLES AT MINIMUM 12" SPACING OR PER MANUFACTURE'S RECOMMENDATION

SHEET FLOW

STAPLES (TYP.) 12 INCH ON CENTER AT END OF ECB AT EACH SLOPE CHANGE AND THROUGHOUT ECB AT SPACING RECOMMENDED BY MANUFACTURER

3 FOOT MINIMUM OVERLAP AT ENDS OF BLANKETS. ECB AT HIGHER ELEVATION SHALL OVERLAP ON TOP OF LOWER ECB, OR PER MANUFACTURER LITERATURE.


ECB ISOMETRIC PLAN VIEW
N.T.S.



ECB OVERLAP EXAMPLE
N.T.S.

TEMPORARY EROSION
CONTROL BLANKETS

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


202.15

DATE
AUG '23

STANDARD DRAWING NO.
1200A




TOP OF SLOPE ANCHOR EXAMPLE 1
N.T.S.



TOP OF SLOPE ANCHOR TRENCH EXAMPLE 2
N.T.S.

TEMPORARY EROSION CONTROL
BLANKET, ANCHOR EXAMPLES

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

202.15

DATE
AUG '23


STANDARD DRAWING NO.
1200B

EROSION CONTROL BLANKETS GENERAL NOTES:

1. NCTCOG STANDARD SPECIFICATIONS (2017) SECTION 202.15.
2. EROSION CONTROL BLANKET SHALL BE INSTALLED VERTICALLY DOWN SLOPE AS SHOWN.
3. PRIOR TO THE INSTALLATION: ALL ROCK, DIRT CLODS, STUMPS, ROOTS, TRASH, AND ANY OTHER OBSTRUCTIONS THAT WOULD PREVENT THE BLANKET FROM LYING IN DIRECT CONTACT WITH THE SOIL SHALL BE REMOVED.
4. ANCHORING METHODS PROVIDED ARE EXAMPLES OF THE TYPE OF ANCHORING THE ECB MANUFACTURER MAY RECOMMEND. ALWAYS FOLLOW THE MANUFACTURER'S RECOMMENDATIONS FOR ANCHORING BASED ON THE SITE-SPECIFIC APPLICATION.
5. INSTALLATION AND ANCHORING SHALL CONFORM TO THE RECOMMENDATIONS SHOWN WITHIN THE MANUFACTURER'S PUBLISHED LITERATURE FOR THE APPROVED EROSION CONTROL BLANKET. PARTICULAR ATTENTION MUST BE PAID TO JOINTS AND OVERLAPPING MATERIAL. AT A MINIMUM, THE END OF EACH ROLL OF ECB SHALL OVERLAP THE NEXT ROLL BY 3 FEET AND THE SIDES OF ROLLS SHALL OVERLAP 4 INCHES.
6. IN ABSENCE OF MANUFACTURER'S LITERATURE, A MINIMUM 11-GAUGE WIRE STAPLES, 6-INCHES IN LENGTH AND 1-INCH WIDTH WILL BE USED.
7. AFTER APPROPRIATE INSTALLATION, THE BLANKETS SHOULD BE CHECKED FOR UNIFORM CONTACT WITH THE SOIL, SECURITY OF THE LAP JOINTS, AND THE FLUSHNESS OF THE STAPLES WITH THE GROUND.
8. INSPECTION SHALL BE AS SPECIFIED IN THE SWPPP.

TEMPORARY EROSION CONTROL
BLANKETS, GENERAL NOTES

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


202.15

DATE
AUG '23


STANDARD DRAWING NO.
1200C



TRM HALF ISOMETRIC PLAN VIEW
N.T.S.



END OF TRM OVERLAP EXAMPLE
N.T.S.




TOE ANCHOR DETAIL
N.T.S.

NOTES:

1. TURF REINFORCEMENT MATS SHALL BE INSTALLED VERTICALLY DOWN SLOPE AS SHOWN.
2. PRIOR TO THE INSTALLATION: ALL ROCKS, DIRT CLODS, STUMPS, ROOTS, TRASH AND ANY OTHER OBSTRUCTIONS THAT WOULD PREVENT THE MAT FROM DIRECT CONTACT WITH THE FINISHED SLOPE, SHALL BE REMOVED.

PERMANENT TURF
REINFORCEMENT MATS

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

N/A

DATE
AUG '23

STANDARD DRAWING NO.
1210A

REFER TO UPSTREAM
END ANCHOR EXAMPLE

FLOW

REFER TO END OF TRM
ANCHOR EXAMPLE

3' MIN. OVERLAP

CONTINUOUS
PIECE TRM
WIDTH
VARIES BY
MANUFACTURER

REFER TO DOWNSTREAM
END ANCHOR EXAMPLE

LONGITUDINAL SEAMS
NOT PERMITTED WITHIN
THE FLOWLINE OF THE
CHANNEL

18" MIN. OVERLAP
AT LEAST $\frac{1}{3}$ THE
HEIGHT OF SLOPE


TRM ISOMETRIC PLAN VIEW FOR SMALL CHANNELS/DITCHES

N.T.S.

NOTE: LONGITUDINAL INSTALLATION OF TURF REINFORCEMENT MAT PERMITTED ONLY FOR CHANNEL WIDTHS 0' TO 8'. CONTRACTOR SHALL VERIFY MAT MEETS OVERLAP AND SLOPE REQUIREMENTS STATED ABOVE.

PERMANENT TURF
REINFORCEMENT MATS

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


N/A

DATE
AUG '23


STANDARD DRAWING NO.
1210B



TRM PERIMETER ANCHOR EXAMPLE
N.T.S.



TRM UPSTREAM END ANCHOR EXAMPLE
N.T.S.




TRM DOWNSTREAM END ANCHOR EXAMPLE
N.T.S.

PERMANENT TURF

REINFORCEMENT MAT ANCHORING

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

N/A

DATE
AUG '23

STANDARD DRAWING NO.
1210C

Diagram illustrating the required apron for a temporary pipe slope drain. The apron is constructed from well-graded stone or recycled concrete riprap. The minimum apron length (L) is 10 feet. The apron width is specified as 3 times the pipe diameter (D) plus L. The apron is shown extending from the pipe, which is labeled as a temporary pipe slope drain per NCTCOG 202.13. The apron is labeled with a minimum length of 10 feet and a minimum width of 3 x D + L. The apron is also labeled with a minimum length of 10 feet and a minimum width of 3 x D + L. The apron is also labeled with a minimum length of 10 feet and a minimum width of 3 x D + L.

TEMPORARY PIPE SLOPE DRAIN PER NCTCOG 202.13

0.75L

WELL GRADED STONE OR RECYCLED CONCRETE RIPRAP

SLOPE = 0% ON APRON

OVERFALL ELEVATION

RECEIVING ELEVATION

2T

T


D

FILTER FABRIC PER NCTCOG 202.12.2.3

NOTE: DIMENSIONS OF THE RIPRAP APRON SHALL BE DESIGNED BASED ON FLOW CONDITIONS. TEMPORARY CONTROL DESIGN STORM (2-YEARS, 24-HOUR). PROVIDE CALCULATIONS THAT DOCUMENT THE FOLLOWING PARAMETERS USED TO DESIGN THE APRON.

- PIPE DIAMETER (OR EQUIVALENT FOR FLUME, SWALE, ETC.), D, FEET
- DISCHARGE VELOCITY FROM DRAINAGE STRUCTURE, V_{PIPE} , FT/S
- DETERMINE GRADATION FOR d_{50} WELL GRADED STONE OR RECYCLED CONCRETE RIPRAP
- MEDIAN STONE DIAMETER d_{50} AND MAXIMUM STONE DIAMETER (d_{100}), FEET



North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

DATE
AUG '23

STANDARD DRAWING NO.
1220



DEWATERING CONTROL GENERAL NOTES:

1. THE BAG SHOULD BE A NON-WOVEN, NEEDLE-PUNCHED, GEOTEXTILE. MATERIALS SHOULD CONFORM TO SPECIFICATION 202.5.2.1 AS A MINIMUM.
2. CAPACITY, INSTALLATION, MAINTENANCE, AND REMOVAL OF BAGS AND PUMPS SHOULD CONFORM TO PUBLISHED MANUFACTURER LITERATURE.

DEWATERING CONTROLS

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

203.2


DATE
AUG '23

STANDARD DRAWING NO.
1230



*SANDBAGS MAY BE REPLACED BY A SOIL BERM TO ANCHOR THE PLASTIC LINING.

CONCRETE WASHOUT PLAN VIEW
N.F.S




CONCRETE WASHOUT SECTION A-A
N.F.S

CONCRETE WASHOUT NOTES:

1. WASHOUT AREA MUST BE CLEARLY MARKED WITH SIGNAGE NOTING THE WASHOUT AREA.
2. WASHOUT STRUCTURES SHALL BE CLEANED OUT WHEN THE STRUCTURE IS 75% FULL. TEMPORARY CONCRETE WASHOUT FACILITY SHOULD BE MAINTAINED TO PROVIDE ADEQUATE HOLDING CAPACITY.

CONCRETE WASHOUT
CONTAINMENT

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

N/A


DATE
AUG '23

STANDARD DRAWING NO.
1240



TYPICAL ROCK RIPRAP SLOPE PROTECTION SECTION

N.T.S.



ROCK RIPRAP TOP OF BANK DETAIL

N.T.S.

- ROCK RIPRAP DRY OR GROUTED AS SHOWN ON EROSION CONTROL PLANS
- FILTER FABRIC SPLICES SHALL HAVE A MINIMUM 18 INCHES OVERLAP
- DETERMINE GRADATION FOR d_{50} WELL GRADED STONE
- MEDIAN STONE DIAMETER d_{50} AND MAXIMUM STONE DIAMETER d_{100} , FEET
- SIZING OF $d(\min)$, $d(50)$, AND $d(100)$ AS DETERMINED BY OWNER

$$T = 1.5 \times d_{50}$$

$$d_{\min} = \underline{\hspace{2cm}}$$

$$d_{50} = \underline{\hspace{2cm}}$$

$$d_{100} = \underline{\hspace{2cm}}$$

GROUTED ROCK
RIP RAP

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

803.3


DATE
AUG '23

STANDARD DRAWING NO.
1250A



ROCK RIPRAP TOE OF SLOPE DETAIL

N.T.S.




UPSTREAM ROCK RIPRAP TOE WALL DETAIL

N.T.S.

GROUTED ROCK
RIP RAP

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

803.3


DATE
AUG '23

STANDARD DRAWING NO.
1250B



TEMPORARY TRASH SCREEN DETAIL

N.T.S.



NOTES:

1. CONCENTRATED DITCH FLOW COMING TOWARD THE INSTALLATION WILL REQUIRE A STONE OVERFLOW STRUCTURE TO BE CONSTRUCTED.
2. HEIGHT OF INSTALLATION SHALL BE SHOWN ON PLANS AND MUST BE CHECKED TO VERIFY PONDING WATER WILL NOT CAUSE FLOODING OF PROPERTY OR DAMAGE.
3. ENGINEER TO VERIFY APPLICABILITY OF TEMPORARY TRASH SCREEN.

PROFILE OF TEMPORARY TRASH SCREEN DETAIL

N.T.S.

TEMPORARY TRASH SCREEN

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

N/A


DATE
AUG '23


STANDARD DRAWING NO.
1255




OUTLET TRASH SCREEN BAG
N.T.S.

NOTE: INSTALL COLLAR AND BAG SIZED BY OWNER AND FROM OWNER’S MANUFACTURER OF CHOICE

OUTLET TRASH SCREEN BAG	North Central Texas Council of Governments 	STANDARD SPECIFICATION REFERENCE N/A	
		DATE AUG '23	STANDARD DRAWING NO. 1260








HALF ISOMETRIC VIEW



ENGINEER TO VERIFY
MIN. CONCRETE THICKNESS
FOR STRUCTURE ANCHORAGE

SIDE VIEW WITH HEADWALL

MULTIPLE OUTLET TRASH SCREEN BAG SYSTEM	North Central Texas Council of Governments 	STANDARD SPECIFICATION REFERENCE N/A	
		DATE AUG '23	STANDARD DRAWING NO. 1265A



NOTES:

1. ALL MATERIAL UNLESS OTHERWISE NOTED IS $\frac{1}{4}$ " PAINTED STEEL WELDED CONNECTIONS
2. ATTACH USING $\frac{1}{2}$ " x 2" THREADED BOLTS WITH 12" WASHERS AND NUTS.
3. ALL DIMENSIONS ARE BASED ON FIELD MEASUREMENTS, ENGINEER TO VERIFY LENGTHS AND THICKNESS, DEPENDING ON APPLICATION

**MULTIPLE OUTLET TRASH
SCREEN BAG SYSTEM**

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


N/A

DATE
AUG '23


STANDARD DRAWING NO.
1265B




PINTLE HINGE DETAIL



EXPLODED PINTLE HINGE DETAIL



BREAK AWAY PIN DETAIL



POST INTALLED CONCRETE ANCHOR

NOTES:

1. ALL MATERIAL UNLESS OTHERWISE NOTED IS $\frac{1}{4}$ " PAINTED STEEL WELDED CONNECTIONS.
2. ATTACH USING $\frac{1}{2}$ " X 2" THREADED BOLTS WITH $\frac{1}{2}$ " WASHERS AND NUTS.
3. ALL DIMENSIONS ARE BASED ON FIELD MEASUREMENTS, ENGINEER TO VERIFY LENGTHS AND THICKNESS, DEPENDING ON APPLICATION

MULTIPLE OUTLET TRASH
SCREEN BAG SYSTEM

North Central Texas Council of Governments





STANDARD SPECIFICATION REFERENCE

N/A


DATE
AUG '23

STANDARD DRAWING NO.
1265C



MULTIPLE OUTLET TRASH SCREEN BASKET SYSTEM

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


N/A

DATE
AUG '23


STANDARD DRAWING NO.
1270A




TRASH BASKET
TOP VIEW




TRASH BASKET
FRONT VIEW



TRASH BASKET
SIDE VIEW



TRASH BASKET
ISOMETRIC VIEW




MOUNTING BRACKET

NOTES:

1. OVERALL SIZE AND LOCATION TO BE DETERMINED BY THE OWNER.
2. SIZE AND SPACING OF MESH TO BE DETERMINED BY THE OWNER.
3. SIZING OF STRUCTURAL MEMBERS AND CONNECTIONS AS DETERMINED BY OWNER.

MULTIPLE OUTLET TRASH SCREEN BASKET SYSTEM

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

N/A

DATE
AUG '23

STANDARD DRAWING NO.
1270B

DIVISION 2000 PAVEMENT SYSTEMS

TABLE OF CONTENTS


<i><u>Drawing #</u></i>	<i><u>Subject</u></i>	<i><u>Section I: Item #</u></i>
<u>2010A</u>	<u>Six-Lane Divided Thoroughfare With Bike Lane</u>	301, 303.
<u>2010B</u>	<u>Six-Lane Divided Thoroughfare With Bike Lane</u>	303
<u>2015A</u>	<u>Six-Lane Divided Thoroughfare Without Bike Lane</u>	301, 303.
<u>2015B</u>	<u>Six-Lane Divided Thoroughfare Without Bike Lane</u>	303
<u>2020A</u>	<u>Four-Lane Divided Thoroughfare With Bike Lane</u>	303
<u>2020B</u>	<u>Four-Lane Divided Thoroughfare With Bike Lane</u>	303
<u>2025A</u>	<u>Four-Lane Divided Thoroughfare Without Bike Lane</u>	303
<u>2025B</u>	<u>Four-Lane Divided Thoroughfare Without Bike Lane</u>	303
<u>2030</u>	<u>2- & 4-Lane Undivided Thoroughfare With Bike Lane</u>	303
<u>2035</u>	<u>2- & 4-Lane Undivided Roadway With Optional Parking (Without Bike Lane)</u>	303
<u>2040</u>	<u>Reinforced Concrete Pavement Alleys</u>	301, 303.
<u>2050</u>	<u>Reinforced Concrete Pavement Joints</u>	303.5.4.
<u>2060</u>	<u>Reinforced Concrete Pavement Transverse Joint Spacing</u>	303.5.4.
<u>2070</u>	<u>Reinforced Concrete Pavement Street Headers</u>	303.5.4.
<u>2110</u>	<u>Pavement Systems General Notes</u>	301. 302. 303.
<u>2120</u>	<u>Concrete Curb & Gutter Integral, Separate, and Doweled</u>	305.1
<u>2130</u>	<u>Median Island Pavement Nose & Left Turn Lane</u>	305.3
<u>2150A</u>	<u>Residential Drive Approach Connecting to Asphalt Streets with Curb and Gutter</u>	305.2

<u>Drawing #</u>	<u>Subject</u>	<u>Section I: Item #</u>
<u>2150B</u>	<u>Residential Drive Approach Connecting to Existing Rural Type Asphalt Street</u>	305.2
<u>2150C</u>	<u>Residential Drive Approach On a Concrete Street</u>	305.2
<u>2155A</u>	<u>Commercial Driveway Approach</u>	305.2
<u>2155B</u>	<u>Commercial Driveway Approach Section View</u>	305
<u>2160</u>	<u>Alley Approach Radius Return Type</u>	305.2
<u>2170</u>	<u>Reinforced Concrete Sidewalks Joints and Spacing</u>	305.2
<u>2180</u>	<u>Reinforced Concrete Retaining Wall Integral with Sidewalks</u>	802.2

BIKE LANE
 5 - 7 FT. REF CH. 4 (DESIGN OF
 ON-ROAD FACILITIES) AASHTO GUIDE
 FOR THE DEVELOPMENT OF BICYCLE
 FACILITIES, 2012. OR AS UPDATED.

$\Delta = 11^\circ 28' 40''$
 $R = 250.00'$
 $T = 25.13'$
 $L = 50.08'$

$V = 15'$ MIN.



SCHEMATIC PLAN
 N.T.S.

NOTE:
 THIS LAYOUT IS SCHEMATIC AND
 NOT INTENDED TO BE USED FOR
 CONSTRUCTION.

SIX-LANE DIVIDED THOROUGHFARE
 WITH BIKE LANE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


303

DATE


AUG '23

STANDARD DRAWING NO.

2010B



(FILL SECTIONS ONLY. ALTERNATE REVERSE SLOPE ACCEPTABLE. NOT TO EXCEED 4:1)



NOTES:

1. MIN. PAVEMENT DEPTH AND STRENGTH SHALL BE 8" - CLASS "C" OR "PC", OR AS SPECIFIED BY OWNER. MIN. HMAC THICKNESS SHALL BE 2" TYPE D SURFACE COURSE OVER 8" TYPE B BINDER COURSE.
2. MIN CURB HEIGHT AND WIDTH SHALL BE 6", OR AS SPECIFIED BY OWNER.
3. ALTERNATIVE MATERIALS, SUBGRADE, THICKNESS, AND STEEL MAY BE UTILIZED WITH MORE DETAILED ANALYSIS AS APPROVED BY OWNER.
4. IF LIME STABILIZED SUBGRADE IS UTILIZED A MINIMUM OF 40LBS/SY IS REQUIRED. REFERENCE SECTION 301.

① SAWED LONGITUDINAL CONTRACTION JOINT OR CONSTRUCTION JOINT.

SIX-LANE DIVIDED THOROUGHFARE
WITHOUT BIKE LANE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

301, 303

DATE

AUG '23


STANDARD DRAWING NO.

2015A



STANDARD DRAWING NO.
2015B

DATE AUG '23	STANDARD DRAWING NO. 2020A



NOTE:
 THIS LAYOUT IS SCHEMATIC AND
 NOT INTENDED TO BE USED FOR
 CONSTRUCTION.

FOUR-LANE DIVIDED THOROUGHFARE WITH BIKE LANE


North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE
 303

DATE
 AUG '23

STANDARD DRAWING NO.
 2020B



(FILL SECTIONS ONLY. ALTERNATE REVERSE SLOPE ACCEPTABLE. NOT TO EXCEED 4:1.)



NOTES:

1. MIN. PAVEMENT DEPTH AND STRENGTH SHALL BE 8" - CLASS "C" OR "PC", OR AS SPECIFIED BY OWNER.
2. MIN CURB HEIGHT AND WIDTH SHALL BE 6", OR AS SPECIFIED BY OWNER.
3. ALTERNATIVE SUBGRADE, THICKNESS, AND STEEL MAY BE UTILIZED WITH MORE DETAILED STUDY AND ANALYSIS AS APPROVED BY OWNER.
4. IF LIME STABILIZED SUBGRADE IS UTILIZED A MINIMUM OF 40LBS/SY IS REQUIRED. SEE SECTION 301.
5. SEE DETAIL 2170 FOR SIDEWALKS.

① SAWED LONGITUDINAL CONTRACTION JOINT OR CONSTRUCTION JOINT.

FOUR-LANE DIVIDED THOROUGHFARE
WITHOUT BIKE LANE


North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
303

DATE
AUG '23

STANDARD DRAWING NO.
2025A




STREET WIDTH(W)	A	R.O.W. WIDTH	CROWN HEIGHT*
40'	8' OR 10'	VARIES	6"
44'	11'	VARIES	8"

*SEE NOTE 4

FOUR TRAVEL LANES

N.T.S.



TWO TRAVEL LANES

N.T.S.

① INDICATES SAWED LONGITUDINAL CONTRACTION OR CONSTRUCTION JOINT.

NOTES:

- ALL REINFORCEMENT SHALL BE 4" BARS ON 18" CENTERS BOTH WAYS, EXCEPT WHERE NOTED.
- ALTERNATIVE MATERIALS, SUBGRADE, THICKNESS, AND STEEL MAY BE UTILIZED WITH MORE DETAILED STUDY AND ANALYSIS AND AS APPROVED BY OWNER.
- PAVEMENT STRENGTH SHALL CONFORM TO CLASS "C" OR "PC" CONCRETE, OR AS SPECIFIED BY THE OWNER.
- STRAIGHT CROWN OR PARABOLIC CROWN AS APPROVED BY OWNER.
- SEE DETAILS 2170 FOR SIDEWALKS.

2- & 4-LANE UNDIVIDED THOROUGHFARE
WITH BIKE LANE


North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
303

DATE
AUG '23

STANDARD DRAWING NO.
2030




LANES	STREET WIDTH(W)	A	B	R.O.W. WIDTH	CROWN HEIGHT*
2 TRAVEL LANES W/ 2 PARKING LANES	36'	8'	10'	VARIES	6"
2 TRAVEL LANES W/ 2 PARKING LANES	40'	10'	10'	VARIES	6"
4 TRAVEL LANES	44'	11'	11'	VARIES	8"

*SEE NOTE 4

FOUR TRAVEL LANES OR TWO TRAVEL LANES & TWO PARKING LANES

N.T.S.



ONE TRAVEL LANE & TWO PARKING LANES

N.T.S.

① INDICATES SAWED LONGITUDINAL CONTRACTION OR CONSTRUCTION JOINT.

NOTES :

- ALL REINFORCEMENT SHALL BE 4" BARS ON 18" CENTERS BOTH WAYS, EXCEPT WHERE NOTED.
- ALTERNATIVE SUBGRADE, THICKNESS, AND STEEL MAY BE UTILIZED WITH MORE DETAILED STUDY AND ANALYSIS AND AS APPROVED BY OWNER.
- PAVEMENT STRENGTH SHALL CONFORM TO CLASS "C" OR "PC" CONCRETE, OR AS SPECIFIED BY THE OWNER.
- STRAIGHT CROWN OR PARABOLIC CROWN AS APPROVED BY OWNER.
- SEE DETAILS 2170 FOR SIDEWALKS.
- FOR ALTERNATE OFF-STREET BIKE OPTIONS, SEE AASHTO SHARED USE PATH GUIDELINES.
- BIKE LANES MAY BE ADDED PER AASHTO GUIDELINES.

2- & 4-LANE UNDIVIDED ROADWAY

WITH OPTIONAL PARKING (WITHOUT BIKE LANE)



North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
303

DATE
AUG '23

STANDARD DRAWING NO.
2035



NOTES:

1. CROWN SECTION MAY BE USED IN LIEU OF INVERT WITH PROVISION OF AN ADEQUATE DRAINAGE DESIGN AND AS APPROVED BY OWNER.
2. REINFORCED WITH NO. 3 BARS AT 18" C-C BOTH WAYS OR AS APPROVED BY OWNER.
3. ALTERNATIVE SUBGRADE, THICKNESS, AND STEEL MAY BE UTILIZED WITH MORE DETAILED STUDY AND ANALYSIS AND AS APPROVED BY OWNER.
4. EXPANSION JOINTS TO BE PLACED AT INTERSECTION AND NOT TO EXCEED 600' BETWEEN JOINTS.
5. CONCRETE SHALL BE CLASS "C" OR "PC", OR AS SPECIFIED BY OWNER.
6. SEE DETAIL 2170 FOR SIDEWALKS.

ALLEY WIDTH (W)	A	B	R.O.W. WIDTH (C)
10'	5'	2'-6"	15'
12'	6'	2'-6"	17'
16'	8'	2'-6"	21'
20'	10'	2'-6"	25'

REINFORCED CONCRETE PAVEMENT

ALLEYS


North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
301, 303


DATE
AUG '23

STANDARD DRAWING NO.
2040



CONSTRUCTION JOINT


N.T.S.



KEYWAY JOINT

(FOR PAVEMENT THICKNESS > 6")

N.T.S.




SAWED CONTRACTION JOINT

N.T.S.

NOTE:

1. APPLY BACKER ROD AS APPROVED BY OWNER



EXPANSION JOINT

(SPACED 600 FT. MAXIMUM; LOCATE AT STRUCTURES AND AT INTERSECTION P.C.'S & P.T.'S)

N.T.S.

REINFORCED CONCRETE PAVEMENT

JOINTS

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


303.5.4.

DATE

AUG '23

STANDARD DRAWING NO.

2050



SPACING DIAGRAM FOR TRANSVERSE JOINTS
N.T.S.

REINFORCED CONCRETE PAVEMENT
TRANSVERSE JOINT SPACING


North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
303.5.4.


DATE
AUG '23

STANDARD DRAWING NO.
2060




STREET HEADER FOR FUTURE PAVEMENT

N.T.S.



STREET HEADER AT EXISTING PAVEMENT

N.T.S.



NOTES:

1. PAVEMENT BARS TO BE BENT DOWN INTO HEADER.

2. HEADER AND PAVEMENT TO BE MONOLITHIC.

STREET HEADER AT RAILROAD

N.T.S.

REINFORCED CONCRETE PAVEMENT

STREET HEADERS

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
303.5.4.

DATE
AUG '23

STANDARD DRAWING NO.
2070

GENERAL NOTES:

1. REINFORCED CONCRETE PAVEMENT:
 - A. ALL CURBS SHALL BE PLACED INTEGRAL WITH PAVEMENT UNLESS OTHERWISE APPROVED BY THE OWNER.
 - B. CURBS SHALL MEET THE SAME COMPRESSIVE STRENGTH AS SPECIFIED FOR THE PAVEMENT.
 - C. BAR LAPS SHALL BE 30 DIAMETERS.
 - D. REINFORCING BARS SHALL BE SUPPORTED BY CHAIRS OR OTHER DEVICES APPROVED BY THE OWNER.
2. SUBGRADE: (UNLESS OTHERWISE SPECIFIED BY OWNER)
 - A. SUBGRADE UNDER ALL PAVEMENTS SHALL BE STABILIZED TO MINIMUM DEPTH OF 6" FOR 2 LANE RESIDENTIAL ROAD AND 8" FOR ALL OTHERS. IF THE P.I. IS 15 OR GREATER, LIME SHALL BE USED, IF THE P.I. IS LESS THAN 15, CEMENT SHALL USED OR AS RECOMMENDED BY A GEOTECH ENGINEER. LABORATORY TESTS MUST BE PERFORMED TO DETERMINE THE AMOUNT OF CEMENT REQUIRED TO LOWER THE P.I. TO 15 OR BELOW SATURATION P.I. ($PH \geq 12.4$) WILL BE THE LIMIT WHEN A SOIL'S P.I. CANNOT BE BROUGHT TO 15 OR LOWER.
 - B. WHERE THE IN PLACE MATERIAL HAS A P.I. OF LESS THAN 15, THE SUBGRADE SHALL BE SCARIFIED TO A MINIMUM DEPTH OF 6" AND RECOMPACTED.
 - C. WHERE SULFATES ARE PRESENT, CONSULT A GEOTECHNICAL ENGINEER FOR RECOMMEND SUBGRADE TREATMENT.
3. IF THE ROADWAY IS A DESIGNATED BIKE ROUTE OR BIKE USAGE IS ANTICIPATED, REFER TO AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS AASHTO GUIDE FOR THE DEVELOPMENT OF BICYCLE FACILITIES (2012, 4TH EDITION) AND THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (TMUTCD):
https://mutcd.fhwa.dot.gov/resources/state_info/texas/tx.htm

PAVEMENT SYSTEMS

GENERAL NOTES

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


301. 302. 303.

DATE

AUG '23


STANDARD DRAWING NO.

2110




INTEGRAL CURB & GUTTER

N.T.S.



SEPARATE CURB & GUTTER

N.T.S.



DOWELED CURB


N.T.S.

NOTES:

1. REINFORCEMENT SHALL BE NO. 4 BARS, UNLESS OTHERWISE SPECIFIED.
2. CONCRETE SHALL BE CLASS "C" OR "PC".
3. "CF" IS 6" UNLESS OTHERWISE SPECIFIED.
4. ALL CURBS ARE CONSTRUCTED OF PORTLAND CEMENT CONCRETE UNLESS OTHERWISE SHOWN.
5. GRADE SHALL BE MEASURED AT BACK OF CURB.
6. SEE ROADWAY SECTIONS FOR SUBGRADE SUBGRADE SHALL EXTEND 1' BEYOND BACK OF CURB.

CONCRETE CURB & GUTTER
INTEGRAL, SEPARATE, & DOWELED

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


305.1

DATE


AUG '23

STANDARD DRAWING NO.


2120



CONCRETE NOSE FOR MEDIAN ISLAND




NOTE: MEDIAN PAVING SHALL EXTEND TO POINT WHERE MEDIAN IS 6' WIDE. IF MEDIAN IS 6' WIDE, PAVING SHALL EXTEND 15' FROM NOSE. FOR MEDIANS WIDER THAN 6' PAVING SHALL EXTEND 10' FROM NOSE. ALL DISTANCES ARE MINIMUM.



MEDIAN ISLAND PAVEMENT
NOSE & LEFT TURN LANE


North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
305.3


DATE
AUG '23

STANDARD DRAWING NO.
2130



TYPICAL DRIVE APPROACH CONNECTING TO ASPHALT STREETS WITH CURB AND GUTTER

N.T.S.



SECTION 'A-A'

N.T.S.

NOTES:

1. THE SLOPE OF THE DRIVE WHERE SIDEWALKS CROSS SHALL HAVE A MAXIMUM CROSS SLOPE OF 2%.
2. REMOVE ANY EXISTING SIDEWALK AT NEAREST JOINT AND CONNECT REPLACED SECTION TO DRIVE WITH (3) - NO. 4 SMOOTH DOWEL BARS ON 18" CENTERS WITH 3/4" REDWOOD EXPANSION JOINT, WITH 1" REMOVABLE CAP STRIP. SEAL WITH SELF LEVELING GRAY SILICONE SEALANT.
3. RESIDENTIAL DRIVE APPROACH 10% MAX SLOPE*; MIN. 5" SLAB THICKNESS
* MAXIMUM SLOPE AS APPROVED BY OWNER
4. ALL CONNECTIONS TO STATE RIGHT-OF-WAY SHALL USE TXDOT DETAILS.
5. ALL CURB AND GUTTER SHALL BE 30" UNLESS OTHERWISE DIRECTED BY THE CITY.
6. CONCRETE SHALL BE CLASS C, 6 SACK AND HAVE COMPRESSIVE STRENGTH OF 3600 PSI @28 DAYS.
7. IF STREET IS BEING REPLACED, PAVEMENT THICKNESS SHALL BE 6" FOR RESIDENTIAL AND 8" FOR COLLECTOR OR LARGER.

RESIDENTIAL DRIVE APPROACH CONNECTING TO
ASPHALT STREETS WITH CURB AND GUTTER


North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
305.2


DATE
AUG '23

STANDARD DRAWING NO.
2150A



TYPICAL DRIVE APPROACH CONNECTING TO EXISTING RURAL TYPE ASPHALT STREETS

N.T.S.



SECTION 'A-A'

N.T.S.

NOTES:

1. THE SLOPE OF THE DRIVE WHERE SIDEWALKS CROSS SHALL HAVE A MAXIMUM CROSS SLOPE OF 2%.
2. RESIDENTIAL DRIVE APPROACH 10% MAX SLOPE*; MIN. 5" SLAB THICKNESS
* MAXIMUM SLOPE AS APPROVED BY OWNER
3. ALL CONNECTIONS TO STATE RIGHT-OF-WAY SHALL USE TXDOT DETAILS.
4. CONCRETE SHALL BE CLASS C, 6 SACK AND HAVE COMPRESSIVE STRENGTH OF 3600 PSI @ 28 DAYS.
5. MINIMUM VELOCITY THROUGH PIPE IS 2.5fps. MINIMUM SLOPE IN PIPE IS 0.5% UNLESS OTHERWISE DESIGNED TO MEET MINIMUM SLOPE REQUIREMENTS
6. IN SOME CASES A SWALE MAY BE PROVIDED IN LIEU OF THE PIPE. THE PROPERTY OWNER AND OWNER'S ENGINEERS WILL NEED TO DETERMINE IF A SWALE CAN BE USED IN LIEU OF A PIPE.
7. USE OF RURAL SECTION AS APPROVED BY OWNER.

RESIDENTIAL DRIVE APPROACH CONNECTING
TO EXISTING RURAL TYPE ASPHALT STREET

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


305.2

DATE


AUG '23

STANDARD DRAWING NO.

2150B



N.T.S.



N.T.S.

SEE NOTES FOR 2150A

RESIDENTIAL DRIVE APPROACH ON A CONCRETE STREET

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


305.2

DATE

AUG '23

STANDARD DRAWING NO.

2150C



NOTES:

1. THE SLOPE OF THE DRIVE WHERE SIDEWALKS CROSS SHALL HAVE A MAXIMUM CROSS SLOPE OF 2%.
2. REMOVE ANY EXISTING SIDEWALK AT NEAREST JOINT AND CONNECT REPLACED SECTION TO DRIVE WITH (3) - NO. 4 SMOOTH DOWEL BARS ON 18" CENTERS WITH 3/4" REDWOOD EXPANSION JOINT, WITH 1" REMOVABLE CAP STRIP. SEAL WITH SELF LEVELING GRAY SILICONE SEALANT.
3. COMMERCIAL DRIVE APPROACH 10% MAX SLOPE*; MIN. 7" SLAB THICKNESS
* MAXIMUM SLOPE AS APPROVED BY OWNER
4. ALL CONNECTIONS TO STATE RIGHT-OF-WAY SHALL USE TXDOT DETAILS.
5. ALL CURB AND GUTTER SHALL BE 30" UNLESS OTHERWISE DIRECTED BY THE CITY.
6. CONCRETE SHALL BE CLASS C, 6 SACK AND HAVE COMPRESSIVE STRENGTH OF 3600 PSI @28 DAYS.
7. IF STREET IS BEING REPLACED, PAVEMENT THICKNESS SHALL BE 6" FOR RESIDENTIAL AND 8" FOR COLLECTOR OR LARGER.

COMMERCIAL DRIVEWAY APPROACH

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


305.2

DATE

AUG '23

STANDARD DRAWING NO.

2155A



SECTION 'A-A'
N.T.S.

COMMERCIAL APPROACH (CONCRETE PAVING)

NOTES:

1. THE SLOPE OF THE DRIVE WHERE SIDEWALKS CROSS SHALL HAVE A MAXIMUM CROSS SLOPE OF 2%.
2. REMOVE ANY EXISTING SIDEWALK AT NEAREST JOINT AND CONNECT REPLACED SECTION TO DRIVE WITH (3) - NO. 4 SMOOTH DOWEL BARS ON 18" CENTERS WITH 3/4" REDWOOD EXPANSION JOINT, WITH 1" REMOVABLE CAP STRIP. SEAL WITH SELF LEVELING GRAY SILICONE SEALANT.
3. COMMERCIAL DRIVE APPROACH 10% MAX SLOPE*; MIN. 7" SLAB THICKNESS
* MAXIMUM SLOPE AS APPROVED BY OWNER
4. ALL CONNECTIONS TO STATE RIGHT-OF-WAY SHALL USE TXDOT DETAILS.
5. ALL CURB AND GUTTER SHALL BE 30" UNLESS OTHERWISE DIRECTED BY THE CITY.
6. CONCRETE SHALL BE CLASS C, 6 SACK AND HAVE COMPRESSIVE STRENGTH OF 3600 PSI @28 DAYS.
7. IF STREET IS BEING REPLACED, PAVEMENT THICKNESS SHALL BE 6" FOR RESIDENTIAL AND 8" FOR COLLECTOR OR LARGER.

COMMERCIAL DRIVEWAY APPROACH
SECTION VIEW

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


305

DATE

AUG '23

STANDARD DRAWING NO.


2155B




ALLEY APPROACH RADIUS RETURN TYPE

NOTES:

1. THE SLOPE OF THE DRIVE WHERE SIDEWALKS CROSS SHALL HAVE A MAXIMUM CROSS SLOPE OF 2%.
2. REMOVE ANY EXISTING SIDEWALK AT NEAREST JOINT AND CONNECT REPLACED SECTION TO DRIVE WITH (3) - NO. 4 SMOOTH DOWEL BARS ON 18" CENTERS WITH 3/4" REDWOOD EXPANSION JOINT, WITH 1" REMOVABLE CAP STRIP. SEAL WITH SELF LEVELING GRAY SILICONE SEALANT.
3. COMMERCIAL DRIVE APPROACH 10% MAX SLOPE*; MIN. 7" SLAB THICKNESS
* MAXIMUM SLOPE AS APPROVED BY OWNER
4. ALL CONNECTIONS TO STATE RIGHT-OF-WAY SHALL USE TXDOT DETAILS.
5. ALL CURB AND GUTTER SHALL BE 30" UNLESS OTHERWISE DIRECTED BY THE CITY.
6. CONCRETE SHALL BE CLASS C, 6 SACK AND HAVE COMPRESSIVE STRENGTH OF 3600 PSI @28 DAYS.
7. IF STREET IS BEING REPLACED, PAVEMENT THICKNESS SHALL BE 6" FOR RESIDENTIAL AND 8" FOR COLLECTOR OR LARGER.



SECTION A-A
N.T.S.



NOTES:

1. MIN. PAVEMENT DEPTH AND STRENGTH SHALL BE 6" - CLASS "C", OR AS SPECIFIED BY CITY.
2. CURB HEIGHT AND WIDTH SHALL BE 6", OR AS SPECIFIED BY CITY. SEE STANDARD CONSTRUCTION DETAIL 2120.
3. SUBGRADE SHALL MATCH ALLEY PAVEMENT SUBGRADE

SECTION B-B
N.T.S.

ALLEY APPROACH RADIUS RETURN TYPE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE




305.2

DATE

AUG '23

STANDARD DRAWING NO.

2160



NOTE:

1. REFER TO STANDARD SPECIFICATION ITEM 305.2 FOR ALTERNATE REINFORCEMENT.
2. CROSS SLOPE OF SIDEWALK SHALL BE 2% MAX.
3. OTHER THAN 5'-0" SIDEWALK WIDTH MAY BE SPECIFIED BY OWNER.
IF LESS THAN 5' SIDEWALK IS USED, THE TOOLED JOINT IS TO MATCH THE WIDTH OF SIDEWALK.
4. SIDEWALK SHALL BE CLASS "C" CONCRETE UNLESS OTHERWISE SPECIFIED BY OWNER.
5. ALL HONEYCOMB IN BACK OF CURB TO BE TROWEL-PLASTERED BEFORE POURING SIDEWALK.
6. LUG MAY BE FORMED BY SHAPING SUBGRADE TO APPROXIMATE DIMENSIONS SHOWN.
7. IF 5' WIDTH CANNOT BE ACHIEVED, MUST BE COMPLIANT WITH ADA AND PROWAG PASSING REQUIREMENTS.

REINFORCED CONCRETE SIDEWALKS

JOINTS AND SPACING


North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
305.2

DATE
AUG '23

STANDARD DRAWING NO.
2170



NOTE:

1. PROVIDE VERTICAL EXPANSION IN WALL AT 25' MAX. SPACING (USE EXPANSION JOINT, STANDARD DRAWING NO. 2050, AND MODIFY AS REQUIRED)
2. WALL DESIGN ASSUMES NO SURCHARGE. A SPECIAL ENGINEERING ANALYSIS IS REQUIRED FOR OTHER CONDITIONS.

RETAINING WALL WITH
INTEGRAL SIDEWALK

N.T.S.

REINFORCED CONCRETE RETAINING WALL

INTEGRAL WITH SIDEWALK

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
802.2

DATE
AUG '23


STANDARD DRAWING NO.
2180

STANDARD DRAWING NO.
2180

DIVISION 3000 GENERAL UNDERGROUND CONDUIT

TABLE OF CONTENTS

<u>Drawing #</u>	<u>Subject</u>	<u>Section I: Item #</u>
<u>3010</u>	<u>Embedment</u> <u>Class "A" & "A-1"</u>	504.5
<u>3020</u>	<u>Embedment</u> <u>Class "B", "B+", & "B-1"</u>	504.5
<u>3030</u>	<u>Embedment</u> <u>Class "B-2", "B-3", & "B-4"</u>	504.5
<u>3040</u>	<u>Embedment</u> <u>Class "C", "C+", & "C-1"</u>	504.5
<u>3050</u>	<u>Embedment</u> <u>Class "D+" & "G"</u>	504.5
<u>3060</u>	<u>Embedment</u> <u>Class "G-1" & "H"</u>	504.5
<u>3070A</u>	<u>Pavement Cut and Repair</u> <u>Concrete and Parkway</u>	402
<u>3070B</u>	<u>Pavement Cut and Repair</u> <u>Asphalt</u>	402
<u>3070C</u>	<u>Pavement Cut and Repair</u> <u>Extent – Residential</u>	402
<u>3070D</u>	<u>Pavement Cut and Repair</u> <u>Extent – Multiple Lanes</u>	402
<u>3080</u>	<u>Infiltration Protection</u> <u>Conduit Under Channel</u>	504; 803.




CLASS "A"

CLASS "B" CONCRETE CRADLE
PLAIN CONC. LF 2.8
REINF. CONC. LF 3.4 P=0.4%

N.T.S

NOTES:

1. LF = LOAD FACTOR TO BE USED TO DETERMINE 3 EDGE BEARING BASED ON TYPE OF EMBEDMENT.
2. FREE-FALL OF CONCRETE NOT TO EXCEED 5 FT. MAXIMUM.
3. P = Rho FOR STEEL %
4. Bc = OUTSIDE DIAMETER OF PIPE
5. Bd = TRENCH WIDTH
6. USE OF 95% DENSITY UNDER PAVED SURFACE AND 90% IN UNPAVED AREAS



CLASS "A-1"

CLASS "B" CONCRETE CAP
PLAIN CONC. LF 2.8
REINF. CONC. LF 3.4 P=0.4%
REINF. CONC. LF 4.8 P=1.0%

N.T.S

EMBEDMENT

CLASS "A" & "A-1"

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

504.5

DATE
AUG '23

STANDARD DRAWING NO.
3010

STANDARD DRAWING NO.

3010


SELECT OR GRANULAR MATERIAL COMPACTED TO 90% OF STD. PROCTOR DENSITY SEE NOTE 3

COVER EMBEDMENT
WITH FILTER
FABRIC/GEOTEXTILE AS
REQUIRED BY OWNER


COVER EMBEDMENT
WITH FILTER FABRIC/GEOTEXTILE
AS REQUIRED BY OWNER

GRANULAR MATERIAL COMPACTED
TO 90% OF STD. PROCTOR
DENSITY. SEE NOTE 3


COVER EMBEDMENT
WITH FILTER
FABRIC/GEOTEXTILE
AS REQUIRED BY OWNER



CLASS "B"
N.T.S.



CLASS "B+"
N.T.S.



CLASS "B-1"
N.T.S.

NOTES:

1. Bc = OUTSIDE DIAMETER OF PIPE
2. Bd = TRENCH WIDTH
3. USE 95% DENSITY UNDER PAVED SURFACE AND 90% IN UNPAVED AREAS

STANDARD DRAWING NO.
3020

EMBEDMENT

CLASS "B", "B+", & "B-1"


North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
504.5

DATE
AUG '23

STANDARD DRAWING NO.
3020



CLASS "B-2"

N.T.S.

CLASS "B-3"

N.T.S.

CLASS "B-4"

N.T.S.

NOTES:

1. Bc = OUTSIDE DIAMETER OF PIPE
2. Bd = TRENCH WIDTH
3. USE 95% DENSITY UNDER PAVED SURFACE AND 90% IN UNPAVED AREAS
4. REFER TO 504.6.2

EMBEDMENT

CLASS "B-2", "B-3", & "B-4"


North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
504.5

DATE
AUG '23

STANDARD DRAWING
3030



NOTES:

1. Bc = OUTSIDE DIAMETER OF PIPE
2. Bd = TRENCH WIDTH
3. USE 95% DENSITY UNDER PAVED SURFACE AND 90% IN UNPAVED AREAS

STANDARD DRAWING NO.
3040

EMBEDMENT

CLASS "C", "C+", & "C-1"

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

504.5

DATE
AUG '23


STANDARD DRAWING NO.
3040

SELECT OR GRANULAR MATERIAL
COMPACTED TO 90%
STD. PROCTOR DENSITY.
SEE NOTE 4



CLASS "D+"

N.T.S.



CLASS "G"

N.T.S.

NOTES:

1. Bc = OUTSIDE DIAMETER OF PIPE
2. Bd = TRENCH WIDTH
3. D = INSIDE DIAMETER OF PIPE
4. USE 95% DENSITY UNDER PAVED SURFACE AND 90% IN UNPAVED AREAS

STANDARD DRAWING NO
3050

EMBEDMENT

CLASS "D+" & "G"

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


504.5

DATE

AUG '23


STANDARD DRAWING NO.

3050



CLASS "H"

N.T.S.



CLASS "G-1"

N.T.S.

NOTES:

1. Bc = OUTSIDE DIAMETER OF PIPE
2. Bd = TRENCH WIDTH
3. D = INSIDE DIAMETER OF PIPE
4. USE 95% DENSITY UNDER PAVED SURFACE AND 90% IN UNPAVED AREAS

EMBEDMENT

CLASS "G-1" & "H"

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

504.5



DATE
AUG '23

STANDARD DRAWING NO.
3060

STANDARD DRAWING NO.

3060


GENERAL NOTE: CHECK WITH STREET OWNER FOR
SPECIFIC REQUIREMENTS NOT CONTAINED HEREIN



PAVEMENT CUT AND REPAIR

CONCRETE AND PARKWAY

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

402


DATE _____

AUG '23


STANDARD DRAWING NO.

3070A

GENERAL NOTE: CHECK WITH STREET OWNER FOR
SPECIFIC REQUIREMENTS NOT CONTAINED HEREIN




CONCRETE PAVEMENT WITH ASPHALT OVERLAY



N.T.S.

PAVEMENT CUT AND REPAIR
ASPHALT

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

402

DATE




AUG '23

STANDARD DRAWING NO.

3070B

GENERAL NOTES


1. REMOVE AND REPLACE A MINIMUM 4' (ASPHALT) OR 3' (CONCRETE) LONGITUDINAL, OR 2' (ASPHALT) 1' (CONCRETE) FROM THE EDGE OF THE TRENCH, WHICHEVER IS GREATER.
2. IF WITHIN 3' OF AN EXISTING JOINT, THEN REMOVE TO THE EXISTING JOINT.
3. MULTIPLE LOCATIONS ARE TO BE A MINIMUM OF 10' APART FROM EDGE OF REPAIR TO EDGE OF REPAIR, IF LESS THAN 10' APART, A CONTINUOUS SECTION MUST BE REPLACED.
4. A GUTTER OF AT LEAST 12' MAY REMAIN, PROVIDED THAT THE CURB AND GUTTER IS NOT DAMAGED BY THE CONSTRUCTION ACTIVITY.
5. EXACT PAVEMENT REMOVAL LOCATIONS TO BE APPROVED BY OWNER PRIOR TO CONSTRUCTION.



VARIABLE WIDTH RESIDENTIAL STREET

PAVEMENT CUT AND REPAIR
EXTENT — RESIDENTIAL

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

402


DATE
AUG '23

STANDARD DRAWING NO.


3070C

GENERAL NOTES

1. REMOVE AND REPLACE A MINIMUM OF 3' (CONCRETE) OR 4' (ASPHALT) LONGITUDINAL, OR 1' (CONCRETE) OR 2' (ASPHALT) FROM THE EDGE OF THE TRENCH, WHICHEVER IS GREATER.
2. IF WITHIN 3' OF AN EXISTING JOINT, THEN REMOVE TO THE EXISTING JOINT.
3. MULTIPLE LOCATIONS ARE TO BE A MINIMUM OF 10' APART FROM EDGE OF REPAIR IF LESS THAN 10' APART, A CONTINUOUS SECTION MUST BE REPLACED.
4. A GUTTER OF AT LEAST 12' MAY REMAIN, PROVIDED THAT THE CURB AND GUTTER IS NOT DAMAGED BY THE CONSTRUCTION ACTIVITY.
5. EXACT PAVEMENT REMOVAL LOCATIONS TO BE APPROVED BY OWNER PRIOR TO CONSTRUCTION.




VARIABLE WIDTH CONCRETE STREET
WITH MULTIPLE LANES



VARIABLE WIDTH ASPHALT STREET
WITH MULTIPLE LANES





STANDARD SPECIFICATION REFERENCE
504; 803

DATE
AUG '23

STANDARD DRAWING NO.
3080

North Central Texas Council of Governments



INFILTRATION PROTECTION

CONDUIT UNDER CHANNEL

DIVISION 4000 WATER DISTRIBUTION

TABLE OF CONTENTS

<u>Drawing #</u>	<u>Subject</u>	<u>Section I: Item #</u>
<u>4010A</u>	<u>Horizontal Thrust Block At Pipe Bend</u>	502.4
<u>4010B</u>	<u>Horizontal Thrust Block At Pipe Bend</u>	502.4
<u>4010C</u>	<u>Horizontal Thrust Block At Pipe Bend</u>	502.4
<u>4020</u>	<u>Horizontal Thrust Block At Tees and Plugs</u>	502.4
<u>4030</u>	<u>Vertical Thrust Block At Pipe Bend</u>	502.4
<u>4040</u>	<u>Thrust Block General Notes</u>	502.4
<u>4050</u>	<u>Gate Valve 4" To 12" Box & Extension Stem</u>	502.6
<u>4060A</u>	<u>Vault Construction Horizontal Gate Valve ≥ 16"</u>	702.5
<u>4060B</u>	<u>Vault Construction Horizontal Gate Valve ≥ 16"</u>	702.5
<u>4070A</u>	<u>Vault Construction Vertical Gate Valve ≥ 16"</u>	702.5
<u>4070B</u>	<u>Vault Construction Vertical Gate Valve ≥ 16"</u>	702.5
<u>4080A</u>	<u>Vault Construction Butterfly Valve ≥ 48"</u>	702.5
<u>4080B</u>	<u>Vault Construction Butterfly Valve ≥ 48"</u>	702.5
<u>4090</u>	<u>Combination Air Vacuum Valve Type "1"</u>	502.6
<u>4100A</u>	<u>Combination Air Vacuum Valve Type "2"</u>	502.6
<u>4100B</u>	<u>Air Vent Standard Dimension and Detail</u>	502.6

<u>4110</u>	<u>Flush Point Installation</u> <u>Type “1”</u>	502.1
<u>4120</u>	<u>Fire Hydrant</u> <u>Installation</u>	502.3
<u>4130</u>	<u>Water Service Installation</u> <u>3/4” or 1” Line</u>	502.10
<u>4140</u>	<u>Water Service Installation</u> <u>1 1/2” or 2” Line</u>	502.10
<u>4150</u>	<u>4” Meter</u>	502.10
<u>4190A</u>	<u>Large Service Meter Vault</u> <u>Installation</u>	702.5
<u>4190B</u>	<u>Large Service Precast Vault</u>	702.5
<u>4200</u>	<u>Water Main Lowering Below</u> <u>Stormwater Main</u>	506

I.D. (IN.)	T (IN.)	$\Delta = 11.25^\circ$ C (FT.)	$\Delta \geq 22.50^\circ$ C (FT.)	E (FT.)
4,6,8	0.4	1.5	1.5	0.9
10,12	0.5	1.5	1.5	1.2
16,18	0.6	1.5	1.5	1.6
20	0.7	1.5	1.5	1.8
24	0.9	1.5	1.5	2.1
30	2.9	1.5	1.9	2.6
36	4.5	1.5	2.3	3.3
42	5.0	1.8	2.6	3.8
48	5.5	2.0	3.0	4.3
54	6.0	2.3	3.4	4.8
60	6.5	2.5	3.8	5.3
66	6.8	2.8	4.1	5.7
72	7.5	3.0	4.5	6.3
78	7.5	3.3	4.9	6.7
84	8.0	3.5	5.3	7.2
90	8.5	3.8	5.6	7.7
96	9.0	4.0	6.0	8.2

I.D. (IN.)	Δ = 11.25°								I.D. (IN.)	Δ = 22.50°							
	G (FT.)	THRUST (TONS)	EARTH			ROCK				G (FT.)	THRUST (TONS)	EARTH			ROCK		
			A (FT.)	B (FT.)	VOL. (C.Y.)	A (FT.)	B (FT.)	VOL. (C.Y.)				A (FT.)	B (FT.)	VOL. (C.Y.)	A (FT.)	B (FT.)	VOL. (C.Y.)
4,6,8	0.4	1.0	1.0	1.5	0.1	1.0	1.0	0.1	4,6,8	0.8	2.0	1.5	1.5	0.1	1.0	1.0	0.1
10,12	0.6	2.2	1.5	1.5	0.1	1.0	1.5	0.1	10,12	1.1	4.4	2.0	2.5	0.3	1.5	1.5	0.1
16,18	0.8	5.0	2.0	2.5	0.3	1.5	2.0	0.2	16,18	1.6	9.9	3.0	3.5	0.6	2.0	2.5	0.3
20	0.9	6.2	2.0	3.5	0.4	1.5	3.0	0.3	20	1.8	12.3	3.5	3.5	0.7	2.0	3.0	0.4
24	1.1	8.9	3.0	3.5	0.5	1.5	3.0	0.3	24	2.2	17.7	4.0	4.5	1.0	3.0	3.5	0.5
30	1.4	10.4	3.0	3.5	0.6	2.0	3.5	0.4	30	2.7	20.7	5.0	4.5	1.5	3.0	4.0	0.8
36	1.7	15.0	3.5	4.5	0.9	2.0	4.0	0.5	36	3.3	29.8	5.5	5.5	2.3	4.0	4.0	1.3
42	1.9	20.4	4.5	5.0	1.5	2.5	5.0	0.8	42	3.8	40.5	7.0	6.0	3.9	4.5	5.0	2.1
48	2.2	26.6	4.5	6.0	2.0	2.5	6.0	1.1	48	4.4	52.9	8.0	7.0	5.7	4.5	6.0	2.8
54	2.5	33.7	6.0	6.0	3.0	3.0	6.0	1.4	54	4.9	67.0	9.0	8.0	8.0	6.0	6.0	4.1
60	2.7	41.6	6.0	7.0	3.8	3.0	7.0	1.8	60	5.5	82.7	9.5	9.0	10.6	6.0	7.0	5.3
66	3.0	50.3	6.5	8.0	5.1	3.5	8.0	2.7	66	6.0	100.1	10.5	10.0	14.1	6.5	8.0	7.2
72	3.3	59.9	7.5	8.0	6.3	4.0	8.0	3.3	72	6.6	119.1	11.0	11.0	17.6	7.5	8.0	9.1
78	3.6	70.2	8.0	9.0	8.1	4.0	9.0	3.9	78	7.1	139.8	12.0	12.0	22.5	8.0	9.0	11.7
84	3.8	81.5	8.5	10.0	10.3	4.5	10.0	5.3	84	7.6	162.1	13.0	12.5	27.2	8.5	10.0	14.8
90	4.1	93.5	9.5	10.0	12.2	5.0	10.0	6.3	90	8.2	186.1	14.0	13.5	33.7	9.5	10.0	17.7
96	4.4	106.4	10.0	11.0	15.0	5.0	11.0	7.4	96	8.7	211.7	15.0	14.5	41.2	10.0	11.0	21.8

TABLES OF DIMENSIONS AND QUANTITIES

HORIZONTAL THRUST BLOCK
AT PIPE BEND

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
502.4

DATE
AUG '23

STANDARD DRAWING NO.
4010B

$\Delta = 30^\circ$									$\Delta = 45^\circ$								
I.D. (IN.)	G (FT.)	THRUST (TONS)	EARTH			ROCK			I.D. (IN.)	G (FT.)	THRUST (TONS)	EARTH			ROCK		
			A (FT.)	B (FT.)	VOL. (C.Y.)	A (FT.)	B (FT.)	VOL. (C.Y.)				A (FT.)	B (FT.)	VOL. (C.Y.)	A (FT.)	B (FT.)	VOL. (C.Y.)
4,6,8	1.0	2.6	2.0	1.5	0.2	1.0	1.5	0.1	4,6,8	1.5	3.9	2.0	2.0	0.2	1.5	1.5	0.1
10,12	1.5	5.9	2.5	2.5	0.3	2.0	1.5	0.2	10,12	2.2	8.7	3.5	2.5	0.5	2.0	2.5	0.3
16,18	2.2	13.2	3.5	4.0	0.8	2.5	3.0	0.4	16,18	3.2	19.5	4.5	4.5	1.2	3.0	3.5	0.6
20	2.4	16.3	4.5	4.0	1.0	3.0	3.0	0.5	20	3.6	24.1	5.5	4.5	1.5	3.5	3.5	0.7
24	2.9	23.4	6.0	4.0	1.4	3.5	3.5	0.7	24	4.3	34.6	8.0	4.5	2.3	4.5	4.0	1.1
30	3.6	27.5	6.5	5.0	1.9	3.5	4.0	0.9	30	5.4	40.6	8.5	5.0	3.2	5.5	4.0	1.6
36	4.4	39.5	7.0	6.0	3.4	4.5	4.5	1.6	36	6.5	58.5	10.0	6.0	5.3	6.5	4.5	2.6
42	5.1	53.8	8.0	7.0	5.1	5.5	5.0	2.5	42	7.5	79.6	11.5	7.0	8.1	8.0	5.0	4.2
48	5.8	70.3	9.0	8.0	7.4	6.0	6.0	3.7	48	8.6	104.0	13.0	8.0	11.9	9.0	6.0	6.3
54	6.5	89.0	10.0	9.0	10.3	7.0	6.5	5.3	54	9.7	131.5	15.0	9.0	17.1	10.5	6.5	8.9
60	7.3	110.0	11.0	10.0	13.9	7.5	7.5	7.3	60	10.7	162.4	16.5	10.0	23.1	11.0	7.5	12.0
66	8.0	132.9	12.5	11.0	18.9	8.5	8.0	9.6	66	11.8	196.5	18.0	11.0	30.1	12.0	8.5	16.2
72	8.7	158.2	13.5	12.0	24.0	9.0	9.0	12.3	72	12.9	233.9	19.5	12.0	38.6	14.0	8.5	20.7
78	9.4	185.6	14.5	13.0	30.0	10.0	9.5	15.6	78	13.9	274.5	21.5	13.0	49.8	14.5	9.5	25.9
84	10.1	215.3	15.5	14.0	37.1	10.5	10.5	19.5	84	15.0	318.4	23.0	14.0	61.2	15.5	10.5	32.6
90	10.9	247.1	16.5	15.0	45.0	11.5	11.0	23.9	90	16.1	365.5	24.5	15.0	74.5	17.5	10.5	39.6
96	11.6	281.2	18.0	16.0	55.5	12.5	11.5	28.9	96	17.1	415.6	26.0	16.0	89.5	18.5	11.5	48.5

$\Delta = 67.50^\circ$									$\Delta = 90^\circ$								
I.D. (IN.)	G (FT.)	THRUST (TONS)	EARTH			ROCK			I.D. (IN.)	G (FT.)	THRUST (TONS)	EARTH			ROCK		
			A (FT.)	B (FT.)	VOL. (C.Y.)	A (FT.)	B (FT.)	VOL. (C.Y.)				A (FT.)	B (FT.)	VOL. (C.Y.)	A (FT.)	B (FT.)	VOL. (C.Y.)
4,6,8	2.1	5.6	3.0	2.0	0.3	2.0	1.5	0.2	4,6,8	2.7	7.1	5.0	1.5	0.4	2.0	2.0	0.2
10,12	3.1	12.6	5.5	2.5	0.8	3.5	2.0	0.4	10,12	4.0	16.0	6.5	2.5	1.0	3.5	2.5	0.5
16,18	4.7	28.3	7.5	4.0	1.9	5.5	3.0	0.9	16,18	6.0	36.0	9.0	4.0	2.4	4.5	4.0	1.0
20	5.2	34.9	9.0	4.0	2.3	5.5	3.5	1.2	20	6.6	44.4	10.0	4.5	3.1	6.0	4.0	1.5
24	6.2	50.3	11.5	4.5	3.5	6.5	4.0	1.6	24	7.9	64.0	14.5	4.5	5.0	8.0	4.0	2.1
30	7.8	58.9	12.0	5.0	4.8	7.5	4.0	2.2	30	9.9	75.0	15.0	5.0	6.7	10.0	4.0	3.3
36	9.4	84.9	14.5	6.0	8.2	9.5	4.5	3.8	36	11.9	108.0	18.0	6.0	11.4	12.0	4.5	5.3
42	10.9	115.5	17.0	7.0	12.8	11.0	5.5	6.3	42	13.9	147.0	21.0	7.0	17.8	14.0	5.5	8.7
48	12.5	150.9	19.0	8.0	18.4	13.0	6.0	9.2	48	15.9	192.0	24.0	8.0	26.2	16.0	6.0	12.4
54	14.0	191.0	21.5	9.0	26.0	15.0	6.5	12.9	54	17.9	243.0	27.0	9.0	36.9	18.0	7.0	18.1
60	15.6	235.8	24.0	10.0	35.6	16.0	7.5	17.6	60	19.9	299.8	30.0	10.0	50.3	20.0	7.5	24.0
66	17.1	285.3	26.0	11.0	46.0	18.0	8.0	23.0	66	21.8	362.8	33.0	11.0	66.2	22.0	8.5	32.5
72	18.7	339.5	28.5	12.0	57.8	19.0	9.0	28.4	72	23.8	431.8	36.0	12.0	85.6	24.0	9.0	41.0
78	20.2	398.5	31.0	13.0	75.7	21.0	9.5	37.4	78	25.7	506.7	39.0	13.0	108.2	26.0	10.0	53.2
84	21.8	462.1	33.5	14.0	94.7	22.0	10.5	46.5	84	27.7	587.7	42.0	14.0	134.4	28.0	10.5	64.8
90	23.3	530.5	35.5	15.0	114.4	24.5	11.0	58.2	90	29.0	674.6	45.0	15.0	164.9	30.0	11.5	81.2
96	24.9	603.6	38.0	16.0	138.9	25.5	12.0	70.0	96	31.6	767.5	48.0	16.0	199.0	32.0	12.0	95.1

TABLE OF DIMENSIONS AND QUANTITIES

HORIZONTAL THRUST BLOCK

AT PIPE BEND

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


502.4

DATE

AUG '23

STANDARD DRAWING NO.


4010C



PLAN OF PLUG THRUST BLOCK

N.T.S.

REFER TO
STD. DWG. No. 4040
FOR GENERAL NOTES.




PLAN OF TEE THRUST BLOCK

N.T.S.

I.D. (IN.)	THRUST (TONS)	C (FT.)	EARTH		ROCK	
			A (FT.)	VOL. (C.Y.)	A (FT.)	VOL. (C.Y.)
4,6,8	5.1	1.5	2.5	0.3	2.0	0.2
10,12	11.3	1.5	3.5	0.6	2.5	0.3
16,18	25.5	2.0	5.5	1.6	4.0	0.9
20	31.5	2.0	6.0	1.9	4.0	0.9
24	45.2	2.5	7.0	3.1	5.0	1.7
30	53.0	3.0	7.5	4.1	5.5	2.4
36	76.3	4.0	9.0	7.3	6.5	4.2
42	104.0	4.5	10.5	11.0	7.5	6.2
48	136.0	5.0	12.0	15.6	8.5	8.7
54	172.0	5.5	13.5	21.4	9.5	11.9
60	212.0	6.0	15.0	28.4	10.5	15.7
66	257.0	6.5	16.5	36.8	11.5	20.5
72	305.0	7.5	17.5	47.2	12.5	27.2
78	358.0	8.0	19.0	58.9	13.5	33.7
84	416.0	8.5	20.5	72.3	14.5	41.2
90	477.0	9.0	22.0	87.7	15.5	49.7
96	543.0	9.5	23.5	104.8	16.5	61.0

HORIZONTAL THRUST BLOCK
AT TEES AND PLUGS

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

502.4


DATE
AUG '23

STANDARD DRAWING NO.
4020



ELEVATION "B-B"

N.T.S.



SECTION "A-A"


N.T.S.

REFER TO
STD. DWG. No. 4040
FOR GENERAL NOTES.

Δ →	11.25°		22.50°		30°		45°		67.50°		90°		← Δ
I.D. (IN.)	THRUST (TONS)	VOL. (C.Y.)	THRUST (TONS)	VOL. (C.Y.)	THRUST (TONS)	VOL. (C.Y.)	THRUST (TONS)	VOL. (C.Y.)	THRUST (TONS)	VOL. (C.Y.)	THRUST (TONS)	VOL. (C.Y.)	I.D. (IN.)
4,6,8	1.0	0.5	2.0	1.0	2.5	1.3	3.6	1.8	4.6	2.3	5.0	2.5	4,6,8
10,12	2.2	1.1	4.3	2.2	5.7	2.8	8.0	4.0	10.5	5.2	11.3	5.7	10,12
16,18	5.0	2.5	9.7	4.9	12.7	6.4	18.0	9.0	23.5	11.8	25.5	12.7	16,18
20	6.1	3.1	12.0	6.0	15.7	7.9	22.2	11.1	29.2	14.5	31.4	15.7	20
24	8.2	4.4	17.3	8.7	22.6	11.3	32.0	16.0	41.8	20.9	45.2	22.6	24
30	10.5	5.2	20.3	10.1	26.5	13.3	37.5	18.8	49.0	24.5	53.1	26.5	30
36	14.9	7.5	29.2	14.6	38.2	19.1	54.0	27.0	70.5	35.3	76.4	38.2	36
42	20.3	10.1	39.8	19.9	52.0	26.0	73.5	36.7	96.0	48.0	104.0	52.0	42
48	26.5	13.2	51.9	26.0	67.9	33.9	96.0	48.0	126.0	62.7	136.0	67.9	48
54	33.5	16.8	65.7	32.9	85.9	42.9	122.0	60.7	159.0	79.4	172.0	85.9	54
60	41.4	20.7	81.2	40.6	106.0	53.0	150.0	75.0	196.0	98.0	212.0	106.0	60
66	50.1	25.0	98.2	49.1	128.0	64.2	182.0	90.7	237.0	119.0	257.0	128.0	66
72	59.6	29.8	117.0	58.4	153.0	76.3	216.0	108.0	282.0	141.0	305.0	153.0	72
78	69.9	35.0	137.0	68.6	179.0	90.0	254.0	127.0	331.0	166.0	358.0	179.0	78
84	81.1	40.5	159.0	79.5	208.0	104.0	294.0	147.0	384.0	192.0	416.0	208.0	84
90	93.1	46.5	183.0	91.3	239.0	119.0	337.0	169.0	441.0	221.0	477.0	239.0	90
96	106.0	53.0	208.0	104.0	272.0	136.0	384.0	192.0	502.0	251.0	543.0	272.0	96

VERTICAL THRUST BLOCK
AT PIPE BEND

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

502.4

DATE
AUG '23

STANDARD DRAWING NO.
4030


GENERAL NOTES FOR ALL THRUST BLOCKS:

1. CONCRETE FOR BLOCKING SHALL BE CLASS "B".
2. ALL CALCULATIONS ARE BASED ON INTERNAL PRESSURE OF 200 PSI FOR DUCTILE IRON, P.V.V, AND 150 PSI FOR CONCRETE PIPE.
3. VOLUMES OF THRUST BLOCKS ARE NET VOLUMES OF CONCRETE TO BE FURNISHED. THE CORRESPONDING WEIGHT OF THE CONCRETE (CLASS "B") IS EQUAL TO OR GREATER THAN THE VERTICAL COMPONENT OF THE THRUST ON THE VERTICAL BEND.
4. WALL THICKNESS (T) ASSUMED HERE FOR ESTIMATING PURPOSES ONLY.
5. POUR CONCRETE FOR BLOCKS AGAINST UNDISTURBED EARTH.
6. DIMENSIONS MAY BE VARIED AS REQUIRED BY FIELD CONDITIONS WHERE AND AS DIRECTED BY THE ENGINEER. THE VOLUME OF CONCRETE BLOCKING SHALL NOT BE LESS THAN SHOWN HERE.
7. THE SOIL BEARING PRESSURES ARE BASED ON 1000 LBS./S.F. IN SOIL AND 2000 LBS./S.F. IN ROCK.
8. USE POLYETHYLENE WRAP OR EQUAL BETWEEN CONCRETE AND BEND, TEE, OR PLUG TO PREVENT THE CONCRETE FROM STICKING TO IT.
9. CONCRETE SHALL NOT EXPAND BEYOND JOINTS.
10. RESTRAINED JOINTS AND/OR THRUST BLOCKING SHALL BE USED TO RESIST THRUST FORCES AT ALL FITTINGS. IF USED IN LIEU OF THRUST BLOCKING, RESTRAINING LENGTH SHALL BE CALCULATED IN ACCORDANCE WITH AWWA M41 FOR DUCTILE IRON PIPES AND AWWA M23 FOR PVC PIPES.
11. IF ADDING ADDITIONAL SACRIFICIAL ANODE DETAIL: SACRIFICIAL ANODES CAN BE ADDED TO FITTINGS AS DIRECTED BY OWNER AND/OR ENGINEER.

THRUST BLOCK

GENERAL NOTES

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

502.4

DATE


AUG '23

STANDARD DRAWING NO.

4040

NOTE:

IN UNPAVED AREAS, INSTALL 2' x 2' x 6" CONCRETE VALVE PAD FLUSH WITH THE TOP OF VALVE BOX. REINFORCE WITH #3 BARS ON 6" CENTERS BOTH WAYS.




GATE VALVE BOX AND
EXTENSION STEM

N.T.S.

GATE VALVE 4" TO 12"
BOX & EXTENSION STEM

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

502.6

DATE
AUG '23

STANDARD DRAWING NO.

4050



PLAN
N.T.S.

STANDARD DRAWING NO.
4060A

VAULT CONSTRUCTION
HORIZONTAL GATE VALVE $\geq 16"$


North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
702.5

DATE
AUG '23


STANDARD DRAWING NO.
4060A



PROFILE
N.T.S.

North Central Texas Council of Governments 	STANDARD SPECIFICATION REFERENCE	
	DATE	702.5
VAULT CONSTRUCTION HORIZONTAL GATE VALVE $\geq 16"$	STANDARD DRAWING NO.	
	AUG '23	4060B

STANDARD DRAWING NO.
4060B



GATE VALVE SIZE	DIMENSION TABLE											
	A	B	C	D	E	F	G	H	J	K	L	M
16"	20"	20"	12"	12"	44 1/2"	1"	48"	12"	10"	24"	12"	16"
18"	20"	20"	12"	12"	51 3/8"	2"	48"	12"	12"	24"	12"	18"
20"	22"	18"	12"	12"	56 5/8"	1"	48"	12"	12"	24"	16"	20"
24"	26"	14"	12"	12"	64 3/8"	1"	60"	18"	14"	30"	18"	24"
30"	28"	12"	12"	12"	80 5/8"	3"	60"	18"	18"	30"	20"	30"
36"	32"	8"	12"	12"	90 1/16"	4"	72"	18"	18"	36"	24"	36"
42"	34"	6"	15"	9"	107 3/4"	5"	84"	24"	20"	36"	30"	42"
48"	36"	4"	14"	10"	121 5/8"	4"	96"	24"	26"	42"	36"	48"
54"	36"	4"	9"	15"	142 1/2"	3"	120"	24"	32"	46"	40"	54"

NOTES:

1. PROVIDE CORPORATION AND CURB STOPS A MAXIMUM OF 12" FROM EACH END OF GATE VALVE, AS SHOWN. CORPORATION AND CURB STOP SIZES SHALL BE 1" FOR 16", 20", AND 24" NOMINAL PIPE DIAMETERS; 2" FOR 30" AND LARGER DIAMETERS. 2" TAPS SHALL BE MADE AS A 2" FLANGED OUTLET WITH INSULATED ADAPTOR KIT. COPPER RISERS SHALL BE PROVIDED BETWEEN THE CORPORATION AND CURB STOPS. CURB STOPS SHALL BE INSTALLED AT AN ELEVATION 12" ABOVE THE TOP SURFACE OF VAULT BOTTOM SLAB.
2. POLYURETHANE CUSHION PAD.
3. STANDARD PRECAST DIMENSIONS MAY BE USED WITH APPROVAL OF THE OWNER AND MAY REQUIRE AN INCREASE IN SIZE TO THE NEXT READILY AVAILABLE PRECAST DIMENSION.

VAULT CONSTRUCTION

VERTICAL GATE VALVE $\geq 16"$

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


702.5

DATE

AUG '23

STANDARD DRAWING NO.

4070A




REFER TO STD. DWG. 4070A FOR DIMENSION TABLE AND GENERAL NOTES.

VAULT CONSTRUCTION

VERTICAL GATE VALVE $\geq 16"$

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


702.5

DATE

AUG '23

STANDARD DRAWING NO.

4070B



PLAN
N.T.S.

STANDARD SPECIFICATION REFERENCE
702.5

DATE
AUG '23

STANDARD DRAWING NO.
4080A


North Central Texas Council of Governments



VAULT CONSTRUCTION

BUTTERFLY VALVE ≥ 48"

STANDARD DRAWING NO.
4080A



PROFILE
N.T.S.

VAULT CONSTRUCTION
BUTTERFLY VALVE $\cong$ 48"

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE
702.5

DATE
AUG '23

STANDARD DRAWING NO.
4080B


STANDARD DRAWING NO.
4080B



COMBINATION AIR VACUUM VALVE		North Central Texas Council of Governments		STANDARD SPECIFICATION REFERENCE	
TYPE "1"				502.6	
				DATE	STANDARD DRAWING NO.
				AUG '23	4090

NOTE:

WHEN NOT IN PAVING OR WALK, A CONCRETE PAD REINFORCED W/ #3 BARS AT 12" C-C EACH WAY, SHALL EXTEND A MINIMUM OF 2' AROUND THE M.H. AND VENT PIPE, AND SHALL BE A MINIMUM OF 4" THICK.



NOTE:

1. ON 4" AND LARGER TWO PIECE COMBINATION AIR VALVES, THE OUTLET PIPING OF THE SMALL VALVE SHALL BE VENTED INTO THE SIDE OF LARGER VENT PIPE THAT GOES ABOVE GROUND.
2. ALTERNATE AWWA APPROVED MATERIAL MAY BE SUBSTITUTED AS APPROVED BY OWNER FOR FITTINGS.


TYPE "2" AIR VALVE

N.T.S.

COMBINATION AIR VACUUM VALVE

TYPE "2"

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


502.6

DATE

AUG '23

STANDARD DRAWING NO.


4100A



AIR VENT

N.T.S.

AIR VALVE	GATE VALVE	FLG. OUTLET	MIN. FITTING HEIGHT	VENT PIPE D	M.H. DIA.
2"	2"	8"	26"	2"	5'
3"	3"	18"	31"	3"	5'
4"	4"	18"	38"	4"	5'
6"	6"	18"	46"	6"	5'
8"	8"	18"	53"	8"	6'
10"	10"	20"	62"	10"	6'
12"	12"	24"	72"	12"	6'




PLAN VIEW

N.T.S.

AIR VENT STANDARD
DIMENSION AND DETAIL

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

502.6

DATE
AUG '23


STANDARD DRAWING NO.
4100B



FLUSH POINT INSTALLATION	STANDARD SPECIFICATION REFERENCE 502.10	
	DATE AUG '23	STANDARD DRAWING NO. 4110
North Central Texas Council of Governments 		
TYPE "1"		

NOTES:

1. IN GENERAL, ALL FIRE HYDRANTS SHALL CONFORM TO AWWA STANDARD SPECIFICATIONS FOR FIRE HYDRANTS FOR ORDINARY WATER WORKS SERVICE, C-502. FIRE HYDRANTS SHALL HAVE A 5 1/4" MIN. VALVE OPENING AND A BARREL APPROXIMATELY 7" INSIDE DIAMETER. ALL HYDRANTS SHALL BE EQUIPPED WITH A BREAKAWAY FLANGE.
2. ALL JOINTS SHOULD BE MECHANICAL WITH PROPERLY DESIGNED JOINT RESTRAINTS AND THRUST BLOCKING AS REQUIRED.
3. TYPICAL VALVE: ACTUAL VALVE LOCATION WILL DEPEND ON LOCATION OF WATER MAIN.
4. F.H. NO CLOSER THAN 18" TO EXISTING OR PROPOSED SIDEWALKS. (USUAL)
5. STANDARD BURY DEPTH 4' FEET
6. SET FIRE HYDRANT ON THE LOT LINE EXTENDED WHEN POSSIBLE.
7. F.H. SHALL BE LOCATED MINIMUM 1 FT. OUTSIDE OF THE AREA BETWEEN THE P.C.'S OF THE CORNER TURNING RADII AT INTERSECTIONS. (SEE PLAN VIEW)
8. PLACEMENT OF F.H. SHALL BE WHERE PUMPER NOZZLE IS PERPENDICULAR TO AND FACING THE NEAREST CURB.



FIRE HYDRANT INSTALLATION

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE
502.3

DATE
AUG '23

STANDARD DRAWING NO.
4120

STANDARD DRAWING NO.
4120



WATER SERVICE INSTALLATION

3/4" OR 1" LINE

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE
502.10

DATE
AUG '23

STANDARD DRAWING NO.
4130

STANDARD DRAWING NO.
4130



NOTE:

1. LOCATION OF METER BOX WITHIN THE AVAILABLE PARKWAY SHALL BE SPECIFIED BY OWNER.
2. IF THE SIDEWALK IS ADJACENT TO THE CURB, THEN THE METER LOCATION IS DETERMINED BY THE OWNER OR UTILITY.

WATER SERVICE INSTALLATION

1 1/2" OR 2" LINE


STANDARD SPECIFICATION REFERENCE
502.10

DATE
AUG '23

STANDARD DRAWING NO.
4140

North Central Texas Council of Governments





PLAN VIEW

4" METER

OUTSIDE OF PAVEMENT AREA,
A CLASS "A" CONCRETE PAD SHALL
BE CONSTRUCTED AND EXTEND
2 FT. AROUND HATCH AND BE
A MINIMUM OF 4 IN. THICK.

3'-0" X 4'-0" ALUMINUM
ACCESS HATCH APPROVED
BY OWNER

EXISTING OR
PROPOSED
PAVEMENT

1/4" PER 1'-0"

SLOPE

#4 BARS AT 12"
C.-C. EACH WAY

CLASS "F" CONCRETE

VALVE
RISER
STACK

VERTICAL FITTINGS
AS NECESSARY TO
MEET CONSTRUCTION
ELEVATION

4'-0" MIN.
5'-0" MAX

1 1/2" P.V.C.
DRAIN PIPE
FROM HATCH
ALONG WALL
TO ROCK
EMBEDMENT

PRECAST METER VAULT
SIZED AS SPECIFIED FOR
EACH METER (SEE STD.
DWG. NO. 4190B).

SEAL OPENINGS AROUND SERVICE
MAIN WITH BRICK AND MORTAR JOINTS.
COAT EXTERIOR BRICK AREA WITH 1/2"
MORTAR COATING.

SEAL JOINT BETWEEN VAULT
AND FLOOR SLAB WITH MASTIC
STRIPS.

DISTRIBUTION
MAIN

SERVICE
MAIN

CAST IN PLACE FLOOR SLAB
OR PRECAST FLOOR SLAB
(SEE STD. DWG. NO. 4190B)

#4 BARS AT 10"
EACH WAY
(CENTERED IN SLAB)

CRUSHED ROCK, STANDARD GRADATION
4" MIN. THICK - IN ROCK
6" MIN. THICK - IN EARTH

- NOTES:
1. ALL BURIED TEES AND BENDS
SHALL BE THRUST BLOCKED
PER STANDARD DRAWINGS 4010-4040.
 2. ALL BURIED D.I. PIPE AND C.I. FITTINGS
SHALL BE POLY-WRAPPED AS SPECIFIED
FOR THE ADJECENT DISTRIBUTION MAIN.

ELEVATION VIEW

(D.C. METER SHOWN) N.T.S.

LARGE SERVICE METER

VAULT INSTALLATION

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

702.5



DATE

AUG '23

STANDARD DRAWING NO.


4190A

STANDARD DRAWING NO. 4190A



LARGE SERVICE METER PRECAST VAULT

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


702.5

DATE

AUG '23

STANDARD DRAWING NO.

4190B



NOTES:

1. IF THE WATER MAIN IS BEING LOWERED UNDER WASTEWATER, THEN IT MUST COMPLY WITH TCEQ REQUIREMENTS

WATER MAIN LOWERING

BELOW STORMWATER MAIN

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE
506

DATE
AUG '23


STANDARD DRAWING NO.
4200

DIVISION 5000 WASTEWATER COLLECTION**TABLE OF CONTENTS**


<u>Drawing #</u>	<u>Subject</u>	<u>Section I: Item #</u>
<u>5010</u>	<u>Wastewater Main Tie-In</u> <u>At Cleanout or M.H. Stubout</u>	502.10
<u>5020</u>	<u>Wastewater Manhole</u> <u>Precast</u>	502.1
<u>5030</u>	<u>Wastewater Manhole</u> <u>Cast-In-Place</u>	502.1
<u>5040</u>	<u>Wastewater Manhole</u> Fiberglass	502.1
<u>5050</u>	<u>Wastewater Manhole</u> <u>Pressure-Type</u>	502.1
<u>5060</u>	<u>Wastewater Manhole</u> <u>Vented</u>	502.1
<u>5070</u>	<u>Wastewater Manhole</u> <u>Outside Drop Connections</u>	502.1
<u>5080</u>	<u>Wastewater Manhole</u> <u>Inside Drop Connection</u>	502.1
<u>5090</u>	<u>Wastewater Manhole</u> <u>Invert Detail</u>	502.1
<u>5100</u>	<u>Wastewater Access</u> <u>Device</u>	502.1
<u>5110</u>	<u>Wastewater Main</u> <u>Cleanout</u>	502.2
<u>5120</u>	<u>Wastewater Laterals</u> <u>With & Without Cleanout</u>	502.10
<u>5130</u>	<u>Wastewater Lateral</u> <u>Connections</u> In Earth & In Rock	502.10
<u>5140</u>	<u>Wastewater Lateral Cleanout</u> <u>Frame & Cover</u>	502.10
<u>5170</u>	<u>Abandonment of Manhole</u> <u>In or Out of Pavement</u>	504



AT STUBOUT
N.T.S.



AT CLEANOUT
N.T.S.




"C-T" PIPE ADAPTER
N.T.S.

NOTE:

THIS DETAIL FOR USE ONLY WHEN NEW MAIN WILL NOT MATE WITH EXISTING MAIN JOINT DUE TO DIFFERENT DIMENSIONS OR MATERIALS AND A MANHOLE IS NOT REQUIRED.

WASTEWATER MAIN TIE-IN
AT CLEANOUT OR M.H. STUBOUT

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


502.10

DATE

AUG '23

STANDARD DRAWING NO.

5010



WASTEWATER MANHOLE PRECAST

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

502.1





DATE

AUG '23

STANDARD DRAWING NO.

5020



FRAME CAST IN CONC.



TRANSITION DETAIL FOR
5' & 6' DIA. M.H.'S

NOTES:

1. WHERE M.H.'S ARE IN "PROPOSED" PAVING, FRAME & COVER SHALL BE SET 18" MAX BELOW TOP OF PAVEMENT OR AS REQUIRED TO CONSTRUCT PAVEMENT SECTION, INCLUDING SUBGRADE.
2. WHERE M.H.'S ARE OUTSIDE OF PAVEMENT, FRAME & COVER SHALL BE CENTERED IN 5'X5' CONCRETE PAD CLASS "A" CONCRETE, 4" THICK
3. POLY WRAP AROUND MANHOLE OR JUST CONE AND RISER SECTION; AND/OR A CHIMNEY SEAL INSIDE THE RISER. A RAIN PAN COULD BE INSIDE THE MANHOLE COVER.




STUBOUT CONNECTION

WASTEWATER MANHOLE CAST-IN-PLACE

North Central Texas Council of Governments





FIRST MAIN LINE JOINT TO BE A MIN. OF-
OF 5' LONG WITH CONC. CRADLE (FROM
SAME POUR AS BASE) UNDER THE
ENTIRE LENGTH

1. CONCRETE BASE TO BE POURED IN - PLACE IN TRENCH.
2. M.H. CUT-OUT TO BE MADE AT TIME OF INSTALLATION.
3. M.H. TO BE INSTALLED BY INSERTING INTO WET CONCRETE BASE.
4. FUTURE CONNECTIONS, IF A SEALANT BETWEEN PIPE & M.H. IS NEEDED, USE APPROVED SILICONE SEALANT.
5. FIBERGLASS IS JUST ONE EXAMPLE OF AN ALTERNATIVE MATERIAL. OTHER MATERIALS COULD BE USED, PER APPROVAL BY CITY ENGINEER.

WASTEWATER MANHOLE FIBERGLASS

STANDARD SPECIFICATION REFERENCE
502.1


DATE AUG '23	STANDARD DRAWING NO. 5040

North Central Texas Council of Governments




STANDARD DRAWING NO.
5040

N.T.S.



SECTION A - A

N.T.S.



North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


502.1

DATE _____

AUG '23

STANDARD DRAWING NO.

5050




NOTES:

1. ELEVATE TOP OF VENT MIN. 1' ABOVE 100-YEAR FLOOD ELEVATION.
2. FRAME AND COVER SHALL BE BOLTED.

WASTEWATER MANHOLE
VENTED

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

502.1

DATE

AUG '23

STANDARD DRAWING NO.

5060

GAS SEALED
DROP CONNECTION
N.T.S.

STANDARD
DROP CONNECTION
N.T.S.

SEE DETAIL 5020/5030
FOR BARREL AND CONE

REVERSE 45°
WYE ONLY

REVERSE 45°
WYE ONLY

45° BEND

CAPPED
GAS TIGHT
(6" NONSHRINK
GROUT PLUG)

MIN. 1"
(SEE
NOTE 1)

45° BEND

6" MIN.

VARIABLE 2' MIN.

6" MIN.

CLASS "F"
CONCRETE

CLASS "F"
CONCRETE

4" MIN.

90° LONG
RADIUS BEND

CLASS "F" CONCRETE
BASE 12" THICK

90° LONG
RADIUS BEND

12" MIN.

12" MIN.

ROCK FOUNDATION


GEOTEXTILE
MATERIAL

NOTE:

1. EXTEND INWARD & CUT-OFF TOP FOR EASE OF
CAMERA ACCESS AS REQUESTED BY OWNER

WASTEWATER MANHOLE
OUTSIDE DROP CONNECTIONS

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


502.1

DATE

AUG '23

STANDARD DRAWING NO.

5070




ELEVATION
N.T.S.

PLAN
N.T.S.

NOTE:

1. FLOW LINE OF SURCHARGE LINE NORMALLY PLACED AT TOP OF EXISTING WASTEWATER LINE UNLESS NOTED OTHERWISE ON PLANS.
2. MAXIMUM SPACING OF 4' ON PIPE STRAPS. 2 STRAPS MINIMUM. ALL STRAP PARTS SHALL BE STAINLESS STEEL.

REMOVE PORTION OF DROP PIPE TO CONNECT AS SHOWN



WEIR DETAIL
N.T.S.

WASTEWATER MANHOLE

INSIDE DROP CONNECTION

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


502.1

DATE

AUG '23

STANDARD DRAWING NO.


5080



PLAN
N.T.S.

T = WALL THICKNESS
D = MANHOLE DIAMETER
d = PIPE DIAMETER


NOTE:
REFER TO MANHOLE
STANDARD DRAWINGS
FOR ADDITIONAL
DETAIL OF M.H.



SECTION A-A
N.T.S.

WASTEWATER MANHOLE INVERT DETAIL

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

502.1


DATE
AUG '23

STANDARD DRAWING NO.
5090



WASTEWATER ACCESS DEVICE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

502.1


DATE

AUG '23

STANDARD DRAWING NO.

5100

H'	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	H'
Y'	10	12	14	17	19	22	24	27	29	31	34	36	39	41	43	46	48	Y'



SECTION "X - X"

N.T.S.

PROFILE VIEW

N.T.S.


- NOTES:
1. IF CLEANOUT IS PLACED IN ADVANCE OF PAVEMENT PLACE SAND AROUND CLEANOUT CASTING IN LIEU OF CLASS "B" CONCRETE.
 2. IF CLEANOUT IS OUTSIDE OF PAVEMENT, CENTER CASTING IN 15"x15" CLASS "A" CONCRETE PAD "4" THICK.
 3. ONLY TO BE USED WITH EXPRESS CONSENT OF THE OWNER.

STANDARD SPECIFICATION REFERENCE		502.2	
North Central Texas Council of Governments		DATE	
WASTEWATER MAIN		AUG '23	
CLEANOUT		STANDARD DRAWING NO.	
		5110	



- ① WASTEWATER MAIN
- ② 4" WYE OR TAP
- ③ 4" WASTEWATER LAT. (LENGTH VARIES)
- ④ 4" X 4" TEE OR WYE AS REQ'D. BY OWNER.
- ⑤ 4" STACK (LENGTH VARIES)
- ⑥ 4" WASTEWATER LAT. CLEANOUT CASTING

- ⑦ 4" WASTEWATER PIPE (LENGTH VARIES)
- ⑧ ADAPTOR
- ⑨ BUILDING SEWER LAT.
- ⑩ CLASS "B" CONCRETE
- ⑪ COMPACTED AS SPECIFIED,
OR INUNDATED SAND



1. CLEANOUT CASTING TO BE FURNISHED AND PLACED PER SPECIAL CONDITIONS, IN VEHICLE TRAFFIC AREAS AND FOR COMMERCIAL MAINLINE LATERALS, WASTEWATER CLEANOUT SHALL BE OF CAST IRON.
2. SLOPE OF LATERAL TO BE 2% MIN., UNLESS INSTRUCTED OTHERWISE BY OWNER.
3. THE WASTEWATER LATERAL SHALL BE CONNECTED TO BUILDING LATERAL AND CONSTRUCTED IN SUCH MANNER AS TO CLEAR EXISTING UTILITIES AND PROPOSED FACILITIES SUCH AS STORM SEWER MAINS, PAVING, SIDEWALKS, RETAINING WALLS, ETC. VERTICAL BENDS (22.5° MAX.) MAY BE USED IF APPROVED BY OWNER.
4. EXTEND TRACER WIRE TO JUST ABOVE CLEANOUT PLUG, PROVIDE 24' NEATLY COILED WIRE IN BOX


5. THE MAINLINE LATERAL LATERAL CONNECTION TO THE PRIVATE BUILDING LATERAL SHALL BE AS CLOSE TO THE PROPERTY LINE AS POSSIBLE.
6. INSTALL 4" STOPPER OR CAP AT PROPERTY LINE IF BUILDING LATERAL DOES NOT EXIST.
7. SUBSTITUTE 4" FOR 6" FITTINGS IF PLANS OR SPEC. COND. CALL FOR 4" LATERAL DOES NOT EXIST.
8. THE CLEANOUT STACK & CASTING MAY BE PLACED IN THE PARKWAY, VEHICLE TRAFFIC AREAS, OR SIDEWALK, IF NECESSARY.
9. FOR 6" SERVICES OR LARGER, INSTALL A MANHOLE.
10. MINIMUM 9' SEPARATION FROM WATER SERVICE.

WITH & WITHOUT CLEANOUT

502.10

AUG '23

5120



TRENCH WITH SLOPING SIDES


N.T.S.

NOTES:

1. WYE SHALL BE SUPPORTED AS SHOWN FOR WYE CONNECTION SUPPORT.
2. LATERALS ARE TO CLEAR ALL EXISTING UTILITIES. 11 1/4" OR 22 1/2" BEND, ONLY, MAY BE REQUIRED.

WASTEWATER LATERAL CONNECTIONS
IN EARTH & IN ROCK

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE




502.10

DATE
AUG '23

STANDARD DRAWING NO.
5130




COVER
N.T.S.





CLEANOUT FRAME BOTTOM
N.T.S.

NOTES:

1. THE WORDS "WASTEWATER LATERAL CLEANOUT" SHALL BE CAST INTO TOP OF COVER.
2. MATERIALS TO BE CAST IRON, P.V.C. OR ABS PLASTIC.



CLEANOUT FRAME TOP
N.T.S.



ASSEMBLY VIEW
N.T.S.

WASTEWATER LATERAL
CLEANOUT FRAME & COVER

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

502.10

DATE
AUG '23


STANDARD DRAWING NO.

5140



ABANDONMENT OF MANHOLE IN OR OUT OF PAVEMENT

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

504

DATE
AUG '23

STANDARD DRAWING NO.


5170

DIVISION 6000 STORMWATER DRAINAGE**TABLE OF CONTENTS**

<i><u>Drawing #</u></i>	<i><u>Subject</u></i>	<i><u>Section I: Item #</u></i>
<u>6010A</u>	<u>Storm Water Manhole</u> <u>4', 5', or 6' Square</u>	502.1.4.1
<u>6010B</u>	<u>Storm Water Manhole</u> <u>4', 5', or 6' Square</u>	502.1.4.1
<u>6020A</u>	<u>Curb Inlet</u> <u>5', 10', 15' or 20' Opening</u>	702
<u>6020B</u>	<u>Curb Inlet</u> <u>Cross Section & Inlet throat</u>	702
<u>6020C</u>	<u>Curb Inlet</u> <u>Rebar</u>	702
<u>6020D</u>	<u>Curb Inlet</u> <u>Bill of Reinforcing Steel</u>	702
<u>6020E</u>	<u>Curb Inlet</u> <u>Summary of Quantities</u>	702
<u>6030A</u>	<u>Curb Inlet Recessed</u> <u>5', 10', 15', or 20' Opening</u>	702
<u>6030B</u>	<u>Curb Inlet Recessed</u> <u>Cross Section & Center Beam</u>	702
<u>6030C</u>	<u>Curb Inlet Recessed</u> <u>Inlet Throat</u>	702
<u>6030D</u>	<u>Curb Inlet Recessed General</u> <u>Notes</u>	702
<u>6030E</u>	<u>Curb Inlet Recessed</u> <u>Rebar</u>	702
<u>6030F</u>	<u>Curb Inlet Recessed</u> <u>Bill of Reinforcing Steel</u>	702
<u>6030G</u>	<u>Curb Inlet Recessed</u> <u>Summary of Quantities</u>	702
<u>6040</u>	<u>Drop Inlet</u> <u>2', 4', 5', or 6' Square</u>	702

<u>6050</u>	<u>Low Flow Channel Lining</u> <u>Concrete Reinforced</u>	803.3
<u>6060</u>	<u>Concrete Apron</u> <u>Vertical Headwall</u>	803.3
<u>6070</u>	<u>Concrete Apron</u> <u>Sloping Headwall</u>	803.3
<u>6080</u>	<u>Storm Drain Pipe Collar for Field Connection</u>	501, 702.
<u>6090</u>	<u>Subdrains</u> <u>Pavement Subgrade</u>	301

Note: Drawings of other types of inlet structures are not included in this division but may be utilized if they are of a design by an engineer and approved at the discretion of the owner.




PLAN

N.T.S

M.H. SIZE (W)	V	T	E	F	G	H
4'-0"	5'-4"	0'-8"	0'-6"	1'-6"	0'-6"	2'-0"
5'-0"	6'-4"	0'-8"	0'-6"	1'-6"	0'-8"	2'-2"
6'-0"	7'-6"	0'-9"	0'-9"	1'-6"	0'-10"	2'-4"

TABLE OF DIMENSIONS

N.T.S




SECTION B-B

N.T.S

STORM WATER MANHOLE

4', 5', OR 6' SQUARE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


502.1.4.1

DATE


AUG '23

STANDARD DRAWING NO.

6010A



*REFERENCE TABLE 6010A



NOTES:

1. SLOPE INVERT OF MANHOLE AS INDICATED ON PLAN-PROFILE SHEET.
2. LAYERS OF REINFORCING STEEL NEAREST THE INTERIOR AND EXTERIOR SURFACE SHALL HAVE A COVER OF 2" CLEAR OF BARS, UNLESS OTHERWISE NOTED.
3. CONCRETE SHALL BE CLASS "C".
4. PRECAST PRODUCTS MAY BE USED AT THE APPROVAL OF THE OWNER.

STORM WATER MANHOLE
4', 5', OR 6' SQUARE

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


502.1.4.1

DATE
AUG '23

STANDARD DRAWING NO.
6010B



N.T.S.	CURB INLET	North Central Texas Council of Governments	STANDARD SPECIFICATION REFERENCE	
			702	
			DATE	STANDARD DRAWING NO.
6020A	5', 10', 15' OR 20' OPENING		AUG '23	6020A



SECTION "A-A"


GENERAL NOTES:
N.T.S.

1. ALL CONCRETE SHALL BE CLASS "C" CONCRETE.
2. REINFORCING BARS SHALL BE STANDARD GRADE STEEL, DEFORMED REINFORCING BARS OF A DIAMETER AND LENGTH AS SHOWN.
3. CHAMFER ALL EXPOSED CORNERS 3/4" EXCEPT WHERE OTHERWISE NOTED.
4. DIMENSIONS RELATING TO REINFORCING STEEL ARE TO OUTSIDE EDGE OF BARS.
5. FIELD CUT AND BEND BARS AS NECESSARY TO ACCOMMODATE STORM SEWER PIPE.
6. RING AND COVER SHALL BE APPROVED BY THE OWNER AND INSTALLED BY THE CONTRACTOR.
7. INLET OPENING SHALL BE 6" MIN. OR 8" MAX.
8. PRECAST PRODUCT MAY BE USED AT THE APPROVAL OF THE OWNER.


SECTION "X-X"

N.T.S.

9. ALLOW 1" MIN. CLEAR SPACE BETWEEN OD OF PIPE OR BOX AND INSIDE WALL OF INLET (OD OF PIPE OR BOX SHOULD ACCOUNT FOR SKEWED CONDITIONS).
10. DEPTHS GREATER THAN 10' NEED TO BE STRUCTURALLY ENGINEERED.
11. KEYWAY JOINT TO BE MIN. 18" ABOVE FLOWLINE, UNLESS APPROVED BY ENGINEER.



#4 BARS A
N.T.S.




#4 BARS B
N.T.S.




#4 BARS C & D
N.T.S.




#4 BARS E
N.T.S.




#4 BARS F
N.T.S.




#4 BARS G
N.T.S.



#4 BARS J
N.T.S.



#3 BARS M
N.T.S.



#5 BARS N
N.T.S.



BILL OF REINFORCING STEEL

DEPTH "D"	ALL WIDTHS AND LENGTHS		OPENING LENGTH "L" = 5ft			OPENING LENGTH "L" = 10ft			OPENING LENGTH "L" = 15 ft			OPENING LENGTH "L" = 20 ft		
			Widths "W"			Widths "W"			Widths "W"			Widths "W"		
			3ft	4ft	5ft	3ft	4ft	5ft	3ft	4ft	5ft	3ft	4ft	5ft
	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS
	C	D	E	J	F	F	F	F	F	F	F	F	F	F
3'-6"	17	3	2	4	20	24	28	10	10	20	28	32	36	18
3'-9"	18	"	"	"	"	"	"	"	"	20	"	"	"	"
4'-0"	19	"	"	"	"	"	"	"	"	24	"	"	"	"
4'-3"	19	"	"	"	"	"	"	"	"	24	"	"	"	"
4'-6"	21	"	"	"	"	"	"	"	"	26	"	"	"	"
4'-9"	21	"	"	"	"	"	"	"	"	26	"	"	"	"
5'-0"	21	"	"	"	"	"	"	"	"	26	"	"	"	"
5'-3"	23	"	"	"	"	"	"	"	"	28	"	"	"	"
5'-6"	23	"	"	"	"	"	"	"	"	28	"	"	"	"
5'-9"	25	"	"	"	"	"	"	"	"	30	"	"	"	"
6'-0"	25	"	"	"	"	"	"	"	"	30	"	"	"	"
6'-3"	26	"	"	"	"	"	"	"	"	30	"	"	"	"
6'-6"	27	"	"	"	"	"	"	"	"	32	"	"	"	"
6'-9"	27	"	"	"	"	"	"	"	"	32	"	"	"	"
7'-0"	29	"	"	"	"	"	"	"	"	34	"	"	"	"
7'-3"	29	"	"	"	"	"	"	"	"	34	"	"	"	"
7'-6"	30	"	"	"	"	"	"	"	"	34	"	"	"	"
7'-9"	31	"	"	"	"	"	"	"	"	36	"	"	"	"
8'-0"	31	"	"	"	"	"	"	"	"	36	"	"	"	"
8'-3"	32	"	"	"	"	"	"	"	"	36	"	"	"	"
8'-6"	33	"	"	"	"	"	"	"	"	38	"	"	"	"
8'-9"	34	"	"	"	"	"	"	"	"	38	"	"	"	"
9'-0"	35	"	"	"	"	"	"	"	"	40	"	"	"	"
9'-3"	36	"	"	"	"	"	"	"	"	40	"	"	"	"
9'-6"	37	"	"	"	"	"	"	"	"	42	"	"	"	"
10'-0"	38	"	"	"	"	"	"	"	"	42	"	"	"	"

NOTES:

- FOR CONVENIENCE, DEPTHS OF INLETS SHOWN IN ABOVE TABLES ARE IN INCREMENTS OF 3 INCHES BUT ANY DEPTHS OTHER THAN THOSE SHOWN ABOVE MAY BE USED WHEREVER DEEMED NECESSARY. QUANTITIES FOR OTHER DEPTHS FALLING WITHIN THE LIMITS OF THE TABLE MAY BE FOUND BY INTERPOLATION.
- DEPTHS GREATER THAN 10' NEED TO BE STRUCTURALLY ENGINEERED.

STANDARD DRAWING NO.
6020D

North Central Texas Council of Governments



CURB INLET

BILL OF REINFORCING STEEL

STANDARD SPECIFICATION REFERENCE
702

DATE
AUG '23

STANDARD DRAWING NO.
6020D

SUMMARY OF QUANTITIES FOR CURB INLETS

DEPTH "D"	5'-0" OPENING						10'-0" OPENING						15'-0" OPENING						20'-0" OPENING					
	WIDTH 3'-0"		WIDTH 4'-0"		WIDTH 5'-0"		WIDTH 3'-0"		WIDTH 4'-0"		WIDTH 5'-0"		WIDTH 3'-0"		WIDTH 4'-0"		WIDTH 5'-0"		WIDTH 3'-0"		WIDTH 4'-0"		WIDTH 5'-0"	
	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.
3'-6"	2.62	306	2.95	332	3.28	373	4.12	479	4.64	521	5.20	564	5.69	667	6.40	721	7.10	775	7.20	846	8.11	909	9.03	976
3'-9"	2.70	309	3.04	341	3.39	373	4.25	494	4.78	536	5.34	579	5.87	687	6.58	741	7.30	796	7.42	874	8.34	937	9.27	1010
4'-0"	2.78	328	3.14	364	3.49	399	4.38	518	4.92	565	5.49	610	6.05	718	6.77	776	7.49	835	7.64	909	8.58	976	9.51	1046
4'-3"	2.87	334	3.23	370	3.59	406	4.51	526	5.06	573	5.64	619	6.22	729	6.95	787	7.69	847	7.87	922	8.81	990	9.75	1061
4'-6"	2.95	356	3.32	394	3.69	431	4.64	558	5.20	607	5.79	656	6.40	770	7.14	830	7.88	891	8.09	973	9.04	1043	9.99	1115
4'-9"	3.03	361	3.41	410	3.79	438	4.77	566	5.34	616	5.94	665	6.57	780	7.32	841	8.07	903	8.31	986	9.27	1056	10.23	1129
5'-0"	3.12	367	3.51	416	3.90	445	4.90	574	5.47	624	6.09	674	6.75	791	7.51	853	8.27	915	8.53	999	9.50	1070	10.47	1144
5'-3"	3.20	383	3.60	424	4.00	465	5.03	600	5.61	652	6.23	704	6.93	827	7.69	890	8.46	955	8.76	1044	9.73	1118	10.71	1194
5'-6"	3.28	389	3.69	430	4.10	472	5.16	608	5.75	661	6.38	713	7.11	837	7.88	901	8.66	967	8.98	1057	9.97	1131	10.95	1208
5'-9"	3.37	405	3.78	451	4.20	495	5.29	635	5.89	690	6.53	744	7.28	874	8.07	940	8.85	1007	9.20	1102	10.20	1178	11.19	1258
6'-0"	3.45	415	3.88	460	4.30	504	5.42	646	6.03	702	6.68	757	7.45	888	8.25	954	9.05	1022	9.42	1119	10.43	1196	11.43	1276
6'-3"	3.53	425	3.97	470	4.41	515	5.55	661	6.17	718	6.83	773	7.63	908	8.44	975	9.24	1044	9.64	1147	10.66	1223	11.67	1305
6'-6"	3.62	437	4.06	486	4.51	532	5.68	681	6.31	739	6.97	797	7.81	935	8.62	1005	9.43	1057	9.87	1178	10.89	1258	11.92	1340
6'-9"	3.70	441	4.15	490	4.61	537	5.81	688	6.45	747	7.12	806	7.98	945	8.81	1015	9.63	1066	10.09	1191	11.12	1272	12.15	1355
7'-0"	3.78	460	4.25	510	4.71	560	5.94	716	6.59	777	7.27	837	8.16	981	8.99	1053	9.82	1126	10.31	1237	11.35	1319	12.40	1404
7'-3"	3.86	465	4.34	516	4.81	567	6.07	724	6.72	785	7.42	846	8.33	992	9.18	1065	10.02	1138	10.53	1249	11.59	1333	12.64	1418
7'-6"	3.95	477	4.43	529	4.91	570	6.20	742	6.86	804	7.57	866	8.51	1016	9.36	1089	10.21	1163	10.75	1290	11.82	1365	12.88	1451
7'-9"	4.03	491	4.53	544	5.02	597	6.33	762	7.00	826	7.71	890	8.67	1040	9.55	1116	10.41	1193	10.98	1313	12.05	1399	13.12	1498
8'-0"	4.12	496	4.62	550	5.12	604	6.46	770	7.14	834	7.86	899	8.86	1051	9.73	1129	10.60	1205	11.20	1325	12.28	1412	13.36	1510
8'-3"	4.20	504	4.71	559	5.22	613	6.59	784	7.28	849	8.01	915	9.04	1069	9.92	1149	10.80	1228	11.42	1353	12.51	1440	13.60	1529
8'-6"	4.28	519	4.80	576	5.32	632	6.71	804	7.42	871	8.16	938	9.21	1107	10.10	1176	10.99	1257	11.64	1385	12.74	1474	13.84	1565
8'-9"	4.37	528	4.90	586	5.42	643	6.84	819	7.56	886	8.31	954	9.39	1119	10.29	1199	11.18	1280	11.87	1410	12.97	1500	14.08	1592
9'-0"	4.45	545	4.99	605	5.53	664	6.97	842	7.70	912	8.46	982	9.56	1148	10.47	1231	11.38	1313	12.09	1447	13.21	1539	14.32	1631
9'-3"	4.53	554	5.08	614	5.63	674	7.10	858	7.84	929	8.60	999	9.74	1169	10.66	1252	11.57	1335	12.31	1474	13.44	1563	14.56	1660
9'-6"	4.62	568	5.17	630	5.73	692	7.23	878	7.97	950	8.75	1022	9.92	1195	10.84	1280	11.77	1365	12.53	1505	13.67	1600	14.80	1696
10'-0"	4.78	582	5.36	645	5.93	708	7.49	900	8.11	974	9.05	1048	10.27	1227	11.21	1312	12.16	1399	12.98	1546	14.13	1642	15.29	1739

NOTE:

- FOR CONVENIENCE, DEPTHS OF INLETS SHOWN IN ABOVE TABLES ARE IN INCREMENTS OF 3 INCHES BUT ANY DEPTHS OTHER THAN THOSE SHOWN ABOVE MAY BE USED WHEREVER DEEMED NECESSARY. QUANTITIES FOR OTHER DEPTHS FALLING WITHIN THE LIMITS OF THE TABLE MAY BE FOUND BY INTERPOLATION.
- DEPTHS GREATER THAN 10' NEED TO BE STRUCTURALLY ENGINEERED.

CURB INLET

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

702

DATE

AUG '23


SUMMARY OF QUANTITIES

STANDARD DRAWING NO.

6020E

NOTE:

FIELD CUT BARS B & C TO
CLEAR MANHOLE.



NOTES:

1. LOCATION OF ACCESS OPENING TO BE AT OUTFALL END, UNLESS OTHERWISE DIRECTED BY THE OWNER.
2. IF INLET OPENING IS OVER 10' WIDTH, THEN THERE SHALL BE A MANHOLE OPENING AT EACH END OF INLET.

STANDARD DRAWING NO.
6030A

CURB INLET RECESSED


5', 10', 15' OR 20' OPENING

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
702

DATE
AUG '23
STANDARD DRAWING NO.
6030A



15' AND 20' INLETS

N.T.S.

CURB INLET RECESSED

CROSS SECTION & CENTER BEAM

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

702


DATE _____

AUG '23

STANDARD DRAWING NO.

5030B

STANDARD DRAWING NO.
6030B



CURB INLET RECESSED

INLET THROAT

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

DATE AUG '23	STANDARD DRAWING NO. 6030C

GENERAL NOTES:

1. ALL REINFORCING STEEL SHALL BE GRADE 60. DEFORMED REINFORCING BARS AT A DIAMETER & LENGTH AS SHOWN.
2. ALL CONCRETE SHALL BE CLASS "C". ALL EXPOSED CORNERS SHALL BE CHAMFERED 3/4".
3. ALL REINFORCING STEEL SHALL HAVE A MINIMUM COVER OF 2" CLEAR OF THE BARS.
4. 10'-0" OF EXISTING CURB AND GUTTER UPSTREAM AND 10'-0" OF EXISTING CURB AND GUTTER DOWNSTREAM SHALL BE REMOVED AND REPOURED INTEGRALLY WITH EACH INLET.
5. ALL BACK FILLING SHALL BE PERFORMED BY MECHANICAL TAMPING TO 95% STANDARD PROCTOR DENSITY.
6. PRECAST PRODUCTS MAY BE USED AT THE APPROVAL OF THE OWNER.
7. ALLOW 1" MIN. CLEAR SPACE BETWEEN OD OF PIPE OR BOX AND INSIDE WALL OF INLET (OD OF PIPE OR BOX SHOULD ACCOUNT FOR SKEWED CONDITIONS).
8. FIELD CUT & BEND BARS AS NECESSARY TO ACCOMODATE STORM SEWER PIPE.
9. RING & COVER SHALL BE APPROVED BY THE OWNER AND INSTALLED BT CONTRACTOR.
10. WHEN POURING INVERTS, THE BOTTOM SHALL BE SLOPED NO MORE THAN 1/4"/FT TOWARD PIPE.
11. INLET OPENING SHALL BE 6" MIN OR 8" MAX.
12. 10 FT. MAX DEPTH.

STANDARD DRAWING NO.
6030D

CURB INLET RECESSED

GENERAL NOTES


North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE
702

DATE
AUG '23

STANDARD DRAWING NO.
6030D



#4 BARS A
N.T.S.



#4 BARS B
N.T.S.


FIELD CUT D BARS
AS NECESSARY AT
TRANSITIONS




#4 BARS C & D
N.T.S.




#4 BARS E
N.T.S.




#4 BARS F
N.T.S.




#4 BARS G
N.T.S.



#4 BARS J
N.T.S.



#3 BARS M
N.T.S.



#5 BARS N
N.T.S.

CURB INLET RECESSED

REBAR



BILL OF REINFORCING STEEL

DEPTH "D"	ALL WIDTHS AND LENGTHS				OPENING LENGTH "L" = 5ft						OPENING LENGTH "L" = 10ft						OPENING LENGTH "L" = 15 ft						OPENING LENGTH "L" = 20 ft																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
					Widths "W"						Widths "W"						Widths "W"						Widths "W"																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
					3ft		4ft		5ft		3ft		4ft		5ft		3ft		4ft		5ft		3ft		4ft		5ft																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
	BARS	C	D	E	J	F	F	A	B	G	BARS	BARS	BARS	BARS	BARS	F	F	F	A	B	G	BARS	BARS	BARS	BARS	BARS	F	F	F	A	B	G	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS	BARS

NOTE:

- FOR CONVENIENCE, DEPTHS OF INLETS SHOWN IN ABOVE TABLES ARE IN INCREMENTS OF 3 INCHES BUT ANY DEPTHS OTHER THAN THOSE SHOWN ABOVE MAY BE USED WHEREVER DEEMED NECESSARY. QUANTITIES FOR OTHER DEPTHS FALLING WITHIN THE LIMITS OF THE TABLE MAY BE FOUND BY INTERPOLATION.
- DEPTHS GREATER THAN 10' NEED TO BE STRUCTURALLY ENGINEERED.

CURB INLET RECESSED

BILL OF REINFORCING STEEL

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE
702

DATE
AUG '23

STANDARD DRAWING NO.
6030F

SUMMARY OF QUANTITIES FOR CURB INLETS

DEPTH "D"	5'-0" OPENING						10'-0" OPENING						15'-0" OPENING						20'-0" OPENING					
	WIDTH 3'-0"		WIDTH 4'-0"		WIDTH 5'-0"		WIDTH 3'-0"		WIDTH 4'-0"		WIDTH 5'-0"		WIDTH 3'-0"		WIDTH 4'-0"		WIDTH 5'-0"		WIDTH 3'-0"		WIDTH 4'-0"		WIDTH 5'-0"	
	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.	CONC C.Y.	STEEL LBS.
3'-6"	2.87	324	3.23	357	3.59	390	4.41	496	4.95	540	5.50	584	5.94	684	6.67	742	7.40	799	7.48	858	8.40	926	9.31	995
3'-9"	2.96	333	3.32	367	3.69	401	4.54	512	5.09	556	5.64	601	6.12	706	6.86	764	7.60	822	7.70	886	8.63	955	9.55	1024
4'-0"	3.04	353	3.42	390	3.79	428	4.66	537	5.23	585	5.79	633	6.29	737	7.04	799	7.79	861	7.92	923	8.86	996	9.79	1068
4'-3"	3.12	358	3.51	396	3.89	434	4.79	545	5.37	594	5.94	643	6.47	748	7.23	811	7.99	873	8.14	937	9.09	1010	10.03	1083
4'-6"	3.21	376	3.60	417	4.00	457	4.92	573	5.51	624	6.09	675	6.64	786	7.41	850	8.18	915	8.36	984	9.32	1059	10.27	1134
4'-9"	3.29	382	3.69	423	4.10	464	5.05	581	5.65	633	6.24	684	6.82	796	7.60	862	8.37	927	8.59	997	9.55	1073	10.51	1149
5'-0"	3.37	387	3.79	429	4.20	471	5.18	589	5.79	641	6.38	693	7.00	807	7.78	873	8.57	939	8.81	1011	9.78	1087	10.75	1164
5'-3"	3.46	406	3.88	450	4.30	493	5.31	617	5.92	671	6.53	725	7.17	845	7.97	912	8.76	980	9.03	1057	10.02	1136	10.99	1215
5'-6"	3.54	411	3.97	456	4.40	500	5.44	625	6.06	680	6.68	735	7.35	855	8.15	924	8.96	992	9.25	1071	10.25	1150	11.23	1229
5'-9"	3.62	429	4.06	476	4.50	523	5.57	653	6.20	710	6.83	767	7.52	893	8.34	963	9.15	1034	9.48	1118	10.48	1199	11.48	1280
6'-0"	3.71	435	4.16	482	4.61	530	5.70	661	6.34	719	6.98	776	7.70	903	8.53	975	9.35	1046	9.70	1131	10.71	1213	11.72	1295
6'-3"	3.79	444	4.25	492	4.71	540	5.83	676	6.48	735	7.12	793	7.88	925	8.71	997	9.54	1069	9.92	1159	10.94	1242	11.96	1324
6'-6"	3.87	459	4.34	509	4.81	559	5.96	697	6.62	757	7.27	818	8.05	952	8.90	1026	9.74	1100	10.14	1191	11.17	1276	12.20	1361
6'-9"	3.96	464	4.43	515	4.91	566	6.09	705	6.76	766	7.42	827	8.23	962	9.08	1037	9.93	1112	10.36	1205	11.40	1290	12.44	1376
7'-0"	4.04	482	4.53	536	5.01	589	6.22	733	6.90	796	7.57	859	8.40	1000	9.27	1077	10.12	1154	10.59	1252	11.64	1339	12.68	1427
7'-3"	4.12	488	4.62	542	5.12	595	6.35	741	7.04	805	7.72	869	8.58	1010	9.45	1088	10.32	1166	10.81	1265	11.87	1353	12.92	1442
7'-6"	4.21	497	4.71	552	5.22	606	6.48	756	7.17	821	7.87	885	8.76	1032	9.64	1110	10.51	1189	11.03	1293	12.10	1382	13.16	1471
7'-9"	4.29	512	4.80	568	5.32	625	6.61	777	7.31	843	8.01	910	8.93	1059	9.82	1139	10.71	1219	11.25	1326	12.33	1417	13.40	1508
8'-0"	4.37	517	4.90	574	5.42	632	6.74	785	7.45	852	8.16	919	9.11	1069	10.01	1150	10.90	1231	11.48	1339	12.56	1431	13.64	1522
8'-3"	4.46	526	4.99	584	5.52	642	6.87	800	7.59	868	8.31	936	9.28	1091	10.19	1173	11.10	1254	11.70	1367	12.79	1459	13.88	1551
8'-6"	4.54	541	5.08	601	5.63	661	7.00	820	7.73	891	8.46	961	9.46	1118	10.38	1201	11.29	1285	11.92	1399	13.02	1494	14.12	1588
8'-9"	4.62	550	5.17	611	5.73	672	7.13	836	7.87	907	8.61	978	9.64	1139	10.56	1224	11.49	1308	12.14	1427	13.26	1522	14.36	1617
9'-0"	4.71	565	5.27	628	5.83	691	7.26	856	8.01	929	8.75	1002	9.81	1166	10.75	1252	11.68	1339	12.36	1460	13.49	1557	14.60	1654
9'-3"	4.79	574	5.36	638	5.93	701	7.39	872	8.15	945	8.90	1019	9.99	1187	10.93	1275	11.87	1362	12.59	1487	13.72	1585	14.85	1683
9'-6"	4.87	588	5.45	654	6.03	720	7.52	892	8.29	968	9.05	1044	10.16	1214	11.12	1303	12.07	1393	12.81	1520	13.95	1620	15.09	1720
10'-0"	5.04	603	5.64	670	6.24	738	7.78	916	8.56	993	9.35	1070	10.51	1246	11.49	1337	12.46	1428	13.25	1561	14.41	1662	15.57	1764

NOTE:


- FOR CONVENIENCE, DEPTHS OF INLETS SHOWN IN ABOVE TABLES ARE IN INCREMENTS OF 3 INCHES BUT ANY DEPTHS OTHER THAN THOSE SHOWN ABOVE MAY BE USED WHEREVER DEEMED NECESSARY. QUANTITIES FOR OTHER DEPTHS FALLING WITHIN THE LIMITS OF THE TABLE MAY BE FOUND BY INTERPOLATION.
- DEPTHS GREATER THAN 10' NEED TO BE STRUCTURALLY ENGINEERED.

CURB INLET RECESSED


SUMMARY OF QUANTITIES

North Central Texas Council of Governments





SECTION "A-A"
N.T.S.



INLET SIZE	T	W
2' SQUARE	7"	2'-0"
4' SQUARE	7"	4'-0"
5' SQUARE	8"	5'-0"
6' SQUARE	9"	6'-0"

PLAN OF TOP SLAB
N.T.S.


NOTES:

1. MATERIAL AND WORKMANSHIP SHALL CONFORM WITH THE REQUIREMENTS OF NCTCOG STANDARD SPECIFICATIONS FOR STANDARD CONCRETE MANHOLES. MINIMUM CLASS "C" CONCRETE.
2. LAYERS OF REINFORCING STEEL NEAREST THE INTERIOR AND EXTERIOR SURFACES SHALL HAVE A COVER OF 2" CLEAR OF BARS, UNLESS OTHERWISE NOTED.
3. FOR DETAILS OF REINFORCING OF LOWER PORTION OF INLET SEE APPROPRIATE SQUARE MANHOLE DETAILS.
4. DEPTH OF DROP INLET FROM FINISHED GRADE TO FLOW LINE OF INLET IS VARIABLE. APPROXIMATE DEPTH WILL BE SHOWN ON PLANS AT LOCATION OF INLET.
5. ALL STANDARD DROP INLETS SHALL HAVE ONE OPENING ON EACH SIDE UNLESS OTHERWISE SHOWN ON PLANS.
6. TOP SLAB MAY BE REINFORCED SAME AS 4' SQUARE MANHOLE.
7. PRECAST PRODUCTS MAY BE USED AT THE APPROVAL OF THE OWNER.
8. ALLOW 1" MIN CLEAR SPACE BETWEEN OD OF PIPE OR BOX AND INSIDE WALL OF INLET (OD OF PIPE OR BOX SHOULD ACCOUNT FOR SKEWED CONDITIONS).
9. DEPTHS OF GREATER THAN 10' NEED TO BE STRUCTURALLY ENGINEERED.

DROP INLET

2', 4', 5', OR 6' SQUARE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE


702

DATE
AUG '23

STANDARD DRAWING NO.
6040


FILL AREAS SHALL BE COMPACTED TO 95% STD. PROCTOR DENSITY AT OPTIMUM MOISTURE CONTENT PRIOR TO CHANNEL EXCAVATION.

* GEO TEXTILE RECOMMENDED AT CONNECTION OF TOP OF SLOPE TO EARTHEN MATERIAL.




REINFORCED CONCRETE
CHANNEL SECTION
N.T.S.

CONSTRUCTION JOINT
N.T.S.




ALTERNATE
CONSTRUCTION JOINT
N.T.S.




TRANSVERSE EXPANSION JOINT
SPACE 100' C-C AND USE AT ENDS OF CURVES - P.C. AND P.T.
N.T.S.

*REFER TO ISWM FOR ALTERNATE BIOSWALE OPTIONS


STANDARD DRAWING NO. 6050	ALTERNATE CONSTRUCTION JOINT N.T.S.	LOW FLOW CHANNEL LINING CONCRETE REINFORCED	North Central Texas Council of Governments 	STANDARD SPECIFICATION REFERENCE 803.3 DATE AUG '23 STANDARD DRAWING NO. 6050




SECTION "B-B"
N.T.S.




SECTION "A-A"
N.T.S.




DETAIL "D"
N.T.S.



PLAN
N.T.S.



BAR DETAIL
N.T.S.




SECTION "C-C"
N.T.S.

NOTES:

1. CONCRETE SHALL BE CLASS "C"
2. SEE TXDOT DETAILS FOR ADDITIONAL HEADWALL OPTIONS.

CONCRETE APRON
VERTICAL HEADWALL

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE


803.3

DATE
AUG '23


STANDARD DRAWING NO.
6060




PLAN
N.T.S.



SECTION A-A
N.T.S.



SECTION B-B
N.T.S.




SECTION C-C
N.T.S.

NOTES:

1. CONCRETE SHALL BE CLASS "A".
2. WHEN SITE IT NOT APPLICABLE, SEE TXDOT

CONCRETE APRON
SLOPING HEADWALL

North Central Texas Council of Governments




STANDARD SPECIFICATION REFERENCE

803.3

DATE
AUG '23

STANDARD DRAWING NO.
6070



SECTION
N.T.S.

LIMITS OF EXCAVATION

DEPTH OF TRENCH (FT.)	DIST. IN FT. OUTSIDE NEAT LINES OF PIPE SUBDRAIN
0 TO 6	1.00
6 TO 10	1.50
10 TO 15	2.00
OVER 15	2.50

FILTER MATERIAL SPECIFICATIONS

SIEVE SIZE	PERCENTAGE RETAINED ON SIEVE	
	TYPE A	TYPE B
1 1/2	----	0 - 10
3/4	0 - 10	20 - 40
3/8	15 - 35	----
NO. 4	35 - 55	40 - 60

TYPES OF PIPE ACCEPTABLE FOR USE AS SUBDRAIN

1. PERFORATED CORRUGATED METAL PIPE.
2. PERFORATED PVC PIPE.
3. PERFORATED POLYETHYLENE PIPE.


MATERIAL FINER THAN NO. 4 SIEVE

4	----
20	35 - 65
50	75 - 100

SUBDRAINS

PAVEMENT SUBGRADE

North Central Texas Council of Governments



STANDARD SPECIFICATION REFERENCE

301

DATE
AUG '23

STANDARD DRAWING NO.
6090